




Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:- ee-baij-hp@nic.in

CERTIFICATE

**CERTIFIED THAT THE TENDERS OF WORKS, AS
CALLED VIDE THIS OFFICE LETTER NO.PWD/BD/TA/NIT/2023-24/-
12582-12631 DATED 14-11-2023. ARE URGENT NATURE
AND PUBLIC INTEREST.**


**Executive Engineer,
Baijnath Division,
HP.PWD, Baijnath.**



Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:- ee-baij-hp@nic.in

"NOTICE INVITING TENDER"

Sealed item rate of tender form No. 6 & 8 are hereby invited by the Executive Engineer, Baijnath Division H.P.PWD., Baijnath on behalf of the Governor of HP for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rule and also registered under the HP General Sales Tax act 1968 so as to reach in this office on or before **28.11.2023** up to **11.30 A.M** and will be opened on the same day at **12.00 Noon** in the presence of intending contractors or their authorized representatives. The tender forms can be had from his office against cash payment (Non refundable) on **25.11.2023 between 2.00 PM up to 4.30 P.M** and the application for issue of tender forms shall be received on **24.11.2023 up to 12.00 Noon**.

The earnest money in the shape of National Saving Certificate/Time Deposit accounts/Saving Accounts in any Post Office/Bank in H.P. duly pledged in favour of the XEN H.P.PWD., Baijnath must be accompanied with the each tender. Conditional/incomplete tenders and the tenders received without earnest money as mentioned above will be similarly rejected, the offer of the tender shall be kept open for 75 days. The XEN reserves the right to accept or reject any or all tenders or to drop the proposal of the tender without assigning any reasons.

Sr. No.	Name of work.	Amount put to tender/Estimated cost.	Earnest Money	Cost of tender form	Time limit
1	C/O road along with tiles nearby Govt. Primary School Khalenu 300 mtr. Mohal Kudail (SH: Providing and Laying Inter locking paver Block 60mm thick 0/575 to 0/599 app.) deposit work	Rs.1,48,023/-	Rs. 3,000/-	Rs.350/-	One Month
2	C/O Link road from Behru to Majherna railway station km 0/00 to 0/500 (SH: Providing and laying W.B.M. G-I and C.C. Pavement km 0/050 to 0/135)	Rs.2,89,897/-	Rs. 5,800/-	Rs.350/-	One Month
3	C/O Pucca Path from Chobin road to Mehta Basti Sh. Jagdish Mehta house Mohal Chobin (Providing and laying C.C. Pavement)	Rs.1,97,929/-	Rs. 4,000/-	Rs.350/-	One Month
4	C/O Pucca Path from G.M.S. Mahalpatt to the house of Sh. Girdhari Lal and others Mohal Mahalpatt (SH: C/o E/wall & C.C. Pavement at RD 009 to 0/027) Deposit work	Rs.77,435/-	Rs.1,600/-	Rs.350/-	One Month
5	C/O Street/Path from Sh. Ashok Kumar House ward no.7 (Mohal Chobin) (SH: Providing and Laying Inter locking paver Block) (Deposit work)	Rs.1,95,859/-	Rs.4,000/-	Rs.350/-	One Month
6	C/O Cement Concrete Pavement Dharaman Sungal Jadyala Road to Shamshan Ghat Nouri Km 0/00 to 8/00 (SH: C/O C.C. Pavement at R.D. 0/00 to 0/080) Deposit work	Rs.2,97,694/-	Rs.6,000/-	Rs.350/-	One Month
7	Completion of Mahila Bhawan Near Khola Pahloon Mahol Mahalpatt (SH: Cement Plaster, preceding and Fixing Steel Shutters etc)	Rs.48,479/-	Rs. 1000/-	Rs.350/-	Two Months
8	C/O Road form IPH water Tank to Lower Chobin (SH; Providing and laying C.C.Pavement)	Rs.1,97,929/-	Rs. 4,000/-	Rs.350/-	One Month
9	C/O Sheep Dipping tank at Veterinary Hospital (Village Sansal) (SH: C/O Sheep dipping tank)	Rs.4,99,225/-	Rs.10,000/-	Rs.350/-	Two Months
10	C/O link road to village Chaluhi Sanyar Patt at RD 0/00 to 1/500 Mohal Rajot (SH: P/L Kharnja stone soling and C.C. Pavement at RD 0/150 to 0/192)	Rs.1,48,313/-	Rs.3,000/-	Rs.350/-	One Month
11	A/R & M/O various residential building of PWD under Baijnath division HPPWD Baijnath (SH: Providing and supplying of Farm No. 8 for various works.)	Rs.70,000/-	Rs.1,400/-	Rs.350/-	Two Months
12	C/O Puli near Sh. Sesh Ram house Mohal Gadiyara (SH: P/L C.C. Pavement and C/O Both sides approaches) Deposit work	Rs.49,444/-	Rs.1,000/-	Rs.350/-	One Month
13	R/D on Baijnath Langhu Gadiyara road Km 0/00 to 5/700 (SH: C/O R/Wall at RD 5/327 to 5/341.70)	Rs.1,91,104/-	Rs.3,900/-	Rs.350/-	One Month

Terms and conditions:-

1. The contractor should be registered as dealer under H.P. GST Tax Act. 2018 and also produce the Tin number, H.P. sales Tax clearance certificate from the Excise and Taxation Department.
2. The Pan Number, latest Income Tax clearance certificate and EPF No (Where applicable) duly attached with the application.
3. The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained.
4. In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
5. Only two tenders form will be issued to the contractor/firm which may be noted.
6. The contractor will also have to attach the labour employer license from the labour office with the application.
7. Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
8. The contractor shall be responsible for rectifying defects noticed within One year from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.

9. The contractor shall have all required machinery such as Truck/ Tipper, Mixture, water tanker Vibrator etc or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
10. The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an under taking viz he will get complete the works in hand before award of work with in schedule time.
11. All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
12. The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/ permit.

Executive Engineer,
Bajjnath Division.,
H.P.PWD..Bajjnath.

For & On behalf of the governor of H.P.

NO:-PWD/BD/TA/NIT/2023-24/-

12502 - 12631

Dated:- 14-11-2023

- 1 Copy to the F.C. cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
- 2 The Engineer-in-chief, HPPWD, Shimla.
- 3 The Chief Engineer (MZ), HPPWD, Mandi.
- 4 The Superintending Engineer, JNR. Circle HPPWD, Joginder Nagar.
- 5 All the Assistant Engineer working under this Division.
- 6 Drawing Branch in this office.
- 7 Notice Board.
- 8 The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
Bajjnath Division.,
H.P.PWD..Bajjnath.

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : C/O road along with tiles near by Govt Primary School Khalenu 300 mtr Mohal Kudail . (Sh:-Providing and Laying Inter locking paver Block 60 mm thick 0/575 to 0/599 app.) Deposit work				Estimate Cost: 1,48,023.00 ✓ Earnest Money: 3,000.00 ✓ Time Limit : One Month ✓		
Sr.n	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:4:8 (one Cement : two coarse sand : four graded stone aggregate 40 mm nominal size) .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	7.20	Cum.			
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:2:4 (one Cement : two coarse sand : four graded stone aggregate 40 mm nominal size) .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	0.38	Cum.			
3	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in-Charge 60mm (sixty millimeter) thick cement concrete paver block of M-35 grade with approved colour, design & pattern..The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	72.00	Sqm			

Executive Engineer
 Building Division
 H.P.N.S.D., Baljodh 2

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work :- C/O Link road from Behru to Majherna railway station km 0/00 to 0/500 .

(Sh :- Providing and laying W.B.M G-I and C. C Pavement km 0/050 to 0/135)

Estimate Cost: 2,89,897.00/-

Earnest Money:5,800.00/-

Time Limit : one Months

SCHEDULE OF WORKS

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P	
				Figures	Words		
1	Stone soling properly hand packed filling intersects with kharanja stone and consolidating with power road roller to the requested gradient and camber including spreading watering and rolling of binding moorum or earth etc complete as per HPPWD specification 100 mm spread thickness (finished work including materials and labour) The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	24.54	Per Cubic metre				
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Milimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals . The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	36.81	Per Cubic metre				

6/11/2018

6/11/2018

6/11/2018

DNIT/DRAFT SCHEDULE OF QUANTITY


3

Name of work :- C/O Pucca Path from Chobin road to Mehta Basti Sh. Jagdish Mehta House Mohal Chobin
(Sh :-Providing and laying C. C Pavement)

Estimate Cost: 1,97,929.00/-
Earnest Money:4,000.00/-
Time Limit : one Month

SCHEDULE OF WORKS

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Stone soling properly hand packed filling intersects with kharanja stone and consolidating with power road roller to the requested gradient and camber including spreading watering and rolling of binding moorum or earth etc complete as per HPPWD specification 100 mm spread thickness (finished work including materials and labour) The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	22.50	Per Cubic metre			
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Milimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	24.00	Per Cubic metre			


Engineer
Chobin
2 2

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work : C/O Pucca Path from G.M.S Mahalpatt to the house of Sh. Girdhari Lal and others Mohal Mahal patt
(SH: C/O E/Wall & C C Pavement at RD 0/004 to 0/027) Deposit work

Estimate Cost: 77,435.00/-
Earnest Money: 1,600.00/-
Time Limit : One Month

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In – Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	2.00	Per Cum				
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	3.75	Per Cum				
3	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including entire carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	4.00	Each				
4	Stone soling properly hand packed filling intersects with kharanja stone and consolidating with power road roller to the requested gradient and camber including spreading watering and rolling of binding moorum or earth etc complete as per HPPWD specification 100 mm spread thickness (finished work including materials and labour) The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	6.75	Per Cum				
5	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Milimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	6.75	Per Cum				
Total							

[Signature]
 Executive Engineer
 District Engineer
 D.D., Bijnor

(5)

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : C/O Street /Path from Sh. Ashok Kumar House ward no.7. (MOHAL CHOBIN) (Sh:-Providing and Laying Inter locking paver Block) (DEPOSIT WORK)				Estimate Cost: 1,95,859.00 Earnest Money:4,000.00 Time Limit : One Month		
Sr.n	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:4:8 (one Cement : two coarse sand : four graded stone aggregate 40 mm nominal size) .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	4.77	Cum.			
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:2:4 (one Cement : two coarse sand : four graded stone aggregate 40 mm nominal size) .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	0.44	Cum.			
3	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in-charge (sixty millimeter) thick cement concrete paver block of M-35 grade with approved colour, design & pattern..The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	111.00	Sqm			

Executive Engineer
Public Works Division
Muzaffarpur

DNIT/DRAFT SCHEDULE OF QUANTITY

6

Name of work :- C/O Cement Concrete Pavement Dharaman Sungal Jadiyahala Road to Samshan Ghat Nouri km 0/00 to 8/00 . (SM :- C/o C.C. Pavement At R.D 0/00 to 8/080) (DEPOSIT WORK)			Estimate Cost: 2,97,694.00/- Earnest Money: 6,000.00/- Time Limit : One Months
---	--	--	--

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Stone soling properly hand packed filling intersects with kharanja stone and consolidating with power road roller to the requested gradient and camber including spreading watering and rolling of binding moorum or earth etc complete as per HPPWD specification 100 mm spread thickness (finished work including materials and labour) The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	25.20	Per Cubic metre			
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Milimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	37.80	Per Cubic metre			

Engineer
Division
Bhilai, Bilaspur

7

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : Completion of Mahila Bhawan Near Khola Pahloon Mahol Mahalpatt .
(S.H. : Cement Plaster ,Providing and Fixing Steel shutters etc

Estimate Cost: 48,479.00
Earnest Money: 1000.00
Time Limit : Two Months

SCHEDULE OF WORKS

Sl. No.	Description of work	No.or Qty.	Unit	Rate to be entered by the Bidder		AMOUNT Rs. P
				Figures	Words	
1	6mm (six millimeter) cement plaster 1:3 (one cement isto three sand) in ceiling complete including curing complete as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	37.27	Per square metre			
2	15mm (fifteen milimeters) thick cement plaster in single coat on the rough side of brick/concrete/stone walls for interior plastering upto any floor level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm (eighty milimetewrs) in girth, in rough side with cement mortar 1:6 (one cement isto six sand) complete including curing as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	70.02	Per square metre			
3	Providing and Fixing in position steel shutters complete with bolts , nuts locking arragement , stoppers ,handles , including applying a priming coat of approved steel primer .)The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	1.80	Per square metre			

Executive Engineer
Rajpath Division
H.P.P.D., Rajpath

DNIT/DRAFT SCHEDULE OF QUANTITY


8

Name of work :- C/O Road from IPH water Tank to Lower Chobin
(Sh :-Providing and laying C. C Pavement)

Estimate Cost: 1,97,929.00/-
Earnest Money:4,000.00/-
Time Limit : one Months

SCHEDULE OF WORKS

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Stone soling properly hand packed filling intersects with kharanja stone and consolidating with power road roller to the requested gradient and camber including spreading watering and rolling of binding moorum or earth etc compleete as per HPPWD specification 100 mm spread thickness (finished work including materials and labour) The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	22.50	Per Cubic metre			
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Milimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803,1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	24.00	Per Cubic metre			


 Engineer
 8

DNIT/DRAFT SCHEDULE OF QUANTITY


Name of work :- C/O sheep Dipping tank at Veterinary Hospital (Village Sansal)
SH: (c/o sheep dipping tank)

Estimate Cost: 4,99,225.00
 Earnest Money: 10,000.00
 Time Limit : Two Months

Sl. No.	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In – Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	34.66	Cum			
2	Providing form work with steel plates of 3.15mm (three decimal one five milimeter) thick, welded with angle iron in frames of 30x30x5mm (thirty into thirty into five milimeter) so as to give a fair finish including centring, shuttering strutting and propping etc, with wooden battens and ballies for all heights/depths of propping and centring below supporting floor to ceiling and removal of the same for in-situ reinforced concrete and plain concrete work in vertical surface such as walls up to any thickness but not. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	16.26	Sqm			
3	Providing and laying cement concrete 1:6:12 (One cement isto six sand isto twelve aggregate) graded crushed/broken stone aggregate 40mm (forty milimeter) nominal size mechanically mixed and curing complete, excluding cost of form work in foundation and plinth. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	4.97	cum			

4	Providing and laying cement concrete 1:4:8 (One cement isto four sand isto eight aggregate) graded crushed/broken stone aggregate 40mm (fourty milimeter) nominal size mechanically mixed and curing complete, excluding cost of form work in foundation and plinth. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	0.81	cum			
5	Providing and laying cement concrete work 1:2:4 (1 Cement:2 Sand:4 graded stone aggregate 20 mm nominal size) and curing complete excluding cost of form work and reinforcement for reinforced concrete work in :Suspended Floor roofs, landing and shelves and their support balconies,beams,girders,bressumers and contilever upto floor twolevel.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	6.15	cum			
6	Providing mild steel/Tor steel reinforcement for R.C.C. work including bending, binding and placing in position complete upto floor two level :Tor Steel The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	492.00	Kilogram			
7	Brick work using common burnt clay building bricks in foundation and plinth in :- Cement Mortar 1:6 (one Cement : six Sand) Second Class Bricks The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	6.33	cum			
8	Random rubble masonry/polygonal rubble masonry (uncoursed/brought to courses) with hard stones of approved quality in foundation and plinth including leveling up with cement concrete 1:6:12 (1 cement :6 sand : 12 graded stone aggregate 20mm nominal size) at plinth level in Cement Mortar 1:6 (One cement:Six sand) The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	18.63	cum			
9	Squared rubble masonry coursed with hard stone of approved quality in foundation and plinth including raking out joints in:-Cement Mortar 1:6 (one cement : six sand) The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	5.78	cum			
10	Providing and fixing M.S. grills of required patterns in wooden frames of windows etc. with M.S. Flats, square or round bars with round headed bolts and nuts or by screws.Plain grill.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	722.00	Kilogram			

11	Providing and fixing on wall face PVC (D-Plast) rain water pipes of working pressure not less than 4.5 kg/sqm including filling the joints with approved adhesive complete. 150mm dia (one hundred fifty millimeters) pipes (scour pipe for outlet) The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	20.00	Rmt			
12	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint. In gratings framed guard bars, ladders, railing, brackets and similar works. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	2.70	Qntl			
13	20mm (twenty millimeter) Cement plaster in single coat on rough side of brick/stone masonry for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth Cement Mortar 1:6 (One cement: Six sand) The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	91.62	Sqm			
14	Providing and laying in trenches, galvanised mild steel tubes (medium grade), tube fittings (earth work in trenches to be measured and paid separately) :- 25mm (Twenty Five millimeter) nominal bore The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	60.00	Rmt			
15	Providing and fixing Providing (I) C.P Brass bib tap with Capstan head The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	1.00	Each			
16	Providing and fixing G.I./M.I Union of following sizes (where not included in the items .25mm (twenty five millimeter) The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	4.00	Each			


 Executive Engineer
 Drainage Division
 D.P.S. D., Daljnath


DNIT/DRAFT SCHEDULE OF QUANTITY

(10)

Name of work :- C/O Link Road to Village Chaluhi Sanyar Patt at RD 0/00 to 1/500 . Mohal Rajot .
(SH:- P/L Kharanja stone soling and C C Pavement at RD 0/150 to 0/192

Estimate Cost: 1,48,313.00/-
Earnest Money: 3,000.00/-
Time Limit : One Month

SCHEDULE OF WORKS						
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Stone soling properly hand packed filling intersects with kharanja stone and consolidating with power road roller to the requested gradient and camber including spreading watering and rolling of binding moorum or earth etc complete as per HPPWD specification 100 mm spread thickness (finished work including materials and labour) The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	8.51	Per Cubic metre			
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Milimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	19.85	Per Cubic metre			


 Executive Engineer
 Baijnath Division
 H.P.W.D., Baijnath

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work: A/R & M/O various residential buildings of PWD under Baijnath division HPPWD Baijnath
(Sub Head:- Providing and supplying of Form No. 8 for various works.)

Estimate Cost : 70,000.00

Earnest Money : 1,400.00

Time Limit : Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		Amount Rs.
				Figures	Words	
1	Providing and supplying of Form No. 8 (Eight) comprising 112 (one hundred twelve) pages printed with black ink as per the norms of CPWD mannual complete in all respect. The rates shall be included all taxes, GST levy by the Govt. time to time and carriage of material with in all leads, lifts and as per the direction of Engineer-in-Charge.					


Executive Engineer
 Baijnath Division
 H.P.P.W.D. Baijnath

<p>Estimate Cost: 49,444.00/- Earnest Money: 1,000.00/- Time Limit : One Month</p>

Executive Secretary
Barracks Division
H.P.R. 2, Gajnah 8

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work : R/D on baijnath Langhu Gadiyara road km 0/00 to 5/700 (SH: C/O R/wall at RD 5/327 to 5/341.70)						Estimate Cost: 1,91,104.00/- Earnest Money: 3,900.00/- Time Limit : One Month	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P	
				Figures	Words		
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In – Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	15.73	Per Cum				
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	36.01	Per Cum				
3	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals. including entire carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	13.52	Per Cum				
4	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including entire carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	12.00	Each				
Total							

Executive Engineer
Baijnath Division
H.P.R.W.D., Baijnath