


HPPWD NOTICE INVITING TENDER BHARWAIN DIVISION HPPWD BHARWAIN TEHSIL AMB DISTRICT UNA (H.P).  
Phone No. 01976-255822 , Web :- www. hppwd.gov.in & email address ee-bharw-hp@nic.in.

Sealed tenders on item rates basis are hereby invited on behalf of Governor of Himachal Pradesh by the Executive Engineer Bharwain Division, HPPWD, Bharwain Tehsil Amb District Una (HP) from the experienced contractors/ firms enlisted in appropriate class with Himachal Pradesh PWD for the following works. The tender shall be received in his office on or before 10.11.2023 up to 10.30 A.M and shall be opened on the same day at 11.00 A. M in the presence of contractors / firms or their authorized representatives , who wish to be present at the time of opening of tenders. The tender applications shall be entertained and tender form shall be sold up to two days before the date of opening of tender i.e 08.11.2023 up to 12.00 Noon. Draft Notice Inviting Tenders/ Drawing/ Specifications can be seen in the office of the Executive Engineer on any working day between 11.00 A. M to 4.00P. M. Ambiguous / Telegraphic / Conditional tenders or tender by Fax shall not be entertained/ considered in any case. The earnest money in the shape of National Saving Certificate / Time Deposit Account / FDR in any of the Post Office in H.P./ Nationalized Bank duly pledged in favour of Executive Engineer must be accompanied with the application. Conditional tenders and the tenders received without earnest money will out rightly be rejected. The contractor shall accompany his enlistment/ renewal orders with his application for obtaining the tender documents. The Executive Engineer reserves the right to reject the tender without assigning any reasons. The work will be completed by the contractor within the stipulated period. The contractor will have to submit his registration under the H. P General Sale Tax Act 1968 and also labour license under contract Act 1970 from the competent authority. The contractors/ firms are requested to insert the rate of each item in words as well as figures, failing which XEN reserves the right to accept/ reject any or overall tenders. The tender shall only be issued to those contractors/ firms, who are found eligible/ suitable and competent as per the above conditions. The offer shall remain valid up to 45 days after the opening of tender. If any of the date mentioned above happens to be Local / Gazetted Holidays the same shall be process on next date. **The contractor should be registered as dealer under GST Act, Valid copy of Registration as required, copy of PAN Card, EPF failing which no tender form will be issued to him.**

Sr. No	Name of work.	Estimated cost.	Earnest Money	Time Limit	Form No.	Cost of
1	Repair/ restoration of Bharwain Chintpurni Talwara road km 0/0 to 15/310 (SH: C/O Retaining wall at RD 5/845 to 5/855.	499817/-	10000/-	Three month	PWD-8	350/-
2.	Repair/ restoration of rain damages on Jole to khurwain road 0/0 to 8/0(SH:- P/L 80mm thick NTC Paver block between RD 3/215 to 3/285 ) against DC Deposit.	499720/-	10000/-	Three Months	PWD-8	350/-
3.	Restoration of rain damages on Jole to Kaint via Choorā Amroh Dharun Kuthru Sanjot Km 0/0 to 14/255 (SH:- Removal of Slips, rain cuts and C/o unlined surface drain etc.)	498768/-	10000/-	Three Months	PWD-8	350/-
4.	A/R & M/O various roads under Bharwain Sub-Division (Section Chintpurni )( P/F Centre line & roads studs etc)	472500/-	9500/	Three months	PWD-8	350/-
5.	A/R & M/O various roads under Bharwain Division Bharwain Division (Koharchhan Section) (SH:- P/F Cat eye Road Studs, Rumble Srips and speed breakers)	442500/-	8850/-	Three months	PWD-8	350/-
6	Repair/ restoration of rain damages on Jole to Khurwain road Km 0/0 to 8/0 (Sh:- P/L 80mm thick NTC Paver block between RD 3/290 to 3/350)	499870/-	10000/-	Three months	PWD-8	350/-

1. The Xen reserve the right to accept or reject the tender with assigning any reason.
2. The tender forms will not be issued to those contractors those performance is not founds satisfactory.
3. The list of similar type of work executed & work done performance certificate issued by the concerned Executive Engineer/GST/EPF No should accompanied with application.
4. Certificate: - Certificate that the tender have been invited in exigencies/emergency of work.

  
Executive Engineer,  
Bharwain Division  
HPPWD, Bharwain.

No. PWB/CB/TA /Tender /2023- 11216 -240

Dated 03/11/23


Copy forwarded to the following for information and necessary action, please.

- 1 The Engineer in Chief, HppWD, Shimla for information.
2. The Chief Engineer, (HZ) HppWD, Hamirpur.
3. The Superintending Engineer, 15<sup>th</sup> Circle, HPPWD, Una.
4. All the contractor working under this Division.
5. Drawing Branch in this office.
6. All the Assistant Engineer, working under this Division.
7. Notice Board.

Executive Engineer,  
Bharwain Division.

Certificate

Certified that the works are of urgent in nature and for large public Interest, so there are exigencies /emergency in calling these without press vide this office letter No PWB/CB/TA-1/ Tender/2023:- 119216-240 dt 03/11/2023

  
Executive Engineer,  
Bharwain Division,  
HPPWD, Bharwain.

1

Schedule of Quantity

Estimate Cost-499817/-  
Earnest Money-10000/-  
Time- Three Months

Name of Work:- Repair / Restoraion of Bharwain Chintpurni Talwara road Km. 0/0 to 15/310 (SH:-Construction of Retaining wall from RD 5/845 to 5/855)

Sr No.	Sub-Head and Items of work	Quantity		Rates in		Unit	Amount
				Figure	Words		
1	Excavation in earth work in foundation and trenches etcetera in all kind and classification of soil such as pick work, jumper work, pick jumper work, blasting work and hard blasting work and saturated soil any other mixed verity of soil in dry or saturated condition upto any depth and lift upto any height including chiseling/wedging out rocks where blasting prohibited dewatering pumping or bailing out water where required and/ removal of slush separately as directed which may arise during the execution including stacking the serviceable and unserviceable material and then returning stacked soil in any thickness of layers when required into plinth side of foundation etcetera consolidating each deposited layers by ramming and watering then disposing of all surplus unserviceable excavated earth as specified dumping place as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi , royalty , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	91.35	Cubic metre	180.00	Rs. One hundred eighty and paise zero only	Per cubic metre	16443
2	providing and laying in position cement concrete 1:4:8(one cement: four sand: eight graded/crushed stone aggregate 40mm (forty millimeter) nominal size mechanically mixed and curing complete including cost of centering and shuttering in Retaining wall / Breast wall as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of material/ machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi , royalty , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	132.63	Cubic metre	3450.00	Rs. Three thousand four hundred fifty and paise zero only	Per cubic metre	457574
3	Providing weepholes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeters) dia PVC pipe OF MAKE D-PLAST/POLY having pressure of 4.5 kg per square meter extending through the full width of the structures with slope of (1V):20(H) (one vertical: twenty horizontal) towards drawing face complete as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi , royalty , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	39.00	Numbers	230.00	Rs. Two hundred thirty and paise zero only	Each	8970
4	Back filling with granular material behind abutment, wing wall and return wall complete as per drawing and direction of Engineer in charge including carriage of materials/machinery required to execute the work as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	30.60	Cubic metre	550.00	Rs. Five hundred fifty and paise zero only	Per cubic metre	16830
<b>Percentage rate (Above or Below)</b>							
<b>Total</b>							<b>499817</b>

  
Executive Engineer  
Bharwain Division  
HPPWD Bharwain


2

Schedule of Quantity

Name of Work:-Repair / restoraton of rain damages on Jole to Khurwain road Km. 0/0 to 8/0(SH:- P/L-.80mm thick NTC Paver blcok between RD 3/215 to 3/285) against Dc Deposit

Estimate Cost-499720/-  
Earnest Money-10000/-  
Time- Three Months

Sr. No.	Sub-Head and Items of work	Quantity		Rates in		Unit	Amount	
		Sqm	Cum	Words	Figure*			
1	Dismantling manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres bituminous road lead as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery labour cess or other taxes imposed by the Government.	51.00		100.00	Rs one hundred and paise zero only	Per Square metre	5100	
2	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm ) to wet mix macadam (WMM)specification including premixing the material with water at OMC in for all leads and lifts, laying in uniform layers with mechanical paverfinisher in sub-base/ base course on well prepared surface and compacting with vibratory roller of 8 (eight) to 10 (ten) tonne capacity to achieve the desired density/ complete as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentials. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	47.35	Cum	1600.00	Rs one thousand six hundred and paise zero only	Per Cubic metre	75760	
3	Providing and laying of NTC Interlocking Concrete Block Pavements haeving thickness 80mm(eighty millimetre) M-40 (M-forty) grade as per CPPWD specification and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentials. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or Government.	280.00	Sqm	1350.00	Rs one thousand three hundred fifty and paise zero only	Per Square metre	378000	
4	Providing and laying in position specified grade of reinforcement cement concrete work M-25 (M-twenty five) design mix to obtained compressive strength design mix with minimum cement contents not less than 400 kgs (four hundred kilogram) per cubic metre curing complete including cost of form work in foundation footings bases of columns and the like mass concrete including the cost of centering, shuttering and finishing upto all height as per CPWD specifications 2019 complete and including entire carriage of materials with in all leads and lifts and other incidentials. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	6.81	Cum	6000.00	Rs six thousand and paise zero only	Per Cubic metre	40860	
<b>Percentage rate (Above or Below)</b>								
<b>Total</b>								<b>499720</b>

  
 Executive Engineer  
 Bharwain Division  
 HPPWD Bharwain

3

Schedule of Quantity

Estimate Cost- 498768/-  
Earnest Money-10000/-  
Time- Three Months

Name of Work:-Restoration of rain damages on Jole to Kaint via Choora Amroh Dharun Kuhru Sanjot km 0/000 to 14/255 (SH:- Removal of Slips, rain cuts and C/O unlined surface drain etc.)

NN	Sub-Head and Items of work	Quantity		Rates in		Unit	Amount
				Words	Figure		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material upto any lift and lead as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	3660.50	Cubic metre	85.00	Rs eighty five and paise zero only	Per cubic metre	311143
2	Restoration of rain cuts with soil, moorum gravel or a mixture of these, clearing the loose soil, benching for 300mm width laying fresh material in layers not exceeding 250 mm and compaction with plate compactor or power rammer to restore the original alignment, level and slopes as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	1015.71	Cubic metre	120.00	Rs one hundred twenty and paise zero only	Per cubic metre	121885
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions excavated material to be used in embankment at site with in any lead and lift as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	1730.00	Running metre	38.00	Rs thirty eight and paise zero only	Per running metre	65740
<b>Total</b>							<b>498768</b>
<b>Percentage rate (Above or Below)</b>							

  
Executive Engineer  
Bharwain Division  
HPPWD Bharwain

4

DNIT

Estimate Cost-472500/-  
Earnest Money-9500/-  
Time- Three Months

Name of Work:-AR/MO various roads under Bharwain Sub- Division (Section Chintpurni) (SH:- P/F Center line & Roads Studs etc. )

Sr. No.	Sub-Head and Items of work	Quantity		Rates in		Unit	Amount	
		Figure	Words	Figure	Words			
1	Providing and applying 2.5 mm thick road marking strips (retro- reflective) of specified shade/ colour using hot thermoplastic material by fully/ semi automatic thermoplastic paint applicator machine fitted with profile shoe, glass beads dispenser, propane tank heater and profile shoe heater, driven by experienced operator on road surface including cost of material, labour, T&P, cleaning the road surface of all dirt, seals, oil, grease and foreign material etc. complete as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi , royalty , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	450.00	Sqm	650.00	Rs. Six hundred fifty and paise zero only	Per Sqm	292500	
2	Providing and fixing post delimiters made of ABS round body fitted with 2 nos 100 mm dia high reflective reflectors and mounted on MS pipe of 65 mm dia duly powder coated anti-rust and anti theft steel to be installed as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi , royalty , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	100.00	Numbers	750.00	Rs Seven hundred fifty and paise zero only	Each	75000	
3	Providing and fixing Glow studs of size 100x20 mm made of heavy duty body shall be moulded ASA (Acrylic styrene Acrylonitrile) or HIP (High impact polystyrene) or ABS having electronically welded micro-prismatic lens with abrasion resistant coating as approved by Engineer in charge. The glow stud shall support a load of 13635 kg tested in accordance with ASTM D4280. The slope of retro-reflective surface shall be 35 (+/-5) degrees to base. The reflective panels on both sides with at least 12 cm of reflective area up each side. The luminance intensity should be as per the specification and shall be tested as described in ASTM 1: 809 as recommended in BS: 873 part 4: 1973. The studs shall be fixed to the Road surface using the adhesive conforming to IS, as per procedure recommended by the manufacturer complete as per CPWD specifications 2019 complete and direction of Engineer-in charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkhana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	300.00	Numbers	350.00	Rs Three hundred fifty and paise zero only	Each	105000	
<b>Total</b>								<b>472500</b>
<b>Percentage rate (Above or Below)</b>								

*H.P.P.W.D.*  
Executive Engineer,  
Bharwain Division,  
H.P.P.W.D. Bharwain

5

Schedule of Quantity

Estimate Cost-442500/-

Earnest Money-8850/-

Time- Three Months

Name of Work:-AR/MO various roads under Bharwain Division (Koharchhan Section ) (SH:- P/F Cat eye Roads Studs , rumble strips and speed breakers )

Sr. No.	Sub-Head and Items of work	Quantity		Rates in		Unit	Amount
				Figure	Words		
1	Providing and fixing Glow Studs of Size 100x100x20 mm made of heavy duty body shall be moulded ASA (Acrylic styrene Acrylonitrile) or HIP (High impact polystyrene) or ABS having electronically welded micro-prismatic lens with abrasion resistant coating as approved by Engineer-in-Charge. The Glow stud shall support a load of 13635 kg tested in accordance with ASTM D4280. The slope of retro-reflective surface shall be 33(+/-5) degree to base. The reflective panels on both sides with at least 12cm of reflective area up each side. The luminance intensity should be as per the specification and shall be tested as described in ASTM I:809 as recommended in BS :873 part 4: 1973. The studs shall be fixed to the road surface using the adhesive conforming to IS, as per procedure recommended by the manufacturer complete as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi , royalty , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	850.00	Each	350.00	Rs. Three hundred fifty and paise zero only	Each	297500
2	Providing and fixing of dual -directional reflective speed breaker/rumble-strip plastic high impact resistant plastic body of size 775X150X32mm having 6 glass large 12mm dia reflective lenses to one side (12 Nos. on both side ) provided with two steel zinc plated nails of 12mm and of length 120mm for fixing to road by hammering CAT PART No. GPL- 07-02 make GREENS or equivalent as per CPWD specifications 2019 complete and direction of Engineer-in- charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi , royalty , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	250.00	Each	580.00	Rs. Five hundred eighty and paise zero only	Each	145000
<b>Total</b>							<b>442500</b>

Percentage rate (Above or Below)

  
 Executive Engineer  
 Bharwain Division  
 HPPWD Bharwain

6

Schedule of Quantity

Estimate Cost-499870/-  
Earnest Money-10000/-  
Time- Three Months

Name of Work:-Repair / restoraton of rain damages on Jole to Khurwain road Km. 0/0 to 8/0(SH):- P/L 80mm thick NTC Paver blocok between RD 3/290 to 3/350)

Sr. No.	Sub-Head and Items of work	Quantity		Rates in		Unit	Amount
				Figure	Words		
1	Dismantling manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres bituminous road lead as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	52.50	Sqm	100.00	Rs one hundred and paise zero only	Per Square metre	5250
2	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm ) to wet mix macadam (WMM)specification including premixing the material with water at OMC in for all leads and lifts, laying in uniform layers with mechanical paverfinisher in sub-base / base course on well prepared surface and compacting with vibratory roller of 8 (eight) to 10 (ten) tonne capacity to achieve the desired density, complete as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	47.35	Cum	1600.00	Rs one thousand six hundred and paise zero only	Per Cubic metre	75760
3	Providing and laying of NTC Interlocking Concrete Block Pavements haeving thickness 80mm(eighty millimetre) M-40 (M-forty) grade as per CPPWD specification and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	280.00	Sqm	1350.00	Rs one thousand three hundred fifty and paise	Per Square metre	378000
4	Providing and laying in position specified grade of reinforcement cement concrete work M-25 (M-twenty five) design mix to obtained compressive strength design mix with minimum cement contents not less than 400 kgs (four hundred kilogram) per cubic metre curing complete including cost of form work in foundation footings bases of columns and the like mass concrete including the cost of centering, shuttering and finishing upto all height as per CPWD specifications 2019 complete and including entire carriage of materials with in all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	6.81	Cum	6000.00	Rs six thousand and paise zero only	Per Cubic metre	40860
<b>Total</b>							<b>499870</b>
<b>Percentage rate (Above or Below)</b>							

  
 Executive Engineer  
 Bharwain Division  
 HPPWD Bharwain