



E-Mail id - ee-bil2-hp@nic.in
Phone No. 01978-222551

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

"NOTICE INVITING TENDERS"

Sealed items rates tender for the following works are hereby invited by the Executive Engineer Bilaspur Division No. II HPPWD Bilaspur (H.P.) from the eligible contractors of the appropriate class registered in HPPWD, as per revised enlistment rules so as to reach in the office undersigned on 20/11/2023 up to 10:30 AM and will be opened on the same day at 11:00 AM in the presence of intending contractors. The tender application will be received in this office against cash payment on 18/11/2023 up to 10:00 AM to 02:00 PM and tender form can be had from this office on same day from 03:00 PM to 05:00 PM. The earnest money as shown against each in the shape of FDR of any bank in Himachal Pradesh duly pledged in the name of undersigned must accompany with each tender. The tender form will be issued on contractor giving proof of enlistment, GST, PAN No. etc. Conditional tender and tender received without earnest money will be outrightly rejected. The offer of the tender shall be kept open for 90 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors on the office of the undersigned on any working day during the office hours.

Sr. No.	Name of work	Estimated of cost	Earnest Money	Cost form	Time limit
1	Special Repair PHC Building at Toba Sh. Naina Devi Ji Distt. Bilaspur (HP) (SH:- Demolition of concrete slab, Form work, C/o stair case, white washing, Distempering and Railing of stairs)	Rs. 2,64,115/-	Rs. 5,300/-	Rs. 350/-	Three Month
2	Restoration of Rain damages on Chilla Chougla Behal Sai Kanaita Sai Brahmna (GP Kacholi) Km. 0/0 to 4/150 (SH:- C/o B/wall in wire crate at RD 0/115 to 0/132.50)	Rs. 4,93,167/-	Rs. 10,000/-	Rs. 350/-	Three Month
3	Special Repair PHC Building at Toba Sh. Naina Devi Ji Distt. Bilaspur (HP) (SH:- SH:- P/L R.C.C. slab and ceiling plastering) Deposit work	Rs. 4,35,752/-	Rs. 8,700/-	Rs. 350/-	Three Month

Certified that tender of above works are being called of emergent nature in exigency of Public interest.

Terms and Conditions:-

1. The contractor should produce a copy of enlistment/renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/firm shall have his registration and GST No., the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Bilaspur Division No. II HPPWD Bilaspur and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall be similarly rejected.
5. The contractor/firms are requested to insert the rate of each item in words as in figures failing which XEN reserves the rights to accept/reject any tender without assigning any reason at any stage.
6. The tender shall be issued to those contractors who have not more than two works in hand.

No.PW/NBT/CB/Tender-State/EA-1/2023-

9724-33

Copy forwarded to the following for information and necessary action to:-

1. The Engineer-In-Chief HPPWD Nirman Bhawan Nigam Vihar Shimla-2.
2. The Chief Engineer (HZ) HPPWD Hamirpur
3. The Superintending Engineers, 10th Circle, HPPWD Bilaspur.
4. The Executive Engineer (IT) O/o Engineer-in-Chief HPPWD Shimla through email- eeict-pwd-shi@hp.gov.in & ee-bil2-hp@nic.in for uploading the same on HPPWD web portal.
5. All the Assistant Engineers working under this Division.
6. Drawing Branch in this office/Notice Board.

sd/
Executive Engineer,
Bilaspur Divn.No.II,
HP.PWD., Bilaspur.

Dated:- 14-11-2023

[Signature]
Executive Engineer,
Bilaspur Divn.No.II,
HP.PWD., Bilaspur.

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.2,64,115/-Only.

Earnest Money :- Rs.5,300/-

Time:- Three Months.

NAME OF WORK:- Special Repair P.H.C Building at Toba the. Sh. Naina Devi Ji Distt. Bilaspur (H.P) (SH):- Demolition of Concrete Slab, Form Work, C/O Stair case, White Washing, Distemping and Railing of stairs). (Deposit Work)

Sr No.	Description of items.	Quantity		Rates in		Unit	Amount
				Figure.	Words.		
1	2	3		4	5	6	7
1	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in-charge including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	9.43	cubic metre			Per cubic metre	
2	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.40	cubic metre			Per cubic metre	
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering All work up to plinth level 1:4:8 (one Cement : Four coarse sand) : Eight graded stone aggregate 40 mm (forty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.77	Cubic Metre			Per Cubic Metre	
4	Centering and shuttering including strutting, propping etc. and removal of form for all heights including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.						
i)	Foundations, footings, bases of columns, etc. for mass concrete	25.82	Square Meter			Per Square Meter	
ii)	stairs, (excluding landings) except spiral staircases	7.28	Square Meter			Per Square Meter	

5	Formwork cement concrete work in walls (any thickness), including attached pilasters, buttresses, piers and abutments, piers, columns, piers, abutments, posts and struts etc. above plinth level up to 1:1.5:3 (One cement One sand Five coarse sand) Three graded stone aggregate 20 mm (Twenty millimeter) nominal size including carriage tax material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.43	cubic metre			Per cubic metre
6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Mild steel and Medium Tensile steel bars including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1286.00	Kilogram			Per Kilogram
7	3 mm (Six Millimeter) cement plaster 1:3 (One cement : Three fine sand) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	23.85	Square Meter			Per Square Meter
8	White washing with lime to give an even shade Old work (two or more coats including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	100.00	Square Meter			Per Square Meter
9	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade : Old work (one or more coats) including water thinnable priming coat with cement primer including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	199.20	Square Meter			Per Square Meter
10	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, riveting, fixing in position and applying a priming coat of approved steel primer all complete, including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	138.27	Kilogram			Per kilogram
	Total:-					

SCHEDULE OF QUANTITY.			Estimated cost:- Rs.4,93,167/-Only.			
			Earnest Money :- Rs.10,000/-			
			Time:- Three Months.			
NAME OF WORK:-Restoration of Rain Damages onChilla Chougla Behal Sai Kanaita Sai Brahamna (GP Kacholi) km 0/00 to 4/150 (SH:- C/o B/wall in wire crate at RD 0/115 to 0/132.50)						
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2	3	4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	63.53			Per cubic metre	
2	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimeter) dia GI wire confirming to IS:280 and IS:4826 in 100 mm (One hundred Millimeter) x100 mm (One hundred Millimeter) mesh(Woven diagonally) including 10percent extra for laps and joints laid with stone boulders weighing not less than 25kg as per drawing and technical specification clause 301. including cost of form work and curing complete including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	164.15			Per Cubic metre	
					Total:-	

Executive Engineer,
Bilaspur Division No. 2,
H.No. 12, Bazar (H.P.)

Estimated cost:- Rs.4,35,752/-Only.
Earnest Money :- Rs.8,700/-
Time:- Three Months.

Earnest Money :- Rs.8,700/-

Time:- Three Months.

R.C.C Slab and Ceiling Plastering) . (Deposit Work)

Total:-

[Signature]
Barrister,
Barrister Division No. 2
P.O. Box 100, Barrister (M.A.)