

OFFICE OF

EXECUTIVE ENGINEER, CHAMBA DIVISION HPPWD CHAMBA
HIMACHAL PRADESH, PUBLIC WORKS DEPARTMENT CHAMBA
Phone No. 01899-222229 Email ee-cha-hp@nic.in
NOTING INVITING TENDER

Sealed item rate tender on form 6&8 are hereby invited by the Executive Engineer, Chamba Division HPPWD Chamba on behalf of the Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HPPWD. So as to reach in his office on or before 02/12/2023 to 11:00 AM and the same shall be opened on the same day at 11:30 AM, in the presence of the intending Contractor or their authorized representatives if any. The tender form can be obtained from his office on cash payment (Non refundable) on 01/12/2023 upto 4.00 PM and the application for issue of tender form shall be received on 30/11/2023 upto 12.00 noon. The earnest money in the form of FDR from nationalized bank in HP duly pledged in favour of the Executive Engineer, Chamba Division HPPWD Chamba must be accompanied with each tender. The tender form will be issued to contractor who giving proof of enlistment, GST, Conditional tenders and the tenders received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer, reserves the right to reject the tender without assigning any reason. Special care should be taken to write the rates both in figure and in words.

Sr. No	Name of work	Estimated Cost	Earnest money	Cost of form	Time limit	Eligible Class
1	Restoration of Rain Damages on Ghoom Janjla road Km. 0/0 to 4/800 (SH:- Construction of PCC Retraining wall at RD 1/916.25 to 1/924.40)	360656/-	7213/-	350/-	One Month	D & C
2	Restoration of Rain Damages on Chaned Bhanota Road Km. 0/0 to 3/0 (SH:- Construction of PCC Retaining wall at RD 0/090 to 0/105)	3,79,037/-	7580/-	350/-	One Month	D & C
3	Repair of Ambedkar Bhawan Library Building at Dharog Chamba (SH:- P/L Floor tile, pestering, shutter work, putty)	2,84,560/-	5700/-	350/-	One Month	D & C
4	Construction of Link road to village Deri Km. 0/0 to 2/460 (SH:- Construction of wire crates at RD. 0/150 to 0/170)	4,90,875/-	9820/-	350/-	One Month	D & C
5	Restoration of Rain Damages on Parel Kohlari road Km. 0/0 to 12/500 (SH:- Construction of PCC Retaining walls at various Rds)	4,99,964/-	10000/-	350/-	One Month	D & C

6	Restoration of Rain Damages on Parel Kohlari road Km. 0/0 to 12/500 (SH:- Construction of PCC Retaining walls at various Rds)	4,99,964/-	10000/-	350/-	One Month	D & C
7	Restoration of rain damages on Sahoo Parotha Kurena Dhar road Km. 0/0 to 6/700 (SH:- Construction of PCC Retaining wall at RD 2/150 to 2.160)	1,94,630/-	3,900/-	350/-	One Month	D & C
8	Restoration of rain damages on Sahoo Parotha Kurena Dhar road Km. 0/0 to 6/700 (SH:- Construction of PCC Retaining wall at RD 2/630 to 2/640)	3,88,110/-	7800/-	350/-	One Month	D & C
9	A/R & M/O on Non-Residential Building under Chamba Division HPPWD., Chamba (SH:- Repair of PWD Canteen Chamba Division)	1,75,899/-	3600/-	350/-	One Month	D & C

TERMS AND CONDITIONS:-

- 1.The contractor should produce a copy of enlistment /renewal at time of application .
- 2.Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
- 3.The contractor /firm have his registration and GST No. ,the copy of same be attached with the application
- 4.The earnest Money shall be deposited duly pledged in favour of executive Engineer, Chamba Division HPPWD Chamba and cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected .
- 5.The contractor /firms are requested to insert the rate of each item in works as well as in figures failing which XEN reserves the right to accept/reject any tender without assigning any reasons at any stage.

Executive Engineer,
Chamba Division
HPPWD Chamba

No. PWC-WA-II/Contract/2022-23- 10405-454 Dated:- 18-11-2023

Copy forwarded to:-


- 1.The F.C-Cum-Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information, please.
2. The Engineer-in-Chief, HPPWD., Shimla
3. The Chief Engineer (KZ) HPPWD Dharamshala
- 4 The Superintending Engineer, 7th Circle HPPWD Dalhousie .
5. The Executive Engineer (IT Cell) office of Engineer-in-Chief HPPWD Shimla for uploading the NIT on the Departmental website.
- 6 All the Assistant Engineers under Chamba Division
7. All the Contractor working under this division
- 8 H.D.M./Supdt./Acctt. of this office.
9. Notice Board..

Executive Engineer,
Chamba Division
HPPWD Chamba

OFFICE OF
EXECUTIVE ENGINEER, CHAMBA DIVISION HPPWD CHAMBA
HIMACHAL PRADESH, PUBLIC WORKS DEPARTMENT CHAMBA
Phone No. 01899-222229 Email ee-cha-hp@nic.in

CERTIFICATE

Certified that tender of works , as called vide this office
letter No. PWC-WA-II/Contract/2022-23- 10405-454 Dated:18/ 11/2023
are emergent nature in exigency of public interest


Executive Engineer, ,
Chamba Division
Division, HPPWD

NAME OF WORK: ~ Rest. of RID on Ghoom Janjla Road Km 0/0-4/800
 (SH: Construction of PCC R/wall at RD 1/916.25 to 1/924.40) D.N.I.T

Sr. No.	Description of items	Quantity	In fig.	Rate		Unit	Amount
				In words			
1	Earthwork in excavation in all kind of soils for structures as per drawing and technical specifications Clause 1104 including setting out, construction of shoring and bracing, removal of slumps and other deleterious material and disposal upto all leads including dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lifts as per the direction of the Engineer in charge and other incidentals.	9.98	350.00	Three Hundred & Fifty Only		Per cum	3493-00
2	Providing and laying plain cement concrete 1:5:10 (one cement into five sand into ten graded stone aggregate forty millimetre nominal size) in open foundation complete as per drawing and HPWD technical specifications clause 802,803 and 1202 as per the direction of the Engineer in charge including carriage of materials within all leads and lifts and other incidentals.	69.31	4900.00	Forty Nine Thousand Only		Per cum	339619-00
3	Backfilling with granular material behind abutment, wing wall and return wall complete as per drawings and MORD technical specifications clause 1204.3.8	13.81	950.00	Nine Hundred Fifty Only		Per cum	13119-00
4	Providing weapholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) diameter PVC pipe extending through the full width of the structures with stop of 1(V):20(H) towards drawing face complete as per drawing and HP. PWD technical specifications clauses 614,709,1204.3.7	15	255.00	Two Hundred Ninety Five Only		Each	4425-00
TOTAL							360656-00

[Signature]

D.N.I.T approved for Rs 360656/- only

Executive Engineer
 Ganga Division
 HPWD, CHAMBA

2

D.H.1.T

NAME OF WORK: RESTO of R/D CHANED BHANOTHA ROAD Km 010 to 810
 SH: Construction of PCC R/wall at RD 01090 TO 0105.00

Estimated cost: 379037/-
 Earnest money: 7580/-
 Time Limit: One Month

Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
	Earthwork in excavation in all kind of soils for structures as per drawing and technical specifications Clause 1104 including setting out, construction of shoring and bracing, removal of slumps and other deleterious material and disposal upto all leads including dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lifts as per the direction of the Engineer in charge and other incidentals..	30.82	350.00	Three Hundred & Fifty Only	Per cum	10787.00
	Providing and laying plain cement concrete 1:5:10 (one cement isto five sand isto ten graded stone aggregate forty millimetre nominal size) in open foundation complete as per drawing and HPPWD technical specifications clause 802,803 and 1202 as per the direction of the Engineer in charge including carriage of materials within all leads and lifts and other incidentals.	70.05	4900.00	Forty Nine Thousand Only	Per cum	3,43,245.00
	Backfilling with granular material behind abutment, wing wall and return wall complete as per drawings and MORD technical specifications clause 1204.3.8	19.80	950.00	Nine Hundred Fifty Only	Per cum	18,810.00
	Providing weapholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) diameter PVC pipe extending through the full with of the structures with slop of 1(V):20(H) towards drawing face complete as per drawing and HP. PWD technical specifications clauses 614,709,1204.3.7	21	295.00	Two Hundred Ninety Five Only	Each	6195.00
	TOTAL					3,79,037.00

D.H.1.T approved for Rs 379037 only

Executive Engineer
 Charge Division
 H.P.W.D. CHAMBA

Assistant Engineer
 Charge PWD P.W. N.H.T
 CHAMBA

DNIT
SCHEDULE OF QUANTITIES

Estimated Cost: Rs. 284560/-
Earnest Money :- Rs. 5700/-
Time Limit :- One month

Name of work:- Repair of Ambedkar Bhawan Library Building at Dharog Chamba (SH:- P/L Floor tile, plastering, Shutter work, Putty)

Sr. No	Description of Work / Item (S)	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Providing and laying vitrified floor tiles double charged size of 600 x 600 mm (six hundred into six hundred millimetre) of Kazaria/ Somany/ Jonhson/Orient-Bell in flooring (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm (twenty millimetre) thick cement mortar 1:4 (one cement isto four coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm (three point three kilogram/ per square metre) including grouting the joints with white cement and matching pigments etcetera complete as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	114.30	1700.00	Rupees One Thousand Seven Hundred Only	Per Square Metre	194310.00
2	Providing & fixing 40 mm (forty millimetre) thick second class deodar wood shutter with pannel of 12 mm thick (twelve millimetre) phenol bonded pre-laminated board (both side) particle board paneled ISI marked No. IS-12823 including black enamel iron butt hinges with necessary screws complete as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	10.80	4800.00	Rupees Four Thousand Eight Hundred Only	Per Cubic Metre	51840.00
3	6mm (six millimetre) thick cement plaster to ceiling in cement mortar 1:3 (one cement isto three sand) as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	90.00	160.00	Rupees One Hundred & Sixty Only	Per square metre	14400.00
4	Applying Birta white/J.K wall care putty over plastered surface after thoroughly brushing the surface free from mortar drops, dust loose materials and other foreign matter sand papered smooth to give final matter finish to the surface complete as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	320.13	75.00	Rupees Seventy Five Only	Per Square Metre	24010.00
Total						284560.00

DNIT approved for Rs 284560/-only.


Engineer
Sd/- Division P.C.
Muzaffargarh

Executive Engineer
Chamba Division
H.P.P.W.D. CHAMBA

Draft Schedule of Quantity

Name of work :- Construction of Link road to village Deri Km. 0/0 to 2/460 (SH:- Construction of wire crates at RD. 0/150 to 0/170)

Estimated Cost:- Rs. 490875/-

Earnest Money:- Rs. 9820/-

Time Limit One month

S.No.	Descriptions of Item.	Qty.	Rate		Unit	Amount
			In fig	In words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material as per design including carriage of material within all leads and lifts and as per the direction of the engineer-in-charge and other incidentals.	90.00	350.00	Rupees Three hundred fifty only.	Per Cubic Metre	31500.00
2	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 including carriage of materials within all leads and lifts and other incidentals as per the directions of Engineer-in-Charge.	187.50	2450.00	Rupees two thousand four hundred fifty only.	Per Cubic Metre	459375.00
Total						490875.00

Draft approved for Rs. 490875/- only.

Assistant Engineer
Chamba Sub Division No. 10
H P. P. W. D. Chamba

Executive Engineer,
Chamba Division
HPPWD Chamba

DNIT

Name of work: Restoration of Rain damages on Parel Kohlari road Km. 0/0 to 12/500 (SH:- C/o P.C.C. Retaining walls at various RD's)

Estimated Cost:- 499964/-

Earnest Money:- 10000/-

Time Limit One month

S.No.	Descriptions of Item.	Qty.	Rate		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all kind of soil for structures as per drawing and technical Specification Clause 1104 including setting out, construction of shoring and bracing, removal of slumps and other deleterious material and disposal up to all leads including dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lifts as per the directions of Engineer-in-Charge and other incidentals	45.01	350.00	Rupees Three hundred fifty only	Per Cubic Metre	15754.00
2	Providing and laying cement concrete 1:5:10 (One cement is to five sand is to Ten graded crushed stone aggregate 40mm (forty millimeter) nominal size open foundation complete as per drawing and technical specification clauses- 802, 803, 1202 and 1203 or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental.	93.05	4900.00	Rupees Forty nine thousand only	Per Cubic Metre	455945.00
3	Backfilling with granular material behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 within all leads and lifts as per the directions of Engineer-in-Charge and other incidentals	22.30	950.00	Rupees Nine hundred fifty only	Per Cubic Metre	21185.00
4	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3 within all leads and lifts as per the directions of Engineer-in-Charge and other incidentals	24.00	295.00	Rupees Two hundred ninety five only	Per Cubic Metre	7080.00
Total						499964.00

DNIT Approved for Rs 499964/- only

Assistant Engineer,
Chamba Sup Division No-II
H.P.P.W.D. Chamba (H.P.)

Executive Engineer,
Chamba Division,
HP:PWD Chamba

DNIT

Name of work : Restoration of Rain damages on Patel Kohlari road Km. 0/0 to 12/500 (SH.- C/o P.C.C. Retaining walls at various RD's)

Estimated Cost:- 499964/-
Earnest Money:- 10000/-
Time Limit One month

S.No.	Descriptions of Item.	Qty.	Rate		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all kind of soil for structures as per drawing and technical Specification Clause 1104 including setting out, construction of shoring and bracing, removal of slumps and other deleterious material and disposal up to all leads including dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lifts as per the directions of Engineer-in-Charge and other incidentals	45.01	350.00	Rupees Three hundred fifty only	Per Cubic Metre	15754.00
2	Providing and laying cement concrete 1:5:10 (One cement is to five sand is to Ten graded crushed stone aggregate 40mm (forty millimeter) nominal size open foundation complete as per drawing and technical specification clauses- 802, 803, 1202 and 1203 or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental.	93.05	4900.00	Rupees Forty nine thousand only	Per Cubic Metre	455945.00
3	Backfilling with granular material behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 within all leads and lifts as per the directions of Engineer-in-Charge and other incidentals	22.30	950.00	Rupees Nine hundred fifty only	Per Cubic Metre	21185.00
4	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3 within all leads and lifts as per the directions of Engineer-in-Charge and other incidentals	24.00	295.00	Rupees Two hundred ninety five only	Per Cubic Metre	7080.00
Total						499964.00

DNIT Approved for Rs 499964/- only

Assistant Engineer,
Chamba Sub Division No.-II
H.P.W.D. Chamba (I.L.P.)

Executive Engineer,
Chamba Division,
HP:PWD Chamba

Draft Schedule of quantities

Name of Work: Restoration of rain damages on Sahoo parroth akurena Dhar road km 0/0 to 6/700 (SH-Const. of PCC retaining wall at RD 2/150 to 2/160)

Estimated Cost: Rs. 1,94,630/-
 Earnest Money : Rs. 3900/-
 Time Limit : One Month.

Sr.No	Description of Work / Item (S)	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated Suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeter). Compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	15.00	350.00	Rupees Three Hundred & fifty Only	Per Cubic Metre	5250.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete 1:5:10 (One cement is to five sand is to ten graded crushed stone aggregate 40mm (forty millimeter) nominal size in or under water including pumping or bailing out water) surface and sub soil water), dewatering for all heights / depths and any quantum of water including removal of slush which may arise at the time of laying under water for all heights / depths, including the cost of form work and curing for 14 (fourteen) days complete in Retaining walls and Breast walls etcetera as per drawings and MORD technical specification section 802.500 and 1200 and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government	35.60	4900.00	Rupees four Thousand Nine Hundred Only	Per Cubic Metre	17440.00
3	Back filling with granular material behind abutments, return walls, wing walls and retaining walls etc. complete as per drawings and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	12.00	950.00	Rupees Nine Hundred & fifty Only	Per Cubic Metre	11400.00
4	Providing 100mm (Hundred millimeter) diameter PVC pipe Weep holes in brick masonry/stone masonry, plain/reinforced concrete abutments, wing walls return walls and retaining /breast walls etc., extending through the full width of the structure with slope of 1 (V) : 20 (H) (one vertical is to twenty horizontal) towards drawing face complete as per drawings and MORD technical specifications clause 614, 709, 1204.3.7 or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	12.00	295.00	Rupees Two Hundred & Ninety Five Only	Each	3540.00
Total:						194630.00

DNT approved for Rs 194630/- only

Executive Engineer
 Chamba Division
 H.P.W. & CHAMBA

2

Draft Schedule of quantities

Name of Work:- Restoration of rain damages on Sahoo paroth akurena Dhar road km 0/0 to 6/700 (SH:-Const. of PCC retaining wall at RD 2/630 to 2/640)

Estimated Cost: Rs. 3,88,110/-
Earnest Money :- Rs. 7800/-
Time Limit :- One Month.

Sl.No	Description of Work / Item (S)	Qty.	In fig.	Rate		Unit	Amount
				In words			
1	Earth work in excavation for all type of structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORO technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated Suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimetre). Compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	38.40	350.00	Rupees Three Hundred & Fifty Only		Per Cubic Metre	13440.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete 1:5:10 (One cement is to five sand is to ten graded crushed stone aggregate 40mm (forty millimetre) nominal size in or under water including pumping or bailing out water) surface and sub soil water), dewatering for all heights / depths and any quantum of water including removal of slush which may arise at the time of laying under water for all heights / depths, including the cost of form work and curing for 14 (fourteen) days complete. Retaining walls and Breast walls etcetera as per drawings and MORO technical specification section 802.900 and 1200 and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	72.70	4900.00	Rupees Four Thousand Nine Hundred Only		Per Cubic Metre	356230.00
3	Back filling with granular material behind abutments, return walls, wing walls and retaining walls etc. complete as per drawings and MORO technical specification clause 1204.3.8 or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	13.20	950.00	Rupees Nine Hundred & Fifty Only		Per Cubic Metre	12540.00
4	Providing 100mm (Hundred millimetre) diameter PVC pipe Weep holes in brick masonry/stone masonry, plain/reinforced concrete abutments, wing walls return walls and retaining /breast walls etc., extending through the full width of the structure with slope of 1 (V) : 20 (H) (one vertical is to twenty horizontal) towards drawing face complete as per drawings and MORO technical specifications clause 614, 709, 1204.3.7 or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	20.00	295.00	Rupees Two Hundred & Ninety Five Only		Each	5900.00
Total							388110.00

DNR approved for Rs 388110/-only

Executive Engineer
Chamara Division
H.P.W. CHAMBA

Draft schedule of quantities

Name of Work: **ALRA 110 Non Residential Guiding under Chamba Division, H.P. D**
(SMI- Repair of Pao Canton Chamba Division)

Estimated Cost: Rs. **1,75,899/-**
 Earnest Money :- Rs. **3600/-**
 Time Limit :- **one Month**
 Amount

S.No.	Item	Qty.	Unit	Rate		Amount
				In fig.	In words.	
1	Dismantling cement concrete floors upto floor two level including stacking of serviceable materials and disposal of un-serviceable materials within 20 metres lead including cartage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	58.92	Per square metre	55.00	Rupees Fifty Five Only	3241.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete 1:6:12 (one cement isto four sand isto eight graded crushed stone aggregate 40 mm (forty millimetre) nominal size) and curing complete excluding the cost of form work in foundation and plinth including cartage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	0.68	Per cubic metre	4250.00	Rupees Four Thousand Two Hundred & Fifty Only	2890.00
3	15 mm (fifteen millimetre) cement plaster in single coat on rough side of brick / concrete / stone masonry for interior plastering upto floor all levels including arses, internal rounded angle, chamfer and / or rounded angle not exceeding 80mm (eighty millimetre) in girth and finished even and smooth in cement mortar 1:6 (one cement isto six sand) as per the directions of the Engineer-in-charge including cartage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	69.12	Per square metre	275.00	Rupees Two Hundred & Seventy Five Only	19008.00
4	Providing and laying 10mm (ten millimetre) thick water proof stain and impact resistant heavy duty, Matt finish vetified tiles Orient Bell / Nitco / Kalaria of equivalent shade 600x600x10mm (six hundred into six hundred into ten millimetre) size manufactured of approved shade and colour in flooring, treads of steps and landing laid over 12mm (twelve millimetre) thick cement mortar 1:3 (one cement isto three sand) with 1st quality granite border jointed with cement slurry mixed with pigment to match the shade of tiles as required complete including cartage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	19.63	Per square metre	1650.00	Rupees One Thousand Six Hundred & Fifty Only	32390.00
5	Coloured glazed tiles 6mm (six millimetre) thick and size of 30 x 45 cm of Orient Bell / Nitco / Kalaria make in skirting or risers of steps and dado 12mm (twelve millimetre) thick cement mortar 1:3 (one cement isto three sand) finished with flush pointing in white cement as per the directions of the Engineer-in-charge including cartage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	32.25	Per Square metre	1500.00	Rupees One Thousand Five Hundred Only,	48375.00

6	Providing and laying 19mm (nineteen millimetre) thick Polished Granite stone in kitchen worktop in, required design and patterns, in liner as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm (eighteen millimetre) thick stone slab over 20 mm (twenty millimetre) (average) thick base of cement mortar 1:4 (one cement isto four coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and polishing etcetera all complete as specified and as directed by the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	4.12	Per Square metre	4550.00	Rupees Four Thousand Five Hundred & Fifty Only	18746.00
7	Providing and fixing 19mm (nineteen millimetre) thick water proof commercial board shutters for cup boards with butt joints and fixing with nail and screws, hinges etc. complete as per the directions of the Engineer-in-charge including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	7.24	Per Square metre	2050.00	Rupees Two Thousand & Fifty Only	14842.00
8	Providing second class Kail wood work in frames of doors, windows, clerestory windows and other frames wrought, framed and fixed in position complete including carriage of material within all leads and lifts and as per the direction of the engineer-in-charge and other incidentals including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	0.015	Per cubic metre	95000.00	Rupees Ninety Five Thousand Only	1425.00
9	Providing & fixing 40mm (forty millimetre) 1st class Kail wood in doors, windows and clerestory window shutters including hinges complete as per the direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	1.20	Per Square metre	4100.00	Rupees Four Thousand One Hundred Only	4920.00
10	Painting two coats (excluding priming coat) on new wood and wood based surfaces with enamel paint to give an even shade including cleaning the surface of dirt, dust and other foreign matter, sand papering and stopping with enamel paint other than white as per the directions of the Engineer-in-charge including carriage of material within all leads and lifts, GST and other incidentals.	31.47	Per Square metre	105.00	Rupees One Hundred & Five Only	3304.00
1	Finishing walls with weather proof exterior grade emulsion of approved design (Apexulima) or its equivalent on undecorated wall surface (two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc. including sand paper smooth complete as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	25.20	Per Square metre	115.00	Rupees One Hundred & Fifteen Only	2898.00

12	Providing and fixing stainless steel Kitchen sink of Diamond/ Unk without drain board 610x510mm (six hundred ten into five hundred, ten millimetre) bowl depth 200mm (two hundred millimetre) of ISI 304 (18/8) as per IS: 13983 with CI brackets and stainless steel plug 40mm (forty millimetre) including painting of fitting and brackets, cutting and making good the walls wherever required or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	1.00	Each	3500.00	Rupees Three Thousand Five Hundred Only	3500.00
13	Providing and fixing C.P. brass waste of 32mm (thirty two millimetre) dia size for sink or wash basin as per the directions of the Engineer-in-charge including carriage of material within all leads and lifts including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	1.00	Each	250.00	Rupees Two Hundred & Fifty Only	250.00
14	Providing and fixing 15mm (fifteen millimetre) nominal bore C.P. brass bib cock of (heavy duty) ISI marked IS No. 8931 & 8934 approved, quality conforming to IS: 8931 or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	1.00	Each	950.00	Rupees Nine Hundred & Fifty Only	950.00
15	Providing and fixing to wall, ceiling and floor galvanised mild steel tubes (medium grade) tube fittings and clamps including making good the wall, ceiling and floor 15 mm (fifteen millimetre) nominal bore within direction of the Engineer-in-charge including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	18.00	Per running metre	370.00	Rupees Three Hundred & Seventy Only	6660.00
16	Government Providing and placing on terrace (at all floor levels) polyethylene water storage tank Sintex marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fitting and base support for tank complete as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	1.00	Each	5200.00	Rupees Five Thousand Two Hundred Only	5200.00
17	Providing and fixing 15mm (fifteen millimetre) nominal bore C.P. brass stop cock (concealed) of (heavy duty) makes ISI marked IS No. 8931 & 8934 or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	2.00	Each	1100.00	Rupees One Thousand One Hundred Only	2200.00
18	Steel work riveted, bolted or welded in built up section, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete as per the direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	50.00	Per Kilogram	102.00	Rupees One Hundred & Two Only	5100.00
Total						175899.00

DUIT Approved for Rs 175899/- only.

Executive Engineer
Sanitation Division
H.P.W.D. CHANBA