


HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
NOTICE INVITING TENDER

Sealed items rate tender on form 6&8 are invited by the Executive Engineer HPPWD Kotla Behar Division Kotla Behar for the following works from the approved and eligible contractors enlisted with HPPWD Department so as to reach in this office on dated 10.11.2023 up to 10.30AM and the same will be opened on the same day at 11.30 AM in the presence of contractors /firms or their authorized representative. The application for purchase of tender forms will be received up to 2.00 PM on dated 8.11.2023 and tender forms can be obtained from this office against cash payment (nonrefundable) on 9.11.2023 from 10.00 AM to 2.00 PM and no tender form shall be issued by the post. The amount of earnest money in shape of FDR of any nationalized bank in H/P duly pledged in the Name of Executive Engineer HPPWD Kotla Behar Division Kotla Behar

The conditional tender and tender received without earnest money (FDR) will be rejected and if holiday declared by the Govt. on the above date due to any reasons the tender shall be received and opened on the next working day. The undersigned reserved the right to rejected tender without assigned any reasons, .

Sr No	Name of work	Estimated cost	Earnest money	Time Limit	Cost of tender form	Form No
1	Restoration of Damages due to OFC on Gurala Ro Didian Road Km 0/0 to 3/800 (SH:- C/O R/wall at Rd 3/040 to 3/062 Deposit work	451950	9000	Two Month	350	6&8
2	Restoration of damages due to OFC Kalehar To Jambrian Da Gharat Road Km 0/0 to 1/525 (SH:- P/L Interlocking paver Block at Rd 0/0 to 0/045 & 0/150 to 0/195 (Deposit work)	436249	9000	Two Month	350	6&8
3	Restoration of Damages Kaloha Pragpur Dhaliara Dada Siba Sansarpur Terrace Road Km 0/0 to 9/00 (SH:- C/O R/wall at Rd 1/495 to 1/510)	494255	10000	Two Month	350	6&8

1) Certified that tender of above works are being called in Exigency of public interest ,

  
Executive Engineer,  
Kotla Behar Division HPPWD.,  
Kotla Behar

NO.PWD/KB/CB/TENDER 2023-24 -

4143-48

DATED 27.10.2023


information please.

Copy to the F.C-Cum-Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla -2 for favour of

Copy to the Engineer-in-Chief HPPWD Shimla for information please.

Copy to the Chief Engineer (KZ) HPPWD Dharamshala for favour of information please.

Copy to the Superintending Engineer 9<sup>th</sup> Circle HPPWD Nurpur for favour of information please.

  
Executive Engineer,  
Kotla Behar Division HPPWD.,  
Kotla Behar



## BILL OF QUANTITY

Name of work:- Restoration of damages due to OFC on Gurula to Didian road Km. 0/0 to 3/800 (SH:- Const. of R/wall at RD. 3/040 to 3/062) (Deposit work).

JOB NO. 1  
Estimate Cost :- Rs. 451950.00  
Earnest Money :-Rs. 9000.00  
Time Limit :- Two Month.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps, and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	44.80 Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:5:10 (One cement isto five sand isto ten graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying under water for all heights/depts and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900,1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government	120.73 Cubic metre			Per cubic metre	
3	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	15.18 Cubic metre			Per Cubic metre	
4	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P V C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614.709,1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials, with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	66.00 Number			Each	
<b>TOTAL</b>						

Executive Engineer,  
Kota Behar Division,  
HPPWD Kota Behar.



# BILL OF QUANTITY

Name of work:- Restoration of damages due to OFC on Kalehar to Jambrian da Gharat road Km. 0/0 to 1/525 (SH:- P/L Interlocking Paver Block at RD. 0/00 to 0/045  
0/150 to 0/195 ) (Deposit work).

JOB NO. 2  
Estimate Cost :- Rs. 436249.00  
Earnest Money :- Rs. 9000.00  
Time Limit :- Two Month.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	51.34 Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade-M20 (M-Twenty) Nominal mix 1:2:4 (one cement isto two sand isto four graded crushed stone aggregate (40mm) forty millimeter nominal size) in or under water in open foundation for all types of structure and the like in Catchpit flooring etcetera, including cost of form work and curing complete as per drawing and MORD technical specification section 800, 900 & 1200 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water for all heights/depths and any quantum of water complete including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	7.63 Cubic metre			Per Cubic metre	
3	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	24.30 Cubic metre			Per Cubic metre	
4	Providing and laying of inter locking concrete paver blocks make of NITC/NITCO/HPPWD approved having thickness 80mm (eighty millimeter) Grade M-40 IS Code-15658:2006 and Technical Specification Clause 1504 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	243.00 Square metre			Per square metre	
TOTAL						

Executive Engineer,  
Kotla Behar Division,  
HPPWD Kotla Behar.



# BILL OF QUANTITY

Name of work:- Restoration of damages Kaloha Pragpur Dhaliara Dada Siba Sansarpur Terrace Road km 0/0 ot 9/00 (Sh:- C/O R/wall at Rd 1/495 to 1/51

Estimate Cost :- Rs. 494255  
Earnest Money :-Rs. 10000  
Time Limit :- Two Month.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps, and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	58.35 Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:5:10 (One cement isto five sand isto ten graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying under water for all heights/depts and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical Specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	131.85 Cubic metre			Per cubic metre	
3	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	32.40 Cubic metre			Per Cubic metre	
4	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P V C, pipe Weep Holes in brick masonry/stone masonry plan/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614, 709, 1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	48.00 Number			Each	
TOTAL						

Executive Engineer  
Kotla Behar Division  
HPPWD Kotla Behar