



Office of  
**EXECUTIVE ENGINEER (KULLU DIVISION)**  
**H.P. PUBLIC WORKS DEPARTMENT, KULLU-175101**  
**FAX: 01902-222571, E.mail. ee-kul2-hp@nic.in**

No.PW/KD/TA/Tender/2023-2024-18754-63

Dated: 1-11-2023


To

The Executive Engineer, I.T. Cell,  
Nigam Bihar Shimla-2.

**Subject:- Publishing of Notice inviting tender.**

Enclosed please find herewith copies of notice inviting tender for the up loading on department website 13.11.2023 as per notification issued by Secretary (PW) to the Govt. of HP Shimla vide letter No.PBW(S)A(3)1/2020 dated 16.07.2021. As per works mentioned in the Tender Notice is urgent nature of work in the public interest.


DA/As above.

  
Executive Engineer,  
Kullu Division,  
HP PWD, Kullu.

Copy alongwith notice inviting tender is forwarded to the following for information and necessary action.

1. Engineer-in-Chief, HP.PWD, Shimla.
2. Chief Engineer, (MZ) HP.PWD, Mandi.
3. Superintending Engineer, 6<sup>th</sup> Circle HP.PWD, Kullu.
4. Supdt./DAO/HDM of this office.
5. Notice Board.

DA/Nil.

  
Executive Engineer,  
Kullu Division,  
HP PWD, Kullu.

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
NOTICE INVITING TENDER**

The Executive Engineer, Kullu Division HP.PWD, Kullu on behalf of the Government of Himachal Pradesh invites the **offline tender i.e. on percentage rates** for the following works from the eligible contractors/Firms registered with HP.PWD, department, so as to reach in the office as per time schedule given below:-

1	Date of receipt of application for tender form.		10.11.2023 upto 4:00 PM		
2	Date of issue/sale of tender form.		10.11.2023 upto 4:00 PM		
3	Date of receipt of tender.		13.11.2023 upto 10:30 AM		
4	Date of opening tender.		13.11.2023 upto 11:00 AM		
Sr. No.	Name of work	Estimated cost	Earnest money	Time limit	Cost of form
1	2	3	4	5	6
1	Restoration of rain damages on various road under Bhunter-2 Section (SH:- Hiring of Tipper for removal of slips/muck/debries at various RDs) Job No.1.	1,03,811/-	2,100/-	45 days	350/-
2	Restoration of flash flood on Bhunter Manikaran road Km. 0/0 to 1/610 (SH:- Construction of embankment with approved material at RD 1/040 to 1/050).	4,91,102/-	9,900/-	7 days	350/-
3	Restoration of flash flood on Bhunter Manikaran road Km. 0/0 to 1/610 (SH:- Construction of embankment with approved material at RD 0/995 to 1/010).	4,95,090/-	10,000/-	7 days	350/-
4	Restoration of flash flood on Bhunter Manikaran road Km. 0/0 to 1/610 (SH:- Construction of embankment with approved material at RD 1/140 to 1/155).	4,96,328/-	10,000/-	7 days	350/-
5	Restoration of flash flood on Bhunter Manikaran road Km. 0/0 to 1/610 (SH:- Construction of embankment with approved material at RD 1/010 to 1/020).	4,92,340/-	9,900/-	7 days	350/-
6	RRD on Dohranallah to Chestha road Km. 0/0 to 8/760 (SH:- C/O Retaining wall and Pushta at RD 7/215 to 7/227.50) Job No.1.	4,63,302/-	9,300/-	Two months	350/-
7	RRD on Dohranallah to Chestha road Km. 0/0 to 8/760 (SH:- C/O Retaining wall and Pushta at RD 7/227.50 to 7/240) Job No.2.	4,63,490/-	9,300/-	Two months	350/-
8	RRD on Manikaran Barshaini road Km. 0/00 to 15/00 (SH:- Construction of retaining wall at RD 9/317.50 to 9/325).	4,98,489/-	10,000/-	Two months	350/-
9	RRD on Manikaran Barshaini road Km. 0/00 to 15/00 (SH:- Construction of retaining wall at RD 9/310 to 9/317.50).	4,97,956/-	10,000/-	Two months	350/-
10	RRD on Bhunter Manikaran road Km. 1/610 to 35/110 (SH:- Providing and laying WBM Grade-III in alternate road (At RD 25/00) Km. 0/00 to 0/500).	4,89,750/-	10,000/-	Two months	350/-
11	RRD on Bhunter Manikaran road Km. 1/610 to 35/110 (SH:- Construction of retaining wall at RD 22/905 to 22/921.25).	4,93,233/-	10,000/-	Two months	350/-
12	RRD on Bhunter Manikaran road Km. 1/610 to 35/110 (SH:- Construction of retaining wall at RD 22/921.25 to 22/937.50).	4,98,545/-	10,000/-	Two months	350/-
13	RRD on Bhunter Manikaran road Km. 1/610 to 35/110 (SH:- Construction of retaining wall at RD 27/755 to 27/763).	3,42,388/-	7,000/-	Two months	350/-

14	Restoration of rain damages on Ratocha Dhara road Km. 0/00 to 5/00 (SH:- Construction of Breast wall at RD 0/400 to 0/435).	4,88,331/-	10,000/-	Two months	350/-
15	Restoration of rain damages on Sharni to Pini road (SH:- Construction of Breast wall at RD 11/400 to 11/420).	4,35,277/-	8,800/-	Two months	350/-
16	RRD on Work Shop Gadouri road Km. 0/00 to 0/900 (SH:- C/O U-shape drain & V-shape drain in Km. 0/420 to 0/470 (both side) and repair of drain).	3,70,136/-	7,500/-	Two months	350/-
17	Restoration of rain damages on Buins Bai to Bhullang road Km. 0/0 to 11/020 (SH:- C/O wire crated retaining wall CCC Toe wall Km. 8/350 to 8/375).	4,84,738/-	10,000/-	Two months	350/-
18	Restoration of rain damages on Buins Bai to Bhullang road Km. 0/0 to 11/020 (SH:- C/O wire crated retaining wall CC Toe wall Km. 6/720 to 6/745).	4,88,230/-	10,000/-	Two months	350/-
19	RRD on Lashani to Sangtehar road Km. 0/00 to 3/660 (SH:- C/O PCC R/wall at RD 2/256 to 2/272).	4,97,268/-	10,000/-	Two months	350/-
20	RRD on Lashani to Sangtehar road Km. 0/00 to 3/660 (SH:- C/O PCC R/wall at RD 2/240 to 2/256).	4,97,776/-	10,000/-	Two months	350/-
21	Restoration of rain damages on Jungrubhu Thana to Tosh road Km. 0/0 to 1/950 (SH:- C/O crated R/wall of damaged road at RD 1/890 to 1/938.75 under LADA Deposit (Phase-VII) Job No.4.	4,92,402/-	10,000/-	Two months	350/-
22	RRD on Bhunter Manikaran road Km. 1/610 to 35/110 (SH:- Providing and laying GSB & WBM Grade-II at RD 4/390 to 4/530).	3,95,841/-	8,000/-	Two months	350/-
23	RRD on Darka Gadiara road Km. 0/00 to 1/800 (SH:- C/O wire crated R/wall at RD 0/335 to 1/350).	4,49,384/-	9,000/-	Two months	350/-
24	RRD on Darka Gadiara road Km. 0/00 to 1/800 (SH:- C/O wire crated at RD 0/350 to 0/365).	4,48,726/-	9,000/-	Two months	350/-
25	A/R and M/O District Sports office at Dhalpur Kullu (SH:- Painting roof and outer wall etc.).	3,36,766/-	6,800/-	Two months	350/-
26	RRD on Bhunter Manikaran road Km. 1/610 to 35/110 (SH:- Providing and laying BM 50mm thick at RD 4/390 to 4/530).	4,26,546/-	8,600/-	Two months	350/-
27	Restoration of rain damages on Sarsari Chong road Km. 0/00 to 5/300 (SH:- Construction of R/wall at RD 3/620 to 3/640).	4,76,260/-	9,600/-	Two months	350/-
28	RRD on Bhunter Manikaran road Km. 1/610 to 35/110 (SH:- Providing and laying BM 50mm thick in the alternate road at (RD 25/00) Km. 0/00 to 0/170).	4,40,039/-	9,000/-	Two months	350/-
29	Construction of welcome gate for Kullu Town neat at Bhootnath Bridge District Kullu (HP) (SH:- C/O welcome gate) Job No.4.	3,23,925/-	6,500/-	Two months	350/-
30	Construction of welcome gate for Kullu Town neat at Bhootnath Bridge District Kullu (HP) (SH:- C/O welcome gate) Job No.3.	4,99,161/-	10,000/-	Two months	350/-

31	Construction of proposed parking opposite to Bus Stand Sarwari Kullu (SH:- Leveling of parking ground) Job No.3.	4,94,014/-	10,000/-	Two months	350/-
32	Construction of proposed parking opposite to Bus Stand Sarwari Kullu (SH:- Leveling of parking ground) Job No.4	4,94,014/-	10,000/-	Two months	350/-
33	Restoration of rain damages on Sangtehar to Birni road Km. 0/0 to 4/200 (SH;- Removal of slips at various RDs and blocked culvert in Km. 0/00 to 2/00) Job No.1.	4,42,879/-	9,000/-	Two months	350/-
34	Restoration of rain damages on Sangtehar to Birni road Km. 0/0 to 4/200 (SH;- Removal of slips at various RDs and blocked culvert in Km. 0/00 to 2/00) Job No.2.	4,42,879/-	9,000/-	Two months	350/-
35	Restoration of rain damages on flash flood on Bhunter Manikaran road (SH:- Hiring of water tanker for sprinkling for damaged portion at Km. 0/0 to 1/850) Job No.1.	2,07,000/-	2,500/-	Two months	350/-
36	Restoration of rain damages on flash flood on Bhunter Manikaran road (SH:- Hiring of water tanker for sprinkling for damaged portion at Km. 0/0 to 1/850) Job No.2.	2,07,000/-	2,500/-	Two months	350/-
37	Balance work of Additional Accommodation in GSSS (Girls) at Sultanpur District Kullu (SH:- P/F wooden door/window frames, fixing paneled door shutter, galazed door shutter and wire gauge shutter etc.) Job No.1.	4,38,712/-	8,800/-	Two months	350/-
38	Balance work of Additional Accommodation in GSSS (Girls) at Sultanpur District Kullu (SH:- P/F wooden door/window frames, fixing paneled door shutter, galazed door shutter and wire gauge shutter etc.) Job No.2.	4,87,656/-	9,800/-	Two months	350/-
39	Restoration of rain damages on Dohra Nallah to Chestha road Km. 0/0 to 8/670 (SH:- Removal of slips/debries at various RDs).	4,55,427/-	10,000/-	One month	350/-
40	Restoration of rain damages on Chharour Nallah to Bharain road Km. 0/0 to 4/200 (SH:- Removal of slips/debries at various RDs).	4,55,406/-	10,000/-	Two months	350/-
41	Restoration of rain damages on Kolibehar to Barahar Km. 0/00 to 6/00 (SH:- Construction of PCC retaining wall on PCC pushta at RD 1/190 to 1/200).	4,88,801/-	9,800/-	Two months	350/-
42	Restoration of rain damages on Kolibehar to Barahar Km. 0/00 to 6/00 (SH:- Constuction of PCC Retaining wall on PCC pushta at RD 1/180 to 1/190).	4,88,740/-	9,800/-	Two months	350/-
43	RRD on Lashani to Sangtehar road Km. 0/00 to 3/660 (SH:- Formation cutting in Km. 0/927 to 1/115).	2,83,007/-	5,800/-	Two months	350/-
44	Restoration of rain damages on Badah Pahnallah to Shillirajgiri (Janahal) road (SH:- Removal of slips at various RD's).	4,91,368/-	10,000/-	Two months	350/-
45	Restoration of rain damages on Badah Pahnallah to Shillirajgiri (Janahal) road (SH:- Removal of slips at various RDs).	4,99,034/-	10,000/-	Two months	350/-



46	Restoration of rain damages on Chharour Nallah to Kashawari road Km. 0/00 to 8/020 (SH:- Construction of PCC Toe wall at Km. 0/270 to 0/090).	3,25,040/-	6,600/-	Two months	350/-
47	Restoration of rain damages on Tapoo Bridge (SH:- P/L 1:2:4 to protect the bridge abutment and CC 1:3:6 for pavement on approach road).	4,87,211/-	9,800/-	Two months	350/-
48	Restoration of rain damages on Badah Pahnallah to Shillirajgiri (Janahal) road Km. 0/00 to 19/700 (SH:- Construction of crated Breast wall at Rd 13/420 to 13/470).	4,49,353/-	9,000/-	Two months	350/-
49	Restoration of rain damages on Badah Pahnallah to Shillirajgiri (Janahal) road Km. 0/00 to 19/700 (SH:- Construction of Breast wall on pushta at RD 11/470 to 11/492).	4,91,530/-	10,000/-	Two months	350/-
50	C/O Parking at Khoriropa (SH:- Metalling and Tarring).	2,58,910/-	5,200/-	Two months	350/-
51	RRD on Bhoot Nath Bridge (SH:- Metalling and Tarring on Bus stand side approach Km. 0/0 to 0/125).8	4,99,737/-	10,000/-	Two months	350/-
52	A/R and M/O residential building under Kullu Division (SH:- Painting, distemping, P/L PVC mat in rooms and fixing view cutter on boundary wall and repairing old damaged door frames of type-V residence hostel Sarwari at Kullu).	4,98,100/-	10,000/-	Two months	350/-
53	Balance work of Additional Accommodation in Judicial Court Complex Kullu (SH:- P/L pavers around the new building etc.).	4,97,629/-	10,000/-	Two months	350/-
54	Balance work of Additional Accommodation in Judicial Court Complex Kullu (SH:- P/L Paneling in top floor, entry gallery, conference hall & p/f PVC mat etc.).	4,97,488/-	10,000/-	Two months	350/-
55	Special repair of Stage at Pradershni Ground Kullu (SH:- P/F 18mm thick ply board flooring over stage).	3,35,011/-	6,800/-	Two months	350/-

The tender documents shall be issued only to those contractor/firm who fulfill the following documents with the application.

1	The valid enlistment/Registration of contractor in Appropriate Class.
2	Permanent account No. (PAN No.).
3	G.S.T. No.
4	Earnest Money in the shape of National Saving certificate/time deposit account in the any of the post office in HP F.D.R. from any Nationalized Bank duly pleaded in favour of the Executive Engineer, Kullu Division HP.PWD, Kullu.
5	The earnest & cost of tender form for the above works should be submitted with the application for the purchase of the tender form. The application received without earnest money & cost of tender form shall summarily be rejected.
6	The offer of the tender shall remain valid upto 90 days after the opening of tender.
7	Ambiguous/telephonic conditional tenders of tender by fax/E-mail not be considered and will be summarily be rejected.
8	Executive Engineer, reserve the right to reject or cancel any or all tenders without assigning any reasons.
9	If the date given above happens to be holiday the same shall be processed on next working day.
10	The contractor/firm must quote their rates in words as well as in figures failing which XEN reserve the right to accept/reject any or all tenders.
11	The tender forms shall not be issued to those contractors/firms whose previous performance is not found satisfactory and who have not executed the previous awarded works within the stipulated period of completion.
12	One contractor shall not have more than two major works in hand at a time.
13	Work should be completed by the contractor within stipulated period.
14	The rates beyond over +5% will be rejected, besides this the Additional Performance security will have to borne @ 20% & 30% for unbalanced bid in case rates is lower than 10% but upto 20% & lower than 20% upto 30% respectively. The tender beyond the limit of -30% will also be excepted.

*[Signature]*  
Executive Engineer,  
Kullu Division,  
HP.PWD,Kullu.

Dated:-1-11-2023

No.PW/KD/TA/2023-2024-

18764-18863

Copy is forwarded to the following for information and necessary action:-

1. Engineer-in-Chief, HP.PWD, Shimla.
2. Chief Engineer, (MZ) HP.PWD, Mandi.
3. Superintending Engineer, 6<sup>th</sup> Circle HP.PWD, Kullu.
4. All the Executive Engineers, in HP.PWD,.
5. All the Assistant Engineers, working under this Division.
6. All the registered contractors, in HP.PWD.
7. Supdt./DA/HDM of this office.
8. Notice Board.

*[Signature]*  
Executive Engineer,  
Kullu Division,  
HP.PWD,Kullu.

# CERTIFICATE

It is certified that the above works are required to be carried out immediately being emergent nature of work in the public interest.

*[Signature]*  
**Executive Engineer,  
Kullu Division, *[Signature]*  
HP.PWD, Kullu.**

13/10/22

### SCHEDULE OF QUANTITY

Estimated cost:- 103811.00  
Earnest money :- 2,100.00

Time :- 45 Days

Name of work:- Restoration of Rain Damages on Various Roads under Bhuntar - 2 Section  
(Sub Head:- Hiring of Tipper for removal of slips /Muck / debris at various Rds) Job No-1

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Hiring of tipper in good condition of minimum 5.50 cubic metre carriage capacity on daily basis from 9.00 AM to 5.00 PM with hydraulic facility, jack facility for Carriage of slips and disposal of same at suitable dumping places including P.O.L. charges and wages of driver and other operational staff as per the direction and entire satisfaction of Engineer-in-charge.	45	2306.90	Rupees two thousand three hundred six and paise ninety only	Per days	103811.00
<b>Conditions</b>						
	1) The cost of P.O.L. will be borne by the contractor/ owner of the vehicle/ machine at his own cost.					
	2) The repair etc. will be got done by the contractor at his own cost					
	<b>Total:-</b>					<b>103811.00</b>

  
Executive Engineer,  
Kullu Division  
HP.PWD Kullu.

2

**Schedule of Quantity**

Name Of Work: Restoration of flush flood on Bhunter Manikaran road Km 0/0 to 1/610

Estimated cost 491102.00

Sub Head :- Construction of embankment with approved material at RD 1/040 to 1/050

Earnest Money 9900.00

Time 7 Days

S.N.	Description	Qty	Unit	Rate in		Amount
				In Figure	In words	
1	Construction of embankment with approved material obtained from borrow pits , transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 as per Technical Specification Clause 301.5 with in all leads and lift of material and as per direction of Engineer -In - Charge	892.75	Per Cubic Metre	550.10	Rupees five hundred fifty and paise ten only	491102.00
					<b>Total</b>	<b>491102.00</b>

  
Executive Engineer  
Kullu Division  
HPPWD Kullu



3

## Schedule of Quantity

Name Of Work: Restoration of flush flood on Bhuntar Manikaran road Km 0/0 to 1/610

Estimated cost

495090.00

Sub Head :-Construction of embankment with approved material at RD 0/995 to 1/010

Earnest Money

10000.00

Time

7 Days

S.N.	Description	Qty	Unit	Rate in		Amount
				In Figure	In words	
1	Construction of embankment with approved material obtained from borrow pits , transporting to site; spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 as per Technical Specification Clause 301.5 with in all leads and lift of material and as per direction of Engineer -In - Charge	900.00	Per Cubic Metre	550.10	Rupees five hundred fifty and paise ten only	495090.00
					<b>Total</b>	<b>495090.00</b>


  
Executive Engineer

Kullu Division

HPPWD, Kullu

4

**Schedule of Quantity**

Name Of Work: Restoration of flush flood on Bhunter Manikaran road Km 0/0 to 1/610

Sub Head :- Construction of embankment with approved material at RD 1/140 to 1/155

Estimated cost 496328.00

Earnest Money 100000.00

Time 7 Days

S.N.	Description	Qty	Unit	Rate in		Amount
				In Figure	In words	
1	Construction of embankment with approved material obtained from borrow pits , transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 as per Technical Specification Clause 301.5 with in all leads and lift of material and as per direction of Engineer -In - Charge	902.25	Per Cubic Metre	550.10	Rupees five hundred fifty and paise ten only	496328.00
<b>Total</b>						<b>496328.00</b>

  
 Executive Engineer  
 Kullu Division  
 HPPWD, Kullu

5

## Schedule of Quantity

Name Of Work: Restoration of flush flood on Bhuntar Manikaran road Km 0/0 to 1/610

Estimated cost

492340.00

Sub Head :- Construction of embankment with approved material at RD 1/010 to 1/020


Earnest Money

9900.00

Time

7 Days

S.N.	Description	Qty	Unit	Rate in		Amount
				In Figure	In words	
1	Construction of embankment with approved material obtained from borrow pits , transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 as per Technical Specification Clause 301.5 with in all leads and lift of material and as per direction of Engineer -In - Charge	895.00	Per Cubic Metre	550.10	Rupees five hundred fifty and paise ten only	492340.00
					<b>Total</b>	<b>492340.00</b>

  
 Executive Engineer  
 Kullu Division  
 HPPWD Kullu


6

**SCHEDULE OF QUANTITY**

Name of work:- RRD on Dohranallah to Cheshra road Km 0/0 to 8/760 .  
(SH:- C/O Retaining wall and Pushta at RD 7/215 to 7/227.50 ) Job No - 1 .

Estimated cost:- Rs. 4,63,302.00  
Earnest money :- Rs. 9,300.00  
Time :- Two months.

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of slumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) ,dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	53.87	365.35	Rupees Three hundred sixty five and paise thirty five only	Per cubic metre	19681.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clause 802,803,1202 & 1203 Nominal Mix 1:4:8 (One cement: Four sand: Eight graded stone) 25 mm (Twenty five millimetre) aggregate within all leads and lift of materials and as per direction of Engineer-in-charge.	24.88	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	123340.00
3	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1204 Random rubble masonry in cement mortar 1:5 (One cement : Six sand ) Random rubble masonry within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	35.80	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	188038.00
4	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 within all leads and lift of materials and as per direction of Engineer-in-charge.	41.99	2736.20	Rupees Two thousand seven hundred thirty six and paise twenty only.	Per cubic metre	114893.00
5	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material, within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	10.81	1604.95	Rupees One thousand four and paise ninety five only	Per cubic metre	17350.00
	<b>Total</b>					<b>463302.00</b>

  
 Executive Engineer,  
 Kullu Division  
 HP.PWD Kullu


**SCHEDULE OF QUANTITY**

Name of work:- RRD on Dohranallah to Chestha road Km 0/0 to 8/760.  
(SH:- C/O Retaining wall and Pushia at RD 7/227.50 to 7/240 ) Job No - 2.

Estimated cost:- Rs. 4,63,490.00  
Earnest money :- Rs. 9,300.00

Time :- Two months.

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre), dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	54.12	365.35	Rupees Three hundred sixty five and paisa thirty five only	Per cubic metre	19773.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clause 802.803,1202 & 1203 Nominal Mix 1:4:8 (One cement: Four sand: Eight graded stone) 25 mm (Twenty five millimetre) aggregate within all leads and lift of materials and as per direction of Engineer-in-charge.	24.88	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	123340.00
3	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand ) Random rubble masonry within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	35.80	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	188038.00
4	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 within all leads and lift of materials and as per direction of Engineer-in-charge.	41.99	2736.20	Rupees Two thousand seven hundred thirty six and paise twenty only.	Per cubic metre	114893.00
5	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	10.87	1604.95	Rupees One thousand four and paise ninety five only	Per cubic metre	17446.00
	<b>Total</b>					<b>463490.00</b>

  
 Executive Engineer,  
 Kullu Division,  
 HP.PWD Kullu.

**SCHEDULE OF QUANTITY**

Name of work:- RRD on Manikaran Barshaini road 0/00 to 15/00  
(SH:- Construction of Retaining wall at RD 9/317.50 to 9/325 ).

Estimated cost:- Rs. 4,98,489.00  
Earnest money :- Rs. 10,000.00

Time :- Two months.

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Earth work in excavation of foundation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps, and other deleterious material and disposal upto any lead of 20 m (Twenty metre), dressing of sides and bottom and back filling the excavated suitable material in ordinary soil upto 3.00 m (Three point zero metre) depth within all leads and lift of materials and as per direction of Engineer-in-charge.	28.13	365.35	Rupees Three hundred sixty five and paise thirty five only.	Per cubic metre	10277.00
2	Providing and laying of boulder apron laid in wire crates with 4 mm (Four millimetre) dia GI wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm (One hundred x One hundred millimetre) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighing not less than 25 kg (Twenty five kilogram) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	140.62	3213.75	Rupees Two thousand seven hundred eighty four and paise thirty only	Per cubic metre	451917.00
6	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material, within all leads and lift of materials and as per direction of Engineer-in-charge.	22.61	1604.95	Rupees One thousand six hundred four and paise ninety five only	Per cubic metre	36295.00
					<b>Total</b>	<b>498489.00</b>

  
Executive Engineer,  
Kullu Division,  
HP.PWD Kulu

**SCHEDULE OF QUANTITY**

Name of work:- RRD on Manikaran Barshaini road 0/00 to 15/00.  
(SH:- Construction of Retaining wall at RD 9/310 to 9/317.50 ).

Estimated cost:- Rs. 4,97,956.00  
Earnest money :- Rs. 10,000.00

Time :- Two months.

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Earth work in excavation of foundation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead of 20 m (Twenty metre), dressing of sides and bottom and back filling the excavated suitable material in ordinary soil upto 3.00 m (Three point zero metre) depth within all leads and lift of materials and as per direction of Engineer-in-charge.	30.98	365.35	Rupees Three hundred sixty five and paise thirty five only.	Per cubic metre	11319.00
2	Providing and laying of boulder apron laid in wire crates with 4 mm (Four millimetre) dia GI wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm (One hundred x One hundred millimetre) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighing not less than 25 kg (Twenty five kilogram) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	140.62	3213.75	Rupees Two thousand seven hundred eighty four and paise thirty only	Per cubic metre	451917.00
6	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift of materials and as per direction of Engineer-in-charge.	21.63	1604.95	Rupees One thousand six hundred four and paise ninety five only	Per cubic metre	34720.00
	<b>Total</b>					<b>497956.00</b>

  
 Executive Engineer,  
 Kullu Division  
 HP, PWD Kullu

10

**SCHEDULE OF QUANTITY**

Name of work:- RRD on Bhuntar Manikaran road Km 1/610 to 35/110  
( SH:- Providing and laying WBM Grade - III in alternate road (AT RD 25/00) Km 0/00 to 0/500 )

Estimated cost:- Rs. 4,89,750.00  
Earnest money :- Rs. 10,000.00  
Time :- Two months.

Sr. No.	Description	Qty	Figure	Words	Rate In	Unit	Amount
1	Providing laying spreading and compacting stone aggregate of specific size to water bond macadam specification including spreading in uniform thickness hand packing rolling with smooth wheel roller 80-100 Kn in stages to proper grade and camber applying and brooming stone screening/ binding material to fill up the intersices of course aggregate watering and compacting to the required density Grading - III as per tech. specification clause 405 by manual means within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	151.87	3224.80	Rupees Three thousand two hundred twenty four and paise eighty only.		Per Cubic metre	489750.00
						<b>Total</b>	<b>489750.00</b>

  
Executive Engineer,  
Kullu Division,  
HP.PWD Kullu



**SCHEDULE OF QUANTITY**

Name of work:- RRD on Bhunjer Manikaran road 1/6/10 to 35/110.  
(SH:- Construction of Retaining wall at RD 22/905 to 22/921.25 ).

Estimated cost:- Rs. 4,93,233.00  
Earnest money :- Rs. 10,000.00

Time :- Two months.

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	52.33	365.35	Rupees Three hundred sixty five and paise thirty five only.	Per cubic metre	19119.00
2	Providing and laying of boulder apron laid in wire crates with 4 mm (Four millimetre) dia GI wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm (One hundred x One hundred millimetre) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighing not less than 25 kg (Twenty five kilogram) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	140.62	3213.75	Rupees Two thousand seven hundred eighty four and paise thirty only	Per cubic metre	451918.00
6	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift of materials and as per direction of Engineer-in-charge.	13.83	1604.95	Rupees One thousand six hundred four and paise ninety five only	Per cubic metre	22196.00
					<b>Total</b>	<b>493233.00</b>

  
 Executive Engineer,  
 Kullu Division,  
 HP, PWD, Kullu

12

**SCHEDULE OF QUANTITY**

Name of work:- RRD on Bhunter Manikaran road 1/610 to 35/110.  
(SH:- Construction of Retaining wall at RD 22/921.25 to 22/937.50 )

Estimated cost:- Rs. 4,98,545.00  
Earnest money :- Rs. 10,000.00

Time :- Two months.

Sr. No.	Description	Qty	Figure	Rate In Words	Unit	Amount
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	53.87	365.35	Rupees Three hundred sixty five and paise thirty five only.	Per cubic metre	19681.00
2	Providing and laying of boulder apron laid in wire crates with 4 mm (Four millimetre) dia GI wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm (One hundred x One hundred millimetre) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighing not less than 25 kg (Twenty five kilogram) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	140.62	3213.75	Rupees Two thousand seven hundred eighty four and paise thirty only	Per cubic metre	451917.00
6	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material within all leads and lift of materials and as per direction of Engineer-in-charge.	16.79	1604.95	Rupees One thousand six hundred four and paise ninety five only	Per cubic metre	26947.00
	<b>Total</b>					<b>498545.00</b>

  
Executive Engineer,  
Kullu Division,  
HP.PWD Kullu

13

**SCHEDULE OF QUANTITY**

Name of work:- RRD on Bhunter Manikaran road 1/6/10 to 35/1/10.  
(SH:- Construction of Retaining wall at RD 27755 to 27763 ).

Estimated cost:- Rs. 3,42,388.00  
Earnest money :- Rs. 7,000.00  
Time :- Two months.

Sr. No.	Description	Qty	Figure	Rate in Words	Unit	Amount
1	Earth work in excavation of foundation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead of 20 m (Twenty metre), dressing of sides and bottom and back filling the excavated suitable material in ordinary soil upto 3.00 m (Three point zero metre) depth within all leads and lift of materials and as per direction of Engineer-in-charge.	32.48	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	11867.00
2	Providing and laying concrete for plain/ reinforced concrete 1:6:12 (One cement :Six sand : Twelve graded stone aggregate 40mm (Forty millimetre nominal size ) in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	6.38	4509.15	Rupees Four thousand five hundred nine and paise fifteen only	Per cubic metre	28768.00
3	Providing and laying concrete for plain/ reinforced concrete 1:4:8 (One cement : Four sand : Eight graded stone aggregate 25 mm (Twenty five millimetre nominal size ) nominal size in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	4.95	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	24539.00
4	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand ) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	30.32	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	159254.00
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 within all leads and lift of materials and as per direction of Engineer-in-charge.	33.82	2736.20	Rupees Two thousand seven hundred thirty six and paise twenty only	Per cubic metre	92538.00
5	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	15.84	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	25422.00
	<b>Total</b>					<b>342388.00</b>

  
 Executive Engineer,  
 Kullu Division,  
 HP.PWD Kullu

14  
**SCHEDULE OF QUANTITY**

Name of work:- Restoration of rain damages on Ratocha Dhara road Km 0/00 to 5/00  
(SH:- Construction of Breast wall at RD 0/400 to 0/435 ).

Estimated cost:- Rs. 4,88,331.00  
Earnest money :- Rs. 10,000.00  
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in hilly area in manual means including cutting and trimming of sides, slopes and disposal of excavated earth work with a lift upto 1.50 mtr (One point fifty metre) and lead up to 20 mtr (Twenty metre) as per drawing and technical specification clause 1603.1.1 within all kind of soil within all leads and lift of materials and as per direction of Engineer-in-charge.	32.55	228.35	Rupees Two hundred twenty eight and paise thirty five only.	Per cubic metre	7433.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	25.90	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	9463.00
3	Providing concrete for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803,1202 and 1203 PCC grade M-10 nominal mix 1:3:6 (One cement : Three sand : Six graded stone aggregate ) within all leads and lift including carriage of materials in all respect and as per direction of Engineer-in-charge.	84.33	5196.30	Rupees Five thousand one hundred ninety six and paise thirty only	Per cubic metre	438204.00
4	Providing weap holes in brick masonry/ stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full with of the structures with slope of 1(v):20 (H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	85.00	390.95	Rupees Three hundred ninety and paise ninety five only.	Each	33231.00
					<b>Total</b>	<b>488331.00</b>



Executive Engineer,  
Kullu Division ,  
HP\_PWD Kullu

**SCHEDULE OF QUANTITY**

Name of work:- Restoration of rain damages on Sharni to Pin road.  
(SH:- Construction of Breast wall at RD 11/400 to 11/420 ).

Estimated cost:- Rs. 4,35,277.00  
Earnest money :- Rs. 8,800.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in hilly area in manual means including cutting and trimming of sides, slopes and disposal of excavated earth work with a lift upto 1.50 mtr (One point fifty metre) and lead up to 20 mtr (Twenty metre) as per drawing and technical specification clause 1603.1.1 within all kind of soil within all leads and lift of materials and as per direction of Engineer-in-charge.	105.00	228.35	Rupees Two hundred twenty eight and paise thirty five only.	Per cubic metre	23977.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	30.90	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	11289.00
3	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand ) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	50.98	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only.	Per cubic metre	267770.00
4	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 including hauling/carrriage of all labour equipment and materials to various location through all modes of transportatin within all leads and lift of materials and as per direction of Engineer-in-charge.	48.33	2736.20	Rupees Two thousand seven hundred thirty six and paise twenty only.	Per cubic metre	132241.00
					Total	435277.00

  
Executive Engineer,  
Kullu Division,  
HP,PWD Kullu

16

**SCHEDULE OF QUANTITY**

Name of work:- RRD on Work Shaop Gadouri road Km 0/00 to 0/900 .

(SH:- C/o U-Shape drain & V-Shape drain in Km 0/420 to 0/470 (both side) and repair of drain ).

Estimated cost:- 3,70,136.00  
Earnest money :- 7,500.00  
Time :- Two months

Sr. No.	Description	Qty	Figure	Words	Rate in	Unit	Amount
1	Earth work in excavation for structure as per drawing and technical specification clause 305 in setting out any dressing removal of stumps and other deleterious material up to a lead of 50.00 mtr (Fifty metre) dressing od sides and bottom and back filling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	34.31	365.35	Rupees Three hundred sixty five and paise thirty five only		Per Cubic metre	12535.00
2	Providing concrete for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803,1202 and 1203 PCC grade M-10 20 m (Twenty metre) nominal mix 1:3:6 (One cement : Three sand : Six graded stone aggregate ) within all leads and lift including carriage of materials in all respect and as per direction of Engineer-in-charge.	42.87	5196.30	Rupees Five thousand one hundred ninety six and paise thirty only.		Per Cubic metre	222765.00
3	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete within all leads and lift and carriage of material in all respect as per direction of Engineer-in-charge.	1556.10	86.65	Rupees Eighty six and paise sixty five only		Per Kilogram	134836.00
						Total	370136.00

  
Executive Engineer,  
Kullu Division ,  
HP.PWD Kullu

**SCHEDULE OF QUANTITY**

Estimated cost:- Rs. 4,94,738.00  
 Earnest money :- Rs. 10,000.00  
 Time :- Two months

Name of work:- Resstoration of rain damages on Buins Bye to Bhullang road Km. 0/0 to 11/020 (SH:- C/O wire crated Retaining wall CC Toe wall km 8/350 to 8/375 )

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift of materials and as per direction of Engineer-in-charge.	21.13	365.35	Rupees Three hundred sixty five and paise thirty five only	Per cubic metre	7720
2	Providing concrete for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 and 1203 PCC grade M-10 nominal mix 1:3:6 (One cement : Three sand : Six graded stone aggregate ) within all leads and lift including carriage of materials in all respect and as per direction of Engineer-in-charge.	45.00	5212.70	Rupees Five thousand two hundred twelve and paise seventy only	Per cubic metre	234572
3	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre ) dia GI wire conforming to IS: 280 and IS: 4826 in 150mmx 150mm(One hundred fifty millimetre into One hundred fifty millimetre ) mesh (woven diagonally ) including 10(Ten) percent extra for laps and joints laid with stone boulders weighing not less than 25 kg.(Twenty five kilogram ) each as per drawing and technical specifications clause 1301 within all leads and lift of materials and as per direction of Engineer-in-charge	78.13	2784.30	Rupees Two thousand seven hundred eighty four and paise thirty only	Per cubic metre	217537
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	21.75	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	34908
					Total	494738

  
 Executive Engineer,  
 Kullu Division,  
 HP.PWD Kullu

**SCHEDULE OF QUANTITY**

Estimated cost- Rs. 4,88,230.00  
 Earnest money :- Rs. 10,000.00  
 Time :- Two months

Name of work:- Resstoration of rain damages on Buins Bye to Bhullang road Km. 0/0 to 1/020 (SH:- C/O wire crated Retaining wall CC Toe wall km 6/720 to 6/745 )

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead ,dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift of materials and as per direction of Engineer-in- charge.	26.38	365.35	Rupees Three hundred sixty five and paise thirty five only	Per cubic metre	9638
2	Providing concrete for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803,1202 and 1203 PCC grade M-10 nominal mix 1:3:6 (One cement : Three sand : Six graded stone aggregate ) within all leads and lift including carriage of materials in all respect and as per direction of Engineer-in- charge.	45.00	5212.70	Rupees Five thousand two hundred twelve and paise seventy only	Per cubic metre	234572
3	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre ) dia GI wire conforming to IS: 280 and IS: 4826 in 150mmx 150mm(One hundred fifty millimetre into One hundred fifty millimetre ) mesh (woven diagonally) including 10(Ten) percent extra for laps and joints laid with stone boulders weighing not less than 25 kg.(Twenty five kilogram ) each as per drawing and technical specifications clause 1301 within all leads and lift of materials and as per direction of Engineer-in- charge	78.13	2784.30	Rupees Two thousand seven hundred eighty four and paise thirty only	Per cubic metre	217537
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material, within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	16.50	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	26482
					<b>Total</b>	<b>488230</b>

  
 Executive Engineer,  
 Kullu Division ,  
 HP.PWD Kullu



SCHEDULE OF QUANTITY

Name of work:- RRD on Lashani to Sangtehar road Km 0/00 to 3/660.  
(SH:- C/O PCC R/wall at RD 2/256 to 2/272 ).

Estimated cost:- Rs. 4,97,268.00  
Earnest money :- Rs. 10,000.00  
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead ,dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift of materials and as per direction of Engineer-in-charge.	28.80	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	10522.00
2	Providing concrete for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803,1202 and 1203 PCC grade M-10 nominal mix 1:3:6 (One cement : Three sand : Six graded stone aggregate ) within all leads and lift including carriage of materials in all respect and as per direction of Engineer-in-charge.	84.48	5196.30	Rupees Five thousand one hundred ninety six and paise thirty only	Per cubic metre	438983.00
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	29.76	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	47763.00
					Total	497268.00

 Executive Engineer,  
Kullu Division ,  
HP.PWD Kullu

20

SCHEDULE OF QUANTITY

Name of work:- RRD on Lashani to Sangtehar road Km 0/00 to 3/660 .  
(SH:- C/O PCC R/wall at RD 2/240 to 2/256 )

Estimated cost:- Rs. 4,97,776.00  
Earnest money :- Rs. 10,000.00  
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead ,dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift of materials and as per direction of Engineer-in-charge.	28.08	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	10259.00
2	Providing concrete for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803,1202 and 1203 PCC grade M-10 nominal mix 1:3:6 (One cement : Three sand : Six graded stone aggregate ) within all leads and lift including carriage of materials in all respect and as per direction of Engineer-in-charge.	84.48	5196.30	Rupees Five thousand one hundred ninety six and paise thirty only	Per cubic metre	438983.00
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	30.24	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	48534.00
					Total	497776.00

  
Executive Engineer,  
Kullu Division ,  
HP.PWD Kullu

21

**SCHEDULE OF QUANTITY**

Name of work:- Restoration of rain damages on Jungru Thana to Tosh road Km 0/0 to 1/950  
 (SH:- C/O Crated R/wall of damaged road at RD 1/890 to 1/938.75 Under LADA Deposit (Phase-VII Job No-IV ).

Estimated cost:- Rs. 4,92,402.00  
 Earnest money :- Rs. 10,000.00  
 Time :- Two months.

Sr. No.	Description	Qty	Figure	Words	Rate in	Unit	Amount
1	Excavation in hilly area in manual means including cutting and trimming of sides, slopes and disposal of excavated earth work with a lift upto 1.50 mtr (One point fifty metre) and lead up to 20 mtr (Twenty metre) as per drawing and technical specification clause 1603.1.1 within all kind of soil within all leads and lift of materials and as per direction of Engineer-in-charge.	81.16	228.35	Rupees Two hundred twenty eight and paise thirty five only		Per cubic metre	18533.00
2	Providing and laying of boulder apron laid in wire crates with 4 mm (Four millimetre) dia GI wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm (One hundred x One hundred millimetre) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighing not less than 25 kg (Twenty five kilogram) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	152.34	3110.60	Rupees Three thousand one hundred ten and paise sixty only.		Per cubic metre	473869.00
						Total	492402.00

  
 Executive Engineer,  
 Kullu Division,  
 HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- RRD on Bhunter Manikaran road Km 1/610 to 35/110  
 ( SH:- Providing and laying GSB & WBM Grade - II at RD 4/390 to 4/530 ).

Estimated cost:- Rs. 3,95,841.00  
 Earnest money :- Rs. 8,000.00  
 Time :- Two months.

Sr. No.	Description	Qty	Rate in			Unit	Amount
			Figure	Words			
1	Preparation of sub grade by dressing to camber depending upon the classification of soil completed within all leads and lift of materials and as per direction of Engineer-in-charge.	708.5	1.65	Rupees One and paise sixty five only	Per Square metre	1169.00	
2	Consolidation of sub grade with road roller including making good the undulation etc. with earth or quarry soil etc. and rerolling the sub grade completed as per HP.PWD specifications Within all leads and lift of materials and as per direction of Engineer-in-charge.	708.50	1.20	Rupees One and paise twenty only	Per Square metre	850.00	
3	Construction of granular sub-base by providing close grade material, conforming to specification mixing in a mechanical mixed plant at OMC, carriage of mixed material by tippers to work at site for all leads and lifts in uniform layers of specified thickness with vibratory road roller to achieve the density complete within all leads and lift of materials and as per direction of Engineer-in-charge.	70.85	2816.85	Rupees Two thousand eight hundred sixteen and paise eighty five only	Per Cubic metre	199574.00	
4	Providing laying spreading and compacting stone aggregate of specific size to WBM Grading - II specification in uniform thickness, hand packing rolling with smooth wheel roller 80-100 Kn in stages to proper grade and camber applying and brooming stone screening/ binding material to fill up the interstices of course aggregate watering and compacting to the required density as per tech. specification clause 405 by manual means within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	53.14	3655.40	Rupees Three thousand six hundred fifty five and paise forty only.	Per Cubic metre	194248.00	
					<b>Total</b>	<b>395841.00</b>	

  
 Executive Engineer,  
 Kullu Division,  
 HP.PWD Kullu

23

SCHEDULE OF QUANTITY

Name of work:- RRD on Darka Gadiara road Km 0/00 to 1/800  
(SH:- C/O wire crated R/wall at RD 0/335 to 1/350 ).

Estimated cost:- Rs. 4,49,384.00  
Earnest money :- Rs. 9,000.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other material upto lead of 50 mtr (Fifty metre) dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	31.50	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	11509.00
2	Providing and laying concrete for plain/ reinforced concrete 1:4:8 (One cement : Four sand : Eight graded stone aggregate 25 mm (Twenty five millimetre nominal size ) nominal size in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	21.60	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only.	Per cubic metre	107080.00
3	Providing and laying of boulder apron laid in wire crates with 4 mm (Four millimetre) dia GI wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm (One hundred x One hundred millimetre) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighing not less than 25 kg (Twenty five kilogram) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	85.94	3428.95	Rupees Three thousand four hundred twenty eight and paise ninety five only	Per cubic metre	294684.00
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	22.50	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	36111.00
					Total	449384.00



Executive Engineer,  
Kullu Division  
HP,PWD Kullu

24

SCHEDULE OF QUANTITY

Name of work:- RRD on Darka Gadiara road Km 0/00 to 1/800  
(SH:- C/O wire crated R/wall at RD 0/350 to 0/365).

Estimated cost:- Rs. 4,48,726.00  
Earnest money :- Rs. 9,000.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other material upto lead of 50 mtr (Fifty metre) dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	29.70	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	10851.00
2	Providing and laying concrete for plain/ reinforced concrete 1:4:8 (One cement : Four sand : Eight graded stone aggregate 25 mm (Twenty five millimetre nominal size ) nominal size in open foundations complete as per drawing and technical specification clause 802.803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	21.60	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only.	Per cubic metre	107080.00
3	Providing and laying of boulder apron laid in wire crates with 4 mm (Four millimetre) dia GI wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm (One hundred x One hundred millimetre) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighing not less than 25 kg (Twenty five kilogram) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	85.94	3428.95	Rupees Three thousand four hundred twenty eight and paise ninety five only	Per cubic metre	294684.00
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	22.50	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	36111.00
					Total	448726.00

 Executive Engineer,  
Kullu Division,  
HP.PWD Kullu

25

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O District sports office at Dhalpur Kullu.  
(SH:- Painting roof and outer walls etc. ).

Estimated cost:- Rs. 3,36,766.00  
Earnest money :- Rs. 6,800.00  
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Painting on G.S. sheet with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade New work (two or more coats) including a coat of approved steel primer but excluding a coat of mordant solution with in all leads and lift of materials and as per direction of Engineer-in-charge.	571.78	111.60	Rupees One hundred eleven and paise sixty only.	Per Square metre	63811
2	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm (Zero point ninety litre/ Ten square metre) over an under coat of primer applied @ 0.90 ltr/10 sqm (Zero point eighty litre/ Ten square metre of approved brand and manufacture with in all leads and lift of materials and as per direction of Engineer-in-charge	623.54	111.60	Rupees One hundred eleven and paise sixty only.	Per square metre	69587
3	Finishing walls with Acrylic Smooth exterior paint of required shade New work (Two or more coat applied @ 1.67 ltr/10 sqm (One point sixty seven litre/ Ten square metre) over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm (Two point twenty kilogram/ Ten square metre)) with in all leads and lift of materials and as per direction of Engineer-in-charge.	526.57	123.05	Rupees One hundred twenty three and paise zero five only.	Per square metre	64794
4	Repairs to plaster of thickness 12 mm (Twelve millimetre) to 20 mm (Twenty millimetre) in patches of area 2.5 sq.meters (Two point five square metre) and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete With cement mortar 1:4 (1 cement : 4 fine sand) with in all leads and lift of materials and as per direction of Engineer-in-charge.	45.00	384.46	Rupees Three hundred eighty four and paise forty six only	Per Square metre	17301
5	Providing and applying white cement based putty of average thickness 1 mm (One millimetre), of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete with in all leads and lift of materials and as per direction of Engineer-in-charge.	45.00	103.40	Rupees One hundred three and paise forty only.	Per Square metre	4653

6	Renewing glass panes and refixing existing wooden fillets: Float glass panes of nominal thickness 4 mm (Four millimetre) (weight not less than 10kg/sqm (Ten kilogram per square metre)) with in all leads and lift of materials and as per direction of Engineer-in-charge.	3.04	1160.10	Rupees One thousand one hundred sixty and paise ten only	Per Square metre	3524
7	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm (Zero point ninety litre/ Ten square metre) over an under coat of primer applied @0.75 ltr/10 sqm (Zero point seventy five litre/ Ten square metre) of approved brand and manufacture with in all leads and lift of materials and as per direction of Engineer-in-charge.	124.93	106.20	Rupees One hundred six and paise twenty only.	Per square metre	13268
8	Providing and fixing double scaffolding system (cup lock type) on the exterior side, up to seven story height made with 40 mm (Forty millimetre) dia M.S. tube 1.5 m (One point five metre) centre to centre, horizontal & vertical tubes joining with cup & lock system with M.S. tubes, M.S. tube chollies, M.S. clamps and M.S. staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for the required duration as approved and removing it there after. The scaffolding system shall be stiffened with bracings, runners, connection with the building etc wherever required for inspection of work at required locations with essential safety features for the workmen etc. complete. The elevational area of the scaffolding shall be measured for payment purpose. The payment will be made once irrespective of duration of scaffolding with in all leads and lift of materials and as per direction of Engineer-in-charge.	321.75	222.00	Rupees Two hundred twenty two only.	Per Square metre	71429
9	Applying priming coat: With ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanized iron/ steel works with in all leads and lift of materials and as per direction of Engineer-in-charge.	571.78	49.67	Rupees Forty nine and paise sixty seven only.	Per Square metre	28400
	<b>Total</b>					<b>336766</b>

  
 Executive Engineer,  
 Kullu Division,  
 HP.PWD Kullu.



26

SCHEDULE OF QUANTITY

Name of work:- RRD on Bhuntar Manikaran road Km 1/610 to 35/110  
(SH:- Providing and laying BM 50mm thick at RD 4/390 to 4/530 ).

Estimated cost:- Rs. 4,26,546.00  
Earnest money :- Rs. 8,600.00  
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg. ( Zero point seven zero to one point zero kilogramme ) / squaremetre using mechanical means as per Technical specification clause 502. including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts of material to the entire satisfaction as per direction of Engineer-in-charge.	708.50	55.05	Rupees Fifty five and paise zero five only	Per Square metre	39003.00
2	Providing and applying tack coat with bitumen Emulsion (RS-1) using emulsion distributor at the rate @ 0.25 to 0.30 kg/sqm (Zero point twenty five to zero point thirty kilogram per square meter ) on the prepared on dry and hungry bituminous surface cleaned with Hydraulic broom as per technical specification clause 503.	708.50	20.00	Rupees Twenty only.	Per Square metre	14170.00
3	Providing and laying bituminous concrete with 100-120 TPH batch type HMP (Hot mix Plant) producing an average output of 75 tonnes per hour using crushed aggregates of specified grading premixed with bituminous binder @ 3.4 to 3.6 percent of mix and filler, transporting the hot mix to work side, laying with a hydraulic paver finisher with sensor control to the required grade level and alignment, rolling with smooth wheeled vibratory and tandem roller to achieve the desired compaction as per MoRTH specification clause 509 complete in all respects.	35.43	10538.35	Rupees Ten thousand five hundred thirty eight and paise thirty five only.	Per Cubic metre	373373.00
					Total	426546.00

  
Executive Engineer,  
Kullu Division,  
HP.PWD Kullu

27

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Sarsari Chong road Km 0/00 to 5/300 .  
(SH:- Construction of R/wall at RD 3/620 to 3/640 ).

Estimated cost:- Rs. 4,76,260.00  
Earnest money :- Rs. 9,600.00

Time :- Two months.

Sr. No.	Description	Qty	Figure	Words	Rate in	Unit	Amount
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	51.30	365.35	Rupees Three hundred Sixty five and paise thirty five only.		Per cubic metre	18742.00
2	Providing and laying concrete for plain/ reinforced concrete PCC Grade 1:6:12 (One cement :Six sand : Twelve graded stone) for nominal mix aggregate foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	9.80	4509.15	Rupees Four thousand five hundred nine and paise fifteen only.		Per cubic metre	44190.00
3	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand ) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	37.32	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only.		Per cubic metre	196021.00
4	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 including hauling/carriage of all labour equipment and materials to various location through all modes of transport within all leads and lift of materials and as per direction of Engineer-in-charge.	63.23	2736.20	Rupees Two thousand seven hundred thirty six and paise twenty only.		Per cubic metre	173010.00
5	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	27.60	1604.95	Rupees One thousand six hundred four and paise ninety five only.		Per cubic metre	44297.00
						Total	476260.00

  
Executive Engineer,  
Kullu Division,  
HP.PWD Kullu

28

SCHEDULE OF QUANTITY

Name of work:- RRD on Bhuntar Manikaran road Km 1/610 to 35/110  
 (SH:- Providing and laying BM 50mm thick in the alternate road at (RD 25/00) Km 0/00 to 0/170 ).

Estimated cost:- Rs. 4,40,039.00  
 Earnest money :- Rs. 9,000.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg. ( Zero point seven zero to one point zero kilogramme ) / squaremetre using mechanical means as per Technical specification clause 502. including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts of material to the entire satisfaction as per direction of Engineer-in-charge.	731.00	55.05	Rupees Fifty five and paise zero five only	Per Square metre	40242.00
2	Providing and applying tack coat with bitumen Emulsion (RS-I) using emulsion distributor at the rate @ 0.25 to 0.30 kg/sqm (Zero point twenty five to zero point thirty kilogram per square meter ) on the prepared on dry and hungry bituminous surface cleaned with Hydraulic broom as per technical specification clause 503.	731.00	20.00	Rupees Twenty only.	Per Square metre	14620.00
3	Providing and laying bituminous concrete with 100-120 TPH batch type HMP (Hot mix Plant) producing an average output of 75 tonnes per hour using crushed aggregates of specified grading premixed with bituminous binder @ 3.4 to 3.6 percent of mix and filler, transporting the hot mix to work side, laying with a hydraulic paver finisher with sensor control to the required grade ,level and alignment, rolling with smooth wheeled vibratory and tandem roller to achieve the desired compaction as per MoRTH specification clause 509 complete in all respects .	36.55	10538.35	Rupees Ten thousand five hundred thirty eight and paise thirty five only.	Per Cubic metre	385177.00
					Total	440039.00

  
 Executive Engineer,  
 Kullu Division ,  
 HP.PWD Kullu

29

Estimated cost:-3,23,925.00  
Earnest money :- 6,500.00  
Time :-Two months.

**SCHEDULE OF QUANTITY**

Name of work :- Construction of welcome gate for Kullu Town near at Bhootnath Bridge Distt. Kullu (HP). (Sh:- C/O welcome gate ) ( Job-4)

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Providing and fixing HPL board (High Pressure aminated Board) of Samart/Marino or equivalent brand having 6mm thickness on wall face of stone ashlar masonry fixed on aluminium frame work of 12mm x 12mm (Twelve millimetre x Twelve millimetre)section on firmly supported with fasteners properly embedded in the masonry \ The HPL board should be provided with approved shade as per architectural drawings to match with the masonry as per direction of Engineer-in-charge with in all leads, lifts and carriage of materials and other incidentals complete.	37.02	8750.00	Ruppes eight thousand seven hundred fifty only	Per Square metre	323925
					Total	323925

  
Executive Engineer,  
Kullu Division ,  
HP.PWD Kullu

30

Estimated cost:-4,99,161.00  
 Earnest money :- 10,000.00  
 Time :-Two months.

### SCHEDULE OF QUANTITY

Name of work :- Construction of welcome gate for Kullu Town near at Bhoothnath Bridge Distt. Kullu (HP). (Shr:- C/O welcome gate) ( Job-3)

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing, in position and binding all complete upto all floor level. Thermo-Mechanically Treated bars of grade Fe-500D or more within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	1522.05	98.00	Rupees ninety eight and paise zero only.	Per killogram	149161
2	Providing and fixing HPL board (High Pressure aminated Board) of Samar/Manino or equivalent brand having 6mm thickness on wall face of stone ashlar masonry fixed on aluminium frame work of 12mm x 12mm (Twelve millimetre x Twelve millimetre)section on firmly supported with fasteners properly embedded in the masonry. The HPL board should be provided with approved shade as per architectural drawings to match with the masonry as per direction of Engineer-in-charge with in all leads, lifts and carriage of amterials and other incidentals complete.	40.00	8750.00	Rupees eight thousand seven hundred fifty only	Per Square metre	350000
					Total	499161

  
 Executive Engineer,  
 Kullu Division ,  
 HP.PWD Kullu

Estimated cost:- 494014.00  
 Earnest money :- 10000.00  
 Time :- Two months

**DRAFT SCHEDULE OF QUANTITY**

Name of work:- Construction of Proposed Parking opposite to Bus Stand Sanwari kullu (Sh:- Leveling of Parking ground) Job No.III

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in soil in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/wedging out of rock (where blasting is not required) and their intermediate classification of soil including, dewatering wherever required setting out to the required line grades, side slopes trimming bottom and level as shown on the drawings as directed by Engineer-in-charge at site according to technical specifications clause 1603.1 & 1603.2 and sorting out useful/un useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in road ways, embankments for grades improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load animal load or mechanical means along with its leveling fine dressing and all labour, machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if any required) Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respect.	2130.75	231.85	Rupees Two hundred thirty one and paise eighty five only	Per cubic metre	494014.00
					<b>Total:-</b>	<b>494014.00</b>

*Exo*

Executive Engineer,  
 Kullu Division,  
 HP.PWD Kullu

32

Estimated cost:- 494014.00  
 Earnest money :- 10000.00  
 Time :- Two months

### DRAFT SCHEDULE OF QUANTITY

Name of work:- Construction of Proposed Parking opposite to Bus Stand Sarwari kullu (Sh)- Leveling of Parking ground) Job No.IV

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in soil in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/wedging out of rock( where blasting is not required ) and their intermediate classification of soil including, dewatering wherever required setting out to the required line grades, side slopes trimming bottom and level as shown on the drawings as directed by Engineer-in-charge at site according to technical specifications clause 1603.1.&1603.2 and sorting out useful/un useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in road ways, embankments for grades improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load animal load or mechanical means along with its leveling fine dressing and all labour, machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if any required) Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respect.	2130.75	231.85	Rupees Two hundred thirty one and paise eighty five only	Per cubic metre	494014.00
					Total:-	494014.00

  
 Executive Engineer,  
 Kullu Division,  
 HP.PWD Kullu

33

Estimated cost:-442879.00  
 Earnest money :- 9000.00  
 Time :- Two months

### DRAFT SCHEDULE OF QUANTITY

**Name of work:-** Restoration of rain damages on Sangtehar to Birni road km. 0/0 to 4/200  
 (SH:- Removal of slips at various Rds and blocked culvert in km. 0/00 to 2/00 ) Job No.1

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materials upto any and any lead as per technical specification 302.3.5 and 1611 within all leads and lift of materials and as per direction of Engineer-in-charge.	3540.20	125.10	Rupees One hundred twenty five and paise ten only.	Per cubic metre	442879.00
					<b>Total</b>	<b>442879.00</b>

  
 Executive Engineer,  
 Kullu Division  
 HP.PWD Kullu.



34

Estimated cost:-442879.00  
Earnest money :- 9000.00  
Time :- Two months

**DRAFT SCHEDULE OF QUANTITY**

**Name of work:-** Restoration of rain damages on Sangtehar to Birmi road km. 0/0 to 4/200  
(SH:- Removal of slips at various Rds and blocked culvert in km. 2/00 to 4/200 ) **Job No.11**

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materials upto any and any lead as per technical specification 302.3.5 and 1611 within all leads and lift of materials and as per direction of Engineer-in-charge.	3540.20	125.10	Rupees One hundred twenty five and paise ten only.	Per cubic metre	442879.00
					<b>Total</b>	<b>442879.00</b>

  
Executive Engineer,  
Kullu Division  
HP.PWD Kullu.

Estimated cost:- 207000.00  
 Earnest money :- 25000.00  
 Time :- Two month

**DRAFT SCHEDULE OF QUANTITY**

**Name of work:-** Restoration of rain damages on flush flood on Bhunter Manikaran road  
 (SH:- Hiring of water tanker for sprinkling for damaged portion at km. 0/0 to 1/850 ) **Job No.1**

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of water tanker 4 Kl Capacity (8000 litres per hour ) with Tractor Mounted for sprinkling of water on damaged Rath ground surface at Dhalpur for C/O sub way . As per direction of Engineer-in-charge . The tanker should sprinkle the water at least two times i.e. morning 8.30 AM onwards and evening at 2.30 PM onwards per day. Any loss to the private /public property or any accident etc. happed during the course of hiring period shall be absolute responsibility of the contractor . Which shall be fully compensated by him (contractor) in all cases. The fuel and tanker driver and other stays for tanker operator will be provided by the contractor. The repair and sapre of tanker also borne by the contractor. The daily log book will be maintained at site which should be duly verified daily by the Engineer-in-charge.	150	1380.00	Rupees One thousand three hundred eighty and paise zero only.	Per Hour	207000.00
					<b>Total:-</b>	<b>207000.00</b>

Executive Engineer,  
 Kullu Division,  
 HP.PWD Kullu

36

Estimated cost:- 207000.00  
 Earnest money :- 2500.00  
 Time :- Two month

**DRAFT SCHEDULE OF QUANTITY**

**Name of work:-** Restoration of rain damages on flush flood on Bhunter Manikaran road  
 (SH:- Hiring of water tanker for sprinkling for damaged portion at km. 0/0 to 1/850 ) **Job No.11**

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of water tanker 4 Kl Capacity (8000 litres per hour ) with Tractor Mounted for sprinkling of water on damaged Rath ground surface at Dhalpur for C/O sub way . As per direction of Engineer-in-charge . The tanker should sprinkle the water at least two times i.e. morning 8.30 AM onwards and evening at 2.30 PM onwards per day. Any loss to the private /public property or any accident etc. happed during the course of hiring period shall be absolute responsibility of the contractor . Which shall be fully compensated by him (contractor) in all cases. The fuel and tanker driver and other stays for tanker operator will be provided by the contractor. The repair and sapre of tanker also borne by the contractor. The daily log book will be maintained at site which shuld be duly verified daily by the Engineer-in-charge.	150	1380.00	Rupees One thousand three hundred eighty and paise zero only.	Per Hour	207000.00
					<b>Total:-</b>	<b>207000.00</b>

  
 Executive Engineer,  
 Kullu Division ,  
 HP.PWD Kullu

37

**SCHEDULE OF QUANTITY**

Name of work:- Balance work of Additional Accommodation in Govt. Sen. School (Girls) at Sultanpur Distt. Kullu. (SH):- P/F wooden door/window frames, fixing pannelled door shutter, glazed door shutter and wire gauge shutter etc. (Job No. - 1).

Estimated cost:- Rs. 4,38,712.00  
Earnest money :- Rs. 8,800.00  
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Providing wood work in frames of door windows, clerestory windows in 2nd class deodar wood in position with necessary stainless steel screws etc. with in all leads and lift of materials and as per direction of Engineer-in-charge.	3.32	132080.00	Rupees One lac thirty two thousand eighty only.	Per Cubic metre	438712.00
					Total	438712.00

  
Executive Engineer,  
Kullu Division,  
HP.PWD Kullu

38

SCHEDULE OF QUANTITY

Name of work:- Balance work of Additional Accommodation in Govt. Sen. School (Girls) at Sultanpur Distt. Kullu. (SH:- P/F wooden door/window frames, fixing pannelled door shutter, glazed door shutter and wire gauge shutter etc. (Job No. - 2).

Estimated cost:- Rs. 4,87,656.00  
Earnest money :- Rs. 9,800.00  
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Providing wood work in frames of door windows, clerestory windows in 2nd class deodar wood in position with necessary stainless steel screws etc. with in all leads and lift of materials and as per direction of Engineer-in-charge.	1.35	132080.00	Rupees One lac thirty two thousand eighty only.	Per Cubic metre	178060.00
2	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm (Zero point ninety litre/ Ten square metre) over an under coat of primer applied @0.75 ltr/10 sqm (Zero point seventy five litre/ Ten square metre) of approved brand and manufacture with in all leads and lift of materials and as per direction of Engineer-in-charge.	260.81	106.20	Rupees One hundred six and paise twenty only.	Per square metre	27698.00
3	Providing and fixing 40 mm (Forty millimetre) thick pannelled shutter for door with deodar wood style rail beading and infill panele of 12 mm (Twelve millimetre) thick phenol bonded prelaminated board both side particle board panel (SI marked 12823 including ISI) marked with in all leads and lift of materials and as per direction of Engineer-in-charge.	23.37	6200.00	Rupees Sixty thousand two hundred only.	Per Square metre	144894.00
4	Providing and fixing pannelled glazed or pannelled and glazed shutters for doors windows and clerestory windows including black enamelled iron butt hinges with necessary screws 40 mm (Forty millimetre) thick 1st class Deodar wood with in all leads and lift of materials and as per direction of Engineer-in-charge.	24.24	5652.00	Rupees Five thousand six hundred fifty two only.	Per Square metre	137004.00
					Total	487656.00

  
Executive Engineer,  
Kullu Division,  
HP.PWD Kullu

39

Estimated cost:-455427.00  
Earnest money :-10000.00

Time :- One month.

Name of work:- Restoration of rain damages on Dohra Nallah to Chestha road Km. 0/0 to 8/670 (SH:- Removal of slips/debries at Various Rds )

**DRAFT SCHEDULE OF QUANTITY**

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materials upto any and any lead as per technical specification 302.3.5 and 1611 within all leads and lift of materials and as per direction of Engineer-in-charge.	3640.50	125.10	Rupees One hundred twenty five and paise ten only.	Per cubic metre	455427.00
					<b>Total</b>	<b>455427.00</b>

  
Executive Engineer,  
Kullu Division ,  
HP.PWD Kullu.

40

Estimated cost:-455406.00  
 Earnest money :-10000.00  
 Time :- Two months.

### DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Chhour Nallah to Bhrain road Km. 0/0 to 4/200 (SH:- Removal of slips/debries at Various Rds )

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materials upto any and any lead as per technical specification 302.3.5 and 1611 within all leads and lift of materials and as per direction of Engineer-in-charge.	3560.40	125.10	Rupees One hundred twenty five and paise ten only.	Per cubic metre	445406.00
					Total	445406.00

  
 Executive Engineer,  
 Kullu Division,  
 HP.PWD Kullu.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Kollibeher to Barahar Km 0/00 to 6/00 .  
(SH):- Construction of PCC Retaining wall on PCC pushta at RD 1/190 to 1/200 ).

Estimated cost:- Rs. 4,88,801.00  
Earnest money :- Rs. 9,800.00  
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	28.90	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	10924.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clause 802,803,1202 & 1203 Nominal Mix 1:4:8 (One cement: Four sand: Eight graded stone) within all leads and lift of materials and as per direction of Engineer-in-charge.	87.10	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	431790.00
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	14.10	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	22630.00
4	Providing weap holes in brick masonry/ stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full with of the structures with slope of 1(v):20 (H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7. within all leads and lift of materials and as per direction of Engineer-in-charge.	60	390.95	Rupees Three hundred ninety and paise ninety five only	Each	23457.00
					Total	488801.00

  
Executive Engineer,  
Kullu Division,  
HP.PWD Kullu



42

**SCHEDULE OF QUANTITY**

Name of work:- Restoration of rain damages on Kolibeher to Barahar Km 0/00 to 6/00 .  
(SH:- Construction of PCC Retaining wall on PCC pushta at RD 1/180 to 1/190 ).

Estimated cost:- Rs. 4,88,740.00  
Earnest money :- Rs. 9,800.00  
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	32.15	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	11746.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clause 802,803,1202 & 1203 Nominal Mix 1:4:8 (One cement: Four sand: Eight graded stone) within all leads and lift of materials and as per direction of Engineer-in-charge.	87.10	4957.40	Rupees Four thousand nine hundred fifty seven and paise forty only	Per cubic metre	431790.00
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 Granular material. within all leads and lift including cartage of materials and as per direction of Engineer-in-charge.	13.55	1604.95	Rupees One thousand six hundred four and paise ninety five only.	Per cubic metre	21747.00
4	Providing weep holes in brick masonry/ stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full with of the structures with slope of 1(v):20 (H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7. within all leads and lift of materials and as per direction of Engineer-in-charge.	60	390.95	Rupees Three hundred ninety and paise ninety five only	Each	23457.00
					Total	488740.00

  
Executive Engineer,  
Kullu Division,  
HP.PWD Kullu

43

**SCHEDULE OF QUANTITY**

Name of work:- RRD on Lashani to Shangtehar road Km 0/00 to 3/660  
( SH:- Formation cutting in Km 0/927 to 1/115 ).

Estimated cost:- Rs. 2,83,007.00  
Earnest money :- Rs. 5,800.00  
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in soil in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/wedging out of rock( where blasting is not required ) and their intermediate classification of soil including, dewatering wherever required setting out to the required line grades, side slopes trimming bottom and level as shown on the drawings as directed by Engineer-in-charge at site according to technical specifications clause 1603.1,&1603.2 and sorting out useful/un useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in road ways, embankments for grades improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load animal load or mechanical means along with its leveling fine dressing and all labour, machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if any required) Recovery for useful material of 55.03 Cum @ 600/-per cubic metre amounting to Rs. 33,018/- only shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respect.	1100.66	257.13	Rupees Two hundred fifty seven and paise thirteen only.	Per cubic metre	283007.00
					<b>Total:-</b>	<b>283007.00</b>

  
Executive Engineer,  
Kullu Division,  
HP.PWD Kullu.

44

**SCHEDULE OF QUANTITY**

Name of work:- Restoration of rain damages on Badah Pahnallah to Shillirajiri (Janahal) road  
( SH:- Removal of Slips at various RD's ).

Estimated cost:- Rs. 4,91,368.00  
Earnest money :- Rs. 10,000.00  
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.50 m (One point fifty metre) and lead upto 1000 m (One thousand metre) a sper technical specification 302.5 and 1611 within all leads and lift including carriage of materials and as per direction of Engineer-in- charge.	3927.80	125.10	Rupees One hundred twenty five and paise ten only	Per cubic metre	491368.00
					Total	491368.00

  
Executive Engineer,  
Kullu Division,  
HP.PWD Kullu

45  
SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Badah Pannallah to Shillirajiri (Janahal) road

( SH:- Removal of Slips at various RD's )

Estimated cost:- Rs. 4,99,034.00  
Earnest money :- Rs. 10,000.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.50 m (One point fifty metre) and lead upto 1000 m (One thousand metre) a sper technical specification 302.5 and 1611 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	3989.08	125.10	Rupees One hundred twenty five and paise ten only	Per cubic metre	499034.00
					Total	499034.00

  
Executive Engineer,  
Kullu Division,  
HP.PWD Kullu

46  
**SCHEDULE OF QUANTITY**

Name of work:- Restoration of rain damages on Chharour Nallah to Kashawari road Km. 0/00 to 8/020 .  
(SH:- Construction of PCC Toe wall at Km 0/270 to 0/290 )

Estimated cost:- Rs. 3,25,040.00  
Earnest money :- Rs. 6,600.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	36.30	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	13262.00
2	Providing concrete for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803,1202 and 1203 PCC grade M-10 nominal mix 1:3:6 (One cement : Three sand : Six graded stone aggregate ) within all leads and lift including carriage of materials in all respect and as per direction of Engineer-in-charge.	60.00	5196.30	Rupees Five thousand one hundred ninety six and paise thirty only	Per cubic metre	311778.00
					Total	325040.00

  
Executive Engineer,  
Kullu Division ,  
HP.PWD Kullu

47  
SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain damages on Tapoo Bridge .

Estimated cost:- Rs. 4,87,211.00

Earnest money :- Rs. 9,800.00

(SH:- P/L CC 1:2:4 to protect the bridge abutment and CC 1:3:6 for pavement on approach road ).

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, any dressing removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) and lift complete including dressing of sides and bottom and backfilling in trenches with excavated material in ordinary soil within all leads and lift of materials and as per direction of Engineer-in-charge.	26.88	365.35	Rupees Three hundred Sixty five and paise thirty five only.	Per cubic metre	9821.00
2	Providing and laying concrete for plain/ reinforced concrete 1:2:4 (One cement : Two sand : four graded stone aggregate 40mm (Forty millimetre nominal size ) in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	40.00	6250.50	Rupees Six thousand two hundred fifty and paise fifty only	Per cubic metre	250020.00
3	Providing laying spreading and compacting stone aggregate of specific size to water bond macadam specification including spreading in uniform thickness hand packing rolling with smooth wheel roller 80-100 Kn in stages to proper grade and camber applying and brooming stone screening/ binding material to fill up the interstices of course aggregate watering and compacting to the required density Grading - III as per tech. specification clause 405 by manual means within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	27.00	3224.80	Rupees Three thousand two hundred twenty four and paise eighty only.	Per Cubic metre	87070.00
4	Providing concrete for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803,1202 and 1203 PCC grade M-10 nominal mix 1:3:6 (One cement : Three sand : Six graded stone aggregate ) within all leads and lift including carriage of materials in all respect and as per direction of Engineer-in-charge.	27.00	5196.30	Rupees Five thousand one hundred ninety six and paise thirty only	Per cubic metre	140300.00
					Total	487211.00

  
Executive Engineer,  
Kullu Division ,  
HP.PWD Kullu

48

**SCHEDULE OF QUANTITY**

Name of work:- Restoration of rain damages on Badah Pahnallah to Shillrajgiri (Janahal) road Km. 0/00 to 19/700

Estimated cost:- Rs. 4,49,353.00

Earnest money :- Rs. 9,000.00

Time :- Two months.

(SH:- Construction of crated Breast wall at RD 13/420 to 13/470 ).

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in hilly area in ordinary rock by manual means requiring not blasting including cutting and trimming of side, slopes and disposal of excavated earth with a lift of 1.50 mtr (One point fifty metre) and lead up to 20 mtr (Twenty metre) as per drawing and technical specification clause 1603.1.1 within all leads and lift of materials and as per direction of Engineer-in-charge.	176.60	228.35	Rupees Two hundred twenty eight and paise thirty five only.	Per cubic metre	40327.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) ,dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	20.00	365.35	Rupees Three hundred sixty five and paise thirty five only.	Per cubic metre	7307.00
3	Providing and laying of boulder apron laid in wire crates with 4 mm (Four millimetre) dia GI wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm (One hundred x One hundred millimetre) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighing not less than 25 kg (Twenty five kilogram) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	125.00	3213.75	Rupees Three thousand two hundred thirteen and paise seventy five only.	Per cubic metre	401719.00
					Total	449353.00

Executive Engineer,  
Kullu Division,  
HP.PWD Kullu

49

**SCHEDULE OF QUANTITY**

Name of work:- Restoration of rain damages on Badah Pahnallah to Shillirajiri (Janahal) road Km. 0/00 to 19/700 .

Estimated cost:- Rs. 4,91,530.00

Earnest money :- Rs. 10,000.00

Time :- Two months.

(SH:- Construction of Breast wall on pushta at RD 11/470 to 1/492 ).

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in hilly area in ordinary rock by manual means requiring not blasting including cutting and trimming of side, slopes and disposal of excavated earth with a lift of 1.50 mtr (One point fifty metre) and lead up to 20 mtr (Twenty metre) as per drawing and technical specification clause 1603.1.1 within all leads and lift of materials and as per direction of Engineer-in-charge.	223.19	228.35	Rupees Two hundred twenty eight and paise thirty five only	Per cubic metre	50965.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 mtr (Fifty metre) ,dressing of sides and bottom and backfilling in trenches with excavated suitable material within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	20.02	365.35	Rupees Three hundred sixty five and paise thirty five only.	Per cubic metre	7314.00
3	Stone masonry work in cement mortar for sub structure complete as per drawing and technical specifications clause 702,704,1202 and 1204 Random rubble masonry in cement mortar 1:6 (One cement : Six sand ) within all leads and lift including carriage of materials and as per direction of Engineer-in-charge.	53.86	5252.45	Rupees Five thousand two hundred fifty two and paise forty five only	Per cubic metre	282897.00
4	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clause 704.6 & 1302.5 including hauling/carriage of all labour equipment and materials to various location through all modes of transportatin within all leads and lift of materials and as per direction of Engineer-in-charge.	54.95	2736.20	Rupees Two thousand seven hundred thirty six and paise twenty only.	Per cubic metre	150354.00
					Total	491530.00

  
Executive Engineer,  
Kullu Division,  
HP.PWD Kullu



50

SCHEDULE OF QUANTITY

Name of work:- Construction of Parking at Khoriropa .  
(SH:- Metalling and Tarring ) .

Estimated cost:- Rs. 2,58,910.00  
Earnest money :- Rs. 5,200.00  
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 KN Statics roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill up the interstices of coarse aggregate, watering and compacting to the required density Grading- I as per technical specification clause 405 by Manual Means including carriage of material within all leads and lift of materials and as per direction of Engineer-in-charge.	26.10	3284.40	Rupees Three thousand two hundred eighty four and paise forty only.	Per Cubic metre	85723.00
2	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 KN Statics roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill up the interstices of coarse aggregate, watering and compacting to the required density Grading- II as per technical specification clause 405 by Manual Means including carriage of material within all leads and lift of materials and as per direction of Engineer-in-charge.	12.38	3446.50	Rupees Three thousand four hundred forty six and paise fifty only.	Per Cubic metre	42668.00
3	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 KN Statics roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill up the interstices of coarse aggregate, watering and compacting to the required density Grading- II as per technical specification clause 405 by Manual Means including carriage of material within all leads and lift of materials and as per direction of Engineer-in-charge.	12.38	3345.00	Rupees Three thousand three hundred forty five only.	Per Cubic metre	41411.00

4	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg. ( Zero point seven zero to one point zero kilogramme) / squaremetre using mechanical means as per Technical specification clause 502. including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts of material to the entire satisfaction as per direction of Engineer-in-charge.	165.00	55.05	Rupees Fifty five and paise zero five only.	Per square metre	8083.00
5	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.25 to 0.30 kg ( zero point two five to zero point three zero kilo gramme)per squaremetre on the prepared granular surfaces treated with primer and cleaned with Hydraulic broom as per technical specification clause 503. including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts of material to the entire satisfaction as per direction of Engineer-in-charge.	165.00	20.00	Rupees Twenty only.	Per Square Metre	3300.00
6	Providing and laying bituminous concrete with 100-120 TPH batch type hot mix plant producing an average output of 75 tonne per hour using crushed aggregates of specified grading premixed with bituminous binder @ 5.4 to 5.6 percent of mix and filler, transporting the hot mix to work side, laying with a hydraulic paver finisher with sensor control to the required grade ,level and alignment, rolling with smooth wheeled vibratory and tandem roller to achieve the desired compaction as per MoRTH specification clause 508 complete in all respects within all leads and lift of materials and as per direction of Engineer-in-charge.	4.95	15500.00	Rupees Fifteen thousand five hundred only.	Per Cubic metre	76725.00
					Total	258910.00

  
 Executive Engineer,  
 Kullu Division  
 HP.PWD Kullu

50 51

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Bhoonthath Bridge.

Estimated cost:- Rs. 4,99,737.00

(SH:- Metalling and Tarring on Bus stand side approach Km 0/00 to 0/125 )

Earnest money :- Rs. 10,000.00

Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 KN Statics roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill up the interstices of coarse aggregate, watering and compacting to the required density Grading- II as per technical specification clause 405 by Manual Means including carriage of material within all leads and lift of materials and as per direction of Engineer-in-charge.	25.31	3446.50	Rupees Three thousand four hundred forty six and paise fifty only.	Per Cubic metre	87231.00
2	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 KN Statics roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill up the interstices of coarse aggregate, watering and compacting to the required density Grading- II as per technical specification clause 405 by Manual Means including carriage of material within all leads and lift of materials and as per direction of Engineer-in-charge.	25.31	3345.00	Rupees Three thousand three hundred forty five only.	Per Cubic metre	84662.00
3	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg.( Zero point seven zero to one point zero kilogramme) / squaremetre using mechanical means as per Technical specification clause 502. including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts of material to the entire satisfaction as per direction of Engineer-in-charge.	337.50	55.05	Rupees Fifty five and paise zero five only.	Per square metre	18579.00

SD 51

4	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.25 to 0.30 kg ( zero point two five to zero point three zero kilo gramme)per squaremetre on the prepared granular surfaces treated with primer and cleaned with Hydraulic broom as per technical specification clause 503. including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts of material to the entire satisfaction as per direction of Engineer-in-charge.	637.50	20.00	Rupees Twenty only.	Per Square Metre	12750.00
5	Providing and laying bituminous concrete with 100-120 TPH batch type hot mix plant producing an average output of 75 tonne per hour using crushed aggregates of specified grading premixed with bituminous binder @ 5.4 to 5.6 percent of mix and filler, transporting the hot mix to work side, laying with a hydraulic paver finisher with sensor control to the required grade ,level and alignment, rolling with smooth wheeled vibratory and landem roller to achieve the desired compaction as per MoRTH specification clause 509 complete in all respects within all leads and lift of materials and as per direction of Engineer-in-charge.	19.13	15500.00	Rupees Fifteen thousand five hundred only.	Per Cubic metre	296515.00
					Total	499737.00

Executive Engineer,  
Kullu Division,  
HP.PWD Kullu

52

**SCHEDULE OF QUANTITY**

Name of work:- A/R & M/O Residential building under Kullu Division.  
 (SH:- Painting, distemper, P/L PVC mat in rooms and fixing view cutter on boundary wall and repairing old damaged door frames of type-V residence behind hotel sarwari at Kullu ).

Estimated cost:- Rs. 4,98,100.00  
 Earnest money :- Rs. 10,000.00  
 Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete. with in all leads and lift of materials and as per direction of Engineer-in-charge.	397.75	11.15	Rupees Eleven and paise fifteen only.	Per Square metre	4435
2	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade New work (two or more coats) over and including water thinnable priming coat with cement primer with in all leads and lift of materials and as per direction of Engineer-in-charge.	397.75	128.50	Rupees One hundred twenty eight and paise fifty only.	Per Square metre	51111
3	Providing and applying white cement based putty of average thickness 1 mm (One millimetre), of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete with in all leads and lift of materials and as per direction of Engineer-in-charge.	238.65	131.00	Rupees One hundred thirty one only.	Per Square metre	31263
4	Providing 2 mm (Two millimetre) thick PVC antistatic vinyl Flooring plain or coloured, carbed or mosaic/metalled finish laid with approved adhesive on sub-floor (damp proofing treatment to be paid for seperately with in all leads and lift of materials and as per direction of Engineer-in-charge.	74.54	1301.50	Rupees One thousand three hundred one and paise fifty only.	Per Square metre	97014
5	Finishing walls with Acrylic Smooth exterior paint of required shade New work (Two or more coat applied @ 1.67 ltr/10 sqm (One point sixty seven litre/ Ten square metre) over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm (Two point twenty kilogram/ Ten square metre)) with in all leads and lift of materials and as per direction of Engineer-in-charge.	68.10	131.20	Rupees One hundred thirty one and paise tewnty only.	Per Square metre	8935
6	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length ( hold fast lugs or dash fastener shall be paid for seperately) Deodar wood with in all leads and lift of materials and as per direction of Engineer-in-charge.	0.15	129393.40	Rupees One Lac twenty nine thousand three hundred ninety three and paise forty only.	Per Cubic metre	19409

7	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm (Zero point ninety litre/ Ten square metre) over an under coat of primer applied @0.75 ltr/10 sqm (Zero point seventy five litre/ Ten square metre) of approved brand and manufacture with in all leads and lift of materials and as per direction of Engineer-in-charge.	549.90	128.50	Rupees One hundred twenty eight and paise fifty only.	Per Square metre	70662
8	Providing and fixing wire gauge shutter using galvanised MS wire gauge of apreature 1.4 mm (One point four millimetre) both direction with wire of dia 0.63 mm (Zero point sixty three millimetre) for door window and clestory window with hinges and necessary screw 35 mm (Thirty five millimetre) klin seasoned wood with in all leads and lift of materials and as per direction of Engineer-in-charge.	3.59	3085.76	Rupees Three thousand eighty five and paise seventy six only.	Per Square metre	11078
9	Providing and fixing bright finished brass handles with screws etc. complete 125 mm (One hundred twenty five millimetre) with in all leads and lift of materials and as per direction of Engineer-in-charge.	10.00	172.70	Rupees One hundred seventy two and paise seventy only.	Each	1727
10	Providing and fixing bright finished brass towels bolts (barrel type) with necessary screws etc. complete 150 x 10 mm (One hundred fifty into Ten millimetre) with in all leads and lift of materials and as per direction of Engineer-in-charge.	10.00	147.90	Rupees One hundred forty seven and paise ninety only.	Each	1479
11	Renewing glass panes and refixing thickness existing wooden fillets, Float glass panes of nominal thickness 4 mm (Four millimetre) (weight not less than 10kg/sqm (Ten kilogram per square metre)) with in all leads and lift of materials and as per direction of Engineer-in-charge.	3.20	1160.10	Rupees One thousand one hundred sixty and paise ten only	Per Square metre	3712
12	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works with in all leads and lift of materials and as per direction of Engineer-in-charge.	219.40	150.40	Rupees One hundred fifty and paise forty only.	Per Kilogram	32998
13	Providing and fixing polycarbonated transparent sheet 1.20 mm (One point twenty millimetre) thick in roofing galvanised or L hooks bolts and nuts with G.I. Limpet and bitumen rubber washer complete with all accessories as required with in all leads and lift of materials and as per direction of Engineer-in-charge.	23.42	4000.00	Rupees Four thousand only.	Per Square metre	93680
14	Providing and fixing 19 mm (Nineteen millimetre) thick water proof commercial board in shelves/box for cup board with butt joints & fixing with nails & screws etc. complete with in all leads and lift of materials and as per direction of Engineer-in-charge.	14.77	1550.00	Rupees One thousand five hundred fifty only.	Per Square metre	22894

15	Providing and fixing 19mm (Nineteen millimetre) thick Commercial Board water proof shutters for up boards l/c fixing with nickel plated piano hinges with screws etc complete with in all leads and lift of materials and as per direction of Engineer-in-charge.	5.02	1850.00	Rupees One thousand eight hundred fifty only.	Per Square metre	9287
16	Providing and fixing 1.00mm (One point zero millimeter) thick wooden shade teak ply on boards/ply wood sheets with approved adhesive and nails etc complete with in all leads and lift of materials and as per direction of Engineer-in-charge.	5.02	707.00	Rupees Seven hundred seven only.	Per Square metre	3549
17	Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 litre (Ten litre) low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm (Forty millimetre) flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required W.C. pan with ISI marked white solid plastic seat and lid with in all leads and lift of materials and as per direction of Engineer-in-charge.	1.00	5666.60	Rupees Five thousand six hundred sixty six and paise sixty only.	Each	5667
18	Providing and fixing calvina wash basin with C.I. brackets, 15 mm (Fifteen millimetre) C.P. brass pillar taps, 32 mm (Thirty two millimetre) C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Flat back wash basin size 550x 400 mm (Five hundred fifty x Four hundred millimetre) with hite vitreous china pedestal with in all leads and lift of materials and as per direction of Engineer-in-charge.	1.00	6310.00	Rupees Six thousand three hundred ten only.	Each	6310
19	Providing and fixing P.V.C. low level flushing cistern with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete. 10 litre (Ten litre) capacity - White with in all leads and lift of materials and as per direction of Engineer-in-charge.	1.00	916.50	Rupees Nine hundred sixteen and paise fifty only.	Each	917
20	Providing and fixing solid plastic seat with lid for pedestal type W.C. pan complete White solid plastic seat with lid with in all leads and lift of materials and as per direction of Engineer-in-charge.	1.00	571.00	Rupees Five hundred seventy one only.	Each	571
21	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete Flexible pipe 32 mm (Thirty two millimetre) dia with in all leads and lift of materials and as per direction of Engineer-in-charge.	4.00	101.10	Rupees One hundred one and paise ten only.	Each	404
22	Providing and fixing 600x450 mm (Six hundred x Four hundred fifty millimetre) bevelled edged mirror of superior glass (of approved quality) complete with 6 mm (Six millimetre) thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete with in all leads and lift of materials and as per direction of Engineer-in-charge.	2.00	1009.90	Rupees One thousand nine and paise ninety only.	Each	2020

23	Providing and fixing 600x120x5 mm (Six hundred x One hundred twenty x Five millimetre) glass shelf with edges round off, supported on anodised aluminium angle frame with C.P. brass brackets and guard rail complete fixed with 40 mm (Forty millimetre) long screws, rawl plugs etc., complete. with in all leads and lift of materials and as per direction of Engineer-in-charge.	2.00	660.60	Rupees Six hundred sixty and paise sixty only.	Each	1321
24	Providing and fixing C.P. brass long nose bib cock of approved quality conforming to IS standards and weighing not less than 810 gms (Eight hundred ten grams) 15 mm (Fifteen millimetre) nominal bore, Cera with in all leads and lift of materials and as per direction of Engineer-in-charge.	3.00	950.00	Rupees Nine hundred fifty only.	Each	2850
25	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 15mm (Fifteen millimetre) nominal bore, Cera with in all leads and lift of materials and as per direction of Engineer-in-charge.	6.00	700.00	Rupees Seven hundred only.	Each	4200
26	Providing and fixing unplasticised P.V.C. connection pipe with PTMT Nuts, collar and bush of approved quality and colour 15 mm (Fifteen millimetre) nominal bore with 45 cm (Forty five centimetre) length with in all leads and lift of materials and as per direction of Engineer-in-charge.	8.00	112.45	Rupees One hundred twelve and paise forty five only.	Each	900
27	Providing and fixing C.P. Centre hole wash basin mixture of approved quality conforming to IS standards and weighing not less than 810 gms (Eight hundred ten grams) 15 mm (Fifteen millimetre) nominal bore with in all leads and lift of materials and as per direction of Engineer-in-charge.	2.00	1500.00	Rupees One hundred forty seven and paise ninety only.	Each	3000
28	Providing and fixing vitreous china pedestal for wash basin complete recessed at the back for the reception of pipes and fittings with in all leads and lift of materials and as per direction of Engineer-in-charge.	1.00	933.60	Rupees Nine hundred thirty three and paise sixty only.	Each	934
29	Providing and fixing aluminium die cast body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 35 kg (Thirty five kilogram) and door width upto 700 mm (Seven hundred millimetre), with necessary accessories and screws etc. complete with in all leads and lift of materials and as per direction of Engineer-in-charge.	6.00	962.00	Rupees One hundred forty seven and paise ninety only.	Each	5775
	<b>Total</b>					<b>498100</b>

  
 Executive Engineer,  
 Kullu Division,  
 HP.PWD Kullu




53

**SCHEDULE OF QUANTITY**

Name of work:- Balance work of Additional Accommodation in judicial court complex kullu.  
(SH:- P/L pavers around the new building etc. )

Estimated cost:- Rs. 4,97,629.00  
Earnest money :- Rs. 10,000.00  
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead dressing of sides and bottom and backfilling in trenches with excavated suitable material with in all leads and lift of materials and as per direction of Engineer-in-charge.	169.86	222.90	Rupees Two hundred twenty two and paise ninety only	Per Cubic metre	37862.00
2	Stone soling properly hand packed filling interstices with tharanja stone and consolidating with power road roller to requested gradient and camber including spreading watering and roling of binding materials moorum or earth etc. with in all leads and lift of materials and as per direction of Engineer-in-charge.	32.04	1250.00	Rupees One thousand two hundred fifty and paise fifty only	Per Cubic metre	40050.00
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand): 6 graded stone aggregate 40 mm (Forty millimetre) nominal size) with in all leads and lift of materials and as per direction of Engineer-in-charge.	21.36	5700.00	Rupees Fifty seven thousand only	Per Cubic metre	121752.00
4	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc. of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm ( Fifty millimetre) thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand 60mm (Sixty millimetre) thick cement concrete paver block of M-35 grade with approved colour, design & pattern with in all leads and lift of materials and as per direction of Engineer-in-charge.	213.61	1394.90	Rupees One thousand three hundred ninety four and paise ninety only.	Per Square metre	297965.00
					Total	497629.00

  
Executive Engineer,  
Kullu Division,  
HP.PWD Kullu

SCHEDULE OF QUANTITY

Name of work:- Balance work of Additional Accommodation in judicial court complex Kullu.  
(SH:- P/F Panelling in top floor, entry gallery, conference hall & p/f pvc mat etc.)

Estimated cost:- Rs. 4,97,488.00  
Earnest money :- Rs. 10,000.00  
Time :- Two months.

Sr. No.	Description	Qty	Rate in		Unit	Amount
			Figure	Words		
1	Providing wood work in frames of false ceiling, partitions etc. sawn and fixed in position with necessary stainless steel screws etc. Sal wood/ hard wood with in all leads and lift of materials and as per direction of Engineer-in-charge.	0.57	122082.60	Rupees One lac twenty two thousand eighty two and paise sixty only.	Per Cubic metre	69587.00
2	Providing and fixing Australian pipne wood paneling manufacture tounge and grooved join in plain lining fixed on wood work complete with in all leads and lift of materials and as per direction of Engineer-in-charge.	119.58	2462.15	Rupees Two thousand four hundred sixty two and paise fifteen only.	Per Square metre	294424.00
3	French srit polishing two or more coats on new works including a coat of wood filler with in all leads and lift of materials and as per direction of Engineer-in-charge.	131.53	290.75	Rupees Two hundred ninety and paise seventy five only.	Per Square metre	38242.00
4	Providing and fixing wooden moulded beading to door and window frames with iron screws, plugs and priming coat on unexposed surface etc. complete :2nd class teak wood 50x12 mm (Fifty x Twelve millimetre) with in all leads and lift of materials and as per direction of Engineer-in-charge.	125.41	175.60	Rupees One hundred seventy five and paise sixty only.	Per Running metre	22022.00
5	Providing and fixing 2mm thick PVC antistatic vinyl Flooring plain or coloured, carbed or mosaic/metalised finish laid with approved adhesive on sub-floor (damp proofing treatment to be paid for separately with in all leads and lift of materials and as per direction of Engineer-in-charge.	38.80	1588.90	Rupees One thousand five hundred eighty eight and paise ninety only.	Per Square metre	61655.00

Name of work:- Special repair to stage at Pradershni ground Kullu.  
(SH:- P/F 18 mm thick ply board flooring over stage ).

Estimated cost:- Rs. 3,35,011.00  
Earnest money :- Rs. 6,800.00  
Time :- Two months.

**SCHEDULE OF QUANTITY**

Sr. No.	Description	Qty	Rate In		Unit	Amount
			Figure	Words		
1	Providing wood work in frames of false ceiling, partitions etc. sawn and fixed in position with necessary stainless steel screws etc. Sal wood/ hard wood with in all leads and lift of materials and as per direction of Engineer-in-charge.	0.79	122082.60	Rupees One lac twenty two thousand eighty two and paise sixty only.	Per Cubic metre	96689
2	Providing and fixing 18 mm (Eighteen millimetre) thick water proof commercial board in shelves/box for cup board with butt joints & fixing with nails & screws etc. complete with in all leads and lift of materials and as per direction of Engineer-in-charge.	127.25	1812.15	Rupees One thousand eight hundred twelve and paise fifteen only.	Per Square metre	230596
3	Providing and fixing wooden moulded beading to door and window frames with iron screws, plugs and priming coat on unexposed surface etc. complete ;2nd class teak wood 50x12 mm (Fifty x Twelve millimetre) with in all leads and lift of materials and as per direction of Engineer-in-charge.	44.00	175.60	Rupees One hundred seventy five and paise sixty only.	Per Running metre	7726
					Total	335011

  
Executive Engineer,  
Kullu Division  
HP.PWD Kullu