

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Scaled item rate tender on form No. 6 & 8 are hereby invited by the **Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan** on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HP PWD (B & R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **30.11.2023** up to **11:00 A.M.** And the same shall be opened on the same day at **04:00 P.M.** in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **29.11.2023** up to **4:00 P.M.** and the application for issue of tender form shall be received on **28.11.2023** up to **12:00 noon.** The applications for issue of tender forms accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates/Saving Account of the Post Office /Time Deposit account/FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 120 days.

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time limit
1.	Restoration of rain damages on link road from Chhughera to Kandi road Km 0/000 to 20/000 in Distt Kangra (HP) (SH:-Balance work of retaining wall in wire crates work in Km 5/465 to 5/485).	498240/-	10000/-	Two months
2.	Restoration of rain damages on link road from Gujrehra to Dadkar Km 0/000 to 4/015 in Distt Kangra (HP) (SH:-Balance work of improvement of road width by providing wall in wire crates work in Km 0/130 to 0/160).	499965/-	10000/-	Two months
3.	Restoration of rain damages on link road from Kandi Rihri Luhna har Km 0/000 to 7/000 in Distt Kangra (HP) (SH:-Improvement of road width by providing retaining wall in wire crates work in Km 1/780 to 1/802.50).	498325/-	10000/-	Two months
4.	Construction of Sports complex in Maharana Partap International School at Dharamgiri in Distt Kangra (HP) (Deposit work) (SH:-Construction of approach road and sitting arrangement).	499040/-	10000/-	Two months
5.	Construction of 50.00 mtrs span PSC box girder bridge over Baner Khad on link road from Naura to Thanpuri at RD 1/375 in Distt Kangra (HP) (SH:-Balance work of Jassour side abutment).	499993/-	10000/-	Three months
6.	Construction of 50.00 mtrs span PSC box girder bridge over Baner Khad on link road from Naura to Thanpuri at RD 1/375 in Distt Kangra (HP) (SH:-Balance work of Barai side abutment).	499998/-	10000/-	Three months
7.	Restoration of rain damages on link road from Samloti to Sarotari Km 0/000 to 4/600 in Distt Kangra (HP) (SH:-Construction of cement concrete berms and road side drain at various reaches between in Km 0/000 to 4/600).	4999604/-	10000/-	Two months
8.	Construction of New 120 Nos Girls Hostel at Dr R.P. Govt. Medical College at Tanda in Distt Kangra (HP) (Deposit work) (SH:-Balance work of providing and fixing stainless steel wire mesh and CPVC pipe fitting etc.)	238034/-	4800/-	Two months
9.	Restoration of rain damages on various roads under HP PWD Sub-Division Nagrota Bagwan in Distt Kangra (HP) (SH:-Providing and laying of hot applies thermoplastic paint strips (Under Telecom Deposit).	207700/-	4200/-	One month

Terms & Conditions:-

- The contractor/firm should be registered as or dealer GST No.
- The intending contractor / firm have to produce the copy of latest enlistment and renewal enlisted in HPPWD.
- If any of the date mentioned above happened to be Gazetted Holidays the same shall be processed on next working day.
- The Executive Engineer reserves the right to accept/reject any tender/application or all tenders without assigning any reason.
- The Contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand.
- Next tender will be issued only after completion of previous works in hand.

HIMSUCHANA AVAM & JAN SAMPARK

No.PW/NBD/TA/Tender/NIT/2023-24-

10976-11005

Dated/

(On behalf of Governor of Himachal Pradesh)

Copy to the following for information and necessary action:-

- The Principal Secy. (PW) to the Govt. of H.P. Shimla.
- The Engineer-in-Chief, HPPWD, Shimla.
- The Chief Engineer (KZ), HPPWD, Dharamshala.
- The Director, Information & Publications Department, H.P. Shimla
- The Executive Engineer (IT), Nigam Vihar Shimla 2 for information. He is requested to upload the same on the department website.
- The Superintending Engineer, 5th Circle, HPPWD, Palampur.
- The Principal, Dr. RPGMC, Tanda.
- The Deputy Commissioner, Kangra at Dharamshala.
- All the S.E.s/E.E.s under North Zone.
- The Sub-Divisional Officer(C) Nagrota Bagwan.
- The Block Development Office Nagrota Bagwan
- All the Assistant Engineer under this Division.
- The Drawing /Accounts Branch in this office.
- The Contractors concerned.
- Notice Board.

Executive Engineer
H.P.P.W.D. Tanda Division
at Nagrota Bagwan

Executive Engineer
H.P.P.W.D. Tanda Division
at Nagrota Bagwan

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 498240.00
 EARNEST MONEY :- ₹ 10000.00
 TIME LIMIT :- TWO MONTHS

NAME OF WORK :- Restoration of rain damages on link road from Chhughera to Kandi road Km 0/000 to 20/000 in Distt. Kangra (H.P.).
 SUB-HEAD :- Balance work of Retaining wall in wire crates work in Km 5/465 to 5/485

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
1	2	3	4	5	6	7
1	Providing and making Gabion structure with Mechanically Woven Double Twisted Hexagonal Shaped Wire mesh Gabion Boxes as per IS 16014:2012, MORTH Clause 2500, of required size, Mesh Type 10x12 (D=100 mm with tolerance of $\pm 2\%$) Zinc coated, Mesh wire diameter 3.0 mm (Three point zero millimetres), mechanically edged/selvedged with partitions at every 1m (One metre) interval and shall have minimum 10 numbers of openings per meter of mesh perpendicular to twist, tying with lacing wire of diameter 2.2mm, supplied @ 3% by weight of Gabion boxes, filled with boulders with least dimension of 200 mm, as per drawing, all complete as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals.	187.50 Cubic metres			Per cubic metre	7
2	Filling available excavated earth (excluding rock) intrenches or embankment in layers (each layer should not exceed 15 cm), with intermediate layer of compacted earth (Soil density of 98%) after every four layers of compacted depth of fly ash, sides & top layer of filling shall be done with earth having total minimum compacted thickness 30 cm or as decided by Engineer-in-charge, including compacting each layer by rolling/ramming and watering, all complete as per drawing and direction of Engineer -in - charge as per drawing and HP.PWD technical specifications and as directed by Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	18.00 Cubic metres			Per cubic metre	
TOTAL :-						



 Executive Engineer,
 H.P.P.W.D., Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 499965.00
EARNEST MONEY :- ₹ 10000.00
TIME LIMIT :- TWO MONTHS

NAME OF WORK :- Restoration of rain damages on link road from Gujrehra to Dadkar Km 0/000 to 4/015 in Distt. Kangra (H.P.).
SUB-HEAD :- Balance work of improvement of road width by providing Retaining wall in wire crates work in Km 0/130 to 0/160

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
1	2	3	4	5	6	7
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within any lead including entire carriage of materials within all leads, lifts and other incidentals.	28.05 Cubic metres			Per cubic metre	7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (One Cement : Four coarse sand) : Eight graded stone aggregate 20 mm (Twenty millimetres) nominal size as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals.	45.00 Cubic metres			Per cubic metre	
3	Providing and making Gabion structure with Mechanically Woven Double Twisted Hexagonal Shaped Wire mesh Gabion Boxes as per IS 16014:2012, MORTH Clause 2500, of required size, Mesh Type 10x12 (D=100 mm with tolerance of $\pm 2\%$) Zinc coated, Mesh wire diameter 3.0 mm (Three point zero millimetres), mechanically edged/selvedged with partitions at every 1m (One metre) interval and shall have minimum 10 numbers of openings per meter of mesh perpendicular to twist, tying with lacing wire of diameter 2.2mm, supplied @ 3% by weight of Gabion boxes, filled with boulders with least dimension of 200 mm, as per drawing, all complete as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals.	117.19 Cubic metres			Per cubic metre	
4	Filling available excavated earth (excluding rock) intranches or embankment in layers (each layer should not exceed 15 cm), with intermediate layer of compacted earth (Soil density of 98%) after every four layers of compacted depth of fly ash, sides & top layer of filling shall be done with earth having total minimum compacted thickness 30 cm or as decided by Engineer-in-charge, including compacting each layer by rolling/ramming and watering, all complete as per drawing and direction of Engineer -in - charge as per drawing and HP.PWD technical specifications and as directed by Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	18.00 Cubic metres			Per cubic metre	
TOTAL :-						499965.00


Executive Engineer,
H.P.P.W.D., Division,
Tanda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST: - ₹ 498325.00
EARNEST MONEY :- ₹ 10000.00
TIME LIMIT :- TWO MONTHS

NAME OF WORK :- Restoration of rain damages on link road from Kandi Rihri Luhna Har Km 0/000 to 7/000 in Distt. Kangra (H.P.)
SUB HEAD :- Improvement of road width by providing Retaining wall in wire crates work in Km 1/780 to 1/802.50

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
1		3	4	5	6	7
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within any lead including entire carriage of materials within all leads, lifts and other incidentals.	59.02 Cubic metres			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (One Cement : Four coarse sand) : Eight graded stone aggregate 20 mm (Twenty millimetres) nominal size as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals.	25.31 Cubic metres			Per cubic metre	
3	Providing and making Gabion structure with Mechanically Woven Double Twisted Hexagonal Shaped Wire mesh Gabion Boxes as per IS 16014:2012.MORTH Clause 2500, of required size, Mesh Type 10x12 (D=100 mm with tolerance of ± 2%) Zinc coated, Mesh wire diameter 3.0 mm (Three point zero millimetres), mechanically edged/selvedged with partitions at every 1m (One metre) interval and shall have minimum 10 numbers of openings per meter of mesh perpendicular to twist, tying with lacing wire of diameter 2.2mm, supplied @ 3% by weight of Gabion boxes, filled with boulders with least dimension of 200 mm, as per drawing, all complete as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals.	140.63 Cubic metres			Per cubic metre	
4	Filling available excavated earth (excluding rock) intrtrenches or embankment in layers (each layer should not exceed 15 cm), with intermediate layer of compacted earth (Soil density of 98%) after every four layers of compacted depth of fly ash, sides & top layer of filling shall be done with earth having total minimum compacted thickness 30 cm or as decided by Engineer-in-charge, including compacting each layer by rolling/ramming and watering, all complete as per drawing and direction of Engineer -in - charge.as per drawing and HP.PWD technical specifications and as directed by Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	40.50 Cubic metres			Per cubic metre	
TOTAL :-						


Executive Engineer,
H.P.P.W.D., Division,
Tanda at Nagrota Bagwaan.

Schedule of Quantity

ESTIMATED COST :- ₹ 499040.00
 EARNEST MONEY :- ₹ 10000.00
 TIME LIMIT :- TWO MONTHS

NAME OF WORK :- Construction of Sports Complex in Maharana Partap International School at Dharamgiri in Distt. Kangra (H.P.) (Deposit work)
 SUB HEAD :- Construction of approach road and sitting arrangement etc;

S. No.	Description of items	Quantity	In fig. 4	Rate In words 5		Unit	Amount
1	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering. Plain cement concrete 1:3:6 (One Cement : Three coarse sand : Ten graded stone aggregate 20 mm (Twenty millimetres) nominal size complete as per drawing and HP.PWD technical specifications and as directed by Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	3 77.89 Cubic metres	4	5	6	Per cubic metre	7
2	Providing and laying concrete for plain reinforcement concrete in open foundation complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 PCC Grade (M-20) (M-twenty) nominal mix 1:2:4 (One cement: Two sand: Four graded/crushed stone aggregate) 40mm (Forty millimetres) thickness as per HPPWD technical specification and as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals.	25.60 Cubic meters				Per cubic metre	
TOTAL :-							


 Executive Engineer,
 H.P.P.W.D., Division,
 Tanda at Nagroa Bagwath.

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹. 499993.00
 EARNEST MONEY :- ₹. 10000.00
 TIME LIMIT : THREE MONTHS

NAME OF WORK :- Construction of 50.00 mtrs span PSC Box Girder bridge over Baner Khad on link road from Naura to Thanpuri at RD 1/375 in Distt. Kangra (H.P.).
 SUB HEAD:- Balance work of Jassour side abutment.

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
1	2 Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (One cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimetres nominal size) as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	3 102.38 Cubic metres	4	5	6 Per cubic metre	7
2	Construction of embankment with approved materials obtained from borrow pits with a lift upto 1.5m (One point five meters) transport to sill spreading grading to required slope and compacted to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000m (One thousand meters) as per Technical Specification Clause 301.5, as directed by the Engineer-in-Charge, including entire carriage of materials within all leads, lifts and other incidentals.	470.65 Cubic metres			Per cubic metre	
3	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals.	65.00 Running metres			Per running metre	
TOTAL:-						



 Executive Engineer,
 H.P.P.W.D., Division,
 Tanda at Nagroa Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹. 499998.00
 EARNEST MONEY :- ₹. 10000.00
 TIME LIMIT : THREE MONTHS

NAME OF WORK :- Construction of 50.00 mtrs span PSC Box Girder bridge over Baner Khad on link road from Naura to Thanpuri at RD 1/375 in Distt. Kangra (H.P.).
SUB HEAD :- Balance work of Barai side abutment.

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
1	2	3	4	5	6	7
1	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (One cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimetres nominal size) as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	100.35 Cubic metres			Per cubic metre	
2	Construction of embankment with approved materials obtained from borrow pits with a lift upto 1.5m (One point five meters) transport to sill spreading grading to required slope and compacted to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000m (One thousand meters) as per Technical Specification Clause 301.5, as directed by the Engineer-in-Charge, including entire carriage of materials within all leads, lifts and other incidentals.	514.25 Cubic metres			Per cubic metre	
3	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals.	60.00 Running metres			Per running metre	
TOTAL:-						


 Executive Engineer,
 H.P.P.W.D., Division,
 Tanda at Nagroa Bagwan.

Schedule of Quantity

ESTIMATED COST :- ₹ 499604.00
EARNEST MONEY :- ₹ 10000.00
TIME LIMIT : TWO MONTHS

NAME OF WORK :- Restoration of rain damages on link road from Samloti to Sarotari Km 0/000 to 4/600 in Distt. Kangra (H.P.)
SUB-HEAD :- Construction of cement concrete berms and road side drain at various reaches between in Km 0/000 to 4/600

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
		3	4	5	6	7
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within any lead complete as per drawing and HP.PWD technical specifications and as directed by Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	44.96 Cubic metres			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering .Plain cement concrete 1:3:6 (One Cement : Three coarse sand : Ten graded stone aggregate 20 mm (Twenty millimetres) nominal size complete as per drawing and HP.PWD technical specifications and as directed by Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	27.35 Cubic metres			Per cubic metre	
3	Providing and laying 450mm (Four hundred fifty millimetre) dia half round NP2 class R.C.C. pipes for drainage purpose fixed over a bed of cement concrete 1:3:6 (One Cement : Three coarse sand : Ten graded stone aggregate 20 mm (Twenty millimetres) nominal size bedding complete as per drawing and HP.PWD technical specifications and as directed by Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	110.00 Running metre			Per running metre	
4	Providing, laying, spreading and compacting stone aggregate of size 63mm to 45mm (sixty three millimeter to forty five millimeter) Grading-II size [75mm (seventy five millimeters) compacted thickness] to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber applying and brooming, stone screening type-A of size 13.2mm (thirteen point two millimetres) nominal size at the rate of 0.22 cum (zero point twenty two) cubic metres per 10 sqm (per ten square metres) and binding material at the rate 0.06 cum (zero point zero six cubic metre) to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specifications clause No. 405 as per drawing and HP.PWD technical specifications and as directed by Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	16.88 Cubic metres			Per cubic metre	
5	Providing and laying concrete for plain reinforcement concrete in open foundation complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 PCC Grade (M-20) (M-twenty) nominal mix 1:2:4 (One cement: Two sand: Four graded/crushed stone aggregate) 40mm (Forty millimetres) thickness complete as per drawing and HP.PWD technical specifications and as directed by Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	33.75 Cubic metres			Per cubic metre	
TOTAL :-						

Executive Engineer,
H.P.P.W.D., Division,
Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 238034.00
 EARNEST MONEY :- ₹ 4800.00
 TIME LIMIT : TWO MONTHS

NAME OF WORK :- Construction of New 120 Nos. Girls Hostel at Dr. R.P.Govt. Medical College at Tanda in District Kangra, (H.P.).
 SUB-HEAD :- Balance work of providing and fixing stainless steel wire mesh and CPVC pipe fitting etc;

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and fixing Apature stainless steel wire gauge of 0.5 mm (Zero point five millimetre) dia wire and 1.4mm (One point four millimetre) on both side in aluminium fly wire mesh shutter for Door, windows, and clerestory windows alongwith necessary fitting complete as per detail drawing, as required at site including carriage of material within all leads, lifts and other incidentals, as per approved specifications, drawing, design and as directed by the Engineer-in-charge.	245.33 Square metres			Per Square metre	
2	Providing and fixing 50mm (Fifty millimetre) Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals.	62.80 Running metres			Per running meter	
3	Providing and fixing CPVC Tee including cutting and threading the pipe etc; including necessary fitting complete as per direction of Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	8 Numbers			Each	
4	Providing and fixing CPVC Elbow including cutting and threading the pipe etc; including necessary fitting complete as per direction of Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	34 Numbers			Each	
5	Providing and fixing CPVC Union including cutting and threading the pipe etc; including necessary fitting complete as per direction of Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	6 Numbers			Each	
6	Providing and fixing CPVC Nipple (Socket Type) including cutting and threading the pipe etc; including necessary fitting complete as per direction of Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	12 Numbers			Each	
TOTAL :-						


Executive Engineer,
 H.P.P.W.D. Division,
 Tanda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST :- Rs. 207700.00
 EARNEST MONEY :- Rs. 4200.00
 TIME LIMIT : ONE MONTH

NAME OF WORK :- Restoration of rain damages on various roads under HPPWD Sub-Division, Nagrota Bagwan in Distt Kangra (HP).
 SUB HEAD :- Providing and laying of hot applied thermoplastic paint strips. (Under Telecom Deposit).

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig	In words		
1	2 Providing and applying 2.5mm (Two point five millimetre) thick road marking strips (retro-reflective) of specified shade/ colour using hot thermoplastic material by fully/ semi automatic thermoplastic paint applicator machine fitted with profile shoe, glass beads dispenser, propane tank heater and profile shoe heater, driven by experienced operator on road surface including cost of material, labour, T&P, cleaning the road surface of all dirt, seals, oil, grease and foreign material etc. complete as per direction of Engineer-in-charge and accordance with applicable specifications and as directed by the Engineer-in-charge including carriage of material within all leads, lifts, height and other incidentals. The rate inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government and rectifying defects noticed within two years as per clause 35 (III) of standard bidding document.	3 335.00 Square metres	4	5	6 Per square metre	7
TOTAL :-						


 Executive Engineer,
 H.P.P.W.D., Division,
 Tanda at Nagrota Bagwan.