

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No:- PW-NHD-HMR-GA-NIT/2023-24

6686

Dated: 04/11/2023

To

✓ The Executive Engineer, (IT Cell),
Nigam Vihar HP Shimla- 02.

Subject:-

Publication of Notice Inviting Tenders.

Enclosed Please find herewith the tender notice for the works mentioned in notice inviting tender for uploading on departmental website. The works mentioned in the tender notice are of urgent nature and invited keeping in view public interest. These tenders are invited to repair the road surface damaged due to heavy rains during monsoon 2023 and to keep the road traffic worthy and providing good Riding Quality to toad users.



Executive Engineer,
National Highway Division,
HP.PWD Hamirpur.

HIMACHAL PRADESH
Public Works Department
NOTICE INVITING TENDER


Sealed Tenders on item rate basis are hereby invited on behalf of Governor of H.P. by **Executive Engineer, NH Division, HPPWD, Hamirpur (H.P)** from the experienced contractor/ firms enlisted in appropriate class with HPPWD for the following works. The tender shall be received in this office on **14-11-2023** up to **11.00 A.M** and the same shall be opened on the same day at **11:30 A.M.** in the presence of Contractor/Firms or their authorized/representatives who wish to be present at the time of opening of tender. The application for issue of tender document shall be received on dated **13-11-2023** up to **12:30 P.M.** on cash payment (Non-Refundable) and tender document will be issued on **13-11-2023** up to **4:00 P.M.** If the office happens to be closed on the scheduled date the tender form document will be sold/ opened on the next working day at the same time and venue.

Sr. No	Name of work	Estimated cost	Earnest money	Time allowed	Cost of form
1	Annual repair and Maintenance on NH-70 (New NH-03) km. 58/400 to 114/00 (SH:- Repairing of Patch/Pot holes with Bituminous Concrete in km. 99/715 to 99/970).	4,79,874.00	10000.00	One Month	350/-
2	Annual repair and Maintenance on NH-70 (New NH-03) km. 58/400 to 114/00 (SH:- Repairing of Patch/Pot holes with Bituminous Concrete in km. 95/050 to 95/290).	4,78,664.00	10000.00	One Month	350/-
3	Annual repair and Maintenance on NH-70 (New NH-03) km. 58/400 to 114/00 (SH:- Repairing of Patch/Pot holes with Bituminous Concrete in km. 95/980 to 96/223.70).	4,78,909.00	10000.00	One Month	350/-
4	Annual repair and Maintenance on NH-70 (New NH-03) km. 58/400 to 114/00 (SH:- Repairing of Patch/Pot holes with Bituminous Concrete in km. 94/650 to 94/890).	4,78,664.00	10000.00	One Month	350/-

Draft notice inviting/ specification special conditions can be seen in this office on any working day between **11:00 AM to 4:00 PM** ambiguous/ Telegraphic conditional tenders by fax shall not be entertained/ considered in any case. The contractors/ firms are requested to insert the rate of each item in words as well as in figure, failing which Executive Engineer, reserves the right to accept/ reject any or all tenders. The intending contractors/ firms are requested to see the site of work before submitting the tenders. All the application must accompany with the Earnest Money in the shape of call at deposit/ N.S.C. purchased from any post office in H.P/FDR from any nationalized bank duly pledged in favour of Executive Engineer. The application without earnest money will not be entertained and out rightly rejected.

CONDITIONS: - The following document are required to be attached with the application: -

- 1 A copy of valid enlistment and renewal certificate.2. A copy of GST.
- 3 Any other information as desired by the Executive Engineer. Any application not accompanied by above documents shall not be entertained. The tender shall be issued to those contractors/ firms who are found eligible, suitable and competent. The decision of the Executive Engineer, regarding suitability, eligibility and competence of the contractor/ firm applying for issue of tenders shall be final. In case, of any information supplied by the contractor/ firm, is found false at any stage the tender is liable to be rejected and action taken against contractor/firm.


Executive Engineer,
National Highway Division,
HP.PWD Hamirpur.

SCHEDULE OF QUANTITY

Name of work :- Annual repair and Maintenance on NH-70 (New NH - 03) Km 58/400 to 114/00(SH:-Repairing of Patch/ Pot holes with Bituminious concrete in Km.99/715 to 99/970)

Name of work :- Annual repair and Maintenance on NH-70 (New NH - 03) Km 58/400 to 114/00(SH:-Repairing of Patch/ Pot holes with Bituminious concrete in Km.99/715 to 99/970)		Estimated Cost:- Rs. Earnest Money:- Rs.		479874.00
		Time Limit:		10000.00
		Rate		One Month
rNo.	Description of item.	Qty.	In Figure	Unit
1	Providing and applying tack coat using bitumen emulsion conforming to IS:8887, using emulsion pressure distributor including preparing the surface and cleaning with mechanical broom. With rapid setting bitumen emulsion -On WBM/MMM @ 0.25kg/sqm (Zero point two five kilogramme per square metre) including entire carriage of materials within all leads and lifts and as per drawings and MORT&H specifications as per the direction of Engineer-in-Charge including all incidentals.	1318.35		Per square metre
2	Providing and laying Bituminous concrete 30mm (Thirty millimetre) compacted thickness with bitumen of grade VG-30 (VISCOSITY GRADE-THIRTY) @ 5.5% (Five point five percent) (percentage by weight of total mix) and lime filler @ 2% (Two percent) (percentage by weight of Aggregate) using crushed stone aggregates of specified grading, premixed with bituminous binder and filler prepared in batch Type Hot Mix Plant of 100-120 (One Hundred - One hundred twenty) TPH capacity, transporting the hot mix to work site by tippers, laying with paver finisher equipment with electronic sensor to the required grade, level and alignment and rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction and density as per specification complete and as per directions of Engineer-in-Charge including entire carriage of materials within all leads and lifts and as per drawings and MORT&H specifications as per the direction of Engineer-in-Charge including all incidentals.	39.55		Per Cubic metre
G.Total				


Executive Engineer,
National Highway Division,
HP.PWD., Hamirpur (HP)

SCHEDULE OF QUANTITY

Name of work :- Annual repair and Maintenance on NH-70 (New NH - 03) Km 58/400 to 114/00(SH):-Repairing of Patch/ Pot holes with Bituminious concrete in Km.95/050 to 95/290)									
				Estimated Cost:- Rs.		478664.00			
				Earnest Money:- Rs.		10000.00			
				Time Limit:		One Month			
rNo.	Description of item.	Qty.	In Figure	Rate	In Words	Unit	Amount		
1	Providing and applying tack coat using bitumen emulsion conforming to IS:8887, using emulsion pressure distributor including preparing the surface and cleaning with mechanical broom. With rapid setting bitumen emulsion -On WB/MW/MM @ 0.25kg/sqm (Zero point two five kilogramme per square metre) including entire carriage of materials within all leads and lifts and as per drawings and MORT&H specifications as per the direction of Engineer-in-Charge including all incidentals.	1315.20				Per square metre			
2	Providing and laying Bituminous concrete 30mm (Thirty millimetre) compacted thickness with bitumen of grade VG-30 (VISCOSITY GRADE-THIRTY) @ 5.5% (Five point five percent) (percentage by weight of total mix) and lime filler @ 2% (Two percent) (percentage by weight of Aggregate) using crushed stone aggregates of specified grading, premixed with bituminous binder and filler prepared in batch Type Hot Mix Plant of 100-120 (One Hundred - One hundred twenty) TPH capacity, transporting the hot mix to work site by tippers, laying with paver finisher equipment with electronic sensor to the required grade, level and alignment and rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction and density as per specification complete and as per directions of Engineer-in-Charge including entire carriage of materials within all leads and lifts and as per drawings and MORT&H specifications as per the direction of Engineer-in-Charge including all incidentals.	39.45				Per Cubic metre			
G.Total								478664.00	


 Executive Engineer,
 National Highway Division,
 HP.PWD., Hamirpur (HP)

SCHEDULE OF QUANTITY

Name of work :- Annual repair and Maintenance on NH-70 (New NH - 03) Km 58/400 to 114/00(SH:-Repairing of Patch/ Pot holes with Bituminious concrete in Km.95/980 to 96/223.70)									
rNo.	Description of item.	Qty.	In Figure	Estimated Cost:- Rs.		Earnest Money:- Rs.		One Month	
				Rate	In Words	Time Limit:	Unit	Amount	
	Providing and applying tack coat using bitumen emulsion conforming to IS:8887, using emulsion pressure distributor including preparing the surface and cleaning with mechanical broom. With rapid setting bitumen emulsion -On WBMA/MMM @ 0.25kg/sqm (Zero point two five kilogramme per square metre) including entire carriage of materials within all leads and lifts and as per drawings and MORT&H specifications as per the direction of Engineer-in-Charge including all incidentals.	1315.98					Per square metre		478909.00
2	Providing and laying Bituminous concrete 30mm (Thirty millimetre) compacted thickness with bitumen of grade VG-30 (VISCOSITY GRADE-THIRTY) @ 5.5% (Five point five percent) (percentage by weight of total mix) and lime filler @ 2% (Two percent) (percentage by weight of Aggregate) using crushed stone aggregates of specified grading, premixed with bituminous binder and filler prepared in batch Type Hot Mix Plant of 100-120 (One Hundred - One hundred twenty) TPH capacity, transporting the hot mix to work site by tippers, laying with paver finisher equipment with electronic sensor to the required grade, level and alignment and rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction and density as per specification complete and as per directions of Engineer-in-Charge including entire carriage of materials within all leads and lifts and as per drawings and MORT&H specifications as per the direction of Engineer-in-Charge including all incidentals.	39.47					Per Cubic metre		10000.00
G.Total									


 Executive Engineer,
 National Highway Division,
 HP.PWD., Hamirpur (HP)

SCHEDULE OF QUANTITY

Name of work :- Annual repair and Maintenance on NH-70 (New NH - 03) Km 58/400 to 114/00(SH:-Repairing of Patch/ Pot holes with Bituminious concrete in Km.94/650 to 94/890)				Estimated Cost:- Rs.		478664.00
				Earnest Money:- Rs.		10000.00
				Time Limit:		One Month
SrNo.	Description of item.	Qty.	In Figure	Rate		Unit
				In Words		
1	Providing and applying tack coat using bitumen emulsion conforming to IS:8887, using emulsion pressure distributor including preparing the surface and cleaning with mechanical broom. With rapid setting bitumen emulsion -On WBM/WMM @ 0.25kg/sqm (Zero point two five kilogramme per square metre) including entire carriage of materials within all leads and lifts and as per drawings and MORT&H specifications as per the direction of Engineer-in-Charge including all incidentals.	1315.20				Per square metre
2	Providing and laying Bituminous concrete 30mm (Thirty millimetre) compacted thickness with bitumen of grade VG-30 (VISCOSITY GRADE-THIRTY) @ 5.5% (Five point five percent) (percentage by weight of total mix) and lime filler @ 2% (Two percent) (percentage by weight of Aggregate) using crushed stone aggregates of specified grading, premixed with bituminous binder and filler prepared in batch Type Hot Mix Plant of 100-120 (One Hundred - One hundred twenty) TPH capacity, transporting the hot mix to work site by tippers, laying with paver finisher equipment with electronic sensor to the required grade, level and alignment and rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction and density as per specification complete and as per directions of Engineer-in-Charge including entire carriage of materials within all leads and lifts and as per drawings and MORT&H specifications as per the direction of Engineer-in-Charge including all incidentals.	39.45				Per Cubic metre
G.Total						


 Executive Engineer,
 National Highway Division,
 HP.PWD., Hamirpur (HP)