

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER

Sealed **percentage rate** tender on form No. 6 and 7/8 are hereby invited by the Executive Engineer (NH) Division HPPWD Nahan on behalf of Governor of HP for the following works from approved and eligible contractor enlisted in HPPWD, so as to reach in this office on **15.11.2023** up to 11:00 AM and shall be opened on the same day at 11.30 AM in the presence of intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (non refundable) up to **14.11.2023 04:00 PM**

The earnest money in the shape of FDR/TDR of any Bank in H.P. duly pledged in favour of Executive Engineer NH Division HP.PWD Nahan must be accompanied with the each tender. Conditional tender and tender received without earnest money will be rejected. The undersigned reserves the right to reject any or all tenders without assigning the reason. The offer of the tender will be kept opened for 75 days.


Sr. No.	Name of works	Estimated Cost	Earnest Money	Time Limit	Eligible Class of contractor	Cost of Form
1	Ordinary repair to Nahan Do Sarka Sarahan Kumarhatti Road on NH 907A Km 0/00 to 78/00 (SH:- Repair of Pot Holes in Km 20/00 to 28/00).	4,98,894/-	10000/-	15 days	All Classes	350/-
2	Ordinary repair to Nahan Do Sarka Sarahan Kumarhatti Road on NH 907A Km 0/00 to 78/00 (SH:- Repair of Pot Holes in Km 30/00 to 33/00).	4,99,785/-	10000/-	15 days	All Classes	350/-
3	Ordinary repair to Nahan Do Sarka Sarahan Kumarhatti Road on NH 907A Km 0/00 to 78/00 (SH:- Repair of Pot Holes in Km 42/00 to 61/00).	4,99,002/-	10000/-	15 days	All Classes	350/-
4	Ordinary repair to Nahan Do Sarka Sarahan Kumarhatti Road on NH 907A Km 0/00 to 78/00 (SH:- Repair of Pot Holes in Km 64/00 to 70/00).	4,98,843/-	10000/-	15 days	All Classes	350/-
5	Ordinary repair to Nahan Do Sarka Sarahan Kumarhatti Road on NH 907A Km 0/00 to 78/00 (SH:- Repair of Pot Holes in Km 70/00 to 75/00).	4,99,942/-	10000/-	15 days	All Classes	350/-

CERTIFICATE:- It is certified that the tenders of above work are exigency/emergent nature and in public interest.

Terms & Conditions:-

1. The Contractors/Bidders must quoted their Permanent Income Tax Account Number/ GST number on the tender alongwith copy of the same be attached with the application.
2. The Contractors/Firms should attach copy of the Registration/Renewal with the application.
3. The contractor/bidders should quote his rates Both in Figures and words, where there is any discrepancy between the rates in figures and words, the rates in words will be governed.
4. The contractors/bidders must inspect the site to ascertain/familiar the site conditions, accessibility etc. before quoting the bid/tender.
5. Conditional and telegraphic tender shall not be accepted and rejected straightway. Tender received after due date and time will be rejected.
6. The contractor/firms should have to produce the details of works in hand in HP. PWD, and its position thereof alongwith application.
7. The tender documents shall be issued to only those contractors who does not have more than two works in hand in any PWD Circle/ Division worth Rs. 1.00 Crore each.
8. The Contractor shall have to establish testing laboratory at site for the day to day testing of material.
9. The offer shall remain valid upto 75 days.

10. The provision of guidelines issued vide the Principal Secretary (PW) to the Govt. of H.P, Shimla vide notification No. PBW (B) A (3) 1/2020-I dated Shimla-2 the 22nd July, 2020 and 07.10.2021 regarding adoption of CPWD work manual 2019 & other publication of CPWD in HPPWD and others as published by the Govt. from time to time Shall also be applicable.
11. The Executive Engineer reserve the right to reject any or all the tenders without assigning any reason.



Executive Engineer
NH Division HPPWD
Nahan

For & on behalf of Governor of Himachal Pradesh

No. PW/NHD-NHN/TA-Tender Notice/ 2022-23: ~~3882~~ -3922 dated: 04-11-2023

Copy along with NIT is forwarded to the following for kind information and necessary action please:-

- 1 The Engineer in Chief HPPWD Nirman Bhawan, Niagam Bihar Shimla.
- 2 The Chief Engineer (NH) HPPWD Shimla please.
- 3 The Deputy Commissioner, Sirmour at Nahan please.
- 4 The Superintending Engineer (NH) Circle HPPWD Shimla.
- 5 The Executive Engineer (IT Cell), to the Engineer-in-Chief HPPWD, Nigam Vihar, HPPWD Shimla-2 alongwith Schedule of Quantity through (email) for taking necessary action in view of Principal Secretary (PW) to the H.P. notification No. PBW (B) A (3) dated 16 July, 2021 for uploading of Notice Inviting Tender on departmental website please.
- 6 The Sub-Divisional Magistrate Nahan/ Paonta Sahib/Pachhad please.
- 7 The District Panchayat Officer, Nahan please.
- 8 The Executive Officer, Municipal Committee Nahan/ Paonta Sahib please.
- 9 All the Assistant Engineer under this division to display on their respective Notice Boards.
- 10 Notice Board of this Office.



Executive Engineer
NH Division HPPWD
Nahan

JS.No.1

SCHEDULE OF QUANTITY
Name of work:- Ordinary repair to Nahan Do Sarka Sarahan Kumartatti road on NH 907A Km 0/00 to 78/00 (SH:- Repair of Pot Holes in Km 20/00 to 28/00)

Sr.No	Description of item/Sub Head	Quantity	Unit	Estimated cost :-		Total Amount in word
				Earnest Money :-	RS.498894/- only	
1	2	3	4	Time Limit :-	15 Days.	7
				Estimate Rate	Total Amount	
1	Providing and applying tack coat with bitumen emulsion RS-1 using emulsion pressure distributor at the rate of 0.20 kg per sqm on the prepared bituminous/granular surface cleaned with mechanical broom including carriage of all labour equipments and materials to various location including all taxes, MC taxes etc through all modes of transportation in all leads and lifts, including all incidental charges as per the direction and entire satisfaction of the Engineer-in-charge. For Patch work & Slurry Seal	878.35	Per Sqm	16.80	14756.00	Fourteen thousand seven hundred fifty six only
2	Providing and laying slurry seal consisting of a mixture of line aggregates, Portland cement filler, bituminous emulsion and water on a road surface including cleaning of surface, mixing of slurry seal in a suitable mobile plant, laying and compacting to provide even riding surface including carriage of all labour equipments and materials to various location including all taxes, MC taxes etc through all modes of transportation in all leads and lifts, including all incidental charges as per the direction and entire satisfaction of the Engineer-in-charge.	100.20	Per Sqm	84.00	8417.00	Eight thousand four hundred seventeen only
3	Providing and laying 40mm thick Bituminous Concrete Grading - II Providing and laying bituminous concrete with higher capacity batch type hot mix plant using crushed aggregates of specified grading, premixed with bituminous binder @ 5.4 Percent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 507 complete in all respects including carriage of all labour equipments and materials to various location including all taxes, MC taxes etc through all modes of transportation in all leads and lifts, including all incidental charges as per the direction and entire satisfaction of the Engineer-in-charge.	31.13	Per Cubic metre	15281.75	475721.00	Four lakhs seventy five thousand seven hundred twenty one only
Quoted Rate % (Percentage) in Figures		Total :-			498894.00	Four lakhs ninety eight thousand eight hundred ninety four only
Quoted Rate % (Percentage) in Words			(*)/(%)			

The contractor shall procure all the materials conforming to specification MORTH&H at his own risk and cost. All the rates including octroi, royalty, malkhana, toll tax, GST or other taxes imposed by the Government.



Executive Engineer
 NH Division
 HPPWD Nahan

SCHEDULE OF QUANTITY

Name of work:- Ordinary Repair to Nahan -Do Sarika-Sarahan-Kumathatti road on NH 907A Km 0/0 to 78/0 in the state of Himachal Pradesh. (Sl:- Repair of pot Holes in KM 30/00 to 33/00)

SCHEDULE OF QUANTITY						
Name of work:- Ordinary Repair to Nahan -Do Sarka-Sarahan-Kumarhathi road on NH 907A km 0/0 to 78/0 in the state of Himachal Pradesh. (SH:- Repair of pot Holes in KM 30/00 to 33/00)						
				Estimated cost :-		Rs.499785/- only
				Earnest Money :-		RS.10000/-only
				Time Limit :-		15 Days
Sr.No	Description of item/Sub Head	Quantity	Unit	Estimate Rate	Total Amount	Total Amount in word
1	2	3		4	5	7
1	Providing and applying tack coat with bitumen emulsion RS-I using emulsion pressure distributor at the rate of 0.20 kg per sqm on the prepared bituminous/granular surface cleaned with mechanical broom including carriage of all labour equipments and materials to various location including all taxes, MC taxes etc through all modes of transportation in all leads and lifts, including all incidental charges as per the direction and entire satisfaction of the Engineer-in-charge.	795.65	Per Sqm	16.80	13367.00	Thirteen thousand three hundred sixty seven only
3	Providing and laying 40mm thick Bituminous Concrete Grading -II Providing and laying bituminous concrete with higher capacity batch type hot mix plant using crushed aggregates of specified grading, premixed with bituminous binder @ 5.4 Percent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 507 complete in all respects including carriage of all labour equipments and materials to various location including all taxes, MC taxes etc through all modes of transportation in all leads and lifts, including all incidental charges as per the direction and entire satisfaction of the Engineer-in-charge.	31.83	Per Cubic metre	15281.75	486418.00	Four lakhs eighty six thousand four hundred eighteen
Total :-					499785.00	Four lakhs ninety nine thousand seven hundred eighty five only
Quoted Rate % (Percentage) in Figures		(+) / (-)				
Quoted Rate % (Percentage) in Words						

The contractor shall procure all the materials conforming to specification MORTH at his own risk and cost. All the rates including octroi, royalty, malikana, toll tax, GST or other taxes imposed by the Government.


 Executive Engineer
 NH Division
 HPPWD Nahan

Vol. No. 3


SCHEDULE OF QUANTITY

Name of Work:- Ordinary Repair to Nahan -Do Sarika-Sarahan-Kumarhatti road on NH 907A Km 0/0 to 78/0 in the state of Himachal Pradesh. (SH:- Repair of pot Holes in KM 42/00 to 61/00)

Estimated cost :- Rs.499002/- only
Earnest Money :- RS.10000/-only
15 Days.

Sr.No	Description of item/Sub Head	Quantity	Unit	Estimate Rate	Total Amount	Total Amount in word
		2				
1	Providing and applying tack coat with bitumen emulsion RS-I using emulsion pressure distributor at the rate of 0.20 kg per sqm on the prepared bituminous/granular surface cleaned with mechanical broom including carriage of all labour equipments and materials to various location including all taxes, MC taxes etc through all modes of transportation in all leads and lifts, including all incidental charges as per the direction and entire satisfaction of the Engineer-in-charge.	3	Per Sqm	16.80	13348.00	Thirteen thousand three hundred forty eight only
3	Providing and laying 40mm thick Bituminous Concrete Grading -II Providing and laying bituminous concrete with higher capacity batch type hot mix plant using crushed aggregates of specified grading, premixed with bituminous binder @ 5.4 Percent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 507 complete in all respects including carriage of all labour equipments and materials to various location including all taxes, MC taxes etc through all modes of transportation in all leads and lifts, including all incidental charges as per the direction and entire satisfaction of the Engineer-in-charge.	31.78	Per Cubic metre	15281.75	485654.00	Four lakhs eighty five thousand six hundred fifty four only
Total :-					499002.00	Four lakhs ninety nine thousand two only
Quoted Rate % (Percentage) in Figures		(+) / (-)				
Quoted Rate % (Percentage) in Words						

The contractor shall procure all the materials conforming to specification MORTH at his own risk and cost. All the rates including octroi, royalty, malkhana, toll tax, GST or other taxes imposed by the Government



Executive Engineer
NH Division
HPPWD Nahan

SCHEDULE OF QUANTITY

Name of work:- Ordinary Repair to Nahan -Do Sarka-Sarahan-Kumarhatti road on NH 907A km 0/0 to 78/0 in the state of Himachal Pradesh. (SH:- Repair of pot Holes in KM 64/00 to 70/00)

SCHEDULE OF QUANTITY						
Name of work:- Ordinary Repair to Nahan -Do Sarka-Sarahah-Kumharhatti road on NH 907 A km 0/0 to 78/0 in the state of Himachal Pradesh. (SH:- Repair of pot Holes in KM 64/00 to 70/00)						
Sr.No	Description of item/Sub Head	Quantity	Unit	Estimated cost :- Earnest Money :- Time Limit :-	Rs.498843/- only RS.10000/-only 15 Days.	
				Estimate Rate 4	Total Amount 5	Total Amount in word 7
1	2	3				
1	Providing and applying tack coat with bitumen emulsion RS-1 using emulsion pressure distributor at the rate of 0.20 kg per sqm on the prepared bituminous/granular surface cleaned with mechanical broom including carriage of all labour equipments and materials to various location including all taxes, MC taxes etc through all modes of transportation in all leads and lifts, including all incidental charges as per the direction and entire satisfaction of the Engineer-in-charge.	794.16	Per Sqm	16.80	13342.00	Thirteen thousand three hundred forty two only
3	Providing and laying 40mm thick Bituminous Concrete Grading -II Providing and laying bituminous concrete with higher capacity batch type hot mix plant using crushed aggregates of specified grading, premixed with bituminous binder @ 5.4 Percent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 507 complete in all respects including carriage of all labour equipments and materials to various location including all taxes, MC taxes etc through all modes of transportation in all leads and lifts, including all incidental charges as per the direction and entire satisfaction of the Engineer-in-charge.	31.77	Per Cubic metre	15281.75	485501.00	Four lakhs eighty five thousand five hundred one only
Total :-					498843.00	Four lakhs ninety eight thousand eight hundred forty three only
Quoted Rate % (Percentage) in Figures		(+) / (-)				
Quoted Rate % (Percentage) in Words						

The contractor shall procure all the materials conforming to specification MORTH at his own risk and cost. All the rates including octroi, royalty, malikhana, toll tax, GST or other taxes imposed by the Government.


Executive Engineer
NH Division
HPPWD Nahan


56 No. 5

SCHEDULE OF QUANTITY

Name of work:- Ordinary Repair to Nahana - Banethi-Sarahan-Kumarhatti road km 0/0 to 78/0 in the state of Himachal Pradesh. (SH:- Repair of pot Holes in KM 70/00 to 75/00)

Sr.No	Description of Item/Sub Head	Quantity	Unit	Estimated cost :-		Total Amount in word
				Earnest Money :-	Rs.499942/- only	
				Time Limit :-	15 Days.	
1	2	3		4	5	7
1	Providing and applying tack coat with bitumen emulsion RS-1 using emulsion pressure distributor at the rate of 0.20 kg per sqm on the prepared bituminous/granular surface cleaned with mechanical broom including carriage of all labour equipments and materials to various location including all taxes, MC taxes etc through all modes of transportation in all leads and lifts, including all incidental charges as per the direction and entire satisfaction of the Engineer-in-charge.	795.90	Per Sqm	16.80	13371.00	Thirteen thousand three hundred seventy one only
3	Providing and laying 40mm thick Bituminous Concrete Grading - II Providing and laying bituminous concrete with higher capacity batch type hot mix plant using crushed aggregates of specified grading, premixed with bituminous binder @ 5.4 Percent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 507 complete in all respects including carriage of all labour equipments and materials to various location including all taxes, MC taxes etc through all modes of transportation in all leads and lifts, including all incidental charges as per the direction and entire satisfaction of the Engineer-in-charge.	31.84	Per Cubic metre	15281.75	486571.00	Four lakhs eighty six thousand five hundred seventy one only
Total :-					499942.00	Four lakhs ninety nine thousand nine hundred forty two only
Quoted Rate % (Percentage) in Figures		(+) / (-)				
Quoted Rate % (Percentage) in Words						

The contractor shall procure all the materials conforming to specification MORTH at his own risk and cost. All the rates including octroi, royalty, malikana, toll tax, GST or other taxes imposed by the Government


Executive Engineer
NH Division
HPPWD Nahana