

Himachal Pradesh
Public Works Department
No. PWN/CB/2nd C /Tender/2023-24/

5220-22

Dated 17-11-2023


To

The Executive Engineer (I.T. Cell)
HPPWD Nirman Bhawan , Nigam Vihar,
Shimla-2
cc-pwd-hp@nic.in

Subject : Publication of Tender Notice.


Sir,

Enclosed please find herewith the Tender Notice of works as given in the Notice inviting tenders for uploading on department web-site as per Notification of the Principal Secretary (PW) to the Govt. of Himachal Pradesh Letter No. PBW-(B)A9(3) 1/2020 dated Shimla-2 the 16th July 2021 as the work mentioned in the tender notice are urgent in nature and public interest.


Executive Engineer
Nurpur Division
HPPWD Nurpur.

Copy forwarded to the Superintending Engineer 9th Circle HPPWD Nurpur for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer (IT Cell) Nigam Vihar Shimla -2 for information and further necessary action.


Executive Engineer
Nurpur Division
HPPWD Nurpur.

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

TENDER

Scaled item rate tenders on the form 6 & 8 are invited by the Executive Engineer Nurpur Division HPPWD, Nurpur on behalf of the Governor of HP for the following works from the approved and eligible contractors enlisted in HPPWD.

TENDER SCHEDULE

1.	Date and time of receipt of application for tender form:-	24.11.2023	Up to 02.00 PM
2.	Date and time of issue of tender form:-	24.11.2023	Up to 05.00 PM
3.	Date and time of receipt of tenders:-	25.11.2023	Up to 10.30AM
4.	Date and time of opening of tenders:-	25.11.2023	At 11.00 AM.

The tenders form will be issued against cash payment (nonrefundable). The earnest money in the shape of NSC/FDR/Deposit at call of any of Post Office/Bank in H.P duly pledged in the name of the Executive Engineer Nurpur Division HPPWD Nurpur must accompany with each tender.


Sr. No.	Name of work.	Estimated cost (Rs.)	Earnest money	Time limit	Cost of form	Eligible class of Contractor
1.	A/R & M/O HP.PWD Non Residential building at Nurpur(SH: Maintenance and keeping of Sanitary service in HPPWD Executive Engineer's office HP.PWD Nurpur including toilets)	177664.00	3600.00	12 Months	350.00	Class -D
2.	A/R & M/O residential / Non Residential building at Nurpur (SH: Painting and distempering in Executive Engineer's Residence HPPWD Division Nurpur)	206678/-	4200/-	One Month	350/-	Class-D
3.	C/O Ladori to Ghalaon road Km 0/00 to 1/750 (SH: providing and laying interlocking paver block at RD 0/720 to 0/810)	470745/-	10000/-	One Month	350/-	Class-D
4.	A/R & M/O Nurpur to Chinwan via Kullian road Km 0/00 to 5/00 (SH: Repair of pot holes and patches at RD 0/00 to 0/700)	198638/-	4000/-	One Month	350/-	Class-D
5.	A/R & M/O Khushinagar Minjgran road Km 0/00 to 12/00(SH: Repair of pot holes and patches at RD 0/00 to 1/00)	198771/-	4000/-	One Month	350/-	Class-D
The contractors/firms should possess the following documents (Photocopy to be attached) :-						
1	The contractor/Firms should be enlisted with the HPPWD.					
2	PAN (Permanent Account No.)					
3	Registration under GST					
4	The Earnest money in the shape of National Saving certificate / time deposit account in any of the post office in HP FDR from any nationalized bank duly pledged in favour of the Executive Engineer Nurpur Division HPPWD Nurpur.					
5	The earnest money and cost of tender form for the above works should be submitted with the application for the purchase of tender form. The application received without earnest money & cost of tender form shall summarily be rejected.					
6	The offer of tender shall remain valid upto 75 days after the opening of tender.					
7	Ambiguous/telegraphic/conditional tenders or tender by Fax/E-mail shall not be entertained /considered in any case and will be summarily be rejected.					
8	The Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason(s)					
9	If the date given above happens to be holiday the same shall be processed on next working day.					
10	The contractor/firm must quote their rates in words as well as in figures failing which XEN reserves the right to accept/reject any or all tenders.					
11	The tenders forms shall not be issued to those contractors /firms whose previous performance is not found satisfactory and who have not executed the previous awarded works within the stipulated period of completion.					
12	One contractor should not have more than two or more works in hand at a time.					
13	Work should be completed by the contractor within stipulated period.					
14	The rates beyond over +5% will be rejected besides this the additional performance security will have to borne @ 20% & 30% for unbalanced bid in case rates is lower than 10% but upto 20% & lower than 20% upto 30% respectively. The tender beyond the limit of 30% will also be excepted.					

HIM SUCHNA AVAM JAN SAMPARK.

(Nk-24)
Executive Engineer,
Nurpur Division, HPPWD, Nurpur,
Telephone No. 01893-220033
e-mail- ee-nur-hp@nic.in
On behalf of Governor of Himachal Pradesh.

CERTIFICATE

It is certified that the tenders called vide this office letter No. PWN/CB/2nd C/Tender/2023-24/5220-22 dated 17.11.2023 is urgent in nature and also in the public interest.


Executive Engineer,
Nurpur Division, HPPWD,
Nurpur,

Name of work: A/R & M/O HP. PWD Non residential building at Nurpur (SH: Maintenance and keeping of Sanitary services in HP PWD Executive Engineer's office HP PWD Nurpur including toilets)

SCHEDULE OF QUANTITY

Estimated:-Rs. 177664.00
Earnest Money :- Rs. 3600.00
Time Limit:- 12 Month

Sr. No	Description of Items	Quantity	Rate (in Rupees)		Unit	Amount (in Rupees)
			In Figure	In Words		
1	Maintenance good house services for cleaning of toilet blocks, wash rooms and cleaning of rooms on hiring basis in the office of HP PWD Division Nurpur including toilet in toilet block complete as per instructions and directions of Engineer- In - Charge including all materials required for cleaning the toilets within all leads and lifts and other incidental. The rates including G.S.T or any other taxes imposed by the Government	365 days			Per day	
				Total		

Chh-24/4
Executive Engineer
Nurpur Divn HPPWD\Nurpur
Chh

Name of work : A/R & M/O residential/ Non residential building at Nurpur (SH: Painting and distempering in Executive Engineer's Residence HPPWD Divn Nurpur


SCHEDULE OF QUANTITY

Estimated cost Rs. 206678.00
Earnest money Rs. 4200.00
Time Limit: - one month

Sr. No.	Description of items	Quantity	Rate in	Unit	Amount
1	Repairs to plaster in patches and under, including cutting the patches in proper shape, raking out joints and preparing and plastering the surface of the walls complete With cement mortar 1:4 (one cement : four sand) including carriage of materials with in all leads and lifts. The rate including of octroi, royalty, Malkana, toll tax, G.S.T. or other taxes imposed by the Government.	15.00 square meter		Per square meter	
2	Removing of old paint, priming and other scraping from any surfaces, concrete surfaces and sand papering the wall surface smooth including necessary repairs to scratches completed The rates are inclusive of all taxes, toll tax, G S T or any other taxes imposed by the Govt.	505.80 square meter		Per square meter	
3	Providing and applying white cement based putty of any thickness of approved brand and manufacturer over the plaster wall surface to give an even shade including carriage of materials with in all leads and lifts. The rate inclusive of Royalty, Malkhana, Octroi, Toll Tax , GST or any other taxes imposed by the Government.	365.09 square meter		Per square meter	
4	Distempering (two coats) with oil bound washable distemper of approved brand and manufacture and of required shade on ceiling/sloping roof surfaces to give an even shade over and including a priming coat with distemper primer of approved brand and manufacture after thoroughly brushing the surface free from mortar droppings and other foreign matter and also including preparing the surface even and sand papered smooth Priming coat with distemper prime.	505.80 square meter		Per square meter	
5	Painting two or more coats(excluding priming coat) on new wood and wood based surfaces with ready mixed paint of approved brand to give an even shade including cleaning the surfaces of all dirt, dust, and other foreign matter, sand papering and stopping with deluxe Multi Surface paint including carriage of materials with in all leads and lifts. The rate inclusive of Royalty, Malkhana, Octroi, Toll Tax , GST or any other taxes imposed by the Government	376.91 square meter		Per square meter	

6	Painting two or more coats(excluding priming coat) on new steel and other metal surfaces under coat with ready mixed paint brushing to give an even shade including cleaning the surfaces of all dirt, dust, and other foreign matter, with ready mixed paint other than white including carriage of materials with in all leads and lifts. The rate inclusive of Royalty, Malkhana, Octroi, Toll Tax , GST or any other taxes imposed by the Government	232.59 square meter			Per square meter	
7	Finishing walls (one or more coats) with weather proof cement paint applied at the rate 2.20 kg (two point two zero kilogram) per 10 sqm.(ten square metre) over the plastered wall surface to previously prepare the surface even and smooth complete and as per approved drawings, design and as per directions of Engineer in charge including carriage of materials within all leads and lifts.	458.53 square meter			Per square meter	
8	Providing and fixing 10/12.50/15.00 (ten / twelve point five / fifteen) liters capacity P.V.C low level flushing cistern with a pair of C.I or M.S. brackets complete with fitting such as lead valve, less syphen , 15mm (fifteen millimeters) nominal size brass ball valve with polythene float C.P. brass handle, unions and couplings for connections with inlet, outlet and overflow pipe 40mm (forty millimeters) dia. P.V.C. flush bend including cutting holes in walls and making good the same and connecting the flush bend with cistern and closet complete as per HPPWD specification or as directed by Engineer In charge including carriage of materials within all leads and lifts. The rate including of octroi, royalty, Malkana, toll tax, G.S.T. or other taxes imposed by the Government	2.00 No.			Each	
9	Providing and fixing 40mm(forty millimeters) thick second class deodar wood paneled glazed or paneled and glazed shutters for doors, windows, and clerestory windows including bright finished/black enameled iron butt hinges with necessary screws including carriage of material in all leads and lifts.	2.60 square meter			Per square meter	
10	Providing and fixing 125 mm aluminium handles anodized dyed to required shade or colour with necessary screws etc in doors complete as per drawing	3.00 Nos			Each	
11	Providing and fixing 150x10 mm aluminum tower bolts(berrel type) anodized dyed to required shade or colour with necessary screw etc in windows and ventilators complete as per drawing or as directed or as direct by Engineer-in Charge	6.00 Nos			Each	
12	Providing and fixing 6mm (six millimeters) plain asbestos cement sheeting ceiling of approved quality with butt jointing wood screws (framed work and cover fillets to be measured and paid for separately) including carriage of materials within all leads and lifts.	2.73 square meter			Per square meter	

13	Supplying and fixing plain glass panes 4mm (four millimeters) thick with putty including removal of broken glass panes where-ever necessary and nails as per directions of Engineer-in- charge including carriage of materials with in all lead and lifts and other incidental charges	1.38 square meter			Per square meter	
14	Providing & fixing galvanized M.S Wire gauze with 0.63 mm dia wire and 1.4 mm aperture on both side fly proof wire gauze to window, clerestory & doors with Mild steel Flat 15x3 mm and nuts & bolts complete. as per directions of Engineer-in- charge including carriage of materials with in all lead and lifts and other incidental charges	1.38 square meter			Per square meter	
15	Providing and fixing Stainless Steel Health Faucet of make Jaquar Kerovit as per directions of Engineer-in- charge including carriage of materials with in all lead and lifts and other incidental charges	2.00 Nos			Each	
			Total			


 Executive Engineer
 Nurpur Division HPPWD
 Nurpur

SCHEDULE OF QUANTITY


Name of work :- Const. of link road Ladori to Ghaloon road km 0/0 to 1/200 (SH: Providing and laying interlocking paver block 80mm thick in km. 0/720 to 0/810

Estimated cost Rs.470745.00

Earnest money Rs.10000.00

Time limit :- one month

Sr. No.	Description of items	Qty.	Rate in		Unit	Amount
			Figures	Words		
2	Providing and laying cement concrete 1:4:8 (one cement; four sand : eight graded /crushed stone aggregate 40mm(forty millimeters) nominal size mixed and vibrated mechanically and curing complete including the cost of form work in foundation and plinth in all depths as per technical specification clause 802, 803 1202 and 1203 including carriage of materials within all leads and lifts and other incidental charges. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	29.70 cubic meter			Per cubic meter	
3	Providing and laying of inter locking concrete paver block (I S I marked) pavement having thickness 80mm (eighty millimeters) over sand base as per drawing and technical specification clause 1504 complete and as per directions of Engineer -in-charge including carriage of materials. The rates is inclusive royalty, toll tax, G S T or any other taxes imposed by the Government.	297.00 square meter			Per square meter	
				Total		


Executive Engineer,
Nurpur Division HPPWD
Nurpur.

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O Nurpur to Chinwan via Kulan road km 0/0 to 5/00
(SH:- Repair of pot holes and patches at RD. 0/700 to 1/400)

Estimated:-Rs. ^{198638.00}~~199754.00~~
Earnest Money :- Rs. ~~4000.00~~
Time Limit:- one Month

Sr. No	Description of Items	Quantity	Rate (in Rupees)		Unit	Amount
			In Figure	In Words		
1	Providing, laying, spreading and compacting stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming , crushable screening at the rate of 0.22 cum (zero point two two cubic metres) per ten square metres, to fill up the intersitices of coarse aggregate, watering and compacting to the required density grading -III 53mm to 22.4mm (fifty three millimetres to twenty two point four millimetres)sizes, 75mm (seventy five millimetres) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government	5.00 cubic meter			Per cubic meter	
2	Repair to pot holes including removal of loose material, trimming of sides, cleaning of surface by providing tack coat with using penetration grade bitumen VG-10 (viscosity grade-ten) at the rate of 3.00 kg (three point zero zero kilograme) per ten square meter, 20 mm (twenty millimeter) thick pre-mix carpet with bitumen VG-10 (viscosity grade-ten) at the rate of 14.60 kg (fourteen point sixty kilograme) per ten square metre and seal coat type B of bitumen VG-10 (viscosity- ten) at the rate of 6.80 kg (six point eighty kilograme) per ten square meter as per technical specification Clause 1904.2.503 and as per directions of Engineer in charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	519.71 square meter			Per square meter	
				Total		

(Signature)
Executive Engineer
Nurpur Division HPPWD
Nurpur

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O Khushinagar Minjgran road km 0/0 to 12/00
(SH:- Repair of pot holes and patches at RD. 0/00 to 1/00)

Estimated:-Rs. 198771.00
Earnest Money :- Rs. 2000.00
Time Limit:- one Month

Sr. No	Description of Items	Quantity	Rate (in Rupees)		Unit	Amount
			In Figure	In Words		
1	Providing, laying, spreading and compacting stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic metres) per ten square metres, to fill up the intersitices of coarse aggregate, watering and compacting to the required density grading -III 53mm to 22.4mm (fifty three millimetres to twenty two point four millimetres) sizes, 75mm (seventy five millimetres) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government	5.00 cubic meter			Per cubic meter	
2	Repair to pot holes including removal of loose material, trimming of sides, cleaning of surface by providing tack coat with using penetration grade bitumen VG-10 (viscosity grade-ten) at the rate of 3.00 kg (three point zero zero kilograme) per ten square meter, 20 mm (twenty millimeter) thick pre-mix carpet with bitumen VG-10 (viscosity grade-ten) at the rate of 14.60 kg (fourteen point sixty kilograme) per ten square metre and seal coat type B of bitumen VG-10 (viscosity- ten) at the rate of 6.80 kg (six point eighty kilograme) per ten square meter as per technical specification Clause 1904.2,503 and as per directions of Engineer in charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	517.04 square meter			Per square meter	
				Total		

(Nurpur Diya)
Executive Engineer
Nurpur Diya HPPWD
Nurpur