

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT.
NOTICE INVITING TENDER**

Sealed percentage rate tenders are hereby invited on Form No.6 &8 by the undersigned on behalf of the Governor of Himachal Pradesh for the following works from the registered contractors of appropriate class enlisted in H.P.PWD, so as to reach in this office on 28-11-2023 upto 11:30 P.M and shall be opened on the same day on 11:30 PM. M in the presence of the intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (Non- refundable) during the working hours.

The earnest money in the shape of National Saving Certificate, FDRs/TDRs/Account/Saving account in any of the Post Office/ Nationalized Bank in H.P. duly pledged in favour of the Executive Engineer, (B&R) Division, H.P.PWD, Sarahan must accompany with each applications/tender. Conditional tenders and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 75 days. The undersigned reserves the right to reject the any or all tender without assigning any reason.


S.No.	Tender Schedule				
1.	Last date for tender receipt of application for tender form	24-11-2023 upto 4:00 PM			
2	Last date of sale of tender forms	25-11-2023 upto 4:00 PM			
3	Date of receipt of tender forms	28-11-2023 upto 11:00 AM			
4	Date of opening of tenders	28-11-2023 at 11:30 PM			
Sr. No	Name of Work	Estimated cost	Earnest Money	Time Limit	Cost of Form
1	R/R damages Dungaghat Bagthan road Km 0/0 to 13/00 (SH:- C/O R/Wall between RD 4/945 to 4/957, Pacca drain in Km 6/460 to 6/690)	371981/-	7500/-	Three Month	350/-
2	R/R damages on Lawassa Chowki Preet Nagar road Km 0/0 to 42/0 (SH:- C/O R/Wall at RD 7/00 to 7/015)	195780/-	4000/-	Three Month	350/-
3	C/O Rister Panwa road Km 0/0 to 2/0 (SH:- C/O 900 mm dia RCC Hume pipe culvert alongwith wing wall at RD 0/045 to 0/505) SCDP	430901/-	9000/-	Three Month	350/-
4	C/O Rister Panwa road Km 0/0 to 2/0 (SH:- P/L Soling in Km 0/500 to 1/00) MNP	386704/-	8000/-	Three Month	350/-
5	R/R damages on Ghargaon to Dagothar via Ganyana Nali Km 0/0 to 5/0 (SH:- Removal of slips)	486495/-	10000/-	One Month	350/-
6	R/R damages on Narag Wasni Dinger road Km 0/0 to 17/600 (SH:- P/L interlocking Paver block (main Bus stand Wasni) between km 9/560 to 9/655)	484237/-	10000/-	Three Month	350/-
7	R/R damages on Narag Wasni Dinger road Km 0/0 to 17/600 (SH:- P/L interlocking Paver block (main Bus stand Wasni) between km 9/370 to 9/465)	484237/-	10000/-	Three Month	350/-
8	R/R Damages on Narag Wasni Dinger road Km 0/0 to 17/600 (SH:- C/O PCC R/Wall at Km 6/300 to 6/315)	322139/-	6500/-	Three Month	350/-
9	R/R Damages on Narag Wasni Dinger road Km 0/0 to 17/600 (SH:- C/O PCC R/Wall at Km 7/310 to 7/325)	380920/-	8000/-	Three Month	350/-
10	Providing CGI Sheet on veterinary department Cow Shade at Bagthan Tehsil Pachhad Distt. Sirmour H.P (SH; - Ceiling, Painting white washing etc.) Deposit	497161/-	10000/-	One Month.	350/-
11	Providing CGI Sheet on veterinary department Cow Shade at Bagthan Tehsil Pachhad Distt. Sirmour H.P (SH; - Dismantling, Providing doors wire gauge shutters, CGS sheet and plastering etc.) deposit	498392/-	10000/-	One Month.	350/-
12	Repair and maintenance of Health Sub Center Sirmouri Mandir Sarahan (Pachhad) Distt Sirmour (SH:- Providing aluminum doors and windows, slab repair and other miscellaneous works)	480841/-	10000/-	Four month	350/-
13	R/R Damages on Naina Tikker Dagothar road Via Shamlati km 0/0 to 12/0 (SH:-C/O PCC R/Wall at RD 2/650 to 2/660)	246483/-	5000/-	Three Month	350/-
14	C/O R/wall in wire create to protect the school playground at GSSS Naya Gaon Tehsil Pachhad Distt Sirmour	286147/-	6000/-	Two Month	350/-

15	R/R Damages on Dungagahat Bagthan Road km 0/0 to 12/450(SH:-C/O PCC R/Wall at RD 4/645 to 4/655)	370226/-	7500/-	Three Month	350/-
16	R/R Damages on Banad Bohal Gagal Shikore road km 0/0 to 5/120 (SH:-C/O PCC B/wall at RD 0/710 to 0/725)	193431/-	4000/-	Three month	350/-

Certificate:-It is certified that the tender of above work are exigency/emergent nature and in public interest.

Terms & conditions:-


1. The contractors/Bidders must submit their Permanent Income Tax Account Number/GST number on the tender along with copy of the same be attached with the application.
2. The contractor/Firms should attached copy of the Registration/Renewal with the application.
3. The contractors/bidders must inspect the site to ascertain/familiar the site conditions, accessibility etc. Before quoting the bid/tender.
4. Conditional and telegraphic tender will not be accepted and rejected straightway. Tender received after due date and time shall not entertained.
5. The contractor/firm should have to produce the detail of work in hand in HPPWD and its position therefore along with application.
6. The tender document shall be issued to only those contractors who does not have more than two works in hand in HPPWD Circle/ Division.
7. The contractor shall have to establish testing laboratory at site for the day to day testing of material.
8. The Executive Engineer reserves the right to reject or cancel any or all the tenders without assigning any reason.


Executive Engineer
HPPWD Division Sarahan
Distt Sirmour HP

No.PW/SRN/Estt-Tender/2022-23- 6657- 6700
Copy forwarded for information and necessary action to:-

Dated:- 18/11/23

1. The Engineer-in-Chief, HP.PWD.Shimla-171002.
2. The Chief Engineer (South) HP.PWD.Shimla-171002.
3. The Superintending Engineer, 12th Circle HPPWD Nahan.
4. The Executive Engineer (IT Cell), Nigam Vihar, HPPWD Shimla-2 for uploaded of Notice Inviting Tenders on Departmental website please.
5. All the Assistant Engineers working under this Division.
6. All Head of Branches of this office.
7. All Intending Bidders/Contractors.
8. Notice Board.


Executive Engineer
HPPWD Division Sarahan
Distt Sirmour HP

DRAFT SCHEDULE OF QUANTITY

Name of work:- R/R Damages Dungaghat Bagthan Road km 0/0 to 13/00 (SH:- C/O R/Wall between RD 4/945 to 4/957, Pacca drain in km 6/460 to 6/690)

Estimated cost:-Rs.3,71,981/-

Earnest money: - Rs 7,500

Time Limit: - Three Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	24.15	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only	4685.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	56.04	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only	264352.00
3	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)).including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge	22.000	Each	270.30	Rs. Two Hundred seventy and paise thirty only	5947.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in-Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	10.56	Per Cubic Metre.	738.00	Rupees seven Hundred thirty eight and paise zero Only.	7793.00
5	Providing and laying Plain Cement Concrete 1:3:6(one cement: three sand: six graded hard stone aggregate 20mm(twenty) millimeter) nominal size) and curing complete including the cost of formwork for plain/reinforced concrete as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	16.10	Per cubic metre	5540.60	Rupees five thousand five hundred forty and paise sixty only	89204.00
						371981.00

T.S. No - 70 / L.No / 2464-65 / dated 6-7-23.

DNIT No. For the year 2023-24

Draft Schedule of Quantity approved for Rs.

371981.00

only

Executive Engineer
Sarahan Division,
HP PWD Saran

DRAFT SCHEDULE OF QUANTITY

Name of work:- -R/R Damages on Lawassa Chowki Preet Nagar Road km 0/0 to 42/0 (SH:- C/O R/Wall at RD 7/00 to 7/015)

Estimated cost:- Rs.1,95,780/-

Earnest money:- - Rs 4,000

Time Limit:- - Three Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	9.65	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only. ✓	1872.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand: Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	39.30	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only. ✓	185386.00
3	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full width of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven) including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge	9.000	Each	270.30	Rs. Two Hundred seventy and paise thirty only. ✓	2433.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	8.25	Per Cubic Metre.	738.00	Rupees seven Hundred thirty eight and paise zero Only. ✓	6089.00
						195780.00

DN/IT No. For the year 2023-24

Draft Schedule of Quantity approved for Rs.

195780.00 ✓

only.


 Executive Engineer
 KSSarahah Division
 HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Estimated cost:-Rs. 4,30,901/-

Name of Work:- C/O Rister Pantwa road km 0/0 to 2/0 (SH-6/O.900mm dia RCC Hume pipe culvert along with wing walls at RD 0/045 and 0/505) SCDP

Earnest money:- Rs. 9,000

Time Limit:- Three Months.

Sr. No.	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five: point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	99.53	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise nil only. ✓	19309.00
2	Providing and laying Plain Cement Concrete 1:3:6 (one cement: three sand: six graded hard stone aggregate 20mm (twenty) millimeter) nominal size} and curing complete including the cost of formwork for plain/reinforced concrete as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	30.22	Per cubic metre	5540.60	Rupees five thousand five hundred forty and paise sixty only. ✓	167437.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	38.62	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only. ✓	182178.00

4	Laying reinforced cement concrete 900 mm (Nine Hundred millimeter) diameter pipe class NP-2 (Non-Pressure-Two) including jointing for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement: two sand) including back filling but excluding excavations, protection works, concrete and masonry works in head walls and parapets as per drawings and technical specifications. C. 1108. all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	15.00	Per Running Metre.	3731.40	Rupees three thousand seven hundred thirty one and paise forty only. ✓	55971.00
5	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full width of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause 7 Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)), including hauling / carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	6.000	Each	270.30	Rupees two hundred seventy and paise thirty only. ✓	1622.00
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	5.94	Per Cubic Metre.	738.00	Rupees seven hundred thirty eight and paise nil only. ✓	4384.00
					Total	430901.00


 Executive Engineer
 K. S. Sarahan Division
 HP, PWD, Sarahan

Estimated cost: Rs. 3,86,704/-

Earnest money: - Rs. 8,000/-

Time Limit: Three Month.

SCHEDULE OF QUANTITY

Name of work :- C/O Rister Panwa Road km 0/0 to 2/0 (SH:- P/L Soling in km 0/500 to 1/00) MNP

Sl. No.	Description	Qty.	Unit	Rate		Amount
				in figures:	in words:	
1	2 Preparation of sub-grade by dressing to camber earth work for the cutting involved for sub-grade to be paid separately depending upon the classification of soil complete as per HPPWD specification	3 1842.50	4 Per Square metre	5 1.80	6 Rupees one and paise eighty only ✓	7 3317.00
	Construction of sub-grade with road roller including making good the undulation etc. with earth or quarry soil etc. and rolling the sub-grade completed as per HPPWD specification	1842.50	Per Square metre.	1.86	Rupees one and paise eighty six only. ✓	3427.00
3	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 1 as per Technical Specification Clause 405.	184.25	Per Cubic Metre.	2062.20	Rupees two thousand sixty two and paise twenty only. ✓	379960.00
						386704.00


Executive Engineer
Sarhan Division
HP, PWD, Sarhan

SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Chargaon to Dagothar via Ganyana Nali km 0/0 to 5/0 (SH:- Removal of slips)

Estimated cost:-Rs. 4,86,495 ✓

Earnest money:- Rs 10,000

Time Limit:- one Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Removal of landslides /slip clearance., Removal of land-slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611	5346.10	Per Cubic Metre.	91.00 ✓	Rupees ninety one and paise nil only ✓	486495.00 ✓
		3	4	5	6	7
						486495.00


Executive Engineer
K. Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Estimated cost:-Rs 4,84,237/-

Name of work:- G.R.R. Damages on: Naragi Wasnt Dinga Road km 0/0 to 17/600 (SH:- P/L interlocking Paver block (main bus stand wasni) between km 9/560 to 9/655)

Earnest money:- Rs. 10,000/-
Time Limit:- Three Month.

Sl. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling all trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	7.60	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only. ✓	1474.00
2	Providing and laying Concrete PCC grade M-20 (Twenty millimeter) nominal size for plain/reinforced concrete in open foundation complete as per drawing and HP PWD technical specifications clause 802, 803, 1202 & 1203 i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	7.60	Per Cubic Metre.	5819.60	Rupees Five thousand eight hundred nineteen and paise sixty only. ✓	44229.00
3	Providing and laying of interlocking concrete block pavement (Zig-Zag in shape) having thickness 80mm as per drawing and technical specification clause 1504 including carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	365.75	Per Square metre	1199.00	Rupees One thousand one Hundred ninety nine and paise zero Only. ✓	438534.00
						484237.00

DNIT No. For the year 23-24

Draft Schedule of Quantity approved for Rs. 484237.00 only.


Executive Engineer
Ks Sarahan Division
HP, PWD, Sarahan

(7)

Estimated cost:-Rs 4,84,237/-

SCHEDULE OF QUANTITY
 Name of work:- R/R Damages on Narag Wasni Dinger Road km 0/0 to 17/600 (SH:- P/L interlocking Paver block (main bus stand wasni) between km 9/370 to 9/465)

Earnest money:- Rs. 10,000/-

Time Limit:- Three Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	3 7.60	Per Cubic Metre.	5 194.00	6 Rupees one hundred ninety four and paise zero only.	7 1474.00
2	Providing and laying Concrete PCC grade M-20 grade 1:2:4 (one cement: Two sand: Four graded hard stone aggregate) M-20 (Twenty millimeter) nominal size for plain/reinforced concrete in open foundation complete as per drawing and HR PWD technical specifications clause 802, 803, 1202 & 1203 i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	7.60	Per Cubic Metre.	5819.60	Rupees Five thousand hundred nineteen and paise six only.	44229.00
3	Providing and laying of interlocking concrete block pavement (Zig-Zag in shape) having thickness 80mm as per drawing and technical specification clause 1504 including carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	365.75	Per Square metre	1199.00	Rupees One thousand Hundred ninety nine and paise zero Only	438534.00
						484237.00

Executive Engineer
 K.S. Sarahan Division
 HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Narag Wasni Dinger road km 0/0 to 17/600 (SH:- C/O PCC R/Wall at km 6/300 to 6/315)

Estimated cost:-Rs. 3,22,139/-

Earnest money:- Rs 6,500/-

Time Limit:- Three Months.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	28.35	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only.	5500.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	63.00	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only.	297184.00
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full width of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven) ,including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	13.000	Each	270.30	Rs. Two Hundred seventy and paise thirty only.	3514.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	21.60	Per Cubic Metre.	738.00	Rupees seven Hundred thirty eight and paise zero Only.	15941.00
						322139.00

Executive Engineer
Sarabhai Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Narag Wasni Dinger road km 0/0 to 17/600 (SH:- C/O PCC R/Wall at km 7/310 to 7/325)

Estimated cost:-Rs. 3,80,920/-

Earnest money:- Rs 8,000 ✓

Time Limit:- Three Months.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	29.93	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only. ✓	5806.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	75.00	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only. ✓	353790.00
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full width of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven) ,including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	15.000	Each	270.30	Rs. Two Hundred seventy and paise thirty only. ✓	4055.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	23.40	Per Cubic Metre.	738.00	Rupees seven hundred thirty eight and paise zero Only. ✓	17269.00
						380920.00


 Executive Engineer
 Sarahan Division
 HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- Providing CGI Sheet on veterinary department Cow Shade at BagthanTeshil pachhad Distt. Sirmour H.P (SH:- Ceiling, Pantingand white washing etc)deposit

Job No.

Estimated cost:-Rs 4,97,161/-

Earnest money:- Rs. 10,000

Time Limit:-three month

Sr. No	Description Items of work	Qty.	Unit	Rate	Amount
				in figures.	in words
1	2	3	4	5	7
1	Providing and fixing wooden plankceiling with tongued and groovedjointing and wood screws(framework and cover fillets to be measured and paid for separately	69.00	Per square metre	3210.68	Rupees three thousand two hundred ten and paise sixty eight only. ✓
2	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floorfive level, excluding cost of centering, shuttering, finishing and reinforcement :1:1.5:3 (1 cement : 1.5 coarse sand) : 3 graded stone aggregate 20 mm nominal size)	1.04	Per cubic metre	7512.00	Rupees seventy five thousand five hundred twelve and paise nil only. ✓
3	Providing and laying cement concrete 1:4:8 (1 cement:4 sand:8 graded stone aggregate 40mm nominal size) and curing complete excluding cost of form work in Foundation and plinth.	18.52	Per cubic metre	5556.00	Rupees five thousand five hundred fifty six and paise nil only. ✓
4	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete. 40 mm thick with 20 mm nominal size stone aggregate	243.75	Per square metre	391.00	Rupees three hundred ninety one and paise nil only. ✓
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:3:6 (1 Cement : 3 coarse sand): 6 graded stone aggregate 40 mm nominal size)	0.90	Per cubic metre	5553.70	Rupees five thousand five hundred fifty three and paise seventy only. ✓

6	Applying priming coat: With ready mixed pink or Grey primer of approved brand and manufacture on wood work (hard and soft wood) including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	88.42	Per square metre	45.00	Rupees forty five and paise nil only. ✓	3979 ✓
7	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture	88.42	Per square metre	104.00	Rupees one hundred four and paise nil only. ✓	9196 ✓
8	Painting one coat (excluding priming coat) on previously painted wood and wood based surfaces with readymixed paint brushing to give an even shade including cleaning of all dirt, dust and other foreign matter sand papering and stopping	127.56	Per square metre	136.19	Rupees one hundred thirty six and paise nineteen only. ✓	17372 ✓
9	White washing with lime on decorated wall surfaces (one coat) to give an even shade including thoroughly brooming the surface to remove all dirt, dust, mortar drops and loose scale of lime wash and other foreign matter	435.56	Per square metre	35.39	Rupees thirty five and paise thirty nine only. ✓	15414 ✓
10	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	168.00	Per Kilo gram	111.00	Rupees one hundred eleven and paise nil only. ✓	18648 ✓
	Total					497161 ✓


 Executive Engineer
 KS Sarahan Division
 HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- Providing CGI Sheet on veterinary department Cow Shade at BagthanTeshil pachhad Distt. Sirmour H.P (SH:- Distmentling , Providing doors wire gauge shutters ,CGS sheet and plasering etc)deposit

Job No.

Estimated cost:-Rs 4,98,392/-

Earnest money:- Rs. 10,000

Time Limit:-three month

Sr. No	Description Items of work	Qty.	Unit	Rate	Amount
1	2	3	4	5	6
1	Dismantling roofing including ridges, hips, valleys, gutters etc.stacking the serviceable materialsand disposal of un-serviceablematerials within 20 Metres lead.	167.86	Per square metre	136.860	Rupees one hundred thirty six and paise eighty six only. 22973
2	Dismantling roofing including ridges, hips, valleys, gutters etc.stacking the serviceable materialsand disposal of un-serviceablematerials within 20 Metres lead.	69.00	Per square metre	106.740	Rupees one hundred six and paise seventy four only. 7365
3	Demolition of brick work above G.L. upto floor two level including stacking of serviceable materials and disposal of un-serviceable materials within 20 Metres lead.	2.560	Per cubic metre	2161.940	Rupees two thousand one hundred sixty one and paise ninety four only. 5535
4	Providing wood work in frames of doors, windows,clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately).	0.056	Per cubic metre	97765.160	Rupees ninety seven thousand seven hundred sixty five only. 5475
5	Providing and fixing paneled or paneled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, excluding panceling which will be paid for separately, all complete as per direction of Engineer-in charge. (Note:- Butt hinges and necessary screws shall be paid separately) Second class teak wood	7.24	Per square metre	4414.000	Rupees four thousand four hundred fourteen only. 31957
6	Providing and fixing wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm in both directions with wire of die 0.63 mm, for doors, windows and clerestory windows with hinges and necessary screws :35 mm thick shutters with ISI marked M.S. pressed butt hinges bright finished of required size Second class teak wood	12.18	Per square metre	3861.000	Rupees three thousand eight hundred sixty one and paise nil only 47027

7	Providing wood work intrusses, purlins, rafters, posts, post plates, wall plates and the like wrought framed, hoisted and fixed in position.	1.63	Per cubic metre	90113.560	Rupees ninety thousand one hundred thirteen and paise fifty six only. ✓	146885 ✓
8	Brick work with common burnt clay modular bricks of class designation 7.5 in foundation and plinth in: Cement Mortar 1:5 (1 cement : 6 coarse sand) including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts, including all incidental charges..	8.23	Per cubic metre	6481.000	Rupees six thousand four hundred eighty one only. ✓	53339 ✓
9	Providing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. 1.00 mm thick with zinc coating not less than 275 gm/m ² 0.63 mm thick with zinc coating not less than 275 gm/ m ²	167.86	Per square metre	864.000	Rupees eight hundred sixty four and paise nil only. ✓	145031 ✓
10	15 (fifteen) millimeters thick cement plaster in single coat on the rough of brick / concrete/stone walls for interior plastering up to all heights including arises. Internal rounded angles, chamfers and rounded angles not exceeding 80 (eighty) millimeters in grith and finished even and smooth in cement mortar 1:5 (one cement : six sand) as per direction of Engineer-in charge and H.P. PWD. Specification, including carriage of all labour, equipment's and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	135	Per square metre	243.000	Rupees two hundred forty three and paise nil only. ✓	32805 ✓
	Total					498392 ✓


 Executive Engineer
 K. Sarahan Division
 HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- Repair and maintenance of Health Sub Centreat Sirmouri Mandir Sarahan (Pachhad) Distt. Sirmour (SH: Providing aluminium doors and windows, Slab repair and other miscellaneous works)

Estimated cost:- Rs 4,80,841/-

Earnest money: - Rs. 10,000/-
Time Limit:- Four months

Sr. No	Description Items of work	Qty.	Unit	Rate	Amount
				in figures.	in words
1	2	3	4	5	7
1	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - Allwork up to plinth level :1:1.5:3 (1 cement : 1.5 coarse sand): 3graded stone aggregate 20 mm nominal size)including carriage of all labour equipment and material to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of the Engineer-in-Charge.	6.851	Per Cubic Metre	8711.70	Rupees Eight thousand seven hundred eleven and paise seventy only ✓
2	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level Mild steel and Medium Tensile steel bars, including carriage of all labour equipment and material to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of the Engineer-in-Charge.	822.195	Per Square Metre	96.40	Rupees ninety six and paise forty only ✓
3	Dismantling doors, windows and clerestory windows, ventilators etc. (wood or steel) shutters including chowkhats, architraves, hold fasts and other attachments etc. complete and stacking them within 20 Metres lead including carriage of all labour equipment and material to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of the Engineer-in-Charge.	14.338	Per Square Metre	212.00	Rupees two hundred twelve and paise nil only ✓
					3040.00

4	Providing and fixing aluminum work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required die and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminum sections shall be smooth, rust free, straight, mitered and jointed mechanically wherever required including cleat angle, Aluminum snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in charge. (Glazing, paneling and dash fasteners to be paid for separately) : All complete as per architectural drawings and the directions of Engineer-In-Charge. For doors windows and ventilators and glazed partitions frames. Anodized aluminum (anodized transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC15)	36.273	Per Kilo Gramme	450.00	Rupees four hundred fifty and paise nil. ✓	16323.00
5	Providing and fixing aluminum work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required die and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminum sections shall be smooth, rust free, straight, mitered and jointed mechanically wherever required including cleat angle, Aluminum snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in charge. (Glazing, paneling and dash fasteners to be paid for separately) : All complete as per architectural drawings and the directions of Engineer-In-Charge. For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) .Anodized aluminum (anodized transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC15)	68.820	Per Kilo Gramme	529.00	Rupees five hundred twenty nine and paise nil only ✓	36406.00
6	Providing and fixing wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm in both directions with wire of die 0.63 mm, for doors, windows and clerestory windows with hinges and necessary screws :35 mm thick shutters with ISI marked M.S. pressed butt hinges bright finished of required size Second class deodarwood including carriage of all labour equipment and material to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of the Engineer-in-Charge.	6.69	Per Square Metre	3976	Rupees three thousand nine hundred seventy six and paise nil only ✓	26590.00

7	Providing and fixing aluminum sliding door bolts, ISI marked anodized (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required color or shade, with nuts and screws etc. complete :300 x 16 mm including carriage of all labour equipment and material to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of the Engineer-in-Charge.	6.000	Each	275.00	Rupees two hundred seventy five and paise nil only ✓	1650.00
8	Providing and fixing aluminum tower bolts, ISI marked, anodized (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required color or shade, with necessary screws etc. complete 250 x 10 mm including carriage of all labour equipment and material to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of the Engineer-in-Charge.	3.000	Each	116.00	Rupees one hundred sixteen and paise nil only ✓	348.00
9	Providing and fixing aluminum handles, ISI marked, anodized (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required color or shade, with necessary screws etc. complete 100 mm including carriage of all labour equipment and material to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of the Engineer-in-Charge.	8.000	Each	59.50	Rupees fifty nine and paise fifty only ✓	476.00
10	Providing and fixing aluminum hanging floor door stopper, ISI marked, anodized (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required color and shade, with necessary screws etc. complete Single rubber stopper including carriage of all labour equipment and material to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of the Engineer-in-Charge.	3.000	Each	42.30	Rupees forty two and paise thirty only ✓	127.00
11	15 mm cement plaster on the rough side of single or half brick wall of mix :1:6 (1 cement: 6 fine sand) including carriage of all labour equipment and material to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of the Engineer-in-Charge.	233.863	Per Square Metre	265.00	Rupees two hundred sixty five and paise nil only ✓	61974.00
12	Providing and applying plaster of paris putty of 2 mm thickness over plastered surface to prepare the surface even and smooth complete. including carriage of all labour equipment and material to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of the Engineer-in-Charge.	263.095	Per Square Metre	182.85	Rupees one hundred eighty two and paise eighty five only ✓	48107.00
13	Finishing walls with Acrylic Smooth exterior paint of required shade :New work (Two or more coat applied @ 1.67ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm) including carriage of all labour equipment and material to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of the Engineer-in-Charge.	263.095	Per Square Metre	168.70	Rupees one hundred sixty eight and paise seventy only ✓	44384.00

14	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS:15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete Size of Tile 500x500 mm including carriage of all labour equipment and material to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of the Engineer-in-Charge.	29.233	Per Square Metre	1598.00	Rupees one thousand five hundred ninety eight and paise nil only ✓	46714.00
15	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S.15622, of approved make, in all colours & shade, inskirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joint with white cement & matching pigments etc. complete	6.075	Per Square Metre	1623.00	Rupees one thousand six hundred twenty three and paise nil only ✓	9860.00
16	6 mm cement plaster of mix 1:3 (1 cement : 3 fine sand) including carriage of all labour equipment and material to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of the Engineer-in-Charge.	29.233	Per Square Metre	192	Rupees one hundred ninety two and paise nil only ✓	5613.00
17	Dismantling of flushing cistern of all types (C.I./PVC/Vitrious China) including stacking of useful materials near the site and disposal of unserviceable materials within 50 metres lead. including carriage of all labour equipment and material to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of the Engineer-in-Charge.	1.000	Each	508	Rupees five hundred eight and paise nil only ✓	508.00
18	Providing and fixing white vitreous china extended wall mounting water closet of size 780x370x690 mm of approved shape including providing & fixing white vitreous china cistern with dual flush fitting, of flushing capacity 3 litre/ 6 litre (adjustable to 4 litre/ 8 litres), including seat cover, and cistern fittings, nuts, bolts and gasket etc complete	1.000	Each	14616.85	Rupees fourteen thousand six hundred sixteen and paise eighty five only ✓	14617.00
19	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Wash basin size 630x450 mm with a pair of 15 mm C.P. brass pillar taps including carriage of all labour equipment and material to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of the Engineer-in-Charge.	1.000	Each	3100.00	Rupees three thousand one hundred and paise nil only ✓	3100.00

20	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 mspacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge 15 mm nominal outer dia Pipes including carriage of all labour equipment and material to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of the Engineer-in-Charge.	100.000	Per Running Metre	220.6	Rupees two hundred twenty and paise sixty only, ✓	22060.00
						480841.00


 Executive Engineer,
 KS Sarahan Division,
 HP, PWD., Sarahan

SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Naina Tikker daother roa dvia Shamlati km 0/0 to 12/0 (SH:- C/O PCC R/Wall at RD 2/650 to 2/660)

Estimated cost:-Rs. 2,46,483/-

Earnest money: - Rs 5,000

Time Limit: - Three Months.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	24.30	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only ✓	4714.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	48.00	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only. ✓	226426.00
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)).including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	24.000	Each	270.30	Rs. Two Hundred seventy and paise thirty only. ✓	6487.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	12.00	Per Cubic Metre.	738.00	Rupees seven Hundred thirty eight and paise zero Only. ✓	8856.00
						246483.00

Executive Engineer,
K. Sarahan Division,
H.P. PW.D., Jammu

SCHEDULE OF QUANTITY

Name of work:-C/O R/Wall in wire crate to protect the school play ground at GSSS Naya Gaon Tehsil Pachhad Distt.

Estimated cost:-Rs.2,86,147/-
Earnest money:- Rs. 6,000
Time Limit:- Two Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	29.72	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only.✓	5766.00✓
2	Providing and laying of boulder apron laid in wire creates with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification clause 1301 as per drawing and HP PWD technical specifications in carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	93.23	Per Cubic Metre.	2846.40	Rupees two thousand eight hundred forty six and paise forty only.✓	265370.00✓
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	20.34	Per Cubic Metre.	738.00	Rs. seven hundred thirty eight and paise nil only.✓	15011.00✓
						286147.00✓


Executive Engineer
K. Sarahan Division
HP, PWD, Sarahan

DRAFT SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Dungaaghat Bagthan road km 0/0 to 12/450 (SH:- C/O PCC R/Wall at RD 4/645 to 4/655)

Estimated cost:- Rs. 3,70,226/-

Earnest money:- Rs 7,500

Time Limit:- Three Months.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	13.39	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only	2598.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	73.060	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only	344639.00
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)).including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge	21.000	Each	270.30	Rs. Two Hundred seventy and paise thirty only	5676.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	23.46	Per Cubic Metre.	738.00	Rupees seven Hundred thirty eight and paise zero Only.	17313.00
						370226.00

*Ts estimate no. Letter no.

Dated :-

DNIT No. For the year 2023-24

Draft Schedule of Quantity approved for Rs.

370226.00

only.


 Executive Engineer
 Sarahan Division
 HP, PWD, Sarahan

DRAFT SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Banar Bohal Gagal Shikore road km 0/0 5/120 (SH:- C/O PCC B/Wall at RD 0/710 to 0/725)

Estimated cost:- Rs. 1,93,431/-

Earnest money:- Rs 4,000

Time Limit:- Three Months.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	29.39	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only	5702.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	39.510	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only	186377.00
3	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven) ,including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge	5,000	Each	270.30	Rs. Two Hundred seventy and paise thirty only	1352.00
						193431.00

Ts estimate no. Letter no. Dated :-

DNIT No. For the year 2023-24

Draft Schedule of Quantity approved for Rs.

193431.00

only.


 Executive Engineer
 KS Sarahan Division
 HP, PWD, Sarahan