

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

Sealed percentage basis tenders are hereby invited by Executive Engineer, NH Division, HP.PWD, Solan on behalf of Governor of Himachal Pradesh for the following works from the approved registered Contractors of appropriate class (D) enlisted with Himachal Pradesh Public Works Department, whose registration stood renewed as per revised instructions and also registered dealers under the Himachal Pradesh, General Sales Tax Act, 1968. The important dates of tender are as under:-

| | Tender Schedule | Date | Time |
|----|---|-------------|-------------|
| 1. | The last date for receipt of application for tender Form. | 16/11/2023 | 4.00 PM |
| 2. | The last date for issue of tender Form | 17/11/2023 | 4.00 PM |
| 3. | The last date for receipt of tender. | 18/11/2023 | 10:30 AM |
| 4. | The date of opening of tender. | 18/11/2023 | 11:00 AM |

The tender forms can be obtained against payment of Rs.350/- (Non refundable) and contractor will be required to produce documents of registration in appropriate class, list of completed works and GST registration certificate. The tenders shall be opened in presence of contractor or their authorized representative.

The earnest money in shape of National Saving Certificate/Time deposit account of nationalized saving or Saving Bank account in any of the post offices and F.D.R. of Nationalized Bank duly pledged in favour of the Executive Engineer, NH Division, HP.PWD, Solan must accompany with the tender offer. The exemption from depositing the earnest money with each tender earlier granted has been withdrawn under Govt. Notification No. PWE (B&R)(B)14(18) / 98-11 dated 4.11.2003 and accordingly the tender received without Earnest Money shall be rejected without assigning any reasons thereto and shall not be entertained.

The tenders will be issued only to them who qualify the criteria after the scrutiny of application Form. The tenders not accompanying the Earnest money shall be rejected at the time of opening. The contractor shall also indicate the detail of Earnest money in the tender document. The request on prescribed application should accompany the registration of appropriate class, GST registration No., work done certificate. The tenders shall be opened on schedule date and time in presence of contractor or in the presence of the authorized representative.

The validity of tenders has been given in the tender document. If any contractor/firm withdraw the offer within validity period then their earnest money shall be forfeited and shall finally be at the disposal of State Govt. The contractors are advised to write the percentage both in figures and in words, failing which the tender shall be rejected.

Conditional and incomplete tenders shall out rightly be rejected.

Application for obtaining the tender form must accompany the latest renewal of enlistment and proof of GST No/NOC from Excise and Taxation Department regarding Tax clearance. The offer shall be kept open for 15 days.

If due to any unforeseen reasons the office of the Executive Engineer, NH Division, HP.PWD, Solan remain closed on the notified date of sale and receipt of tender, the tender will be sold and received/opened on next working day at same specified time.

The Executive Engineer reserves the right to accept or reject the tender without assigning any reason.

Description of JOB:-

| Sr. No. | Name of work | Estimated Cost (in Rs) | Earnest Money | Time |
|---------|--|------------------------|---------------|---------|
| 1 | Special repair in Pinjore Baddi Nalagarh Swarghat Road NH 21 A (New NH 105) from km 35/00 to 66/275 (SH:- Removal of land slides/slips from km 52/780 to 54/970) (Against OR New) | Rs 451466/- | Rs 9500/- | 1 month |
| 2 | Special repair in Pinjore Baddi Nalagarh Swarghat Road NH 21 A (New NH 105) from km 35/00 to 66/275 (SH:- Removal of land slides/slips from km 54/970 to 56/760) (Against OR New) | Rs 454537/- | Rs 9500/- | 1 month |
| 3 | Special repair in Pinjore Baddi Nalagarh Swarghat Road NH 21 A (New NH 105) from km 35/00 to 66/275 (SH:- Removal of land slides/slips from km 56/760 to 58/270) (Against OR New) | Rs 465287/- | Rs 9500/- | 1 month |
| 4 | Special repair in Pinjore Baddi Nalagarh Swarghat Road NH 21 A (New NH 105) from km 35/00 to 66/275 (SH:- Removal of land slides/slips from km 58/310 to 60/440) (Against OR New) | Rs 386971/- | Rs 8000/- | 1 month |
| 5 | Special repair in Pinjore Baddi Nalagarh Swarghat Road NH 21 A (New NH 105) from km 35/00 to 66/275 (SH:- Removal of land slides/slips from km 60/450 to 60/750) (Against OR New) | Rs 460680/- | Rs 9500/- | 1 month |
| 6 | Special repair in Pinjore Baddi Nalagarh Swarghat Road NH 21 A (New NH 105) from km 35/00 to 66/275 (SH:- Removal of land slides/slips from km 61/900 to 62/870) (Against OR New) | Rs 448396/- | Rs 9000/- | 1 month |
| 7 | Special repair in Pinjore Baddi Nalagarh Swarghat Road NH 21 A (New NH 105) from km 35/00 to 66/275 (SH:- Removal of land slides/slips from km 62/870 to 65/210) (Against OR New) | Rs 436110/- | Rs 9000/- | 1 month |
| 8 | Special Repair on Pinjore Baddi Nalagarh Swarghat Road NH 21A (New NH 105) from km 35/00 to 66/275 for the year 2023-24 (SH:- C/o R/wall in gabions structure on D/S of Panjehra Bridge at RD 48/090) (Left bank Part-1) | Rs 467506/- | Rs 9500/- | 1 month |

Term and Conditions:-

The contractor will have to produce following documents and attach attested copies of the same at the time of submitting application for issue of tender Form.

- Enlistment/renewal in appropriate class in HP.PWD.
- PAN Card issued by the Income Tax Department.
- Proof of valid GST Registration.
- Statement showing the ongoing works in HP.PWD.
- E.P.F registration.

Certified that the above work is of emergent nature in exigency of Public Interest.

[Signature]
Executive Engineer,
Solan NH Division,
HP.PWD., Solan.

Dated:- 07/11/2023

No. NHD/CB/TA/NIT/2023-

5093 - 5117

Copy forwarded to the following for information and necessary action:-

- The Engineer-in-Chief, HP.PWD, Shimla.
- The Chief Engineer, NH, HP.PWD, Shimla.
- The Superintending Engineer, NH Circle, HPPWD Shimla
- The Deputy Commissioner, Solan, Distt Solan.
- All the Assistant Engineers under this Division.
- Various registered contractors working under this Division
- Notice Board.
- The Executive Engineer, IT Cell in the o/o Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the

Departmental website.

[Signature]
Executive Engineer,
Solan NH Division,
HP.PWD., Solan.

DRAFT SCHEDULE OF QUANTITY

Estimated Cost 448396.00 /only
Earnest Money Rs. 9000 /only
Time :- 1 Month

NAME OF WORK :- Special Repair n Pinjore Baddi Nalagarh Swarghat Road NH-21A(New NH 105) from km 35/00 to 66/275(SH:- removal of Land slides/slips from km 61/900 to 62/870)(Against OR New)

| Sr.No. | Description of items | Quantity | Rate in Figures | Rate in Words | Unit | Amount | Overall percentage to be quoted by the bidder above /below the estimated cost inclusive of GST) i.e. nearest two decimal places/amount |
|--------------------|---|-------------|-----------------|--|---------|-----------|--|
| 1 | Removal of land slide (Slips) in hilly area (Road side) in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and levelling of road as per direction of Engineer-in-Charge at site, (assuming 5% of the totally quantity to be hard rock where rock breaker is required to breakdown the hard rock/boulders) according to as per technical specification clause 302.3.5 and 1611and sorting useful materials disposed all unuseful materials by all mode of transportation on approved dumping site along with its leveling, fine dressing by all labour, machineries, materials, tools, equipments and safety measures to protect the accidents necessary to complete the work, mechanized means and labour (if required)dumping site to be identified by the contractor and prescribed charges of dumping to be born by the contractor any loss to the public and private property during the course of execution shall be absolute responsibility of contractor which shall have to be duly compensate by him all respect including all leads and lifts with all mode of transport and as per the direction of Engineer-in-charge. The recovery of the usefull stone shall be made @ Rs. 600 per cubic metre for the 1/5th of the quantity of the Hard rock that works out to be 1% of the total quantity of removed slips. | 1946.67 cum | 230.34 | Rs. Rupees two hundred thirty and paise thirty four only | Per cum | 448396.00 | |
| Estimated Cost Rs. | | | | | | 448396.00 | |

[Signature]
Executive Engineer, NH
Division, HPPWD Solan

WORK SCHEDULE OF QUANTITY

Estimated Cost *Rs. 9500 /only*
 Earnest Money Rs. *9500 /only*
 Time :- *1 Month*

NAME OF WORK :- Special Repair n Pinjore Baddi Nalagarh Swarnhat Road NH-21A(New NH 105) from km 35/00 to 66/77(SM) :- removal of Land slides/slips
 from km 60/450 to 60/750(Against OR New)


| Sr.No. | Description of items | Quantity | Rate in Figures | Rate in Words | Unit | Amount | Overall percentage to be quoted by the bidder above/believe the estimated cost inclusive of GST i.e. nearest two decimal places/amount |
|--------|--|-------------|-----------------|--|---------|-----------|--|
| 1 | Removal of land slide (Slips) in hilly area (Road side) in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and leveling of road as per direction of Engineer-in-Charge at site, (assuming 5% of the totally quantity to be hard rock where rock breaker is required to breakdown the hard rock/boulders) according to as per technical specification clause 302.3.5 and 1611 and sorting useful materials disposed all unuseful materials by all mode of transportation on approved dumping site along with its leveling, fine dressing by all labour, machineries, materials, tools, equipments and safety measures to protect the accidents necessary to complete the work, mechanized means and labour (if required) dumping site to be identified by the contractor and prescribed charges of dumping to be born by the contractor any loss to the public and private property during the course of execution shall be absolute responsibility of contractor which shall have to be duly compensate by him all respect including all leads and lifts with all mode of transport and as per the direction of Engineer-in-Charge. The recovery of the usefull stone shall be made @ Rs. 600 per cubic metre for the 1/5th of the quantity of the Hard rock that works out to be 1% of the total quantity of removed slips. | 2000.00 cum | 230.34 | Rs. Rupees two hundred thirty and paise thirty four only | Per cum | 460680.00 | |
| | Estimated Cost Rs. | | | | | 460680.00 | |

Executive Engineer, NH
 Division, HPPWD Solan

DRAFT SCHEDULE OF QUANTITY

Estimated Cost 386971.00 /only
 Earnest Money Rs. 8000 /only
 Time :- 1 Month
 NAME OF WORK :- Special Repair in Pinjore Baddi Nalagarh Swarghat Road NH-21A(New NH 105) from km 35/00 to 66/275(SH:- removal of Land slides/slips from km 58/310 to 60/440)(Against OR New)

| S.No. | Description of items | Quantity | Rate in Figures | Rate in Words | Unit | Amount | Overall percentage to be quoted by the bidder above /below the estimated cost inclusive of GST) i.e. nearest two decimal places/amount |
|-------|--|-------------|-----------------|--|---------|-----------|--|
| 1 | Removal of land slide (Slips) in hilly area (Road side) in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and leveling of road as per direction of Engineer-In-Charge at site, (assuming 5% of the totally quantity to be hard rock where rock breaker is required to breakdown the hard rock/boulders) according to as per technical specification clause 302.3.5 and 1611 and sorting useful materials disposed all unuseful materials by all mode of transportation on approved dumping site along with its leveling, fine dressing, by all labour, machineries, materials, tools, equipments and safety measures to protect the accidents necessary to complete the work, mechanized means and labour (if required) dumping site to be identified by the contractor and prescribed charges of dumping to be born by the contractor any loss to the public and private property during the course of execution shall be absolute responsibility of contractor which shall have to be duly compensate by him all respect including all leads and lifts with all mode of transport and as per the direction of Engineer-In-Charge. The recovery of the useful stone shall be made @ Rs. 600 per cubic metre for the 1/5th of the quantity of the hard rock that works out to be 1% of the total quantity of removed slips. | 1680.00 cum | 230.34 | Rs. Rupees two hundred thirty and paise thirty four only | Per cum | 386971.00 | |
| | Estimated Cost Rs. | | | | | 386971.00 | |


 Executive Engineer, NH
 Division, HPWD Solan

DRAFT SCHEDULE OF QUANTITY

Estimated Cost 465287.00 /only
Earnest Money Rs. 9500 /only
Time :- 1 Month

NAME OF WORK :- Special Repair in Pinjore Baddi Nalagarh Swarghat Road NH-21A(New NH 105) from km 35/00 to 66/275(SH:- removal of land slides/slips from km 56/760 to 58/270)(Against OR New)

| Sr. No. | Description of items | Quantity | Rate in Figures | Rate in Words | Unit | Amount | Overall percentage to be quoted by the bidder above /below the estimated cost inclusive of GST) i.e. nearest two decimal places /amount |
|--------------------|---|-------------|-----------------|--|---------|-----------|---|
| 1 | Removal of land slide (Slips) in hilly area (Road side) in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and leveling of road as per direction of Engineer-in-Charge at site, (assuming 5% of the totally quantity to be hard rock where rock breaker is required to breakdown the hard rock/boulders) according to as per technical specification clause 302.3.5 and 1611 and sorting useful materials disposed all unuseful materials by all mode of transportation on approved dumping site along with its leveling, fine dressing by all labour, machineries, materials, tools, equipments and safety measures to protect the accidents necessary to complete the work, mechanized means and labour (if required) dumping site to be identified by the contractor and prescribed charges of dumping to be born by the contractor any loss to the public and private property during the course of execution shall be absolute responsibility of contractor which shall have to be duly compensate by him all respect including all leads and lifts with all mode of transport and as per the direction of Engineer-in-charge. The recovery of the useful stone shall be made @ Rs. 600 per cubic metre for the 1/5th of the quantity of the Hard rock that works out to be 1% of the total quantity of removed slips. | 2020.00 cum | 230.34 | Rs. Rupees two hundred thirty and paise thirty four only | Per cum | 465287.00 | |
| Estimated Cost Rs. | | | | | | 465287.00 | |

Executive Engineer, NH
Division, HPPWD Solan

SCHEDULE OF QUANTITY

Estimated Cost 454537.00 /only

Earnest Money Rs. 9500 /only

Time :- 1 Month

NAME OF WORK :- Special Repair in Pinjore Baddi Nalagath Swarghat Road NH-21A(New NH 105) from km 35/00 to 66/275(SH:- removal of Land slides/slips from km 54/970 to 56/760)(Against OR New)

| Sr.No. | Description of items | Quantity | Rate in Figures | Rate in Words | Unit | Amount | Overall percentage to be quoted by the bidder above /below the estimated cost inclusive of GST i.e. nearest two decimal places/amount |
|------------------------------|--|-------------|-----------------|--|---------|-----------|---|
| 1 | Removal of land slide (Slips) in hilly area (Road side) in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and leveling of road as per direction of Engineer-in-Charge at site, (assuming 5% of the totally quantity to be hard rock where rock breaker is required to breakdown the hard rock/boulders) according to as per technical specification clause 302.3.5 and 1611and sorting useful materials disposed all unuseful materials by all mode of transportation on approved dumping site along with its leveling, fine dressing by all labour, machineries, materials, tools, equipments and safety measures to protect the accidents necessary to complete the work, mechanized means and labour (if required)dumping site to be identified by the contractor and prescribed charges of dumping to be born by the contractor any loss to the public and private property during the course of execution shall be absolute responsibility of contractor which shall have to be duly compensate by him all respect including all leads and lifts with all mode of transport and as per the direction of Engineer-in-charge. The recovery of the usefull stone shall be made @ Rs. 600 per cubic metre for the 1/5th of the quantity of the Hard rock that works out to be 1% of the total quantity of removed slips. | 1973.33 cum | 230.34 | Rs. Rupees two hundred thirty and paise thirty four only | Per cum | 454537.00 | |
| Estimated Cost Rs. 454537.00 | | | | | | | |

Executive Engineer, NH

Division, HPPWD

Solan

SCHEDULE OF QUANTITY

Estimated Cost 451466 /only
Earnest Money Rs. 9500 /only
Time :- 1 Month

NAME OF WORK :- Special Repair n Pinjore Baddi Nalagarh Swarghat Road NH-21A(New NH 105) from km 35/00 to 66/275(SH:- removal of Land slides/slips from km 52/780 to 54/970)(Against OR New)


| Sr.No. | Description of items | Quantity | Rate in Figures | Rate in Words | Unit | Amount | Overall percentage to be quoted by the bidder above /below the estimated cost inclusive of GST) i.e. nearest two decimal places /amount |
|--------------------|--|-------------|-----------------|--|---------|-----------|---|
| 1 | Removal of land slide (Slips) in hilly area (Road side) in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and leveling of road as per direction of Engineer-in-Charge at site. (Assuming 5% of the totally quantity to be hard rock where rock breaker is required to breakdown the hard rock/boulders) according to as per technical specification clause 302.3.5 and 1611 and sorting useful materials disposed all unuseful materials by all mode of transportation on approved dumping site along with its leveling, fine dressing by all labour, machineries, materials, tools, equipments and safety measures to protect the accidents necessary to complete the work, mechanized means and labour (if required) dumping site to be identified by the contractor and prescribed charges of dumping to be born by the contractor any loss to the public and private property during the course of execution shall be absolute responsibility of contractor which shall have to be duly compensate by him all respect including all leads and lifts with all mode of transport and as per the direction of Engineer-in-charge. The recovery of the usefull stone shall be made @ Rs. 600 per cubic metre for the 1/5th of the quantity of the Hard rock that works out to be 1% of the total quantity of removed slips. | 1960.00 cum | 230.34 | Rs. Rupees two hundred thirty and paise thirty four only | Per cum | 451466.00 | |
| Estimated Cost Rs. | | | | | | 451466.00 | |

Executive Engineer,
NH Division, HPPWD.,
Solari

NAME OF WORK :- Restoration of Rain Damages of Pinjore Baddi Nalagarh Swarghat road NH-21 A (New NH - 105) From Km 35/0 to 66/275 (SH:- Construction of R/walls in Gabions structure on D/S of Panjera bridge at Rd's 48/090)(left bank part-1)

SCHEDULE OF QUANTITY
Estimated Cost 467506 /only
Earnest Money Rs. 9500 /only
Time :- 1 Month

| Sr.N o. | Description of items | Quantity | Rate in Figures | Rate in Words | Unit | Amount | Overall percentage to be quoted by the bidder above /below the estimated cost inclusive of GST) i.e. nearest two decimal places/amount |
|------------|--|-----------|--------------------|---|----------------|--------|--|
| 1 | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sam on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All Kinds of Soil e.g Ordinary rock as per CPWD specification/SOR 2020 including carriage of materials within all leads and lifts by all means including mechanical transport and as per direction of the Engineer-in-Charge. | 47.50 cum | 173.14 | Rs. one hundred seventy three and paise fourteen only | Per cum | 8224 | |
| 2 | Providing and making Gabian structures with Mechanically woven Double Twisted Hexagonal shaped wire mesh Gabions Boxes as per IS 16014:2012, MORT&H clause b2500, of required size, mesh type 10x12 (D=100mm with tolerance of + - 2%) Zinc coated, mesh wire diameter 3.0mm, mechanically edges/selvedged with partitions at every 1m interval and shall have minimum 10 numbers of openings per metre of mesh perpendicular to twist, tying with lacing wire of diameter 2.2mm, supplied @3% by weight of gabion boxes, filled with least dimension of 200mm, as per drawing, all complete as per the direction of engineer in charge.)2x1x1 = 2cum | 90.25 cum | 5089.00 | Rupees Five thousand eighty nine only | Per cum | 459282 | |
| | | | | | Estimated Cost | 467506 | |


Executive Engineer,
NH Division, HPWD.,
Solani

DRAFT SCHEDULE OF QUANTITY

Estimated Cost 436110.00 /only
Earnest Money Rs. 9000 /only
Time :- 1 Month

NAME OF WORK :- Special Repair n Pinjore Baddi Nalagarh Swarghat Road NH-21A(New NH 105) from km 35/00 to 66/275(Sh.:- removal of Land slides/slips from km 62/870 to 65/210)(Against OR New)

| Sr.No. | Description of items | Quantity | Rate in Figures | Rate in Words | Unit | Amount | Overall percentage to be quoted by the bidder above /below the estimated cost inclusive of GST) i.e. nearest two decimal places/amount |
|------------------------------|--|-------------|-----------------|--|---------|-----------|--|
| 1 | Removal of land slide (Slips) in hilly area (Road side) in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and leveling of road as per direction of Engineer-in-Charge at site, (assuming 5% of the totally quantity to be hard rock where rock breaker is required to breakdown the hard rock/boulders) according to as per technical specification clause 302.3.5 and 1611 and sorting useful materials disposed all unuseful materials by all mode of transportation on approved dumping site along with its leveling, fine dressing by all labour, machineries, materials, tools, equipments and safety measures to protect the accidents necessary to complete the work, mechanized means and labour (if required) dumping site to be identified by the contractor and prescribed charges of dumping to be born by the contractor any loss to the public and private property during the course of execution shall be absolute responsibility of contractor which shall have to be duly compensate by him all respect including all leads and lifts with all mode of transport and as per the direction of Engineer-in-charge. The recovery of the usefull stone shall be made @ Rs. 600 per cubic metre for the 1/5th of the quantity of the Hard rock that works out to be 1% of the total quantity of removed slips. | 1893.33 cum | 230.34 | Rs. Rupees two hundred thirty and paise thirty four only | Per cum | 436110.00 | |
| Estimated Cost Rs. 436110.00 | | | | | | | |

Executive Engineer, NH
Division, HPPWD Solan