

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

Short terms tenders on form 6&8 are hereby invited by the Executive Engineer Bangana Division HP.PWD Bangana on behalf of the Governor of H.P. for the following works from the approved and eligible contractors/firms of appropriate class enlisted in HPPWD as per latest instructions so as to reach and open in his office as per time schedule given below The offer of the tender will be kept open for 45 days from the date of opening of the tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

1. Date of receipt of applications for the tender
Form a/w requisite documents: -
2. Date of issue /sale of tender forms against
Cash payment (Non-refundable):-
3. Date of receipt of tenders: -
4. Date of opening of tenders: -

27.12.2023 upto 5.00 PM.

28.12.2023 upto 2:00 to 5.00 PM.

29.12.2023 upto 10.30 A.M.

29.12.2023 at 11.00 A.M.

Sr. No.	Name of Work	Estimated Cost	EMD	Time Limit	Cost of Tender	Eligible class of Contractor
1	Restoration of Rain Damages on Tehi Bijli Ghar to Chaplah road (SH:- C/O R/Wwall in km. 5/530 to 5/569.50 & Wing wall to R.C.C. Hume pipe culvert at RD. 5/900)	499766.00	10000.00	Two Month	350	Class D
2	Balance work for C/O P.H.C. Building at Chalola (C/O approach road in km. 0/030 to 0/60)	312770.00	6300.00	Two Month	350	Class-D
3	C/O Link road to Village Dadyar from U.A.M. Road km. 0/000 to 2/000 (C/O 4.00 Meter R.C.C. Slab culvert at RD. 0/250) Part -1	470270.00	9500.00	Two Month	350	Class-D
4	C/O Link road to ward No. 5 Ajnoli (SH:- P/L Interlocking Paver Block flooring in km. 0/100 to 0/200) Under OTMNP Head	346189.00	7000.00	Two Month	350	Class-D
5	Repair and Maintenance on various road under Dera Baba Rudru Sub Division (SH:- Patch work in Teuri & Dhamandri section)	487223.00	9800.00	Two Month	350	Class-D
6	Restoration of Rain Damages on Una Aghar Mandi road (SH:- Removal of slips at various Rd,s)	476982.00	9600.00	Two Month	350	Class D
7	C/O link road to Village Dhagroon km. 0/000 to 2/000(C/O C.C. Pavement in km. 1/006 to 1/106 & Drain in km. 0/800 to 1/080)	499431.00	10000.00	Two Month	350	Class-D
8	Restoration of Rain Damages on Una Takka Dhamandri road (C/O U-Shape Drain in km. 9/450 to 9/570)	394894.00	8000.00	Two Month	350	Class-D
9	C/O Link road to Abadi Harizen and Tharkhana Dangoli(SH:-P/L Interlocking paver blok 1/200 to 1/230 & V-Shape Drain in km. 1/120 to 1/200) under Head OTMNP	330150.00	6700.00	Two Month	350	Class-D
10	Restoration of Rain Damages on Piploo Rachhoh Road km. 0/000 to 21/660(SH: C/O Wire Crate in km. 20/890 to 20/908)	499433.00	10000.00	Two Month	350	Class-D
11	C/O Link road ti Village Kotla Khas km. 0/000 to 1/750 (SH:- C/O B/Wall in km. 0/330 to 0/390)	264776.00	5300.00	Two Month	350	Class D
12	Restoration of Rain Damages on Una Aghar Mandi Road km. 19/000 to 39/700 (SH:- C/O R/Wall in km. 36/530 to 36/569.50)	373972.00	7500.00	Two Month	350	Class-D
13	C/O Link road to Village Bhattian via Lower Dobar Lashyala km. 0/000 to 5/05(SH:- C/O R/Wall in km. 0/800 to 0/815)	392779.00	7900.00	Two Month	350	Class-D
14	Restoration of Rain Damages on Hatli Kharol road km. 0/000 to 8/825 (SH:- C/O R/Wall in km. 2/795 to 2/800,7/435 to 7/440 & 7/765 to 7/775)	294192.00	6000.00	Two Month	350	Class-D

15	R.R.D on Ghandawal Batuhi road km. 0/000 to 3/000(SH:- P/L Interlocking Paver Block from RD. 1/500 to 1/610)	471278.00	9500.00	Two Month	350	Class-D
16	C/O Tanoh Basater road via Kohldi km. 0/000 to 4/000 (SH:- P/L Interlocking Paver Block from RD. 0/315 to 0/390)	309992.00	6200.00	Two Month	350	Class-D
17	Balance work for the C/O Multipurpose Cultural Center at Samoor Kalan Dstt. Una (H.P.)(SH:- P/F Stainless Steel tables in Kitchen and Pantry and Aluminium work)	320001.00	6400.00	Two Month	350	Class-D
18	R.R.D. on Olinda Bohru road km. 0/000 to 11/000 (SH:- Removal of Slips at various RD.s in km. 0/000 to 3/000)	495792.00	10000.00	Two Month	350	Class-D
19	M/T on Chowkimaniar Dhamandri Dathwara road (SH:- C/O 900mm dia Hume pipe culvert at Rd. 0/260 & 0/400 a/w wing wall)	481048.00	9700.00	Two Month	350	Class-D
20	C/O Combined office building at Bangana Distt. Una (H.P.)(SH:- Demolishing of boundary wall & back filling behind R/Wall)	352832.00	7100.00	Two Month	350	Class-D
21	C/O Link road to Village Jandiyana km. 0/000 to 1/000 (Formation Cutting in km. 0/000 to 0/900)	499707.00	10000.00	Two Month	350	Class-D
22	Supplying, Installation and Commissioning of High Mast SPV (Solar) Street Lights on exsisting High Mast Pole by replacing AC Street Ligting System at Gram Panchayat Bangana and Gram Panchayat Jhalera	170000.00	3400.00	Two Month	350	Class-D
23	A/R & M/O various building under Bangana Division (SH:-Preparation of working estimates)	180000.00	3600.00	Two Month	350	Class-D
24	C/O Link road Kharol to Rounkhar km. 0/000 to 4/000 (SH:- Formation cutting from RD. 0/435 to 1/000)	499358.00	10000.00	Two Month	350	Class-D
25	Stock storage Under Bangana Sub Division (SH:- Supplying and Stacking CC2001002000 Quick lime)	400000.00	8000.00	Two Month	350	Class-D

The Earnest money in the shape of National Saving certificate/Time deposit/Saving account of any post office or FDR of Nationalised Bank duly pledged in the name of undersigned must be accompanied with each tender. The conditional tender and tender not accompanying the earnest money in the proper mode of deposit will summarily be rejected.

The Tender documents to be sent should have invariably be waxed in sealed cover and in failure of that those will not be entertained.

The Copy of valid enlistment, GST Registration No., Income Tax PAN No & EPF No. must be attached with application.

SPECIAL CONDITION:-

1. The tender form will be issued to those contractors who have relevant machinery and equipment, the list of which may be attached with their applications.(The proof of ownership of machinery/legal tie up arrangement).
2. The tender form will not be issued to those contractors who have already two works in hand.The earnest money for the above work should be submitted with the application for the purchase of the tender forms. The application received without earnest money shall summarily be rejected.
3. The conditional/ambiguous/telegraphic tenders or tender by fax shall not entertained/considered in any case.

No.PW/BGN/CB/T-1/2023-24-

7644-73

Copy forwarded to the following for information and necessary action:-

1. The Engineer-in-Chief HPPWD, Nirman Bhawan Shimla.
2. All the Assistant Engineer, working under this Division.
3. Various Contractors working under this Division.
4. Notice Board.

Executive Engineer
Bangana Division
HPPWD Bangana.
Dated 18-12-2023

Executive Engineer,
Bangana Division,
HPPWD Bangana.

Percentage BoQ.

Name of work:- Restoration of Rain Damages on Tehi Bijli Ghar to Chaplah road (SH:- C/O R/W wall in km. 5/530 to 5/569.50 & Wing wall to R.C.C. Hume pipe culvert at RD. 5/900)

PRICE SCHEDULE

This BoQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bids are allowed to enter Bidder name and values only

Sl. No.	Description of work	Estimated Cost	Quantity	Earliest Money	Estimated Rate in Rupee	Time Limit	Two Month
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks (where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in places not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and trailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other mechanicals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government	499766.00	45.74	Per Cubic metre.	402.00	18387.00	Rupees Four Hundred & Two Only
2	Providing and laying in position cement concrete 1:5:10 (one cement : five fine sand : ten graded/ crushed stone aggregate 40 mm (forty millimeter) nominal size mechanically mixed and curing complete excluding the cost of centering and shuttering in all work in foundation and plinth level as per the direction by the Engineer in charge including carriage of materials with in all leads and lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	123.26	Per Cubic metre.	3641.00	448790.00		Rupees Three Thousand Six Hundred & Four Hundred Only
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe make of (D-plast) / Finolex,) working pressure not less than 4.5 (four point five) kg/cm ² extending through the full width of the structures with slope of 1(v)20(H) (one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkana, toll tax, GST, labour cess or other taxes imposed by the Government.	73.000	Each	277.00	20221.00		Rupees Two Hundred & Seventy Seven Only
4	Back filling behind abutment, wing wall and return wall complete as per drawings and MORD 2014 technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST, or other taxes imposed by the Government	14.55	Per Cubic metre.	850.00	12368.00		Rupees Eight Hundred & Fifty Only
Total in Figures							Rupees Four Lakh Nine Thousand Seven Hundred & Sixty Six Only
Quoted Rate in Figures			Excess(+)				
			Less(-)				


 Executive Engineer
 Bangana Division
 H.P.W.D. Bangalore

Percentage BoQ.

Name of work:- Balance work for C/O P.H.C. Building at Chalola (C/O approach road in km. 0/030 to 0/60)

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bids are allowed to enter Bidder name and values only

		Estimated Cost	312770.00	Earnest Money	6300.00	Time Limit	Two Month
Sr. No.	Description of work	Quantity	Unit	Estimated Rate in Words	Total amount without Taxes	AMOUNT Rs. P	
1	Providing and laying cement concrete 1:4:8 (One cement : four coarse sand : eight graded crushed stone aggregate 40mm (forty millimetre) nominal size)mechanically mixed and curing complete excluding cost of form work upto all work plinth level including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST ; labour cess or other taxes imposed by the Government.	14.500	Per Cubic metre.	4296.00	62292.00	Rupees Four Thousand Two Hundred & Ninety Six Only	
2	Construction of pavement with 80mm (eighty millimetre) thick concrete blocks conforming to clause 1504.2.1 of MORC specifications, paved and compacted over a thin bedding of sand layers (material meeting the requirement of Table 1500.6 of these specifications) of specified grading to be spread over a properly constructed and profiled base course and bounded by properly edge restraints conforming to clause 1504.2.2 and 1504.2.3 of these specifications and complete the work to the satisfaction of Junior Engineer and Assistant Engineer of the area. (Subject to further entire satisfaction of the Engineer-in-Charge), including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	193.27	Per Square Meter	1296.00	250478.00	Rupees One Thousand Two Hundred & Ninety Six Only	
Total in Figures		312770.00					Rupees Three Lakh Twelve Thousand Seven Hundred & Seventy Six Only
Quoted Rate in Figures		Excess(+)					
		Less(-)					


 Executive Engineer
 Bangana Division
 H.P.W.D. Bangana

Percentage BoQ.

Name of work:- C/O Link road to Village Dadyar from U.A.M. Road km. 0/000 to 2/000 (C/O 4.00 Meter R.C.C. Slab culvert at RD. 0/250) Part -1

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed enter Bidder name and values only

Sl. No.	Description of work	Estimated Cost	470270.00	Quantity	Earnst Money Unit	9500.00	Estimated Rate in Words	Total amount without Taxes	Time Limit	Two Month AMOUNT Rs. P
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.			67.30	Per Cubic metre.	250.00	16825.00			Rupees Two Hundred & Fifty Only
2	Providing and laying cement concrete work 1:3:6 (one cement: three sand:six graded stone aggregate) 40mm (forty millimetre) nominal size in open foundation mechanically mixed and vibrated including curing complete, including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.			18.78	Per Cubic metre.	4745.00	89111.00			Rupees Four Thousand Seven Hundred & Forty Five Only
3	Providing and laying cement concrete work 1:2.5:5 (one cement: two decimal five sand: five graded stone aggregate) 40mm (forty millimetre) nominal size in substructure mechanically mixed and vibrated including curing complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204 and as per the direction of the Engineer-in-Charge, including carriage of material within all leads, lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.			70.81	Per Cubic Meter	5100.00	361131.00			Rupees Five Thousand One Hundred On
4	Providing and laying in position cement concrete 1:2:4 (One cement : two coarse sand : four graded crushed stone aggregate 20mm (twenty millimetre) nominal size)mechanically mixed and curing complete excluding cost of form work upto all work foundation and plinth level including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST ,labour cess or other taxes imposed by the Government.			0.60	Per Cubic metre.	5338.00	3203.00			Rupees Five Thousand Three Hundred & Thir Eight Only
Total in Figures									470270.00	Rupees Four Lakhs Seventy Thousand Two Hundred & Seventy Only
Quoted Rate in Figures					Excess(+)					
					Less(-)					


 Executive Engineer
 Bangana Division
 H.P.P.W.D. Bangana

percentage boy.

Name of work:-	C/O Link road to ward No. 5 Ajnoli (SH- P/L Interlocking Paver Block flooring in km. 0/100 to 0/200) Under OTNINP Head
----------------	---

INTEL SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bids are allowed to enter Bidder name and values only

Chandu
Executive Engineer
Bangana Division
U. P. W. S. A.


Percentage BoQ.

Name of work:- **Repair and Maintenance on various road under Dera Baba Rudru Sub Division (SH:- Patch wok in Teuri & Dhamandri section)**

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter Bidder name and values only

Sr. No.	Description of work	Estimated Cost	487223.00	Quantity	Earnest Money	9800.00	Estimated Rate in Words	Total amount without Taxes	Time Limit	Two Months
1	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mixer (Pug Mill), carriage of mixed material by tipper to site, laying in uniform layers in sub-base/base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100KN weight to achieve the desired density including lighting, barricading and maintenance of diversion, etc as per Tables 400.11 & 400.12 and Technical Specification Clause 406. Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government			19.10	Per Square metre	1915.00		36577.00		Rupees One Thousand Nine Hundred & Fifteen
2	Providing and applying primer coat with BITUMEN emulsion SS-1 on the prepared surface of granular base including cleaning of road surface with hydraulic brooms and spraying primer @ 0.70kg-1.00 kg (zero decimal seven zero kilogram) to one decimal zero kilogram) per square metre using mechanical means as per M.O.R.D. technical specifications clause 502 including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	254.66		Per Square metre	69.30			17648.00		Rupees Sixty Nine - Paise Thirty Only
3	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat at the rate of 0.30kg (aggregate 13.2mm (thirteen decimal two millimetre) to 5.6mm (five decimal six millimetre) compacted thickness, composed of crushed stone seven cubic metres), mixed with Bitumen VG-30 at the rate 1.46 Kg (one point four six kilogram) per square metres of road surface to required line grade and level to serve as wearing course on a previously prepared base, including mixing and heating binder and aggregate in Hot Mix Plant 30/40 (Thirty/ Forty) Tonne per hour capacity, transporting mixed material with tipper and laying manually to the required grade and camber and rolling with a three Wheel 80-100 (Eighty-hundred) KN static road roller, finished to required level and seal coat seal coat for sealing the voids in a bituminous surface laid to specified level grade and cross fall using type-B as per technical specification clause 510 using BITUMEN VG - 10 at the rate of 0.68 kg (zero point six eight kilogram) premixed with 0.006 (zero point zero-zero six) cubic metre of fine aggregate per Sqm. (square metre) heated in mini hot mix plant and laying manually of mixed material and rolling with power road roller 8-10 (eight to ten) tonne capacity specification Clause 1904.2.503 and 508.1, including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1515.04	Each	285.80				432998.00		Rupees Four Hundred Eighty Five Paise Eight Only
Total in Figures								487223.00		Rupees Four Lakh Eighty Seven Thousand Two Hundred & Twenty Three Only
Quoted Rate in Figures										


Executive Engineer
 Bangana Division


Percentage BoQ.

Name of work:- Restoration of Rain Damages on Una Aghar Mandi road (SH:- Removal of slips at various Rd,s)

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter Bidder name and values only

Sr. No.	Description of work	Estimated Cost	Quantity	Earnest Money	Unit	Estimated Rate in Words	Time Limit	Two Months
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611. including carriage of materials within all leads and lifts and other incidentals. The rate are including of octroi, royalty, Malkhana, tool or other taxes imposed by the Government	476982.00	3974.85	Per Cubic metre	120.00	476982.00		Rupees Four L Seventy Six Thousand N Hundred & E Two Only
Total in Figures						476982.00		
Quoted Rate in Figures				Excess(+)				
				Less(-)				



Executive Engineer
Bangana Division
H.P.P.W.D. Bangana

Percentage BoQ.

Name of work:- C/O link road to Village Dhagroon km. 0/000 to 2/000(C/O C.C. Pavement in km. 1/006 to 1/106 & Drain in km. 0/80 to 1/080)

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bids are allowed to enter Bidder name and values only

Sr. No.	Description of work	Estimated Cost	Quantity	Earnest Money	Unit	Estimated Rate in Words	Time Limit	Two Month AMOUNT Rs.
1	Loosening of the ground upto a level of 300mm below the subgrade level, watered graded and compacted in layers to meet requirement of Tables 300.1 and 300.2 for subgrade construction as MORD per technical Specification Clause 303.5.2 including carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	499431.00	56.00	Per Cubic metre.		90.00	5040.00	Rupees Ninety Only
2	Providing and laying cement concrete 1:4:8 (One cement : four coarse sand : eight graded crushed stone aggregate 40mm (forty millimetre) nominal size)mechanically mixed and curing complete excluding cost of form work upto all work plinth level including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST , labour cess or other taxes imposed by the Government.		49.60	Per Cubic metre.		4100.00	203360.00	Rupees Four Thousand Four Hundred Only
3	Providing and laying in position cement concrete 1:2:4 (One cement : two coarse sand : four graded crushed stone aggregate 20mm (twenty millimetre) nominal size)mechanically mixed and curing complete excluding cost of form work upto all work foundation and plinth level including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST , labour cess or other taxes imposed by the Government.		55.13	Per Cubic metre.		5279.00	291031.00	Rupees Fifty Thousand Seven Hundred Only
Total in Figures							499431.00	Rupees Four Ninety Thousand Four Hundred & Thirty One
Quoted Rate in Figures				Excess(+)				
				Less(-)				


Executive Engineer
 Bangana Division
 H.P.P.W.D. Bangana

Percentage BoQ.

Name of work:- Restoration of Rain Damages on Una Takka Dhamandri road (C/O U-Shape Drain in km. 9/450 to 9/570)

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender.
Bidders are allowed to enter Bidder name and values only

Sr. No.	Description of work	Estimated Cost	Quantity	Earnest Money Unit	Estimated Rate in Words	Time Limit without Taxes	Two Month AMOUNT Rs. P
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in benches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	394894.00	108.00	Per Cubic metre.	223.10	24095.00	Rupees Two Hundred & Twenty Three - Paise Ten Only
2	Providing and laying cement concrete work 1:3:6 (one cement: three sand:six graded stone aggregate) 40mm (forty millimetre) nominal size in open foundation mechanically mixed and vibrated including curing complete, including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge, including carriage of material within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.		63.00	Per Cubic metre.	4600.00	289800.00	Rupees Four Thousand Six Hundred Only
3	Providing and laying in position specified grade of reinforced cement concrete work M-25 (M-twenty five) design mix to obtain compressive strength of 25N/mm² with minimum cement contents not less than 400 kgs.(four hundred kilogram) per cubic metre mechanically mixed and vibrated including curing complete excluding cost of form work finishing and reinforcement with graded crushed stone aggregate 20mm nominal size upto all work foundation and plinth level including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST , labour cess or other taxes imposed by the Government.		5.63	Per Cubic metre	5835.00	32851.00	Rupees Five Thousand Eight Hundred & Thirty Five Only

St. No.	Description of work	Quantity	Unit	Estimated Rate in Words	Total amount without Taxes	AMOUNT Rs. P
4	Supplying, fitting and placing HYSD bar reinforcement of Sail, Tisco, Rimal, Jindal Panther of (JSP) or Shyam Steel in all type of structure complete as per drawing and MORD 2014 technical specification clause 1600.2200 including cutting, bending, binding and placing in position complete in all respect including cost of binding wire upto all heights as per the entire satisfaction and directions of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rates are inclusive octroi, royalty, malkana, toll tax, Goods Service tax, Labour cess, or other taxes imposed by the Government.	450.40	Per Kilogramme	106.90	48148.00	Rupees On Hundred & - Paise Nine Only
Total in Figures					394894.00	Rupees Three Lakh Ninety Four Thousand Eight Hundred & Nine Four Only
	Quoted Rate in Figures			Excess(+) Less(-)		


 Executive Engineer
 Bangana Division
 H.P.P.W.D. Bangana

Percentage BoQ.


Name of work:- C/O Link road to Abadi Harizen and Tharkhana Dangoli(SH:-P/L Interlocking paver blok 1/200 to 1/230 & V-Sha Drain in km. 1/120 to 1/200) under Hrad OTMNP

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bid are allowed to enter Bidder name and values only

Sr. No.	Description of work	Estimated Cost	Quantity	Earrest Money	Estimated Rate in Words	Time Limit	Two Mon
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes	330150.00	4.80	Per Cubic metre.	496.70	2384.00	Ruppes Five Hundred Ninety Six Paise Seven Only
2	Providing and laying cement concrete 1:4:8 (One cement : four coarse sand : eight graded crushed stone aggregate 40mm (forty millimetre) nominal size)mechanically mixed and curing complete excluding cost of form work upto all work plinth level including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST , labour cess or other taxes imposed by the Government.		10.50	Per Cubic metre.	4100.00	43050.00	Ruppes Four Thousand Hundred Only
3	Construction of pavement with 60mm (sixty millimetre) thick concrete blocks conforming to clause 1504.2.1 of MORD specifications, paved and compacted over a thin bedding of sand layers (material meeting the requirement of Table 1500.6 of these specifications) of specified grading to be spread over a properly constructed and profiled base course and bounded by properly edge restraints conforming to clause 1504.2.2 and 1504.2.3 of these specifications and complete the work to the satisfaction of Junior Engineer and Assistant Engineer of the area. (Subject to further entire satisfaction of the Engineer-in-Charge), including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.		240.00	Per Square Meter	982.00	235680.00	Ruppes Ninety Eight Thousand Only

Sr. No.	Description of work	Quantity	Unit	Estimated Rate in Words	Total amount without Taxes	AMOUNT Rs.
4	Providing and laying in position cement concrete 1:2:4 (One cement : two coarse sand : four graded crushed stone aggregate 20mm (twenty millimetre) nominal size)mechanically mixed and curing complete excluding cost of form work upto all work foundation and plinth level including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST , labour cess or other taxes imposed by the Government.	1.80	Per Cubic metre.	5332.00	9598.00	Ruppes Three Thousand & Thirty Only
5	Providing and laying cement concrete work 1:3:6 (one cement: three sand:six graded stone aggregate) 40mm (forty millimetre) nominal size in open foundation mechanically mixed and vibrated including curing complete, including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge, including carriage of material within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.40	Per Cubic metre.	4695.00	39438.00	Ruppes Four Thousand Nine Hundred Ninety Only
Total in Figures					330150.00	Ruppes Three Thousand One Hundred Fifty Only
	Quoted Rate in Figures	Excess(+)				
		Less(-)				


Executive Engineer
 Bangana Division
 H.P.R.W.D. Bangana

Percentage BoQ.

Name of work:- Restoration of Rain Damages on Piploo Rachhoh Road km. 0/000 to 21/660 (SH: C/O Wire Crate in km. 20/890 to 20/908)

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bid are allowed to enter Bidder name and values only

Sr. No.	Description of work	Estimated Cost	Quantity	Earnest Unit	Estimated Rate in Words	Time Limit Total amount without Taxes	Two Mon AMOUN Rs.
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks (where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes	499433.00	44.55	Per Cubic metre.	250.00	11138.00	Ruppes T Hundred Fifty On
2	Providing and laying cement concrete 1:4:8 (One cement : four coarse sand : eight graded crushed stone aggregate 40mm (forty millimetre) nominal size)mechanically mixed and curing complete excluding cost of form work upto all work plinth level including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, labour cess or other taxes imposed by the Government.		16.20	Per Cubic metre.	4100.00	66420.00	Ruppes F Thousand Hundred Only
3	Providing and laying of boulder apron laid in wire crates made with 4mm dia GI wire conforming to IS:280 and IS: 4826 in 100mm x 100mm (one hundred millimetre) mesh (waved diagonally) including 10 (ten) per cent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogramme) each as per drawing and technical specifications Clause No. 1301. including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.		112.50	Per cubic metre	3750.00	421875.00	Ruppes Th Thousand Seven Hundred Fifty On
Total in Figures						499433.00	Ruppes Four L Ninety Nine Thousand Four Hundred & Th Three Only
Quoted Rate in Figures				Excess(+) Less(-)			

Shanu

Executive Engineer
Bangana Division


Percentage BoQ.

Name of work:- C/O Link road ti Village Kotla Khas km. 0/000 to 1/750 (SH:- C/O B/Wall in km. 0/330 to 0/390)

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bids are allowed to enter Bidder name and values only

Sr. No.	Description of work	Estimated Cost	264776.00	Quantity	Earnest Money	Unit	Estimated Rate in Words	Total amount without Taxes	Time Limit	Two Months
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deteriorious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	36.45	Per Cubic metre.	250.00	9113.00	Rupees Two Hundred Fifty Only				
2	Providing and laying in position cement concrete 1:5:10 (one cement : five fine sand : ten graded/ crushed stone aggregate 40 mm (forty millimeter) nominal size mechanically mixed and curing complete excluding the cost of centering and shuttering in all work in foundation and plinth level as per the direction by the Engineer in charge including carriage of materials with in all leads and lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	66.15	Per Cubic metre.	3600.00	238140.00	Rupees Th Thousand Hundred Only				
3	Providing weepholes in brick masonry/ stone masonry/ plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe make of (D-Plast) / Finolex.) working pressure not less than 4.5 (four point five) kg/cm² extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	59.000	Each	297.00	17523.00	Rupees Two Hundred Ninety Seven Only				
Total in Figures		264776.00		Rupees Two L Sixty Four Thousand Seven Hundred Seventy Six Only						
Quoted Rate in Figures		Excess(+)		Less(-)						


Executive Engineer
 Bangana Division
 U.P.B.W.D. Bangalore


Percentage BoQ.

Name of work:- Restoration of Rain Damages on Una Aghar Mandi Road km. 19/000 to 39/700 (SH: C/O R/Wall in km. 36/330 to 36/569.50)

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bid are allowed to enter Bidder name and values only

Sr. No.	Description of work	Estimated Cost	Quantity	Earnest Money	Estimated Rate in Words	Time Limit	Two Mon
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any-quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	373972.00	37.13	Per Cubic metre.	402.00	14926.00	Rupees Five Hundred and Two 0
2	Providing and laying in position cement concrete 1:5:10 (one cement : five fine sand : ten graded/ crushed stone aggregate 40 mm (forty millimeter) nominal size mechanically mixed and curing complete excluding the cost of centering and shuttering in all work in foundation and plinth level as per the direction by the Engineer in charge including carriage of materials with in all leads and lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	92.83		Per Cubic metre.	3641.00	337994.00	Rupees Three Thousand and Hundred Forty C Only
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimeter) dia PVC pipe make of (D-plast) / Emolex.) working pressure not less than 4.5 (four point five) kg/cm² extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	76.00		Each	277.00	21052.00	Rupees Three Hundred and Seventy S Only
Quoted Rate in Figures		Excess(+)	Less(-)			373972.00	Rupees Three Thousand and Ninety Hundred & Se


 Executive Engineer
 Bangana Division
 H.P.W.D. Banoara

Percentage BoQ.

Name of work:- C/O Link road to Village Bhattian via Lower Dohar Lashyala km. 0/000 to 5/05(SH:- C/O R/Wall in km. 0/800 to 0/815)

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bids are allowed to enter Bidder name and values only

Sr. No.	Description of work	Estimated Cost	Quantity	Unit	Earliest	Estimated Rate in Words	Time Limit	Two Mon
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks/ where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and hauling out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess, or other taxes imposed by the Government.	392779.00	31.20	Per Cubic metre.	7900.00	242.00	7550.00	Rupees 1 AMOUN Rs.
2	Providing and laying in position cement concrete 1:3:10 (one cement five fine sand ten graded/ crushed stone aggregate 40 mm (forty millimeter) nominal size mechanically mixed and curing complete excluding the cost of centering and shuttering in all work in foundation and plinth level as per the direction by the Engineer in charge including carriage of materials with in all leads and lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	96.15	Per Cubic metre.	3641.00	350082.00			Rupees 1 Thousand
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe make of (D-plast) / Finolex,) working pressure not less than 4.5 (four point five) kg/cm ² extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	56.00	Each	277.00	15512.00			Rupees 1 Hundred
4	Back filling behind abutment, wing wall and return wall complete as per drawings and MOR.D 2014 technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST, or other taxes imposed by the Government	23.10	Per Cubic metre.	850.00	19635.00			Rupees 1 Hundred
Total in Figures							392779.00	Rupees Three 1
Quoted Rate in Figures			Excess(+)					Ninety Two Th
			Less(-)					Seven Hundred
								Seventy Nine


Executive Engineer
Bangana Division
H.P.P.W.D. Bangana

Percentage BoQ.

Name of work:- Restoration of Rain Damages on Hatli Kharol road km. 0/000 to 8/825 (SH:- C/O R/Wall in km. 2/795 to 2/800, 7/435 to 7/440 & 7/765 7/775)

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bid are allowed to enter Bidder name and values only

are allowed to enter under the following heads:									
Sr. No.	Description of work	Estimated Cost	Quantity	Earnest Money	5900.00	Estimated Rate in Months	Total amount without Taxes	Time Limit	Two Month
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks/ where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and hauling out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	27.60	Per Cubic metre.	421.00	11620.00	Rupees Four Hundred & Twenty One			
2	Providing and laying in position cement concrete 1.5:10 (one cement : five fine sand : ten graded/ crushed stone aggregate 40 mm (forty millimeter) nominal size mechanically mixed and curing complete excluding the cost of centering and shuttering in all work in foundation and plinth level as per the direction by the Engineer in charge including carriage of materials with in all leads and lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	63.00	Per Cubic metre.	3641.00	229385.00	Rupees Three Thousand Six Hundred & Eighty One Only			
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe make of (D-plast) / Finolux,) working pressure not less than 4.5 (four point five) kg/cm ² extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	57.00	Each	277.00	15789.00	Rupees Two Hundred & Seventy Seven Only			
4	Back filling behind abutment, wing wall and return wall complete as per drawings and MORD 2014 technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST, or other taxes imposed by the Government	44.00	Per Cubic metre.	850.00	37400.00	Rupees Eight Hundred & Fifty			
						294192.00	Rupees Two Lakh Ninety Thousand One Hundred Two Only		
	Quoted Rate in Figures	Excess(+) Less(-)							


 Executive Engineer
 Bangana Division
 H.P.P.W.D. Bangana

Percentage BoQ.


Name of work:- R.R.D on Chandawal Batuhi road km. 0/000 to 3/000(SH:- P/LInterlocking Paver Block from RD. 1/500 to 1/610)

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bids are allowed to enter Bidder name and values only

Sr. No.	Description of work	Estimated Cost	Quantity	Earnest Money	Unit	Estimated Rate in Words	Time Limit	Two Mon
1	Excavating, supplying and filling of local earth (including royalty) by mechanical transport upto a lead of 5km also including ramming and watering of the earth in layers not exceeding 20 cm in trenches, plinth, sides of foundation etc. complete as per drawings and technical specification clause 614.709.1204.3.7 including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	471278.00	82.50	Per Cubic metre.		288.00	23760.00	Rupees 1 Hundred Eighty Eighty Only
2	Construction of gravel/soil aggregate sub base/base by providing well graded material of nominal maximum size grading 80mm as per table 2.3 of IRC SP 77-2008, Spreading in uniform layers with tractor mount appropriate grading arrangements on prepared surface, mixing by mix in place method at OMC with tractor mount appropriate rotavator attachment and compaction with three wheel 80-100 KN Static roller capacity to achieve the desired density complete as per specifications contained in Para 2.2.3.6 and 3.7 of IRC SP 77-2008 including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.		34.38	Per Cubic metre.		1511.00	51948.00	Rupees 5 Thousand Hundred Eleven Only
3	Providing and laying in position cement concrete 1:4:8 (One cement : four coarse sand : eight graded crushed stone aggregate 40mm (forty millimetre) nominal size) mechanically mixed and curing complete excluding cost of form work upto all work in foundation and plinth level including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, labour cess or other taxes imposed by the Government.		27.50	Per Cubic metre.		3960.00	108900.00	Rupees 10 Thousand Nine Hundred & Sixty Only
4	Construction of pavement with 80mm (eighty millimetre) thick concrete blocks conforming to clause 1504.2.1 of MORD specifications, paved and compacted over a thin bedding of sand layers (material meeting the requirement of Table 1500.6 of these specifications) of specified grading to be spread over a properly constructed and profiled base course and bounded by properly edge restraints conforming to clause 1504.2.2 and 1504.2.3 of these specifications and complete the work to the satisfaction of Junior Engineer and Assistant Engineer of the area. (Subject to further entire satisfaction of the Engineer-in-Charge), including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.		250.00	Per Square Meter		1100.00	275000.00	Rupees 275 Thousand Only

Sr. No.	Description of work	Quantity	Unit	Estimated Rate in Words	Total amount without Taxes	AMOUNT Rs.
5	Providing and laying in position specified grade of reinforced cement concrete work M-25 (M-twenty five) design mix to obtain compressive strength of 25N/mm ² with minimum cement contents not less than 400 kgs.(four hundred kilogram) per cubic metre mechanically mixed and vibrated including curing complete excluding cost of form work finishing and reinforcement with graded crushed stone aggregate 20mm nominal size upto all work foundation and plinth level including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, labour cess or other taxes imposed by the Government.	2.00	Per Cubic metre	5835.00	11670.00	Rupees Eight Thousand & Thirty One Only
Total in Figures					471278.00	Rupees Four Lacs Seventy One Thousand Two Hundred and Seventy Eight
	Quoted Rate in Figures	Excess(+)				
		Less(-)				


 Executive Engineer
 Bangana Division
 H.P.P.W.D. Bangana

Percentage BoQ.

Name of work:- C/O Tanoh Basater road via Kohldi km. 0/000 to 4/000 (SH:- P/L Interlocking Paver Block from RD. 0/315 to 0/390)

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidder are allowed to enter Bidder name and values only

are allowed to enter Bidding and values only							
		Estimated Cost	309992.00	Earnest Money	6200.00	Time Limit	Two Mon
Sr. No.	Description of work	Quantity	Unit	Estimated Rate in Words	Total amount without Taxes	AMOUNT Rs.	
1	Providing and laying in position cement concrete 1:2:4 (One cement : two coarse sand : four graded crushed stone aggregate 20mm (twenty millimetre) nominal size)mechanically mixed and curing complete excluding cost of form work upto all work foundation and plinth level including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge. The rates are inclusive of octroi, royalty, Malkana. toll tax, GST , labour cess or other taxes imposed by the Government.	5.96	Per Cubic metre.	5200.00	30992.00	Rupees F Thousand Hundree Only	
2	Construction of pavement with 80mm (eighty millimetre) thick concrete blocks conforming to clause 1504.2.1 of MORD specifications, paved and compacted over a thin bedding of sand layers (material meeting the requirement of Table 1500.6 of these specifications) of specified grading to be spread over a properly constructed and profiled base course and bounded by properly edge restraints conforming to clause 1504.2.2 and 1504.2.3 of these specifications and complete the work to the satisfaction of Junior Engineer and Assistant Engineer of the area. (Subject to further entire satisfaction of the Engineer-in-Charge), including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	232.50	Per Square Meter	1200.00	279000.00	Rupees F Thousand Hundree Only	
						309992.00	Rupees Three Nine Thousand Hundred & N Two Only
Quoted Rate in Figures		Excess(+) Less(-)					


 Executive Engineer
 Bangana Division
 H.P.P.W.D. Bangana

Percentage BoQ.

Name of work:- Balance ork for the C/O Multipurpose Cultural Center at Samoor Kalan Dst. Una (H.P.)(SH:- P/F Stainless Steel tables in Kitchen and Pantry and Aluminium work)

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bids are allowed to enter Bidder name and values only

Sl. No.	Description of work	Estimated Cost	Quantity	Earnest Money Unit	Estimated Rate in Words	Time Limit Total amount without Taxes	Two Months AMOUNT Rs.
1	Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, including fixing the railing with necessary accessories and stainless steel dash fasteners, stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in-charge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.) upto all heights in all floor level as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	320001.00	453.64	Per Kilogramme	6400.00	292144.00	Rupees 5 Hundred Forty Five Only
2	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, milled and jointed mechanically wherever required including cleat angle. Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete upto all floor level as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately)/Powder coated aluminium (minimum thickness of powder coating 50 micron) as per the direction by the Engineer-in-charge including entire carriage of materials with in all leads and lifts including other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	19.38		Per Kilogramme	439.00	8508.00	Rupees 8 Hundred Thirty Nine Only
3	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, milled and jointed mechanically wherever required including cleat angle. Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete upto all floor level as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : For fixed portion Powder coated aluminium (minimum thickness of powder coating 50 micron) including entire carriage of materials with in all leads and lifts including other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	21.85		Per Kilogramme	471.60	10304.00	Rupees 10 Hundred Seventy Four Paise Sixty Only
4	Providing and fixing glazing with float glass panes of 5 mm (five millimeter) thickness (weight not less than 12.50 kg/ sqm) in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete upto all floor level as per the architectural drawings and the directions of engineer-in-charge (Cost of aluminium snap beading shall be paid in basic item) as per the direction by the Engineer-in-charge including entire carriage of materials with in all leads and lifts including other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	3.19		Per Square metre.	1259.10	4017.00	Rupees 4 Thousand Hundred Fifty Nine Paise Ten

Sl. No.	Description of work	Quantity	Unit	Estimated Rate in Words	Total amount without Taxes	AMOUNT Rs.
5	Providing and fixing 12mm (twelve millimeter) thick Pre-laminated particle board with decorative lamination on both sides, flat pressed three layer or graded wood particle board conforming to IS : 12823 Grade I Type II, in paneling of Action tea, Novapan, Kiply, National, Archid Ply Green make fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete upto all floor level as per architectural drawings as per the direction by the Engineer-in-charge including entire carriage of materials with in all leads and lifts including other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	2.75	Per Square metre.	1436.40	3950.00	Rupees C Thousand Hundred Thirty Six Paise Four
6	Providing and fixing 300x16mm(three hundred into sixteen millimeter) aluminium sliding door bolts, ISI marked anodized (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete upto all floor level as per the direction by the Engineer-in-charge including entire carriage of materials with in all leads and lifts including other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	2.00	Each	303.70	607.00	Rupees Three Hundred Thirty - Paise Seven
7	Providing and fixing 200x10mm (two hundred into ten millimeter) aluminium tower bolts, ISI marked, anodized (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete upto all floor level as per the direction by the Engineer-in-charge including entire carriage of materials with in all leads and lifts including other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	2.00	Each	70.80	142.00	Rupees Seventy Paise Eight Only
8	Providing and fixing 125mm (one hundred twenty five millimeter) aluminium handles, ISI marked, anodized (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete upto all floor level as per the direction by the Engineer-in-charge including entire carriage of materials with in all leads and lifts including other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	5.00	Each	65.70	329.00	Rupees Sixty - Paise Seven Only
Total in Figures					320001.00	Rupees Three L Twenty Thousa & One Only
Quoted Rate in Figures		Excess(+)				
		Less(-)				


 Executive Engineer
 Bangana Division
 H.P.P.W.D. Bangana

Percentage BoQ.

Name of work:- R.R.D. on Olinda Bohru road km. 0/000 to 11/000 (SH:- Removal of Slips at various RD,s in km. 0/000 to 3/000)

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter Bidder name and values only

Sl. No.	Description of work	Estimated Cost	Quantity	Earnest Money Unit	Estimated Rate in Words	Time Limit	Two Months
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611. including carriage of materials within all leads and lifts and other incidentals. The rate are including of octroi, royalty, Malkhana, tool or other taxex imposed by theGovernment	495792.00	4131.60	Per Cubic metre	120.00	495792.00	Rupees One Hundred Twenty C
Total in Figures						495792.00	Rupees Four L Ninety Five Thousand Seven Hundred & Ninety Two Only
Quoted Rate in Figures				Excess(+) Less(-)			



Executive Engineer
Bangana Division
H.P.P.W.D. Bangana

Percentage BoQ.


Name of work:- M/T on Chowkimaniar Dhamandri Dathwara road (SH:- C/O 900mm dia Hume pipe culvert at Rd. 0/260 & 0/400 a/w wing wall)

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bid are allowed to enter Bidder name and values only

Sr. No.	Description of work	Estimated Cost	Quantity	Earnest Money	Estimated Rate in Words	Time Limit	Two Mon
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	481048.00	66.22	Per Cubic metre	250.00	16555.00	Rupees T Hundred Fifty Or
	Providing and laying cement concrete 1:4:8 (One cement : four coarse sand : eight graded crushed stone aggregate 40mm (forty millimetre) nominal size)mechanically mixed and curing complete excluding cost of form work upto all work plinth level including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST , labour cess or other taxes imposed by the Government.	8.12		Per Cubic metre.	4100.00	33292.00	Rupees F Thousand Hundred Only
	Providing and laying cement concrete work 1:3:6 (one cement: three sand:six graded stone aggregate) 40mm (forty millimetre) nominal size in open foundation mechanically mixed and vibrated including curing complete, including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge, including carriage of material within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	29.87		Per Cubic metre.	4600.00	137402.00	Rupees F Thousand Hundred Only

Sr. No.	Description of work	Quantity	Unit	Estimated Rate in Words	Total amount without Taxes	AMOUN Rs.
	Providing and laying 900mm(nine hundred millimetre) dia reinforced cement concrete pipe NP-2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2(one cement:two sand) but excluding excavation protection work,back filling,concrete and masonry work in head walls and parapets as per technical specifications clause -1106 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	15.00	Per Running meter	3800.00	57000.00	Rupees Thousar Eight Hun Only
	Providing and laying in position cement concrete 1:5:10 (one cement : five fine sand : ten graded/ crushed stone aggregate 40 mm (forty millimeter) nominal size mechanically mixed and curing complete excluding the cost of centering and shuttering in all work in foundation and plinth level as per the direction by the Engineer in charge including carriage of materials with in all leads and lifts and other incidentals. The rate including octroi, royalty, Malkhana, toll tax, sale tax or other taxes imposed by the Government.	63.36	Per Cubic metre.	3600.00	228096.00	Rupees Th Thousand Hundred Only
	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe make of (D-plast) / Finolex,) working pressure not less than 4.5 (four point five) kg/cm ² extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	30.000	Each	290.10	8703.00	Rupees T Hundred Ninety - P Ten Onl
Total in Figures					481048.00	Rupees Four La Eighty One Thousand & For Eight Only
	Quoted Rate in Figures	Excess(+)				
		Less(-)				


Executive Engineer
 Bangana Division
 H.P.P.W.D. Banganga

Percentage BoQ.

Name of work:- C/O Combined office building at Bangana Dist. Una (H.P.)(SH:- Demolishing of boundary wall & back filling behind R/Wall)

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter Bidder name and values only

Sr. No.	Description of work	Estimated Cost	Quantity	Unit	Estimated Rate in Words	Time Limit	Two Months
1	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per the direction by the Engineer-in-charge including entire carriage of materials with in all leads and lifts including other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by	352832.00	17.14	Per Cubic metre.	424.00	7267.00	Rupees Four Hundred Twenty Four Only
2	Loosening of the ground upto a level of 300mm below the subgrade level, watered graded and compacted in layers to meet requirement of Tables 300.1 and 300.2 for subgrade construction as MORD per technical Specification Clause 303.5.2 including carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.		432.00	Per Cubic metre.	92.00	39744.00	Rupees Nine Thousand Two On
3	Back filling behind abutment, wing wall and return wall complete as per drawings and MORD 2014 technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST, or other taxes imposed by the Government.		198.00	Per Cubic metre.	800.00	158400.00	Rupees Eight Hundred
4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to any floor level including scaffolding in all shapes and sizes in cement mortar 1:6 (one cement: six coarse sand) as per the direction by the Engineer in charge including carriage of materials with in all leads and lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.		12.75	Per Cubic metre.	7174.00	-91469.00	Rupees Seven Thousand Four Hundred Seventy Four Only
5	15mm (fifteen millimeter) Cement plaster on the rough side and Fair Side of f brick wall of mix cement mortar 1:6 (one cement: six coarse sand) in any floor level/any height as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.		100.20	Per Square metre.	248.90	24940.00	Rupees Two Hundred Fourty Eight Paise Nine Only
6	Finishing walls with 100% Premium acrylic emulsion paint Nerolac, Berger(Bison Acrylic) Asian Paint (Tractor: Acrylic) Shalimar having VOC less than 50 gm/litre and UV resistance as per IS 15489:2004, Alkali & fungal resistance, dirt resistance exterior paint of required shade (Company Depot Tinted) with silicon additives. New work (Two or more coats applied @1.43 litre/ 10 sqm. Over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm.complete upto all floor level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.		100.20	Per Square metre.	128.60	12886.00	Rupees One Hundred & Twenty Eight Paise Sixty Four Only

Sr. No.	Description of work	Quantity	Unit	Estimated Rate in Words	Total amount without Taxes	AMOUN Rs.
7	Providing and fixing Structural steel work riveted, bolted or welded in built up sections in trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete, upto all floor level as per the direction by the Engineer-in-charge including entire carriage of materials with in all leads and lifts including other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	135.00	Per Kilogramme	106.30	14351.00	Ruppes (Hundred & Paise Only
8	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 litr/ 10 sqm (zero point ninety liter per ten square meter) over an under coat of primer applied @ 0.80 litr/ 10 sqm (zero point eighty liter per ten square meter) of approved brand and manufacture ICI (Dulux Gloss) Nerolac, Berger (Luxol High Gloss) Asian Paints (Premium Apcolite Gloss) Shalimar upto all heights in all floor level as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	34.95	Per Square metre.	108.00	3775.00	Ruppes (Hundred Eight O
Total in Figures					352832.00	Ruppes Three La
	Quoted Rate in Figures			Excess(+)		Fifty Two Thous
				Less(-)		Eight Hundred & Thins Two Only


 Executive Engineer
 Bangana Division
 H.P.P.W.D. Bangana

Percentage BoQ.

Name of work:- C/O Link road to Village Jandiyana km. 0/000 to 1/000 (Formation Cutting in km. 0/000 to 0/900)

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter Bidder name and values only

		Estimated Cost						
St. No.	Description of work	499707.00	Quantity	Earnest Money Unit	10000.00	Estimated Rate in Words	Time Limit	Two Months
1.00	Excavation in hilly area in all heights and depths and in all kind of soil by manual/ mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chiselling , wedging out of rock (where blasting is prohibited) and their intermediate classification of soil , setting out true to the required lines, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by Engineer-in-charge at site according to the MORD technical specification clause 302, 1603.1 and 1603.2 and sorting out useful materials and stacking the same in all leads and lifts on acquired width of road and transportation for filling in road ways, camber ,embankments for grade improvements and disposal of all surplus material to required width of the road or to approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials ,tool and labour if required. Any loss to the public private property during the course to execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all the cases as per the direction of engineer-in-charge including carriage of material with in all leads and lifts. All useful material such as stone, shingle, sand and slates etcetra shall be sorted out. A recovery of 187.20 cum (One hundred eighty seven point two zero) stone to be obtained from excavation cutting at the rate of Rs. 300/- (Rupees three hundred only) per cubic metre shall be effected on prorata bases in each running bill for this item, including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty,malkhana ,toll tax,GST ,labour cess or other taxes imposed by the Government..	1110.5	Per Cubic metre.	450.00	499707.00	Rupees Four Hundred Fifty O		
Total in Figures		499707.00						Rupees Four Lak Ninety Nine Thousand Seven Hundred & Seven Only
Quoted Rate in Figures		Excess(+) Less(-)						


Executive Engineer
 Bangana Division
 H.P.W.D. Bangana

Percentage BoQ.

Name of work:- Supplying, Installation and Commissioning of High Mast SPV (Solar) Street Lights on existing High Mast Pole by replacing AC Street Lighting System at Gram Panchayat Bangana and Gram Panchayat Jhalera

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter Bidder name and values only

Sr. No.	Description of work	Estimated Cost	Quantity	Unit	Estimated Rate in Words	Time Limit	Two Month
		170000.00					AMOUNT Rs. P
1	Supplying, Fixing/ Installation and Commissioning of High Mast SPV (Solar) Street Lighting System 4 nos X 30 Watts (LED + Driver) as per Configuration along with Solar PV Modules and Battery of given Capacity including installation at site, replacing of old AC Street Lights on existing High Mast Pole		2.00	Nos.	85000.00	170000.00	Rupees Eighty Five Thousand Only
Note:-	1.1 LED LUMINARY Solar PV White- LED High Mast Light Consist of White LED Luminary of maximum 4 nos X 30watts (LED Driver) having LEDs which emits ultraviolet light will not be permitted. White colour (colour temperature 5500-6500 K) Lumen efficiency of LED- minimum 130 lumens / watt. The total Luminaries efficiency should not be less than 125 lumens / watt. The illumination should be uniform without dark bands and soothing to the eye. Duty cycle should be dusk to dawn.						
	1.2 Solar PV MODULE Solar PV Modules should be polycrystalline ie IEC 61215 and 61730 Part-1 and Part-2. IS14286 of aggregate capacity 500 Wp (125 Wp X 4 nos), Module Voc Minimum of 21 V.						
	1.3 BATTERY (Li-Ie-Po4) Lithium Ferro Phosphate Battery aggregate capacity 12.8 Volt, 264Ah (66Ah X 4nos) 12.8 Volt 66Ah of 1 Unit as per IEC 62133-2012 or BIS Standards from BIS Recognized labs or MNRE						
	1.4 STRUCTURE A Galvanized/M/S painted Metallic frame structure to be fixed on the pole to hold the SPV Modules and the Battery box should be acid proof and corrosion resistant, hot dip Galvanized metallic box (1P65) with anti theft locking arrangement. The size of box should be as per battery pack size.						
	1.5 ELECTRIC CABLE The Electric cable should be Twin core PVC insulated water and UV resistance copper cable of minimum size 1.5mm.						
Total in Figures						170000.00	Rupees One Lakh Seventy Thousand Only
Quoted Rate in Figures							

1/10/2024

Percentage BoQ.

Name of Work:- A/R & M/O various building under Bangana Division (SH:-Preparation of working estimates)

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender.
Bidders are allowed to enter Bidder name and values only

Sr. No.	Description of work	Estimated Cost	Quantity	Unit	Estimated Rate in Words	Time Limit	Two Month
1	Preparation of working estimate on analysed rates based on HPSR 2020 and latest market rates for Labour material & carriage etc. complete in all respects.as per direction of Engineer-in-Charge.. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	180000.00	3.00	Each	60000.00	180000.00	Rupees Sixty Thousand Only
Total in Figures						180000.00	Rupees One Lakh Eighty Thousand Only
Quoted Rate in Figures					Excess(+) Less(-)		


 Executive Engineer
 Bangana Division
 H.P.P.W.D.Bangana

Percentage BoQ.

Name of work:- C/O Link road Kharol to Rounkhar km. 0/000 to 4/000 (Formation Cutting in km. 0/435 to 1/000)

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter Bidder name and values only

Sr. No.	Description of work	Estimated Cost			Time Limit	Two Months
		499358.00	Quantity	Earnest Unit	10000.00	Estimated Rate in Words
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/ mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chiselling, wedging out of rock(when blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by Engineer-in-charge at site according to the MORD technical specification clause 302, 1603.1 and 1603.2 and sorting out useful materials and stacking the same in all leads and lifts on acquired width of road and transportation for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to required width of the road or to approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials, tool and labour if required. Any loss to the public private property during the course to execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all the cases as per the direction of engineer-in-charge including carriage of material with in all leads and lifts. All useful material such as stone, shingle, sand and slates etcetra shall be sorted out. A recovery of 105.18 cum (One hundred five point one eight) stone to be obtained from excavation cutting at the rate of Rs. 300/- (Rupees three hundred only) per cubic metre shall be effected on pro rata bases in each running bill for this item, including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana, toll tax,GST,labour cess or other taxes imposed by the Government..	2004.65	Per Cubic metre.	249.10	499358.00	Rupees Four Hundred Forty Nine Paise Ten
Total in Figures						
					499358.00	Rupees Four Hundred Thirty Eight Thousand Eight
Quoted Rate in Figures						
					Excess(+)	
					Less(-)	


 Executive Engineer
 Bangana Division


Percentage BoQ.

Name of work:- Stock storage Under Bangana Sub Division (SH:- Supplying and Stacking CC2001002000 Quick lime)

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter Bidder name and values only

Sr. No.	Description of work	Estimated Cost	400000.00	Quantity	Unit	Earnest Money	10000.00	Estimated Rate in Words	Time Limit	Two Month
1	Supplying and stacking CC2001002000 Quick lime corresponding to class A as per specifications 712- ood As amended in polythene based gunny bags of 50 Kg (fifty kilogramme) containing total calcium Manganese oxide 70% for construction works (25kg Pack each bags) complete fitting including carnage of material within all leads and lift of materials and as per direction of Engineer-in-charge The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.		20000.00	PER	Kilogramme	20.00	400000.00			Rupees Twenty Onl
Total in Figures									400000.00	Rupees Four Lak Only
	Quoted Rate in Figures			Excess(+)						
				Less(-)						


 Executive Engineer
 Bangana Division
 H.P.P.W.D. Bangana