



Himachal Pradesh
Public Works Department
HP.PWD Division Bhawarna, Distt. Kangra (H.P.)-176083
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

"SHORT TERM NOTICE INVITING TENDERS"

Sealed item rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Bhawarna Division HP.PWD. Bhawarna on behalf of the Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **04/01/2024** up to 11.00 A.M. and the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) on **03/01/2024** up to 4.00 P.M and the application for issue of tender form shall be received on **02/01/2024** up to 12.00 noon.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Time Limit	Cost of Tender form
1	C/o lik road main road to Neugal Public School Bhawarna Km. 0/0 to 1/00 (SW:- C/o U-shape drain in Km. 0/0 to 0/150)	1,37,014/-	2700/-	Two Months	350/-
2	Improvement of link road from Darang Khas to Brankhar road Km. 0/0 to 2/400 (SW:- C/o R/Wall at RD 2/010 to 2/040) (under MNP)	4,80,786/-	9600/-	Two Months	350/-
3	C/o Boundary wall with R/Wall and P/F gate at Home Guards 9/7 Company Palampur (SW:- Providing Coping of boundary wall, E/Wall, Gate, Grating & cement concrete work in courtyard) (Deposit)	1,70,754	3400/-	Three Months	350
4	Improvement of Thural to Haloon road Km. 0/0 to 1/0 (SW:- C/o Retaining wall at Rd 0/150 to 0/162)	1,56,417/-	3100/-	Two Months	350/-
5	C/o Dadh Malan Massal Rajhoon road (SW:- P/L GSB, WBM G-II in Km. 18/360 to 18/360 & 19/945 to 20/135)	3,57,713/-	7100/-	Three Months	350/-
6	C/o link road to Village Thalehr Km. 0/0 to 1/00 (SW:- P/L Soling & Wearing in Km. 0/00 to 0/490)	4,98,516/-	10,000/-	Three Months	350/-

Terms & Conditions:-

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor/firm have to produce the copy of latest enlistment and renewal enlisted in HP.PWD.
3. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.
5. The contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand.
6. Next tender will be issued only after completion of previous works in hand.

HIM SUCHANA AVM JAN SAMPARK

Executive Engineer
Bhawarna Division
HPPWD Bhawarna

(On behalf of Governor of Himachal Pradesh)

No. PWD/BWD/Tender/NIT/2023-24/-

12400 - 60

Dated:- 29.12.2023

Copy to following for information and necessary action:-

1. The Principal Secy.(PW) to the Govt. of H.P. Shimla.
2. The Engineer-in-Chief, HPPWD. Shimla.
3. The Chief Engineer (KZ), HPPWD, Dharamshala.
4. The Director, Information & Publications Department, HP Shimla.
5. The Executive Engineer (IT), Nigam Vihar Shimla. He is requested to upload the same on the department website.
6. The Superintending Engineer, 5th Circle, HPPWD, Palampur.
7. The Deputy Commissioner, Kangra at Dharamshala.
8. The Sub-Divisional Officer(Civil) Palampur.
9. All the S.E.s/E.E.s under Kangra Zone.
10. All the Assistant Engineers under this Division.
11. The Drawing /Accounts Branch in this office.
12. Notice Board.

Executive Engineer
Bhawarna Division
HPPWD Bhawarna

Schedule of quantity

Name of Work :- C/o link road main road to Neugal Public school Bhawarna Km 0/0 to 1/00

Estimate Cost :- 1,37,014/-
Earnest Money :- 2700/-

Time Limit :- Two Months

(SH:- C/o U-shape drain in Km 0/0 to 0/150)

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In Figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In -Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	63.00			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed/ broken stone aggregate 20mm (twenty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax. GST or other taxes imposed by the Government.	27.56			Per Cubic metre	
Total :-						

Executive Engineer
Bhawarna Division
HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Improvement of link road from Darang Khas to Brankhar road Km 0/0 to 2/400

Estimate Cost :- 4,80,786/-

Earnest Money :- 9600/-

Time Limit :- Two Months

(SH:- C/o R/wall at RD 2/010 to 2/040). (under MNP)

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government.	45.60			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	108.30			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe veep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi. royalty. Malkana, toll tax, GST or other taxes imposed by the Government.	60.00			Each	

4	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	38.10			Per Cubic metre
5	Construction of embankment for road way with approved materials from borrowpits , or other sources in layers of suitable thickness not exceeding 200mm (Two hundred millimeter) thick each layers and compacted with 80-100 (Eighty - Hundred) K.N static/ vibratory road roller to meet the requirement of table 300.1 and 300.2 of technical specifications to lines, grades, levels and cross sections as per Drawings or direction of the Engineer-in-Charge to Technical specification clause 301 and other relevant clauses including preparation of foundation for embankment in all kinds and classification of soils including saturated soil and dewatering/ bailing out of water where ever required including handling of material for construction of embankments within all leads and lifts. The rate shall include carriage of machineries, equipments, tools and materials and safety measures payment of all taxes, octroi royalty GST and other incidentals necessary to complete the work in all respects. The rate is including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	24.30			Per Cubic metre
Total :-					

Executive Engineer
Bhawarna Division
HP PWD Bhawarna

Schedule of quantity

Name of Work :- Construction of Boundary wall with R/Wall and P/F gate at Home Guards 9/7 Company Palampur. (SW):-
Providing Coping of boundary wall, E/Wall, Gate, Grating & cement concrete work in courtyard). (Deposit).

Estimate Cost :- 1,70,754/-

Earnest Money :- 3400-

Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing and laying cement concrete work M-20 design mix to obtain the minimum compressive strength 20N/mm ² (20 newton per square millimeter) and minimum cement content not less than 320 kg/cubic meter and curing complete and mechanically mixed and vibrated as per approved specification, drawing and design, excluding cost of form work and reinforcement for reinforced concrete work in String courses coping bed plates, anchor blocks plain window sills and the like. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	0.59			Per Cubic metre	
2	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	13			Per Cubic metre	
3	Providing, laying, Soling 90 to 45mm (Ninety to forty five milimetre) nominal size Grading-1, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 Kn. Static roller in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 1 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	6.5			Per Cubic metre	

4	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement : four sand : eight graded crushed/ broken stone aggregate 40mm (forty millimetre) nominal size on ground or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification section 800, 900 and 1200 and as per the entire satisfaction and direction of the Engineer -in-Charge including carriage of materials within all lead, and lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	10.28			Per Cubic metre
5	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm (Sixty millimetre) of approved make having compressive strength of M-50 as per drawings and MORD Technical Specification section 1500 including sand bedding, carriage of material within all leads and lifts, other incidentals. The rate is rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the government.	65.00			Per Square metre
6	Steel work bolted in built up sections including cutting hoisting and fixing in position and applying a primer coat of red lead paint in R.S. joists, channels, angles tees, flats with connecting plates or angle cleats as in main and cross beams, hip and jack rafters, purlins connected to common rafter and the like. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, sale tax, GST and any other taxes imposed by the government.	2.500			Per Quintal
7	Providing Cement concrete 1:2:4 (One Cement : Two Sand : Four crushed stone aggregate) Nominal Mix R.C.C. grade M- 20 (M-Twenty) for reinforced concrete in foundations and plinth complete as per drawings and technical specifications Clause 802.803 1202 & 1203 as per the direction of the Engineer-in-Charge including carriage of material within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, GST or other taxes imposed by the Government.	0.740			Per Cubic metre
Total :-					

Executive Engineer
Bhawarna Division
HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Improvement of Thural to Haloon road Km 0/0 to 1/0 (SH:- C/o Retaining wall at RD 0/150 to 0/162).

Estimate Cost :- Rs. 1,56,417/-
Earnest Money :- Rs. 3100/-

Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	20.88			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, malkana,toll tax, GST or other taxes imposed by the Government.	37.23			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	24			Each	
Total :-						

Executive Engineer
Bhawarna Division
HP PWD Bhawarna

Schedule of Quantity

Name of Work :- C/o Dadh Malan Massal Rajhoon road.


Estimate Cost :-Rs. 3,57,713/-
Earnest Money :-Rs. 7100/-

(SH:- P/L GSB, WBM G-II in Km 18/255 to 18/360 & 19/945 to 20/135).

Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Preparation of sub grade by dressing to cambor (Earth work for the cutting involved for sub grade to be paid for spearely depending upon the classification of soil completed as per HP.PWD specifications as per directions of Engineer-in-charge. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1037.66			Per Square metre	
2	Consolidation of sub grade with road roller including making good the undulation etc. with earth or quarry soil etc. and rerolling the sub- grade completed as per HP.PWD specifications as per directions of Engineer-in-charge. The rate is including octroi. royalty, Malkana. toll tax, sale tax. GST or other taxes imposed by the Government.	1037.66			Per Square metre	
3	Construction of Granular Sub Base 125mm thick (One hundred twenty five millimetre thick) by providing well graded material, spreading in uniform layers with tractor grader on prepared surface, mixing by mix in place method with rotavator at OMC. and compacting with three wheel roller 80-100 (Eighty to hundred) KN static roller to achieve the desired density, complete as per MORD Technical Specification clause 401 for grading-I material and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax. GST or other taxes imposed by the Government.	155.65			Per Cubic metre	

4.	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, stone, screening type-B of size 11.2mm (eleven point two millimetre) nominal size at the rate of 0.20 cum. (Zero point two zero cubic metre) per ten square metre and binding materials at the rate of 0.06 cum. (Zero point zero six cubic metre) per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -II. 63mm to 45mm (sixty three millimeters to forty five millimeters) size. 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer -in- Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	70.85			Per Cubic metre
Total:-					


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- C/o Link Road to Village Thalchar Km 0/00 to 1/00

Estimate Cost :-Rs. 4,98,516/-

Earnest Money :-Rs. 10,000/-

Time Limit :- Three Months

(SH:- P/L Soling & Wearing in Km 0/00 to 0/490)

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Preparation of sub grade by dressing to camber (Earth work for the cutting involved for sub grade to be paid for separately depending upon the classification of soil completed as per HP.PWD specifications as per directions of Engineer-in-charge. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1543.00			Per Square metre	
2	Consolidation of sub grade with road roller including making good the undulation etc. with earth or quarry soil etc. and reolling the sub- grade completed as per HP.PWD specifications as per directions of Engineer-in-charge. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1543.00			Per Square metre	
3	Providing, laying, Soling 90 to 45mm (Ninety to forty five millimetre) nominal size Grading-I, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness. hand packing. rolling with three wheel 80-100 Kn. Static roller in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading I as per technical specification Clause 405 as per the direction of Engineer-in-Charge including carriage of material within all leads and tails and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	154.35			Per Cubic metre	

1.	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80, 100 K.N static Road roller in stages to proper grade and camber, applying and brooming, stone, screening (type-B of size 11.2mm (eleven point two millimetre) nominal size at the rate of 0.20 cum. (Zero point two zero cubic metre) per ten square metre and binding materials at the rate of 0.06 cum. (Zero point zero six cubic metre) per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -II, 63mm to 45mm (sixty three millimeters to forty five millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer -in- Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	112.00		Per Cubic metre
Total:-				


 Executive Engineer
 Bhawarna Division
 HP PWD Bawarna