

OFFICE OF THE EXECUTIVE ENGINEER  
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT  
Tel 01972-266099 E-mail : eepwd-bhoranj-hp@gov.in

No:- PW/BHD/TA/NIT/2023-24-

11649-56

Dated:- 23-12-2023

To

The Executive Engineer (IT Cell),  
Nirman Bhawan Nigam Vihar,  
HP Shimla -171002.

**Subject:-** Publication of tender Notice.

Enclosed please find herewith the Tender Notice of various works as given in the Notice inviting Tender as per Notification Pr. Secy (PW) to the Govt. of Himachal Pradesh letter No. PBW(B)A(3)1/2020 dated Shimla-2 the 16<sup>th</sup> July, 2021 as the works mentioned in the tender Notice are of urgent nature and in public interest, the same may be uploaded on the departmental website.

**DA/NIT & Schedule of Qty  
And "A" Certificate**

Executive Engineer,  
Bhoranj Division,  
HP PWD., Bhoranj.

Copy forwarded with its enclosures for information to :-

1. The Engineer-in-Chief, HP:PWD Shimla-2
2. The Chief Engineer. HZ HPPWD., Hamirpur.
3. The Superintending Engineer, 8<sup>th</sup> Circle HPPWD., Hamirpur
4. All the Assistant Engineers working under this Division.
5. Drawing Branch/ Accounts Branch of this office.
6. Notice Board.

Executive Engineer,  
Bhoranj Division,  
HP:PWD., Bhoranj.

OFFICE OF THE EXECUTIVE ENGINEER  
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT  
Tel 01972-266099 E-mail : eepwd-bhoranj-hp@gov.in

**CERTIFICATE**

Certified that the works are of urgent in nature and for larger public interest so there is exigencies/emergency in ceiling these tenders without press vide this office letter No. PW/BHD/TA/NIT/2023-24- 1/657-73 dated 23-12-2023.

  
Executive Engineer  
Bhoranj Division  
HPPWD Bhoranj

**OFFICE OF THE EXECUTIVE ENGINEER  
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT  
Tel 01972-266099 E-mail : eepwd-bhoranj-hp@gov.in**

**NOTICE INVITING TENDER**

Sealed item rate / percentage rate tender are hereby invited on Form No. 6 & 8 by the Executive Engineer, Bhoranj Division, HP PWD., Bhoranj on behalf of the Governor of Himachal Pradesh for the following works from the approved and eligible contractors/ firms of appropriate class enlisted in HPPWD (B&R) whose registration stood registered under the H.P. General Sales tax Act, 1968 so as to reach in this office on or before **03.01.2024 upto 10.30 AM** and shall be opened on the same day at **11.30AM** in the presence of the contractor or their representatives who may like to be present. The tender form can be obtained from this office against cash payment (Non refundable) **upto 4.00 PM on 02.01.2024** for which the application should reach in this office **upto 1.00 PM 02.01.2024**. The offer of the tender will be kept open for 45 days from the date of opening of the tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons. If any of the date mentioned above happens to be holiday the same shall be processed on next working day

Sr. No.	Name of Road	Estimated Cost	Earnest Money	Time	Cost of Tender Form	Eligible class of Contractor
1	R/R damages on Jhanikar Tal road km. 0/0 to 9/0 (SH:- C/O R/Wall at RD. 6/357 to 6/368)	1,22,709/-	3000/-	Two months	Rs. 350/-	Class-D
2	C/O Link road from Main road to house of Sh. Wattan Singh VPO Badehar Tehsil Bhoranj Distt. Hamirpur (HP) (SH:- P/L interlocking paver block at RD. 0/0 to 0/077)	4,85,355/-	10000/-	Two months	Rs. 350/-	Class-D
3	C/O Hamirpur Jahu road (SH:- C/O 600mm dia RCC hume pipe at RD. 20/975 and grill on catch pit alongwith side drain)	2,08,423/-	4500/-	Two months	Rs. 350/-	Class- D
4	R/R Damages on Una Aghar Mandi road km. 79/0 to 91/0 (SH:- C/O R/Wall at RD. 86/730 to 86/740)	1,53,293/-	3000/-	Two months	Rs. 350/-	Class- D
5	C/O Link road Manoh chowk to HSC Jamli km. 0/0 to 1/00 (SH:- C/O R/Wall at RD. 0/350 to 0/360) (Under SCDP)	1,58,013/-	3500/-	Two months	Rs. 350/-	Class- D
6	R/R damages on Lajhyani Bhanwin via Kakrot road km. 0/0 to 4/0 (SH:- C/O R/Wall at RD. 2/480 to 2/515)	2,85,131/-	6000/-	Two months	Rs. 350/-	Class- D
7	R/R damages on Dimmi Jhamber Bhadru road km. 0/0 to 4/0 (SH:- C/O Hume pipe culvert at RD. 2/180, C/O R/Wall at RD. both side wing wall) (SDF/2023/492)	2,96,052/-	6000/-	Two months	Rs. 350/-	Class- D
8	R/R Damages on Hamirpur Jahu road km. 15/345 to 21/780 (SH:- C/O B/Wall at RD. 21/720 to 21/730 and U-shape drain at RD. 21/405 to 21/570)	3,30,882/-	7000/-	Two months	Rs. 350/-	Class- D
9	Preparation of contour site plan and detailed Project report for C/O Rajiv Gandhi Govt. Model Day Boarding School Primary Block at Karah Bhoranj Distt. Hamirpur (HP)	4,95,000/-	10000/-	Two months	Rs. 350/-	Class- D
10	R/R damages on Una Aghar Mandi road km. 79/0 to 90/0 under HPPWD Sub Division Bhoranj Division Bhoranj (SH:- Providing and manufacturing sign board) Job No.2	2,45,000/-	5000/-	Two months	Rs. 350/-	Class- D
11	A/R & M/O on Old Una Aghar Mandi road km. 67/0 to 79/0 (SH:- C/O U-shape drain in Ladrour Bazar in km. 77/900 to 78/00)	1,66,927/-	3500/-	Two months	Rs. 350/-	Class- D
12	R/R damages on Chabb more to Lagmanwin road km. 0/0 to 1/700 (SH:- C/O R/Wall at RD. 1/650 to 1/660 (ii) R/R Damages Nadoh to Manoh via Naltu km. 0/0 to 1/600 (SH:- P/L wire crate at RD. 1/310 to 1/325) (Deposit work SDF/2023-525)	1,86,180/-	4000/-	Two months	Rs. 350/-	Class- D

13	R/R damages on Hamirpur Jahu road (SH:- C/O R/Wall at RD. 20/135 to 20/145, 20/080 to 20/075, 20/930 to 20/940) SDF/ 2023/ 499, 502,511)	2,13,199/-	5000/-	Two months	Rs. 350/-	Class- D
14	R/R damages on Link road Harizan Basti Khatarwar and Bhiar to Kot road (SH:- C/O R/Wall at RD 0/090 to 0/098 & 0/285 to 0/293) (SDF/2023/500 & 514)	1,28,676/-	2500/-	Two months	Rs. 350/-	Class- D

The earnest money in the shape of National Saving Certificate/ Time Deposit/ saving account of any post office or FDR of Nationalized Bank duly pledged in the name of undersigned must be accompanied with each tender. The Conditional tender and tender not accompanying the earnest money in the proper mode of deposit with summarily be rejected.

The Tender documents to be sent should have invariably be waxed in sealed cover and in failure of that those will not be entertained.

The Copy of valid enlistment, GST Registration No. Income Tax PAN No. & EPF No. must be attached with application.

#### TERMS AND CONDITIONS:-

The tender form will be issued to those contractors who have relevant machinery and equipment, the list of which any be attached with their applications (The proof of ownership of machinery/ legal tie up arrangement).

The tender forms will not be issued to those contractors whose performance is not found satisfactory.

The tender form will not be issued to those contractors who have already two works in hand. The earnest money for the above work should be submitted with the application for the purchase of the tender forms. The application received without earnest money shall summarily be rejected.

The conditional/ ambiguous/ telephonic tenders or tender by fax shall not entertain considered in any case.

(i) No Violation of social distancing.

(ii) Mandatorily wearing of face cover by everyone.

(iii) It is further added that any violation of the National directives & guidelines of containment of pandemic Covid-19 is liable for prosecution under section of IPC 1860.

No:-PW/BHD/TA/NIT/2023-24-

11657-73

Copy forwarded with its enclosures for information to :-

1. The Engineer-in-Chief, HP:PWD Shimla-2
2. The Chief Engineer. HZ HPPWD., Hamirpur.
3. The Superintending Engineer, 8<sup>th</sup> Circle HPPWD., Hamirpur.
4. The Computer cell office of the Engineer-in-Chief, HPPWD Shimla for uploading the Notice inviting tender on the Departmental website.
5. All the Assistant Engineers working under this Division.
6. Drawing Branch/ Accounts Branch of this office.
7. Notice Board.

Executive Engineer,  
Bhoranj Division,  
HP:PWD., Bhoranj.  
For and on behalf of Governor of HP.  
Dated:- 23-12-2023

Executive Engineer,  
Bhoranj Division,  
HP:PWD., Bhoranj.



# SCHEDULE OF QUANTITY

Sr No Description of Items

Estimated Cost  
Earnest Money  
Time  
Rs 1,22,709/-  
Rs 3000/-  
2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited ) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre ) compacted thickness including shoring an structing and pumping and bailing out water (surface and sub sol water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	15.93	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size ) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	25.89	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm( one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg per centimeter square. (four kilogramme per centimeter square ) extending through the full width of the structures with slopes of (1V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer-in -Charge, including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	9.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material, including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	2.91	Per Cubic Meter			
<b>Total</b>						

**Terms and Condition:-**

1. Work shall be executed as per PWD specification.

Executive Engineer  
Bhorani Division  
HP PWD Bhorani

# SCHEDULE OF QUANTITY

LINE OF WORK:- C/O link road from Main road to house of Sh. Wattan Singh VPO Badehar Tehsil Bhoranj Distt. Hamirpur(HP), (SH:- P/L  
erlocking paverblock at RD 0/0 TO 0/077.)

Estimated Cost  
Earnest Money  
Time

Rs 4,85,35/-  
Rs. 10000/-  
2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/bedding out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structing and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.70	Per Cubic Meter			
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate) 20 mm (twenty millimeter) nominal size as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	15.88	Per cubic meter			
3	Providing and laying mechanically mixed cement concrete (M-20) (M-twenty) 1:1.5:3 one cement : One & half sand : three graded crushed stone aggregate) 20mm(twenty millimeters) for plain /reinforcement concrete in open foundation complete including cost of form work steel plate complete as per drawings and technical specification Clause 802, 803 1202 & 1204 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	11.55	Per Cubic Meter			
4	Providing and laying heavy duty precast concrete interlocking paver blocks vibro compacted upto M-50(M-fifty) grade including border or kurb block grey or coloured over sub base of concrete with 25mm (twenty millimeters) thick average thickness of cement 1:4 (one cement: four sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks including curing rubbing and polishing complete (sub base concrete) floor to be paid for 80mm( eighty millimeters) thick inter locking blocks (n.l.c) ISI approved, and as per direction of the Engineer-in-charge including entire carriage of materials within all leads and lifts including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	211.75	Per square meter			
Total						

**Terms and Condition:-**  
1. Work shall be executed as per PWD specification.

Executive Engineer  
Bhoranj Division  
H.P.W.D Bhoranj

# SCHEDULE OF QUANTITY

NAME OF WORK: C/O Hamirpur Jahu Road, (SH-1) C/O 600 mm dia R.C.C. Hume pipe at RD 20/975 and grill on catch pit along with side drain

Estimated Cost  
Earnest Money

Rs 2,08,423/-  
Rs. 45000/-  
2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rate in words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structing and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	22.82	Per Cubic Meter			
2	Providing and laying cement concrete 1:4:8 (1 cement : 4 sand : 8 graded stone aggregates 40mm nominal size) and curing complete including cost of form work in foundation and plinth as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1.85	Per cubic metre			
3	Centering and shuttering including strutting, propping etc. and removal of form for Walls (any thickness) including attached plasters, buttresses, plinth and string courses etc as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	33.72	Per square Meter			
4	Providing and laying mechanically mixed cement concrete (M-20) (1:1.5:3 one cement : One & half sand : three graded crushed stone aggregate) 20mm(twenty millimeters) for plain reinforcement concrete in open foundation complete including cost of form work, steel plate complete as per drawings and technical specification Clause 802, 803, 1202 & 1204 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	5.18	Per Cubic Meter			
5	Providing mild steel/Or steel reinforcement for R.C.C. work including bending, bindings and placing in position complete upto floor two level (1 or steel) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	669.00	Per Kilogram me			
6	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approval steel primer all complete as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	109.20	Per Kilogram me			
7	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular materials in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108, 600mm(Six hundred millimeters) dia as per direction of Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	18.00	Per Running meter			
Total						

## Terms and Condition:-

1. Work shall be executed as per PWD specification.

Executive Engineer  
Bhoranj Division  
M.P.W.D Bhoranj



# SCHEDULE OF QUANTITY

NAME OF WORK:- C/O link road from Maunoh Chowk to H.S.C. Jamill km. 0/00 to 1/00 (S.H.) :- C/O R/wall at RD 0/350 to 0/360.) Under SDSP)

Estimated Cost

Rs 1,58,013/-

Earnest Money  
Time

Rs. 3500/-  
2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of slumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structing and pumping and bailing out water (Surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	17.60	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	31.54	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm (one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg per centimeter square. (four kilogramme per centimeter square) extending through the full width of the structures with slopes of (1V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer-in-Charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	16.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material: including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	9.90	Per Cubic Meter			
	<b>Total</b>					
	<b>Terms and Condition:-</b>					

1. Work shall be executed as per PWD specification.

Executive Engineer  
Bhoranj Division  
HP PWD Bhoranj



# SCHEDULE OF QUANTITY

NAME OF WORK:-R/R Damages on Lalpuri Bhanwin via kakrol road km. 0/00 to 4/00  
(SH:- C/O R/wall at RD 2/450 to 2/540) (Deposit work)

## Sr No Description of Items

Sr No	Description of Items	Quantity	Unit	Rate	Estimated Cost	
					Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structing and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	29.75	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement, five sand, ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M. S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per direction of Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	58.52	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm (one hundred ten millimeter) dia PVC pipe De-plastiflex/ vecus pipe having pressure 4kg per centimeter square, (four kilogramme per centimeter square) extending through the full width of the structures with slopes of (1V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer-in-charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	33.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-charge. i) Granular material, including entire carriage of material within all leads and lifts and as per direction of Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	12.67	Per Cubic Meter			
Total						

## Terms and Condition:-

1 Work shall be executed as per PWD specification.

Executive Engineer  
Bhoranj Division  
HP PWD Bhoranj

Estimated Cost  
Earnest Money  
Time

Rs 2,85,131/-  
Rs 6000/-  
2Months

**SCHEDULE OF QUANTITY**  
**NAME OF WORK:- R/R Damages on Dimmi Jhamber Bhadrui road Km. 0/00 to 4/00 (S.H :- C/O Hume Pipe Culvert at Rd. 2/180, C/O Riwall at Rd. Both side wing wall.) (SDF/2023/492).**

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated (suitable approved) material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structing and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	32.83	Per Cubic Meter			
2	Centering and shuttering including strutting, propping etc. and removal of form work for as per the direction of the Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	73.50	Sqm			
3	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded form work with M.S. plates for plain concrete on ground or under water and curing complete including cost of pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	58.06	Per Cubic Meter			
4	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm (one hundred ten millimeter) dia PVC pipe De- plasticized/ vectus pipe having pressure 4kg per centimeter square, (four Kilogram per centimeter square) extending through the full width of the structures with slopes of (1V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204, 3.7 as per direction of Engineer-in-Charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	20.00	Each			
5	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204, 3.8, and as per direction of Engineer-in-Charge. i) Granular material including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.35	Per Cubic Meter			
6	Providing and laying reinforced cement concrete pipe NP3 for culverts on first class bedding of granular materials in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108, 900mm(nine hundred millimeters) dia, as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2.50	Per Running meter			
<b>Total</b>						
<b>Terms and Condition:-</b>						

1. Work shall be executed as per PWD specification.

Executive Engineer  
 Bhurani Division  
 H/PWD Bhurani

Estimated Cost  
 Earnest Money  
 Rs. 2,96,052/-  
 2 Months



# SCHEDULE OF QUANTITY

**NAME OF WORK:- R/R Damages on Hamirpur Jahu road km. 15/345 to 21/780.**  
**(SH:- C/O B/wall at RD 21/720 to 21/730 and u-shape drain at RD 21/405 to 21/570.)**

Estimated Cost Rs 3,30,882/-  
 Earnest Money Rs 7000/-  
 Time 2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out of rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of slumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	91.40	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement five sand ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per direction of Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	23.53	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm (one hundred ten millimeter) dia P.V.C pipe. De-plastic/nolex/ vecalus pipe having pressure 4kg per centimeter square. (four kilogram per centimeter square) extending through the full width of the structures with slopes of (1V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204, 3.7 as per direction of Engineer-in-charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.00	Each			
4	Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10 (M-ten) nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 40mm (forty millimeters) nominal size including centering and shuttering in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	39.19	Per Cubic Meter			
	<b>Total</b>					

**Terms and Condition:-**

1. Work shall be executed as per PWD specification.

Executive Engineer  
 Bhoranj Division  
 (HP PWD Bhoranj)

# SCHEDULE OF QUANTITY

NAME OF WORK:-Preparation of contour site plan and detailed Project report for C/O Rajiv Gandhi Govt. Model Day Boarding School Primary Block at Karah Bhoranj Distt Hamirpur (HP).

S. NO.	Description of item	Quantity	unit	Rate in	Rate in words	Amount
1	Detail survey with DGPS/Total station complete (more than 100 kanal area) and preparation of contour site plan and cross sections in specified scale and its submission in soft and hard copies.	3	4	5	6	7
1	Preparation of detailed project report on analyzed/market rate for the construction of day boarding school as per architectural drawing in manuscript shape and its approval from the competent authority, after approval fairing out the same and submission in penttuplicate and approval of DNIT etc. complete as per direction of Engineer in charge.	1	Job			
			Total			

1. The DPR will be prepared as per HPPWD specification.
2. 50% payment will be made after submission of DPR and balance will be paid after approval from the competent authority.

**Executive Engineer**  
Bhoranj Division  
HP PWD Bhoranj



### Draft Schedule of Quantity

Estimated Cost :-245000.00  
Earnest Money:- 5000.00  
Time: - 3 months

**Name of Work:- R/R damages Una Aghar Mandi Road road km 79/0 to 90/00 under HPPWD Sub-Division  
Bhoranj Division Bhoranj HPPWD Bhoranj. (Providing & manufacturing sign board ) JOB. No. 2.**

Sr. No.	Description of items work	Qty	Unit	Rate In fig.	In words	Amount
1.	Providing and manufacturing steel fabrication of sign boards size following dia make of M.S sheet 1.60mm thickness withw MS pipe 32mm dia. The height of board should not be less than 2430mm and size 4x3 including, welding, priming single coat complete in all respect and to the entrie satisfaction of Engineer in Charge.	50	Each			
					Total	

#### **TERMS AND CONDITIONS:**

1. The work will be carried out as per PWD specification and to the entire satisfaction of the Engineer in charge.
2. The rates shall be inclusive with all taxes and carriage of material in all leads and Tifts.
3. Nothing will be paid for rejected work/material.
4. The material shall be used of ISI marked/reputed make.

~~Executive Engineer~~  
HPPWD Division,  
Bhoranj

# SCHEDULE OF QUANTITY

NAME OF WORK: A/R & M/D on Old Una Aghar Mandi road Km. 67/0 to 79/0.  
(S.H. :- C/O U-Shape drain in ~~the~~ Bazar in Km. 77/300 to 78/000).

Estimated Cost Rs 166927/-  
Earnest Money Rs.3500/-  
Time Two Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structing and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	48.00	Per Cubic Meter			
2	Providing concrete for plain reinforced concrete in P.C.C. grade M-10 (M-ten) nominal mix 1:3:6 (one cement, three sand, six graded crushed stone aggregate) 40mm(forty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	30.00	Per Cubic Meter			
<b>Total:-</b>						

## Terms and Conditions:-

1. Work shall be executed as per PWD specification.

Executive Engineer,  
Bhorani Division  
H.P.W.D Bhorani

# SCHEDULE OF QUANTITY

NAME OF WORK:- (i) R/R Damages on Chab More to Laganwadi road Km. 0/00 to 1/700 (SH:- C/O R/wall at RD/1650 to 1/600). (ii) R/R Damages on Nadoh to Manoh via Naitu Km. 0/00 to 1/600 (SH:- P/L wire at RD. 1/310 to 1/325). (Deposit Work SDF/2023/625)

Estimated Cost Rs 1,86,180/-  
Earnest Money Rs 4000/-  
Time 2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring a structure and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	17.14	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm forty millimetre nominal size ) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	15.20	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm( one hundred ten millimeter) dia PVC pipe De-plasticized/ vedius pipe having pressure 4kg per centimeter square. (four kilogramme per centimeter square ) extending through the full width of the structures with slopes of (1V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer-in-Charge, including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material, including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	3.18	Per Cubic Meter			
5	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeters) dia GI with conforming to IS:280 and IS: 4826 in 100mmx100mm( one hundred millimeters into one hundred millimeters) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boulder weight/ft not less than 25kg. (twenty five kilogramme) each as per drawing and technical specifications clause 1301 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	32.76	Per Cubic Meter			
Total						

## Terms and Condition:-

1. Work shall be executed as per PWD specification.

Executive Engineer  
Bhorani Division  
HPD/WD Bhorani

# SCHEDULE OF QUANTITY

NAME OF WORK:-R/R damage on Hamipur Jahu Road.  
(SH:- C/O R/wall at RD 20/135 to 20/145, 20/060 to 20/075, 20/930 to 20/940.)

Estimated Cost Rs 2,13,199/-  
Earnest Money Rs 5000/-  
Time 2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structing and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government.	21.76	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand: ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	46.87	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm (one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vecus pipe having pressure 4kg per centimeter square, (four kilogramme per centimeter square) extending through the full width of the structures with slopes of (1/V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	10.00	Each			
Total						

Terms and Condition:-

1. Work shall be executed as per PWD specification

Executive Engineer  
Bhorani Division  
H.P.W.D Bhorani



# SCHEDULE OF QUANTITY

NAME OF WORK:-R/R Damages on Link Road Harizan Basti Khatarwar and Bhiar to Kot road.  
(SH:- C/o R/wall at RD 0/090 to 0/098 & 0/285 to 0/293). (SDF/2023/500-514 Deposit work)

Estimated Cost Rs 1,28,676/-  
Earnest Money Rs 2500/-  
Time 2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring a structing and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	10.40	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls/breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	25.44	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm( one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg per centimeter square. (four kilogramme per centimeter square) extending through the full width of the structures with slopes of (1V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer-in-Charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	12.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	12.12	Per Cubic Meter			
<b>Total</b>						

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Executive Engineer  
Bhorani Division  
H/PWD Bhorani