

☎ 01899-240618, 292000
Fax No. 01899-240618

E-mail- ee-dal-hp@nic.in

No. PWD-Dal/TA/Tender /2023-24-
To

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

8596-98

Dated: - **14.12.2023**

The Executive Engineer (IT Cell)
Nigam Bihar Shimla-2

Subject: -

Publishing of Tender Notice.

Dear Sir,

Enclosed please find herewith the tender Notice of work as given in the Notice inviting Tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of Himachal Pradesh letter No. PBW-(B) A9 (3)1/2020 dated Shimla-2 the 16th July 2021 as the work mentioned in the tender notice are urgent in nature and public interest.

DA/ As above.

**Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie.**

Copy forwarded to the Superintending Engineer, 7th Circle, HPPWD, Dalhousie for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer, (IT Cell) Nigam Bihar Shimla-2 for information and further necessary action.

**Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie**

Certificate

Certified that the tenders called vide this office letter No. PWD-/TA/Tender /2023-24:-8596-98 dated. 14-12-23 is emergent nature and in Public interest.


Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

"NOTICE INVITING TENDERS"

Sealed Item rate tender(s) on PWD from No 6 & 7/8 are hereby invited by the Executive Engineer, Dalhousie Division, HPPWD, Dalhousie on behalf of the Governor of HP for the following works from the approved and eligible contractor/firm of appropriate Class enlisted in HPPWD as per the latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening of the tender. The undersigned reserves the right to reject any or all the tender without assigning any reasons:-

- | | |
|---|--|
| 9. Date of receipt of application for the tender Form a/w requisite documents:- | 14.12.2023(between 2:00p.m.to 4:30.p.m.) |
| 10. Date of issued/sale of tender form against Cash payment (non refundable). | 22.12.2023 |

The tender shall be received upto 3:00 PM on 23.12.2023 and will be opened on the same day at 3:30 PM in the presence of intending Contractor or their authorized representative who may like to be present. The tender can be had from this office against cash payment as shown below (Non refundable) during the working hours on 22.12.2023.

The Earnest Money in the shape of National Saving Certificate/FDR of any Bank in HP duly pledged in favour of Executive Engineer, Dalhousie Division, HPPWD, Dalhousie must accompany with each application. Conditional tender and the tender received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 90 days. The XEN reserve the right to accept or reject the tender without assigning any reasons:-

S. No.	Name of work	Estimated cost	Earnest Money	Cost of tender	Time Limit	Class
1.	A/R&M/O HPPWD Rest House at Dalhousie (SH:- Wall Painting Wooden & Roof painting work)	128974/-	2600/-	350/-	One month	Class-D & C
2.	A/R&M/O Type-I Residential Building Kathlog at Dalhousie (SH:- Providing and Fixing Wire Gauge Shutter Primer & Paint work and Providing and fixing Chhajjas in Type-I Quarter etc.)	98393/-	2000/-	350/-	One month	Class-D & C
3	A/R&M/O Non Residential Building (SH:- Painting & Repair work of Assistant Engineer office)	60951/-	1300/-	350/-	Two month	Class-D & C
4	A/R&M/O Residential Building at Banikhet (SH:- Supplying and Laying G.I. Pipe line water storage platform at Type-III quarter at Banikhet)	42171/-	1000/-	350/-	One month	Class-D & C
5	A/R&M/O Type-V residential building at Dalhousie (SH:- Providing and fixing 150mm rain water pipe and Shoe)	40906/-	1000/-	350/-	One month	Class-D & C
6	Repair and Maintenance of two No. Bathrooms at HPPWD Circuit House at Dalhousie (SH:- Dismantling of Tiles Providing and Fixing tiles and Sanitary Work)	169043/-	3400/-	350/-	Two months	D & C
7	Restoration of rain Damages on Dalhousie Jandrigat Chamba via Kohlari road k.m. 0/0 to 11/040 (SH:- Hiring of Excavator cum Loader for removal of slips in various RD.s)	99750/-	2000/-	350/-	Three months	Class-D & C
8	Restoration of rain Damages on Various road under HPPWD Sub Division Banikhet (SH:- Hiring of Excavator cum loader for removal of slips in Bathri Section)	98700/-	2000/-	350/-	Three months	Class-D & C
9	Restoration of rain Damages on Various road under HPPWD Sub Division Banikhet (SH:- Hiring of Excavator cum loader for removal of slips in wungal Section)	97650/-	2000/-	350/-	Three months	Class-D & C
10	C/o link road to village Dharota k.m. 0/0 to 1/870 (SH:- HP Culvert at R.D. 0/720 C/o wing wall at R.D. 715.80 to 718.80 & 721.20 to 724.20)	437523/-	9000/-	350/-	Four months	Class-D & C
11	Restoration of rain Damages on various road under Dalhousie Sub Division (SH:- Removal of slips/ Snow on Banikhet Dalhousie Khajjar road k.m. 0/0 to 6/400 & 15/600 to 27/00 Dalhousie jandrigat Chamba Kohlari road k.m. 0/00 to 11/040, Link road to village Ruliyani k.m. 0/0 to 3/00 & link road to village Kathlog to Bharera k.m. 0/0 to 2/180.)	2,96,100/-	6000/-	350/-	Three months	Class-D & C
12	A/R & M/O Type -III quarter at Dalhousie (SH:- Plastering, painting & putty etc.).	192350/-	4000/-	350/-	Two months	Class-D & C
13	Improvement of Blackspot on Banikhet Dalhousie khajjar road K.m. 15/600 to 27/00 (SH:- C/o R/wall at R.D. 16/110 to 16/180 & fixing of Crash Barriar at R.D. 16/110 to 16/180 in essential reaches	465981/-	9400/-	350/-	Three months	Class-D & C

1. The tender forms will not be issued to those Contractors whose performance is not found satisfactory.
2. The tender shall be issued to those contractor o who have not more than two works in hand.
3. GST No./Earnest Money Tender Form cost, copy of enlistment should be accompanied with application.
4. Application without all documents will not be entertained.
5. Proxy application will not be entertained.

Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie.

No. PWD/TA/Tender /2023-24- 8600-8650
Copy forwarded to the following for information and necessary action please:-

Dated: - 14-12-2023

- 1 Engineer-in-Chief , HPPWD, Shimla.
- 2 All the Chief Engineer in HPPWD.
- 3 All SEs/EE in HPPWD.
- 4 All AEs/Contractor under this Division.
- 5 Deputy Commissioner, Chamba
- 6 BDO Bhattiyat.
- 7 Sub Divisional Magistrate/Tehsildar Dalhousie.
- 8 Notice Board of this office.

Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie

Schedule of Quantity

Estimated Cost: - Rs. 1,28,974.00
Earnest Money: - Rs. 2600.00
Time: - One Month.

Name of work :- A/R & M/O HP PWD Rest House at Dalhousie (SH: - Wall Painting, Wooden & Roof painting work).

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Wall painting two coats with premium acrylic emulsion paint of interior grade. Asian Paints Nerolac surksha Paints/Berger Paints /Delux Paint having VOC (Volatile Organic Compound) consist less than 50 grams (fifty milli grams)/ liter of approved brand and manufacture, including applying additional coats wherever to achieve even shade and colour as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes	687.91		Rupees Nil	Per Square Metre	
2	Painting one coat on previously painted wood or wood based surface with enamel paint Asian Paints/Nerolac surksha Paints/Berger Paints /Delux Paint to give a even shade including cleaning of all dirt, dust and other foreign matter sand papering and stopping with enamel paint other than white within all leads and lifts and as per direction of the Engineer-In-Charge and other incidentals. The rate including of octroi, royalty, Malkana, Tol Tax, sales tax or any other taxes imposed by the Government.	458.54		Rupees Nil	Per Square Metre	
3	Painting one coat (excluding priming coat) on previously painted steel and other metal surfaces with enamel paint brushing to give an even shade including cleaning the surface of all dirt, dust and other foreign matter With Enamel paint other than white as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government.	484.49		Rupees Nil	Per Square Metre	
					Total: -	

Engineer
Dalhousie Division,
HPPWD, Dalhousie

Schedule of Quantity

Estimated Cost: - Rs. 98393.00
Earnest Money: - Rs. 2000.00
Time: - One Month.

Name of work :- A/R & M/O to Type-I Residential Building Kathlog at Dalhousie (SH:- Providing and Fixing Wire Gauge Shutter, Primer & Paint work and

Providing and fixing Chhajjas in Type-I Quarter etc.).

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing and fixing panelled glazed or panelled and glazed shutters for doors windows and clerestory windows. Including black enamelled iron butt hinges with necessary screws. 40 mm (forty millimetre) thick 2nd (second) class deodar wood. as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	0.67			Per Square Metre	
2	Providing and fixing 40 mm (forty millimetre) thick 2nd Class Deodar wood wire gauge shutter using galvanised M.S. wire gauge of 1.5. gauge designation 85g. (eighty five gram) with wire of dia 0.56mm (zero point fifty six millimetre) for doors, windows and clerestory window including bright finished black enamelled iron hinges with necessary screws as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	12.80			Per Square Metre	
3	Steel work welded in built up sections, framed work, including cutting, bolting, fixing in position and applying a priming coat of approved steel primer using structural steel ectetera. In gratings framed guard bars, ladders, railing, brackets and similar works within all leads and lifts and as per direction of the Engineer-in-Charge and other incidentals. The rate including of octroi, royalty, Malkana, Toll Tax, sales tax or GST any other taxes imposed by the Government.	79.20			Per Kilogram	
4	Applying priming coat over new wood and wood based surfaces after and including preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter) sand papering and knotting and as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	13.47			Per Square Metre	
5	Painting two coats(excluding coat) on new wood and wood based surface with enamel paint Asian Paints/Nerolac surksha Paints/Berger Paints /Delux Paint to give an even shade including cleaning the surface of dirt,dust and other foreign matter,sand papering & sloping With white enamel paint and as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	82.18			Per Square Metre	

7	Providing and fixing 0.60 mm (zero point six millimetre) thick prepainted steel sheet Tata/sail/Reliance/Jindal ISI marked Z-120 in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 (twenty) microns over 5 (five) microns primer coating to back coat of polyester of 5 (five) microns over 5 (five) microns primer coating including fixing with prepainted iron J or L hooks, bolts and nuts 6 mm (six millimetre) dia metre with prepainted limpet and rubber washers complete with all accessories as required within all leads and lifts and as per direction of the Engineer-In-Charge and other incidentals. The rate including of octroi, royalty, Malkana, Tol Tax, sales tax GST or any other taxes imposed by the Government.	12.80				Per Square Metre	
8	Providing and fixing 150x34x24 mm (One hundred fifty isto thirty four isto twenty four millimeter) weighing not less than 26gms (twenty six milligrams) PTMT handle with necessary screws etc. complete as per direction of the Engineer-In-Charge and other incidentals. The rate including of octroi, royalty, Malkana, Tol Tax, sales tax GST or any other taxes imposed by the Government.	25.00				Each	
9	Providing and fixing aluminium lower bolts ISI marked, anodized (anodic coating not less than grade AC 10 as per IS: 1868) transparent or dyed to required colour or shade with necessary screws etcetera complete 150x10mm (One hundred fifty into ten millimetre) and as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	10.00				Each	
10	Repairs of plaster with Cement Mortar 1:4 (Cement : 4 fine sand) of thickness 12mm to 20mm (twelve millimeter to twenty millimeter thick) in patches of area 2.5 sq meter (two point five square meter) under including cutting the patch in proper shape, raking, out joints and preparing and plastering the surface of the wall complete, including disposal of rubbish to the dumping ground all complete as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	7.18				Per Square Metre	
	Wall painting two coats with premium acrylic emulsion paint of interior grade, having V.O.C (Volatile Organic Compound) consist less than 50 grams (fifty milli grams) liter of approved brand like shalimar, Nerolac, Burzer, Asian etcetera and manufacture, including applying additional coats wherever to achieve even shade and colour as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government.	7.18				Per Square Metre	
	Total: -						0.00


 Executive Engineer
 Dalhousie Division,
 HPPWD, Dalhousie

Schedule of Quantity

Name of work :- A/R & M/O to Non Residential Building at Banikhet (SH:- Painting, Repair work of Assistant Engineer Office).

Estimated Cost: - Rs. 60,951.00
Earnest Money: - Rs. 1300.00
Time: - Two Month.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing and applying plaster of Paris Putty of 2mm (two millimeter) thickness over plastered surface to prepare the surface even and smooth complete as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	161.73			Per Square Metre	
2	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer Asian Paints/Nerolac surksha Paints/Berger Paints /Delux Paint two or more coats applied on walls @ 1.25 ltr/10 sqm (one point two five litre per ten square meter) over and including one coat of special primer applied @ 0.75 ltr/sqm (Zero point seven five liter per square meter) as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	161.73			Per Square Metre	
3	Painting one coat (excluding priming coat) of Asian Paints/Nerolac surksha Paints/Berger Paints /Delux Paint on previously painted wood or wood based surface with enamel paint other than white to give a even shade including cleaning of all dirt, dust and other foreign matter sand papering and slopping within all leads and lifts and as per direction of the Engineer-In-Charge and other incidentals. The rate including of octroi, royalty, Malkana, Tol Tax, sales tax or any other taxes	38.58			Per Square Metre	
4	Repairs of plaster with Cement Mortar 1:4 (Cement : 4 fine sand) of thickness 12mm to 20mm (twelve millimeter to twenty millimeter thick) in patches of area 2.5 sq meter (two point five square meter) under including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the wall complete, including disposal of rubbish to the dumping ground all complete as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	22.80			Per Square Metre	
	Total:-					


Engineer
 Dalhousie Division,
 HPPWD, Dalhousie

Schedule of Quantity

Estimated Cost: - Rs. 42,171.00
Earnest Money: - Rs. 1000.00
Time: - One Month.

Name of work :- A/R & M/O to Residential Building at Banikhet (SH: - Supplying and Laying G.I Pipe line water storage platform at Type-III Quarter at Banikhet).

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals. The rate including toll tax sale tax GST or other taxes imposed by the Government.	233.78			Per Quental	
2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing 1:3:6 (1 cement: 3 coarse sand: 6 graded stone aggregate 20mm (fifty millimeter) nominal size as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals. The rate including toll tax sale tax GST or other taxes imposed by the Government.	0.36			Per Cubic Meter	
3	Providing and fixing 15mm (fifteen millimeter) nominal bore Galvanised Iron pipes complete with Galvanised Iron fitting and clamps including cutting and making good the walls etcetera. Internal work-Exposed on wall within all leads and lifts and as per direction of the Engineer-In-Charge and other incidentals. The rate including of Tol Tax, sales tax or any other taxes imposed by the Government.	18.00			Per Running Metre	
4	Providing and laying 12 mm (Twelve millimeter thick) Ceramic glazed floor tiles of size 300x300 mm (three hundred isto three hundred) Resite/ Nitco/ Rak/Kajaria/ Orient& Bell/ Simpolo/Johnson/AGL/Somay of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), Jointing with grey cement slurry @ 3.3 kg/sqm including pointing the joints with white cement and matching pigment etc., complete, as directed by the Engineer-in-Charge, including carriage of materials within all leads and lifts. The rate including toll tax sale tax GST or other taxes imposed by the Government.	8.55			Per Square Metre	
Total: -						0.0

Engineer
Dahouse Division,
HPPWD, Dahouse

Schedule of Quantity

Name of work: - A/R & M/O Type-V residential building at Dalhousie (SH:- Providing and fixing 150 mm rain water pipe and

Shoe)

Schedule of Quantity			Estimated Cost: - Rs. 40906.00			
			Earnest Money :- Rs. 1000.00			
			Time Limit :- One Month			
Name of work: - A/R & M/O Type-V residential building at Dalhousie (SH:- Providing and fixing 150 mm rain water pipe and Shoe)						
Sr. No.	Sub head / item of work	Qty.	Rate		Unit	Amount
			in fig.	In Words		
1	Providing and fixing on wall faces PVC (D-plast) or equivalent 150mm dia (one hundred fifty millimetre diametre) rain water pipes working pressure not less than 4.6 Kg (four point six) kilogram per square centimetre of finolex/relpipe/vectul/Reliance including filling the joints with approved adhesive complete including carriage of material within all leads and lifts and as per the direction of the Engineer-in-Charge and other incidentals. The rate including Octroi, toll tax , GST Sales tax or any other taxes imposed by the Government.	78.50			Per Running Meter	
2	Providing and fixing 150 mm (One hundred fifty millimetre) dia PVC shoe working pressure not less than 6 Kg (six) kilogram per square centimetre on wall faces PVC (D-Plast) supreme Finolex or equivalent accessories for rain water pipes including filling the joints with approved adhesives complete as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Octroi, toll tax , GST Sales tax or any other taxes imposed by the Government.	5			Each	
					Total	0.00


Engineer
 Dalhousie Division,
 HPPWD, Dalhousie

Schedule of Quantity

Name of Work:- Repair and Maintenance of two No Bathrooms at HPPWD Circuit House at Dathouse (SH:- Dismantling of Tiles Providing and Fixing tiles and Sanitary Work)

Estimate Cost - Rs.1,69,043 .00
Earnest Money - Rs. 3400.00
Time Limit:- Two Months

Sr. No.	Description	Quantity	Rate		Unit	Amount	Amount in words
			In Fig.	In word			
1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within all leads and lifts as per the direction of the engineer-in charge and other incidentals.. The rate inclusive of Octroi, toll tax , GST or any other taxes imposed by the Government.	46.32			Per Square Metre		
2	Providing and laying 12 mm (Twelve millimeter) thick 300x300 mm (Three hundred into three millimeter) antiskid ceramic tiles of of Resitile/ Nisco Rak/Kajaria/ Orient& Bell/ Simpolo/Johnson/AGL/Somay of 1st Quality conforming to IS:15622 laid on 12 mm thick cement mortar 1:3 (one cement isto three coarse sand), in walls jointing with grey cement slurry @ 3.3 kg/ sqm (Three point three Kilogramme per Square meter) including grouting the joints with white cement and matching pigments etc.. complete including grouting of joints (Payment for grouting of joints to be made) within all leads and lifts as per the direction of the engineer-in charge and other incidentals.. The rate inclusive of Octroi, toll tax , GST or any other taxes imposed by the Government.	36.96			Per Square Metre		
3	Providing and laying 12 mm (Twelve millimeter) thick 300x300 mm (Three hundred into three millimeter) antiskid ceramic tiles of of Resitile/ Nisco Rak/Kajaria/ Orient& Bell/ Simpolo/Johnson/AGL/Somay of 1st Quality conforming to IS:15622 laid on 20 mm (Twenty millimeter) thick cement mortar 1:4 (one cement isto four coarse sand), in floor jointing with grey cement slurry @ 3.3 kg/ sqm (Three point three Kilogramme per Square meter) including grouting the joints with white cement and matching pigments etc.. complete including grouting of joints (Payment for grouting of joints to be made) within all leads and lifts as per the direction of the engineer-in charge and other incidentals.. The rate inclusive of Octroi, toll tax , GST or any other taxes imposed by the Government.	9.36			Per Square Metre		

4	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) Star S.No. 20087 (S-10) with white solid plastic seat and lid having size 57x35x39 CM (Fifty seven into thirty five into thirty nine centimeter) including 10 (Ten) litre low level white flushing cistern sleek plus . Hindware/Cera/Jaguar of Star white/Snow white shade including flush pipe and fixed with Jet pressure , with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required complete as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Octroi, toll tax , GST Sales tax or any other taxes imposed by the Government.	2				Each		
5	Providing and fixing 100 mm (One hundred millimeter) sand cast iron grating for Gully trap as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Octroi, toll tax , GST Sales tax or any other taxes imposed by the Government.	4				Each		
6	Providing and fixing 600x450mm (Six hundred into four hundred fifty millimeters) bevelled edge mirror of Modi Guard/Saint Gobian glass mounted on 6mm (Six millimeters) thick A.C. sheet or plywood sheet and fixed to wooden plugs with C.P. brass screws and washers complete as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Sales tax, toll tax , GST or any other taxes imposed by the	2				Each		
7	Providing and fixing chromium plated brass toilet paper holder of Hindware/Cera/Jaguar of Star white/Snow white and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Sales tax, toll tax , GST or any other taxes imposed by the	2				Each		
8	Providing and fixing 15 mm (fifteen millimeter) nominal bore to wall ceiling and floor galvanised mild steel tubes (Medium grade) tube fittings and clamps including making good the wall, ceiling and floor, within all leads and lifts and as per the direction of the engineer-in-charge and other incidentals . The rate including Sales tax, toll tax , GST or any other taxes imposed by the Government.	52				Per Running Meter		
9	Providing and fixing ISI marked 45cm (forty five centimeters) long and 15mm (fifteen millimeters) nominal bore PVC connection pipe with brass unions complete as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Sales tax, toll tax , GST or any other taxes imposed by the Government.	8				Each		

10	Providing and fixing 150 mm (One hundred fifty millimeter) diameter chromium plated brass shower rose with 15 to (Fifteen to Twenty millimeter) inlet complete as per HPPWD specifications and as directed by the Engineer-in-Charge. including carriage of materials within all leads, lifts and other incidentals. The rate including Sales tax, toll tax, GST or any other taxes imposed by the Government.	2				Each		
11	Providing and fixing 15 mm (Fifteen millimeter) G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete (New work) as per HPPWD specifications and as directed by the Engineer-in-Charge. including carriage of materials within all leads, lifts and other incidentals. The rate including Sales tax, toll tax, GST or any other taxes imposed by the Government.	4				Each		
12	Providing and fixing 15mm (Fifteen millimeters) diameters C.P. brass bib tap ISI marked of CERA/HINDWARE/PRAYAG approved quality (superior or heavy type) and colour of prayag polymet symet bath assets or its equivalent complete as per HPPWD specifications and as directed by the Engineer-in-Charge. including carriage of materials within all leads, lifts and other incidentals. The rate including Sales tax, toll tax, GST or any other taxes imposed by the Government.	2				Each		
13	Providing and fixing 15mm (Fifteen millimeters) diameters C.P. brass long nose bib cock ISI marked of CERA/HINDWARE/PRAYAG (superior or heavy type) weighing not less than 810 gram (Eight hundred ten gram) or its equivalent complete as per HPPWD specifications and as directed by the Engineer-in-Charge. including carriage of materials within all leads, lifts and other incidentals. The rate including Sales tax, toll tax, GST or any other taxes imposed by the Government.	2				Each		
14	Providing and fixing C.P. brass angle valve 15mm (fifteen millimetre) of CERA/HINDWARE/PRAYAG without Nuts and pipe complete upto all floor level as per HPPWD specifications and as directed by the Engineer-in-Charge. including carriage of materials within all leads, lifts and other incidentals. The rate including Sales tax, toll tax, GST or any other taxes imposed by the Government.	18				Each		
						Total:-	0.00	


 Engineer
 Dalhousie Division,
 HPPWD, Dalhousie

Schedule of Quantity

Estimated Cost: - Rs. 97,650.00
Earnest Money :- Rs. 2000.00

Time Limit :- Three Month

Name of work: - Restoration of rain Damages on Various road under HPPWD Sub Division Banikhet (SH:- Hiring of Excavator cum Loader for removal of slips in Wangal Section)

Sr. No.	Sub head / Item of work	Qty.	Rate		Unit	Amount
			in fig.	In Words		
1	Hiring of JCB / Excavator cum loader for cutting / widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts upto any heights and depth as per direction and entire satisfactions of Engineer-in-charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period / execution shall be the absolute responsibility of the JCB / Excavator Owner which shall have to be fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare, watch and ward of machine also be borne by the Contractor / Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	93.00			Per Hour	
					Total	

Note - 1) The physical progress of machine will also be measured while submitting the bill for payment. It is ensured that working progress of machine should be not be less than the amount to be paid.

Note - 2) No deviation shall be allowed in any case.

Note -3) Subject of availbity of funds

Executive Engineer
Bathurst Division,
Mooventi, Dethan

Schedule of Quantity

Name of work: - Restoration of rain Damages on Various road under HPPWD Sub Division Bankhet (SH:- Hiring of Excavator cum Loader for removal of slips in Bathri Section)

Estimated Cost: - Rs. 98,700.00	
Earnest Money :- Rs. 2000.00	
Time Limit :- Three Month	

Sr. No.	Sub head / item of work	Qty.	Rate		Unit	Amount
			in fig.	In Words		
1	Hiring of JCB / Excavator cum loader for cutting / widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts upto any heights and depth as per direction and entire satisfactions of Engineer-in-charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period / execution shall be the absolute responsibility of the JCB / Excavator Owner which shall have to be fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare, watch and ward of machine also be borne by the Contractor / Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	94.00			Per Hour	
	Total					0.00

Note - 1) The physical progress of machine will also be measured while submitting the bill for payment. It is ensured that working progress of machine should be not be less than the amount to be paid.

Note - 2) No deviation shall be allowed in any case.

Note - 3) Subject of availability of funds


Executive Engineer
Dalhousie Division
HPPWD, Dalhousie

Schedule of Quantity

Job No. -- TS No. ---

Estimated Cost: - Rs. 437523.00

Earnest Money :- Rs. 9000.00

Time Limit :- For Month

Name of work: -C/O Link road to village Dharota Km. 0/0 to 1/870 (SH- C/O HP Culvert at RD. 0/720 , C/O wing wall at RD. 715.80 to 718.80 & 721.20 to

724.20).

Sr. No	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including octroi royalty Malkhana toll tax sale tax . GST or any other taxes imposed by the Government.	53.49			Per Cubic Metre	
2	Providing and laying plain cement concrete 1:3:6 (one cement isto three sand isto six graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size including the cost of form work and curing complete as per drawing and M.O.R.D technical specifications clause 802, 803, 1202 and 1203 or as per direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax, GST any or other taxes imposed by the Government.	22.82			Per Cubic Metre	
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade M-15 (M-fifteen) nominal mix 1:2½:5 (One cement isto two and half sand isto five graded crushed stone aggregate 40 mm (forty millimetre) nominal size) in or under water including pumping or bailing out water. (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights and depths for type - A concrete cradle bedding and the like etcetra including curing complete and cost of form work as per drawing and MORD technical specification clause 802, 803, 1202 and 1203 as per direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1.28			Per Cubic Metre	
4	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete grade M-20 (M-Twenty) nominal mix 1:2:4 (one cement isto two sand isto four graded crushed stone aggregate 20 mm (twenty millimeter) nominal size) in open foundation including curing and cost of form work as per drawings and MORD technical specifications clause 802, 803, 1202 and 1203 or as per direction of Engineer-In-Charge including carriage of materials within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, sales tax GST or any other taxes imposed by the Government.	0.37			Per Cubic Metre	

5	Providing and laying (to level or slope) 900 mm dia (nine hundred millimeter diameter) reinforced cement concrete light duty non pressure pipes IS Class NP-2 (two) for culverts as per design in single row on concrete cradle bedding of plain cement concrete grade M-15 (fifteen) in single row including providing and fixing collar with cement mortar 1:2 (One cement isto two sand), but excluding the cost of excavation, protection works, back filling, concrete cradle bedding and masonry work in head walls and parapets etcetera complete as per drawings and M.O.R.D. technical specifications clause 1108 or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, sales tax GST or any other taxes imposed by the Government.	7.50				Per Running Metre	
6	Plain / reinforced cement concrete M-15 in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 & 1204 nominal mix and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax GST or any other taxes imposed by the Government.	1.00				Per Cubic Metre	
7	Providing and Laying plain cement concrete 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (forty millimetre) nominal size mechanically mixed and vibrated in foundation for all type structure complete for all heights / depth including curing and cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octroi, royalty, Malkana, toll tax, sales tax , GST or any other taxes imposed by the Government.	43.56				Per Cubic Metre	
8	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax , GST or any other taxes imposed by the Government.	11.52				Per Cubic Metre	
9	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia meters, PVC pipe extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	14.00				Each	
Total:-							


 Executive Engineer
 Dalhousie Division,
 PWD, Dalhousie

Schedule of Quantity

Name of work: - Restoration of rain Damages on Dalhousie Jandrihat Chmba via Kohlari road km 0/0 to 11/040 (

SH:- Hiring of Excavator cum Loader for removal of slips in various RD,s)

Schedule of Quantity		Estimated Cost: - Rs. 99,750					
		Earnest Money :- Rs. 2000.00					
		Time Limit :- Three Month					
Name of work: - Restoration of rain Damages on Dalhousie Jandrighat Chumba via Kohlari road km 0/0 to 11/040 (							
SH:- Hiring of Excavator cum Loader for removal of slips in various RD,s)							
Sr. No.	Sub head / item of work	Qty.	Rate		Unit	Amount	
			in fig.	In Words			
1	Hiring of JCB / Excavator cum loader for cutting / widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts upto any heights and depth as per direction and entire satisfactions of Engineer-in-charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period /execution shall be the absolute responsibility of the JCB / Excavator Owner which shall have to be fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare, watch and ward of machine also be borne by the Contractor / Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	95.00			Per Hour		
						Total	

Note - 1) The physical progress of machine will also be measured while submitting the bill for payment. It is ensured that working progress of machine should be not be less than the amount to be paid.

Note - 2) No deviation shall be allowed in any case.

Note -3) Subject of availability of funds


Executive Engineer
 Dalhousie Division,
 H.P.W.D. Dalhousie

Schedule of Quantity

Estimated Cost: - Rs. 2,96,100/-
Earnest Money :- Rs. 6000.00

Time Limit :- Three Month

Name of work: - Restoration of rain Damages on various road under Dalhousie Sub Division (SH:- Removal of slips /Snow on Banikhet Dalhousie Khajjar road km 0/0 to 6/400 and 15/600 to 27/0, Dalhousie Jandrihat Chamba via Kohhari road km 0/0 to 11/040, Link road to VBillage Ruliyani km 0/0 to 3/0 and Link road to Village kathlog to Bherera km 0/0 to 2/180
Hiring of Excavator cum Loader for removal of slips in various RD,s)

Sr No	Sub head / item of work	Qty	Rate		Unit	Amount
			in fig.	In Words		
1	Hiring of JCB / Excavator cum loader for cutting / widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts upto any heights and depth as per direction and entire satisfactions of Engineer-in-charge. Any loss to the public / private property or any accident etc happened during the course of hiring period / execution shall be the absolute responsibility of the JCB / Excavator Owner which shall have to be fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare, watch and ward of machine also be borne by the Contractor / Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	282.00			Per Hour	
					Total	

Note - 1) The physical progress of machine will also be measured while submitting the bill for payment. It is ensured that working progress of machine should be not be less than the amount to be paid.

Note - 2) No deviation shall be allowed in any case.

Note -3) Subject of availbity of funds


 Engineer
 Dalhousie Division,
 HFPWD, Dalhousie

Schedule of Quantity

Name of work :- A/R & M/O Type-III 6 nos Quarter at Dalhousie (SH - Plastering, Painting & Putty work).

Estimated Cost - Rs. 1,92,351.00
Earnest Money - Rs. 4000.00
Time - Two Month.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	15mm (fifteen millimetre) thick cement plaster in single coat on fair side of brick / concrete / stone walls for interior plastering upto floor all levels including arrises, internal rounded angles, chamfers and / or rounded angles not exceeding 80mm (eighty millimetre) in girth and finished even and smooth with cement mortar 1:6 (One Cement isto six sand) within all leads and lifts and as per the direction of the engineer-in-charge and other incidentals. The rate inclusive of Royalty, Malkana, Octroi, toll tax, GST Sales tax or any other taxes imposed by the Government.	114.21			Per Square Metre	
2	Applying Birla White/J.K white two or more coats wall care putty over plastered surfaces after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final finish to the surface complete upto all floor level as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Octroi, toll tax, GST Sales tax or any other taxes imposed by the Government.	114.21			Per Square Metre	
3	Wall painting two coats with premium acrylic emulsion paint of interior grade, Asian Paints/Nerolac surksha Paints/Berger Paints /Delux Paint having VOC (Volatile Organic Compound) content less than 50 grams (fifty milli grams) liter of approved brand and manufacture, including applying additional coats wherever to achieve even shade and colour as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government.	1279.58			Per Square Metre	
4	Painting one coat on previously painted wood or wood based surface with enamel paint Asian Paints/Nerolac surksha Paints/Berger Paints /Delux Paints give a even shade including cleaning of all dirt, dust and other foreign matter sand papering and slopping with enamel paint other than white, within all leads and lifts and as per direction of the Engineer-In-Charge and other incidentals. The rate including of octroi, royalty, Malkana, Tol Tax, sales tax or any other taxes imposed by the Government.	296.85			Per Square Metre	
5	Painting one coat (excluding priming coat) on previously painted steel and other metal surfaces with enamel paint brushing to give an even shade including cleaning the surface of all dirt, dust and other foreign matter With Enamel paint other than white as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government.	183.00			Per Square Metre	
Executive Engineer Public Works Division, HPPWD Dalhousie						Total: - 0.00