Himachal Pradesh
Public works Department

Notice inviting Tender

Sealed item rate tenders on form 6 & 8 are invited by the Executive Engineer, Gohar Division, H.P.PWD: Gohar for the following works from the approved and eligible contractors enlisted in H.P.PWD so as to reach in his office on or before **10-01-2024 up to 11.00 A.M.** and will be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The D.N.I.T. tender documents can be had from this office against cash payment (Non refundable) up to 5.00 P.M. **on 09-01-2024**. The applications for issue of tender forms will be received **up to 2.00 P.M. on 08-01-2024**.

The earnest money in the shape of National Saving Certificate/ Time deposit accounts/Saving account/F.D. Rs in any of the Post Office/Nationalized Banks in Himachal Pradesh duly pledged in favour of the Executive Engineer must accompany the request for issue of tender form for each work. Conditional tenders and the tenders received without earnest money will summarily be rejected. The Executive Engineer reserves the right to reject the tenders without assigning any reason. It is further added that the rates be quoted both in words and figures for proper checking to avoid any complications. If the date of opening will be holiday, the tenders will be opened on the next working day at the same time.

Sr. No.	Name of road/work	Estimated Cost	Earnest Money	Time limit	Class of contractor
1	RR Damages on Tandi Nandi road km 0/00 to 9/500 (SH:- C/o PCC R/wall at RD 7/885 to 7/903 & 7/970 to 7/975)	4,04,542/-	10000	Two Months	D
2	C/o Jail Pul to Saryach road km 0/00 to 5/700 (SH:- C/o stone Masonry Retaining wall at RD 0/615 to 0/630) OTMNP	3,10,196/-	6500	Two Months	D
3	C/o link road from Piplagaloo to Jagrot via Dev Baniour Mandir km 0/00 to 1/600 (SH:- C/o 900 mm hume pipe culvert with both side wing wall at RD 0/395)	1,90,163/-	4000	Two Months	D
4	RRD on Badhu Shilanu Nachhet road km. 0/00 to 5/100 (SH:- C/o of P.C.C R/wall at RD 2/570 to 2/585)	3,06,948/-	7000	Two Months	D
5	RRD on Chail Gohar road km 0/00 to 24/00 (SH:- C/o PCC R/wall at RD 0/055 to 0/070)	1,83,100/-	4000	Two Months	D
6	Upgradation of road Kutahchi to Shikari via Khatidhar Khaniyud Devidarh Tokhar road km 0/00 to 18/00 (SH:- C/o 900 mm dia hume pipe culvert at RD 0/480) Under SCSP	2,61,864/-	5500	Three Months	D
7	C/o Sainj Pangliur road km. 0/00 to 6/00 (SH:- C/o Approaches of pangliur bridge at RD 1/030 to 1/060) under SCDP	3,26,725/-	7000	Two Months	D
8	C/o Sainj Pangliur road km. 0/00 to 6/00 (SH:- C/o Approaches of Pangliur bridge at RD 0/965 to 0/990) under SCDP	4,97,508/-	10000	Two Months	D
9	C/o Kutachi Badhu via Sanjala road km 0/00 to 7/0 (SH:- C/o stone Masonary R/wall with toe wall at RD 4/318.50 to 4/337) under OTMNP	4,62,164/-	10000	Two Months	D
10	C/o Kutachi Badhu via Sanjala road km 0/00 to 7/00 (SH:- C/o stone Masonary R/wall at RD 4/300 to 4/318.50) under OTMNP	4,62,026/-	10000	Two Months	D
11	C/o Latogali Badhu via Maryog road km. 0/00 to 5/00 (SH:- Balance work both side appraoces of slab culvert at RD 1/170)) under OTMNP	3,51,053/-	7500	Two Months	D
12	Preparation of DPR for M/T on Chail Chowk to Kukari galoo via Lambidhar, Chowkkri, Samih, Mandogaloo, Kamlon and Riyul Bagra road km 0/00 to 14/00 SH:- Preparation of detailed project report and drawings)	4,13,000/-	9000	Two Months	D
13	C/o Bassa Badhu road km 0/00 to 2/00 (SH:- Providing and laying Paver Block from km km. 0/110 to 0/260) Under SCSP	4,55,728	10000	Three Months	D
14	C/o Bassa Badhu road km 0/00 to 2/00 (SH:- Providing and laying Paver Block from km km. 0/410 to 0/560) Under SCSP	4,55,728	10000	Three Months	D
15	RRD on Nihandigali to Jhungi road km 0/00 to 2/250 (SH:- C/o R/Walls at RD 1/893 to 1/898.40)	2,78,521/-	6000	Two Months	D

Scanned with OKEN Scanner

Certified that tender of above works are being called for emergent nature in exigency of public interest.

GENERAL CONDITIONS:-

1. The Contractors are required to submit the valid Enlistment/GST registration and latest ITR alongwith application form.
2. The Contractors should quote the rates of all the items in the tenders both in figures and words.
3. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
4. An undertaking will have to be given by the contractor that he has not more than two works in hand at the time of opening of this tender.
5. Contractors will have to submit appropriate Earnest Money in the shape of F.D.R along with the application form for getting issued the tender forms. Applications with out EMD shall be summarily rejected.
6. As per Govt. Notification No.PBW(B)A(3)1/2020-I dated 07-10-2021 the tenders above 5% of estimated cost will be summarily rejected. The tender offered below 30 % will also be accepted as per the office letter No. Engineer-in-Chief office letter No. PW-CTR/32-20/Genl Inst. CPWD-2020-37996-38096 dated 13.03.2023 and further ex- post-facto approval has been granted by the Principal Secretary (PW) to the Govt. of H.P. letter No. PBW (B) A(3)1/2020-I dated 10.05.2023. Beside this the additional performance security will have to borne by the bidders as per the said notifications.
7. The contractor can apply only for one work at a time.
8. Conditional and incomplete tenders shall be rejected.
9. The Executive Engineer reserves the right to accept or reject the tender without any reason.

Executive Engineer,
Gohar Division (B&R),
HPPWD Gohar.

No. PW-GHR-Tender/NIT/2023 4921-27 **Dated** 29/12/23

Copy along with Tender inviting Notice forwarded for information:-

1. The Deputy Commissioner, Mandi H.P.
2. The Engineer-in-Chief HP.PWD.Shimla.
3. The Superintending Engineer 1st Circle, HP.PWD Mandi.
4. **The Executive Engineer (IT Cell) O/O Engineer-in-Chief, HPPWD Nirman Bhawan, Nigam Vihar, Shimla-2 for uploading the NIT on departmental website please.**
5. The Sub- Divisional Officer (Civil) Chachiot at Gohar.
6. The Block Development Officer Gohar.
7. The Assistant Engineer HPPWD Sub- Division Gohar/Dhanotu.
8. Various contractors.
9. Notice Board/DB/AB.

Executive Engineer,
Gohar Division (B&R),
HPPWD.,Gohar.

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Estimate Cost: Rs 4,04,542.00 Only
Earnest Money: 10,000.00 Only
Time :- Two Months

Name of Work :- RR Damages on Tandi Nandi road KM 0/000 to 9/500 (SH:- Construction of PCC Retaining wall at RD 7/885 to 7/903 to & 7/970 to 7/975).

S. No.	Sub Head and item of work	Qyt.	Rate in		Unit	Amount
			Figure	In Word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stump and other deleterious material and disposal up to any lead , lifts and dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil within all leads , lifts and carriage of materials and other incidentals .	40.27			per Cubic metre	-
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer –in –Charge completer in all respect.	81.15			per Cubic metre	-
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .	14.87			per Cubic metre	-
4	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer –in –Charge complete in all respect.	20.00			Each	-
					Total	-

Executive Engineer
Golar Division (B&R)
HPPWD Gohar

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Estimate Cost: Rs 3,10,196.00 Only
Earnest Money: 6,500.00 Only
Time :- Two Months

Name of Work :- Construction of Jail Pul to Saryach road KM 0/000 to 5/7000 (SH:-Construction of Stone Masonry Retaining Wall at RD 0/615 to 0/630) Under OTMNP

S. No.	Sub Head and item of work	Qyt.	Rate in		Unit	Amount
			Figure	In Word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stump and other deleterious material and disposal up to any lead , lifts and dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil within all leads , lifts and carriage of materials and other incidentals .	24.38			Per Cubic metre	
2	Providing and laying cement concrete 1:6:12 (one cement : six sand twelve graded crashed stone aggregate 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 including carriage of material within all leads, lifts and other incidental charges. and direction of Engineer-in-Charge.	5.87			Per Cubic metre	
3	Providing and Laying 1:4:8 (one cement : four sand : eight graded crashed stone aggregateand curing complete including cost of form work for plain reinforced concrete in in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 within all leads , lifts and carriage of materials and other incidentals .	2.31			Per Cubic metre	
4	Random rubble masonry Stone masonry in cement mortar In (1:6)for substructure complete as per drawing & technical specification Clauses 702, 704, 1202 and 1204 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	19.13			Per Cubic metre	
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer –in –Charge completer in all respect.	35.45			Per Cubic metre	
6	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .	12.00			Per Cubic metre	
					Total	

Executive Engineer
Gohar Division (B&R)
KPPWD Gohar

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Estimate Cost: Rs. 1,90,163/- only
Earnest Money: Rs 4,000 /- only
Time : Two months

Name of Work :-Construction of link road from piplagaloo to Jagrot via Dev Baniuri Mandir km 0/00 to 1/600 (SH:- Construction of 900mm Hume pipe culvert with both side wing wall at RD 0/395)

S. No.	Sub Head and item of work	Qyt.	Rate in		Unit	Amount
			Figure	Word		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals. as directed by Engineer-incharge.	36.22			Per Cubic Metre	
2	Providing and Laying concrete 1:4:8 (one cement : four sand : eight graded crushed stone aggregate 40mm (forty millimeter) nominal size for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 within all leads , lifts and carriage of materials and other incidentals as directed by Engineer-incharge.	7.01			Per Cubic Metre	
3	Stone masonry in cement mortar for foundation complete as per drawing and technical specification clause 702, 704,1202 and 1204 (random rubble masonry in cement mortar . 1:6(one cement : six sand) within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer –in –Charge complete in all respect.	9.19			Per Cubic Metre	
4	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete 900 mm dia. R.C.C. pipe as per direction of Engineer –in –Charge complete in all respect.	7.50			Per Running Metre	
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer –in –Charge completer in all respect.	18.00			Per Cubic Metre	

Scanned with OKEN Scanner

	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer –in –Charge completer in all respect.	3.66			Per Cubic Metre	
					Total	

3

Executive Engineer
Gohar Division (B&R)
HPPWD Gohar

Scanned with OKEN Scanner

(4)

SCHEDULE OF QUANTITY

Estimate Cost: Rs. 3,06,948/- only
Earnest Money: Rs 7,000/- only
Time :- Two month

Name of Work :- **RRD on Badhu Shilanu Nachhet road KM 0/000 to 5/100 (SH:- Construction of P.C.C. R/Wall at RD 2/570 to 2/585)**

S. No.	Sub Head and item of work	Qyt.	Rate in		Unit	Amount
			Figure	Word		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material Ordinary soil within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer –in –Charge complete in all respect.	6.83			per Cubic metre	
2	Providing and laying cement concrete 1 : 5 : 10 (one cement : five sand : ten graded crashed stone aggregateand curing complete including cost of form work for plain reinforced concrete in R/wall ,B/wall as per drawing and HPPWD technical specifications 802,803,1202, and 1203 within all leads , lifts and carriage of materials and other incidentals as directed by Engineer-incharge.	62.30			Per Cubic metre	
3	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer –in –Charge complete in all respect.	20.00			Each	
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer –in –Charge complete in all respect.	12.90			Each	
					Total	

Scanned with OKEN Scanner

(5)

SCHEDULE OF QUANTITY

Estimate Cost: Rs 1,83,100.00 Only
Earnest Money: 4,000.00 Only
Time :- Two Months

Name of Work :- RRD on Chail Gohar Pandoh road KM 0/000 to 24/000 (SH:- Construction of PCC Retaining wall at RD 0/055 to 0/070).

S. No.	Sub Head and item of work	Qyt.	Rate in		Unit	Amount
			Figure	In Word		
1	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer –in –Charge completer in all respect.	39.60			per Cubic metre	-
2	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer –in –Charge complete in all respect.	10.00			Each	-
					Total	-

Executive Engineer
Gohar (38 R)
HPPWD

Scanned with OKEN Scanner

(6)

SCHEDULE OF QUANTITY

Estimate Cost: Rs. 2,61,864/- only
Earnest Money: Rs 5500 /- only
Time : Three month

Name of Work :- **Upgradation of road Kutahchi to Shikari via Khatidhar Khaniyud Devidarh Tokhar road KM 0/000 to 18/000 (SH:- C/o 900 mm Dia Hume Pipe culvert at RD0/480) Under SCSP**

S. No.	Sub Head and item of work	Qyt.	Rate in		Unit	Amount
			Figure	Word		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals. as directed by Engineer-incharge.	46.37			per Cubic metre	
2	Providing and Laying concrete 1:4:8 (one cement : four sand : eight graded crushed stone aggregate 40mm (forty millimeter) nominal size for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 within all leads , lifts and carriage of materials and other incidentals as directed by Engineer-incharge.	4.41			per Cubic metre	
3	Stone masonry in cement mortar for foundation complete as per drawing and technical specification clause 702, 704,1202 and 1204 (random rubble masonry in cement mortar . 1:5(one cement : five sand) within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer –in –Charge complete in all respect.	12.75			per Cubic metre	
4	Providing and laying cement concrete 1 : 5 : 10 (one cement : five sand : ten graded crashed stone aggregateand curing complete including cost of form work for plain reinforced concrete in R/wall ,B/wall as per drawing and HPPWD technical specifications 802,803,1202, and 1203 within all leads , lifts and carriage of materials and other incidentals as directed by Engineer-incharge.	2.00			per Cubic metre	
5	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete 900 mm dia. R.C.C. pipe as per direction of Engineer –in –Charge complete in all respect.	7.50			per Running metre	

Scanned with OKEN Scanner

6	Providing and laying cement concrete 1:6:12 (one cement : six sand twelve graded crashed stone aggregate 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals .as directed by Engineer-incharge.	2.58				per Cubic metre	
7	Stone masonry in cement mortar for foundation complete as per drawing and technical specification clause 702, 704,1202 and 1204 (random rubble masonry in cement mortar . 1:6(one cement : six sand) within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer –in –Charge complete in all respect.	11.48				per Cubic metre	
8	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer –in –Charge completer in all respect.	10.18				per Cubic metre	
9	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer –in –Charge completer in all respect.	5.20				per Cubic metre	
						Total	

Executive Engineer
B & R Division
H.P.P.W.D Gohar

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

(7)

Estimate Cost: Rs 3,26,725/- only
Earnest Money: Rs 7,000- only
Time :- Two Months

Name of Work :- Construction of Sianj Pangliur road km 0/000 to 6/00 (SH:- Construction of Approaches of pangliur bridge at RD 1/030 to 1/060) Under SCDP

S. No.	Sub Head and item of work	Qyt.	Rate in		Unit	Amount
			Figure	Word		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. as per direction of Engineer –in –Charge complete in all respect.	13.13			per Cubic metre	-
2	Providing and laying cement concrete retaining walls, (any thickness) including attached pilaster, columan's, piers, abutments, pillars, posts , struts, buttresses string or lacing course, parapets, coping , bed blocks, anchor block, plan window sills, fillets, sunken floor etc. up to floor five level including the cost of centering, shuttering and finishing and cement concrete 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size) as per direction of Engineer –in –Charge complete in	67.50			per Cubic metre	-
3	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer –in –Charge complete in all respect.	23.00			Each	-
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer –in –Charge completer in all respect.	7.13			Each	-
					Total	-

Executive Engineer
B & R Division
H.P.P.W.D Gohar

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Estimate Cost: Rs 4,97,508/- only
Earnest Money: Rs 10,000- only
Time :- Two Months

Name of Work :- Construction of Sianj Pangliur road km 0/000 to 6/00 (SH:- Construction of approaches of pangliur bridge at RD 0/965 to 0/990) Under SCDP

S. No.	Sub Head and item of work	Qyt.	Rate in Figure	Rate in Word	Unit	Amount
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. as per direction of Engineer –in –Charge complete in all respect.	18.06			per Cubic metre	-
2	Providing and laying cement concrete retaining walls, (any thickness) including attached pilaster, columan's, piers, abutments, pillars, posts , struts, buttresses string or lacing course, parapets, coping , bed blocks, anchor block, plan window sills, fillets, sunken floor etc. up to floor five level including the cost of centering, shuttering and finishing and cement concrete 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size) as per direction of Engineer –in –Charge complete in	103.13			per Cubic metre	-
3	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer –in –Charge complete in all respect.	36.00			Each	-
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer –in –Charge completer in all respect.	9.69			Each	-
					Total	-

Executive Engineer
B & R Division
H.P.P.W.D Gohar

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

(9)

Estimate Cost: Rs 4,62,164/- only
Earnest Money: Rs 10,000- only
Time :- Two Months

Name of Work :- Construction of Kutachi Badhu via Sanjala road km 0/000 to 7/00 (SH:- Construction of Stone Masonary Retaining Wall with toe wall at RD 4/318.50 to 4/337) Under OTMNP

S. No.	Sub Head and item of work	Qyt.	Rate in		Unit	Amount
			Figure	Word		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. as per direction of Engineer –in –Charge complete in all respect.	14.89			per Cubic metre	-
2	Providing and laying cement concrete retaining walls, (any thickness) including attached pilaster, columan's, piers, abutments, pillars, posts , struts, buttresses string or lacing course, parapets, coping , bed blocks, anchor block, plan window sills, fillets, sunken floor etc. up to floor five level including the cost of centering, shuttering and finishing and cement concrete 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size) as per direction of Engineer –in –Charge complete in all respect.	53.28			per Cubic metre	-
3	Stone masonry in cement mortar for foundation complete as per drawing and technical specification clause 702, 704,1202 and 1204 (random rubble masonry in cement mortar . 1:6(one cement : six sand) within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer –in –Charge complete in all respect.	17.32			per Cubic metre	-
4	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer –in –Charge completer in all respect.	35.34			per Cubic metre	-
5	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer –in –Charge completer in all respect.	8.33			per Cubic metre	-
					Total	-

Executive Engineer
B & R Division
H.P.P.W.D Gohar

Scanned with OKEN Scanner

DRAFT SCHEDULE OF QUANTITY

Estimate Cost: Rs 4,62,026/- only
Earnest Money: Rs 10,000- only
Time :- Two Months

Name of Work :- Construction of Kutachi Badhu via Sanjala road km 0/000 to 7/00 (SH:- Construction of Stone Masonary Retaining Wall at RD 4/300 to 4/318.50) Under OTMNP

S. No.	Sub Head and item of work	Qyt.	Rate in		Unit	Amount
			Figure	Word		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. as per direction of Engineer –in –Charge complete in all respect.	14.43 cum	298.50	Rupees Two Hundred Ninety Eight And Paise Fifty Only	per Cubic metre	4,307.00
2	Providing and laying cement concrete retaining walls, (any thickness) including attached pilaster, columan's, piers, abutments, pillars, posts , struts, buttresses string or lacing course, parapets, coping , bed blocks, anchor block, plan window sills, fillets, sunken floor etc. up to floor five level including the cost of centering, shuttering and finishing and cement concrete 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size) as per direction of Engineer –in –Charge complete in all respect.	53.28 cum	4525.60	Rupees Four Thousand Five Hundred Twenty Five And Paise Sixty Only	per Cubic metre	2,41,124.00
3	Stone masonry in cement mortar for foundation complete as per drawing and technical specification clause 702, 704,1202 and 1204 (random rubble masonry in cement mortar . 1:6(one cement : six sand) within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer –in –Charge complete in all respect.	17.32 cum	5390.90	Rupees Five Thousand Three Hundred Ninety And Paise Ninety Only	per Cubic metre	93,370.00
4	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer –in –Charge completer in all respect.	35.34 cum	3209.50	Rupees Three Thousand Two Hundred Nine And Paise Fifty Only	per Cubic metre	1,13,424.00

Scanned with OKEN Scanner

5	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer –in –Charge completer in all respect.	8.33			per Cubic metre	-
					Total	-

Executive Engineer
B & R Division
H.P.P.W.D Gohar

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

(11)

Estimate Cost: Rs. 3,51,053/- only
Earnest Money: Rs 7500 /- only
Time : Three month

Name of Work :- **Construction of Latogali Badhu via Maryog road KM 0/000 to 5/000 (SH:- C/o Balance work both side appraoces of slab culvert at RD 1/170) Under OTMNP**

S. No.	Sub Head and item of work	Qyt.	Rate in		Unit	Amount
			Figure	Word		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals. as directed by Engineer-incharge.	21.06			per Cubic metre	-
2	Stone masonry in cement mortar for foundation complete as per drawing and technical specification clause 702, 704,1202 and 1204 (random rubble masonry in cement mortar . 1:6(one cement : six sand) within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer –in –Charge complete in all respect.	41.31			per Cubic metre	-
3	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer –in –Charge completer in all respect.	25.99			per Cubic metre	-
4	Filling in foundation trenches as per drawing and technical specification Clause 305.3.9 Earth filling (For marshy soil) including all leads , lifts of material and other incidentals as per direction of Engineer –in –Charge complete in all respect.	361.25			per Cubic metre	-
					Total	-

Executive Engineer
B & R Division
H.P.P.W.D Gohar

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Name of work:- Preparation of DPR for M/T on Chail Chowk to Kukari galoo via Lambidhar , Chowkkri , Samih, Mandogaloo, Kamlon and Riyul Bagra road KM 0/000 to 14/000 (Sub-Head:- Preparation of detailed project report and drawings .)

Estimated Cost:- 4,13,000/-
Earnest Money:- 9,000/-
Time:- Two Month

Sr.No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Preparation of detailed project report soil investigation,prepation of manuscript copy of detailed estimate and drawings complete i.e. Plan, cross-sections, L-sections, cross drainage work, Retaining walls, Breast walls & other necessary provisions taken in the estimate preparation of detailed estimate in the shape of manuscript copy to be fair out after appraoval from the **circle office, Chief office,** preparation of approved copies of detailed estimate alongwith relevent working drawings **(Five sets of DPRs complete**) and soft copies in the form of pan drive if any correction/amendment is desired by the Head office, the same may be corrected as desired and directed by the Engineer-In-Charge complete in all respects	14.000 KM			Per Kilometre	-
				Total:-		-

Executive Engineer
B & R Division
H.P.P.W.D Gohar

Scanned with OKEN Scanner

(13)

DRAFT SCHEDULE OF QUANTITY

Estimate Cost: Rs.4,55,728/- only
Earnest Money: Rs 10,000/- only
Time : Three month

Name of Work :- **Construction of Bassa Baddu road km 0/00 to 2/00 (SH:- Providing and laying Paver Block from km 0/110 to 0/260) Under SCSP**

S. No.	Sub Head and item of work	Qyt.	Unit
1	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour) including carriage of materials , with in all leads .lifts as per direction of Engineer - in - charge .	34.88 cum	per Cubic metre
2	Providing concrete for plain / reinforced concrete in open foundations complete as per drawings and technical specifications clause 802,803,1202 & 1203 P.C.C. grade M-10 nominal mix 1: 3: 6 (one cement : three sand :six graded stone aggregate 20mm (twenty millimeter) within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer - in - charge .	9.06 cum	per Cubic metre
3	Providing and Laying of interlocking concrete Block pavements having thickness 80 mm. as per drawings and Technical Specification clause 1504. within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer - in - charge .	352.50 Sqm	Per square metre

Executive Engineer
Gohar Division (B&R)
HPPWD Gohar

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Estimate Cost: Rs.4,55,728/- only
Earnest Money: Rs 10,000/- only
Time : Three month

Name of Work :- **Construction of Bassa Baddu road km 0/00 to 2/00 (SH:- Providing and laying Paver Block from km 0/410 to 0/560) Under SCSP**

S. No.	Sub Head and item of work	Qyt.	Rate in		Unit	Amount
			Figure	Word		
1	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour) including carriage of materials , with in all leads .lifts as per direction of Engineer - in - charge .	34.88 cum			per Cubic metre	
2	Providing concrete for plain / reinforced concrete in open foundations complete as per drawings and technical specifications clause 802,803,1202 & 1203 P.C.C. grade M-10 nominal mix 1: 3: 6 (one cement : three sand :six graded stone aggregate 20mm (twenty millimeter) within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer - in - charge .	9.06 cum			per Cubic metre	
3	Providing and Laying of interlocking concrete Block pavements having thickness 80 mm. as per drawings and Technical Specification clause 1504. within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer - in - charge .	352.50 Sqm			Per square metre	
					Total	

Executive Engineer
Gohar Division (B&R)
HPPWD Gohar

Scanned with OKEN Scanner

SCHEDULE OF QUANTITY

Estimate Cost: Rs 2,78,521/- only
Earnest Money: Rs 6,000- only
Time :- Two Months

Name of Work :-RRD on Nihandigali to Jhungi road km 0/000 to 2/250 (SH:- Construction of Retaining Walls at RD 1/893 to 1/898.40)

S. No.	Sub Head and item of work	Qyt.		Rate in Figure	Rate in Word	Unit	Amount
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. Ordinary soil (1) Upto 3 m depth as per direction of Engineer –in –Charge complete in all respect.	15.21	cum			per Cubic metre	
2	Providing and laying cement concrete retaining walls, (any thickness) including attached pilaster, columan's, piers, abutments, pillars, posts , struts, buttresses string or lacing course, parapets, coping , bed blocks, anchor block, plan window sills, fillets, sunken floor etc. up to floor five level including the cost of centering, shuttering and finishing and cement concrete 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size) as per direction of Engineer –in –Charge complete in all respect.	58.92	cum			per Cubic metre	
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer –in –Charge completer in all respect.	3.26	cum			per Cubic metre	
4	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 110 mm (one hundred Ten millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer –in –Charge complete in all respect.	9.00	Nos			Each	
						Total	

Scanned with OKEN Scanner