OFFICE OF
Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh
Works Department Jaisinghpur 176095 Phone No. 01894-228030
Email ee-jaipwd-hp@gov.in

"CERTIFICATE"

Certified that the tenders for the works as called vide this office letter No. PWD/JSD/TA/NIT/ 2023-24- 13182-13221 dated 20-12-2023 are of urgent nature and in public interest.

Executive Engineer
Jaisinghpur Division
HPPWD Jaisinghpur

Office of
Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh Works Department Jaisinghpur
176095 Phone No. 01894-228030 Email ee-jaipwd-hp@gov.in

"NOTICE INVITING TENDERS"

Sealed percentage rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, HP.PWD., Division Jaisinghpur on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **26.12.2023 up to 11:30** A.M. and the same shall be opened on the same day at 04:00 P.M. in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **23.12.2023** up to 4:00 PM and the application for issue of tender from shall be received on **23.12.2023** up to 11.30 AM. The applications for issue of tender forms accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates/Saving Account of the Post Office/ Time Deposit account/FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP.PWD Division Jaisinghpur.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for **75** days:-

Sr. No.	Name of Work	Estimated cost in Rs.	EMD	Time limit	Cost of Tender form
1	Improvement Up-gradation and strengthening of Haler to Mungal road KM 0/00 - 5/100 (2) C/O Link road to Village Rananagar KM 0/00 to 5/500 (SH:- Preparation of DPR under Nabard)	243800.00	4900.00	Three month	350/-
2	Construction of building at Govt. Polytechnical college at Talwar in Tehsil Jaisinghpur,Distt. Kangra (HP) and C/O Judicial Court complex at Jaisinghpur District kangra HP (SH:- Investigation soil bearing capacity)	225000.00	4500.00	Two month	350/-
3	Restoration of rain Damages on link road to Village Rananagar Km 0/00 to 5/750 (SH:- C/O R/wall at RD 5/275 to 5/290)	497225.00	10000.00	Two month	350/-
4	Restoration of rain Damages on Dharamshala Dadh Palampur Holta Chadhiar Sandhole road Km 0/00 to 90/00 (SH:- C/O Balance work R/wall at Rd 79/720 to 79/732)	479539.00	9600.00	Two month	350/-

Terms & Conditions:-

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor / firm have to produce the copy of latest enlistment and renewal ellisted in HPPWD.
3. If any of the date mentioned above happened to be Gazetted Holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tenders without assigning any reason.
5. The Contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand.
6. Next tender will be issued only after completion of previous works in hand.

Executive Engineer
Jaisinghpur Division
HPPWD Jaisinghpur.
(On behalf of Governor of Himachal Pradesh)

No. PW/JSD/TA/Tender/NIT/2023-24- 13182-13221 Dated:- 20-12-23

Copy to the following for information and necessary action:-

1. The Principal Secy. (PW) to the Govt. of H.P. Shimla.
2. The Engineer-in-Chief HP.PWD., Shimla.
3. The Chief Engineer (K.Z.) HP.PWD., Dharamshala.
4. The Director, Information & Publications Department, H.P. Shimla.
5. The Executive Engineer (IT) O/O E-in-C, HP.PWD., Nigam Vihar Shimla-2 for information. He is requested to upload the same on the department website.
6. The Superintending Engineer, 5th Circle. HPPWD, Palampur.
7. The Deputy Commissioner, Kangra at Dharamshala.
8. All the S.E.s / E.E.s under Kangra Zone.
9. The Sub Divisional Officer (C) Jaisinghpur
10. The Block Development office Lambagaon.
11. All the Assistant Engineer under this Division.
12. The Drawing /Accounts Branch in this office.
13. Notice Board.

Executive Engineer
Jaisinghpur Division
HPPWD Jaisinghpur.

NAME OF WORK:- IMPROVEMENT UP-GRADATION AND STRENGTHENING OF HALER TO MUNGAL ROAD KM 0/00 - 5/100 (2) C/O LINK ROAD TO VILLAGE RANANAGAR KM 0/00 TO 5/500 (SUB HEAD : PREPARATION OF DETAILED PROJECT REPORT)					ESTIMATED COST:-2,43,800.00 EARNEST MONEY:-4900.00 TIME LIMIT :- 3 months	
SR. NO.	DESCRIPTION OF ITEMS	NO./ QTY./ JOB	UNIT	ESTIMATED RATE (IN RS.)	ESTIMATED RATE IN WORDS	TOTAL AMOUNT INCLUSIVE OF
1	2	3	4	5	6	7
1	PREPARATION OF DETAILED PROJECT REPORT AND DRAWING COMPLETE IN ALL RESPECT IN MANUSCRIPT FROM AND SUBMISSION OF THE SAME TO HIGHER OFFICE FOR APPROVAL. IF ANY CORRECTION / AMENDMENT HAS DESIRED BY THE HEAD OFFICE. THE SAME MAY BE CORRECTED AS DESIRED AND DIRECTED BY THE ENGINEER - IN - CHARGE COMPLETE IN ALL RESPECT. AFTER APPROVAL , THE SAME SHOULD BE SUBMITTED IN SIX NOS. SET OF FAIR COPY ALONGWITH 04 SET OF DRAWINGS (MANUSCRIPT INCLUDED WITH SOFT COPY) . THE PAYMENT EXCLUDES ANY KIND OF SOIL INVESTIGATIONS AND SHALL BE MADE AS PER ACTUAL LENGTH OF ROAD. THE RATE IS INCLUDING OCTROI,ROYALITY,MALKANA,GST OR OTHER TAXES IMPOSED BY THE GOVERNMENT.	10.600	Per kilometre	23,000.000	Rupees Twenty Three Thousand Only	243,800.00
a	TOPOGRAPHY SURVEY BY DIGITAL TOTAL STATION / DUAL FREQUENCY DGPS WITH TWO SECOND ACCURACY, SHOWING ALL OFFSETS SUCH AS TREES, CULVERTS, BRIDGE, ELECTRIC POLES, HAND PUMP SCHOOLS, HABITANTS VILLAGES ETC.					
b	DRAW CROSS SECTION AT 15 M (FIFTEEN METER) INTERVALS, L- SECTION & CALCULATE THE QUANTITY OF EARTH WORK IN STANDARD FORMAT OF AUTO CAD SHOWING ALL LAYERS OF PAVEMENT COMPOMENTS.					
c	PREPARATION OF SURVEY PLAN SHOWING ALL PROVISION AS PER HPPWD SPECIFICATION					
d	PREPARATION OF SURVEY PLAN SHOWING ALL EXISTING PROVISIONS AND PREPARATION OF DETAILED PROJECT REPORT AS PER HPPWD SPECIFICATION					
					TOTAL	243800.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

NOTE:- PAYMENT SCHEDULE

i) RUPEES @ 30 % OF THE AWARDED AMOUNT WILL BE RELEASED AFTER THE SUBMISSION OF THE MANUSCRIPT COPY ALONGWITH DRAWING IN THE DIVISION OFFICE.

ii) RUPEES @ 45 % OF THE AWARDED AMOUNT WILL BE RELEASED APPROVAL OF THE MANUSCRIPT DPR FROM THE COMPETENT AUTHORITY.

Iii) RUPEES @ 25 % OF THE AWARDED AMOUNT WILL BE RELEASED AFTER THE FAIR OUT COPY & (SOFT COPY) OF SIX NO SETS DPR ALONG WITH DRAWINGS AS PER DIVISION OFFICE.

EXECUTIVE ENGINEER
JAISINGHPUR DIVISION
HPPWD JAISINGHPUR

(2)

SCHEDULE OF QUANTITY

Name of work :-Construction of building at Govt. Polytechnical college at Talwar in Tehsil Jaisinghpur Distt. Kangra (HP) and C/O Judicial Court complex at Jaisinghpur District kangra HP (SH:- Investigation soil bearing capacity)

					Estimated cost Rs.	**225000.00**
					Earnest Money Rs.	**4500.00**
					Time Limits	**Two month**
S. N.	**Description of Item**	**Quantity**	**Rate**		**Unit**	**Amount**
			In Figures	**In Word**		
1	Investigation of Bearing capacity of soil for C/O Polytechnic College Building at Talwar and Judicialy Complex Building at Jaisinghpur Site at different locations of minimum 3.00 to 5.00 Mtr (three to Five Meter) meter depth of each bore and submitted the test result complete in all respect .The rate is including GST, toll tax, Sale Tax or other taxes imposed by the Government.	30.00	7500.00	Rupees Seven Thousand Five Hundred Only	Per runing metre.	225000.00
	Total					**225000.00**
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

(3)

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on link road to Village Rananagar Km 0/00 to 5/750 (SH:- C/O R/wall at RD 5/275 to 5/290)

Estimated cost Rs.	**497225.00**
Earnest Money Rs.	**10000.00**
Time Limits	**Two month**

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	70.20	200.00	Rupees Two Hundred Only	Per cubic metre	14040.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specificationi section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equippments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	121.50	3750.00	Rupees Three Thousand Seven Hundred Fifty Only	Per cubic metre	455625.00

3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royality, GST, toll tax or other taxes imposed by the Government.	35.00	250.00	Rupees Two Hundred Fifty Only	Each	8750.00
4	Back filling with granular material behind abutments, wing walls, return walls and retaning walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the directions of Engineer-in-Charge including carriage of material within all leads,lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	19.80	950.00	Rupees Nine Hundred Fifty Only	Per cubic metre.	18810.00
	Total					**497225.00**
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
~~HP.PWD~~ Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Dharamshala Dadh Palampur Holta Chadhiar Sandhole road Km 0/00 to 90/00 (SH:- C/O Balance work R/wall at Rd 79/720 to 79/732)

Estimated cost Rs.	**479539.00**
Earnest Money Rs.	**9600.00**
Time Limits	**Two month**

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	8.58	225.00	Rupees Two Hundred Twenty Five Only	Per cubic metre	1931.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specificationi section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equippments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	123.84	3750.00	Rupees Three Thousand Seven Hundred Fifty Only	Per cubic metre	464400.00

3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royality, GST, toll tax or other taxes imposed by the Government.	20.00	250.00	Rupees Two Hundred Fifty Only	Each	5000.00
4	Back filling with granular material behind abutments, wing walls, return walls and retaning walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the directions of Engineer-in-Charge including carriage of material within all leads,lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	8.64	950.00	Rupees Nine Hundred Fifty Only	Per cubic metre.	8208.00
	Total					**479539.00**
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur