



OFFICE OF

Executive Engineer Jaishingpur Division HPPWD Jaishingpur Himachal Pradesh Works
Department Jaishingpur 176095 Phone No. 01894-228030
Email ee-jaipwd-hp@gov.in

"CERTIFICATE"

Certified that the tenders for the works as called vide this office letter No. PWD/JSD/TA/NIT/ 2023-24- 13058-97 dated 15/12/2023 are of urgent nature and in public interest.

Executive Engineer
Jaishingpur Division
HPPWD Jaishingpur.



Office of
Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh Works Department Jaisinghpur
176095 Phone No. 01894-228030 Email ee-jaipwd-hp@gov.in

"NOTICE INVITING TENDERS"

Sealed percentage rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, HP.PWD., Division Jaisinghpur on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **21.12.2023 up to 11:30 A.M.** and the same shall be opened on the same day at 04:00 P.M. in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **20.12.2023 up to 4:00 PM** and the application for issue of tender form shall be received on **19.12.2023 up to 04:00 PM**. The applications for issue of tender forms accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates/Saving Account of the Post Office/ Time Deposit account/FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP.PWD Division Jaisinghpur.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 75 days:-

Sr. No.	Name of Work	Estimated cost in Rs.	EMD	Time limit	Cost of Tender form
1	A/R & M/O Panchrukhi Lambagoan road Km 0/00 to 5/00 (SH:- Repair of Pot Hole / patch work between Km 0/00 to 5/00)	472350.00	9500.00	Two month	350/-
2	A/R & M/O various roads in Lambagoan Section under HP.PWD Sub Division Jaisinghpur (SH:- Repair of Pot Hole / patch work in various roads (i) Trehla Badhala Dali Road Between Km 2/00 to 4/500 (ii) Bhawarna Jhunga Devi road Between Km 20/500 to 23/00)	492938.00	9900.00	Two month	350/-
3	A/R & M/O various roads in Lambagoan Section under HP.PWD Sub Division Jaisinghpur (SH:- Repair of Pot Hole / patch work in various roads (i) Trehla Badhala Dali Road Between Km 0/00 to 4/500 (ii) Bhawarna Jhunga Devi road Between Km 15/400 to 20/500)	480972.00	9700.00	Two month	350/-
4	A/R & M/O various roads in Jaisinghpur under HP.PWD Sub Division Jaisinghpur (SH:- Repair of Pot Hole / patch work on Tinbar to Lugat road between Km 0/00 to 2/00)	160491.00	3300.00	Two month	350/-

Terms & Conditions:-

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor / firm have to produce the copy of latest enlistment and renewal ellisted in HPPWD.
3. If any of the date mentioned above happened to be Gazetted Holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tenders without assigning any reason.
5. The Contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand.
6. Next tender will be issued only after completion of previous works in hand.

Executive Engineer
Jaisinghpur Division
HPPWD Jaisinghpur

(On behalf of Governor of Himachal Pradesh)

No. PW/JSD/TA/Tender/NIT/2023-24-

13058-97

Dated:-

15/12/2023


Copy to the following for information and necessary action:-

1. The Principal Secy. (PW) to the Govt. of H.P. Shimla.
2. The Engineer-in-Chief HP.PWD., Shimla.
3. The Chief Engineer (K.Z.) HP.PWD., Dharamshala.
4. The Director, Information & Publications Department, H.P. Shimla.
5. The Executive Engineer (IT) O/O E-in-C, HP.PWD., Nigam Vihar Shimla-2 for information. He is requested to upload the same on the department website.
6. The Superintending Engineer, 5th Circle, HPPWD, Palampur.
7. The Deputy Commissioner, Kangra at Dharamshala.
8. All the S.E.s / E.E.s under Kangra Zone.
9. The Sub Divisional Officer (C) Jaisinghpur
10. The Block Development office Lambagoan.
11. All the Assistant Engineer under this Division.
12. The Drawing /Accounts Branch in this office.
13. Notice Board.

Executive Engineer
Jaisinghpur Division
HPPWD Jaisinghpur

1

SCHEDULE OF QUANTITY						
Name of work :- A/R & M/O Panchrukhi Lambagoan road Km 0/00 to 5/00 (SH:- Repair of Pot Hole / patch work between Km 0/00 to 5/00)				Estimated cost Rs.		438850.00
				Earnest Money Rs.		8800.00
				Time Limits		Two month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Repairing of pot holes and removal of loose material trimming of sides by providing with Bitumen Vg-10(ten) tack coat at the rate of 0.30 kg. (zero point thirty kilograms) per Square metre, Open grades premix carpet of 20mm (twenty millimeter) thickness composed of 13.2mm (thirteen decimal two millimeter) to 5.6mm (five decimal six millimeter) aggregate @ 0.27 cum (zero decimal twenty seven cubic metres) mixed with using penetration grade bitumen VG-10(ten) @ 14.60 kg (fourteen point sixty kilogram) per ten square of road surface required line grade and level and seal coat sealing the voids in a bituminous surface laid to specified level grade and cross fall using type-B as per M.O.R.D. technical specification clause 510 premixed with 6.8 kg (six point eight) kilogram bitumen vg-10 (ten) 0.06 (zero point zero six) cubic metre of fine aggregate per 10 Sqm. (Ten square metre) heated in mini hot mix plant and laying manually of mixed material and rolling with power road roller 8-10 (eight to ten capacity) and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	1310.00	335.00	Rupees Three Hundred Thirty Five Only	Per Square metre	438850.00
	Total					438850.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer,
 Jaishingpur Division,
 PWD Jaishingpur

SCHEDULE OF QUANTITY

Name of work :- A/R & M/O Various road in Lambagoan section under HP.PWD Sub Division Jaisinghpur (SH:- Repair of Pot Hole / patch work in various roads (i) Trehla Badhala Dali Road Between Km 2/00 to 4/500 (ii) Bhawarna Jhunga Devi road Between Km 20/500 to 23/00					Estimated cost Rs.		492938.00
					Earnest Money Rs.		9900.00
					Time Limits		Two month
S. N.	Description of Item	Quantity	Rate		Unit	Amount	
			In Figures	In Word			
1	Providing laying spreading and compacting by manual means of stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven decimal point two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications clause 405 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the Government.	24.75	2050.00	Rupees Two Thousand Fifty Only	Per cubic metre	50738.00	
2	Repairing of pot holes and removal of loose material trimming of sides by providing with Bitumen Vg-10(ten) tack coat at the rate of 0.30 kg. (zero point thirty kilograms) per Square metre, Open grades premix carpet of 20mm (twenty millimeter) thickness composed of 13.2mm (thirteen decimal two millimeter) to 5.6mm (five decimal six millimeter) aggregate @ 0.27 cum (zero decimal twenty seven cubic metres) mixed with using penetration grade bitumen VG-10(ten) @ 14.60 kg (fourteen point sixty kilogram) per ten square of road surface required line grade and level and seal coat sealing the voids in a bituminous surface laid to specified level grade and cross fall using type-B as per M.O.R.D. technical specification clause 510 premixed with 6.8 kg (six point eight) kilogram bitumen vg-10 (ten) 0.06 (zero point zero six) cubic metre of fine aggregate per 10 Sqm. (Ten square metre) heated in mini hot mix plant and laying manually of mixed material and rolling with power road roller 8-10 (eight to ten capacity) and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government	1320.00	335.00	Rupees Three Hundred Thirty Five Only	Per Square metre	442200.00	
	Total					492938.00	
	Quoted Rate (in Figures) Percentage	Excess (+)			%		
		Less (-)			%		
	G.Total in Figures						
	G.Total in Words						

Carved

Executive Engineer
Jaisinghpur Division
HPPWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :- A/R & M/O Various road in Lambagoan section under HP.PWD Sub Division Jaisinghpur (SH:- Repair of Pot Hole / patch work in various roads (i) Trehla Badhala Dali Road Between Km 0/00 to 4/500 (ii) Bhawarna Jhunga Devi road Between Km 15/400 to 20/500)					Estimated cost Rs.		480972.00
					Earnest Money Rs.		9700.00
					Time Limits		Two month
S. N.	Description of Item	Quantity	Rate		Unit	Amount	
			In Figures	In Word			
1	Providing laying spreading and compacting by manual means of stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven decimal point two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications clause 405 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the Government.	19.73	2050.00	Rupees Two Thousand Fifty Only	Per cubic metre	40447.00	
2	Reparing of pot holes and removal of loose material trimming of sides by providing with Bitumen Vg-10(ten) tack coat at the rate of 0.30 kg. (zero point thirty kilograms) per Square metre. Open grades premix carpet of 20mm (twenty millimeter) thickness composed of 13.2mm (thirteen decimal two millimeter) to 5.6mm (five decimal six millimeter) aggregate @ 0.27 cum (zero decimal twenty seven cubic metres) mixed with using penetration grade bitumen VG-10(ten) @ 14.60 kg (fourteen point sixty kilogram) per ten square of road surface required line grade and level and seal coat sealing the voids in a bituminous surface laid to specified level grade and cross fall using type-B as per M.O.R.D. technical specification clause 510 premixed with 6.8 kg (six point eight) kilogram bitumen vg-10 (ten) 0.06 (zero point zero six) cubic metre of fine aggregate per 10 Sqm. (Ten square metre) heated in mini hot mix plant and laying manually of mixed material and rolling with power road roller 8-10 (eight to ten capacity) and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government	1315.00	335.00	Rupees Three Hundred Thirty Five Only	Per Square metre	440525.00	
	Total					480972.00	
	Quoted Rate (in Figures) Percentage	Excess (+)			%		
		Less (-)			%		
	G.Total in Figures						
	G.Total in Words						

Chandra

Executive Engineer
Jaisinghpur Division
HPWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :- A/R & M/O Various road in Jaisinghpur under HP.PWD Sub Division Jaisinghpur (SH:- Repair of Pot Hole / patch work on Tinbar to Lugat road between Km 0/00 to 2/00)				Estimated cost Rs.		160491.00
				Earnest Money Rs.		3300.00
				Time Limits		Two month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing laying spreading and compacting by manual means of stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven decimal point two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required densities as per M.O.R.D. technical specifications clause 405 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the Government.	1.98	2050.00	Rupees Two Thousand Fifty Only	Per cubic metre	4059.00
2	Reparing of pot holes and removal of loose material trimming of sides by providing with Bitumen Vg-10(10) tack coat at the rate of 0.30 kg. (zero point thirty kilograms) per Square metre. Open grades premix carpet of 20mm (twenty millimeter) thickness composed of 13.2mm (thirteen decimal two millimeter) to 5.6mm (five decimal six millimeter) aggregate @ 0.27 cum (zero decimal twenty seven cubic metres) mixed with using penetration grade bitumen VG-10(10) @ 14.60 kg (fourteen point sixty kilogram) per ten square of road surface required line grade and level and seal coat sealing the voids in a bituminous surface laid to specified level grade and cross fall using type-B as per M.O.R.D. technical specification clause 510 premixed with 6.8 kg (six point eight) kilogram bitumen vg-10 (ten) 0.06 (zero point zero six) cubic metre of fine aggregate per 10 Sqm. (Ten square metre) heated in mini hot mix plant and laying manually of mixed material and rolling with power road roller 8-10 (eight to ten capacity) and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government	466.96	335.00	Rupees Three Hundred Thirty Five Only	Per Square metre	156432.00
	Total					160491.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

[Signature]

Executive Engineer
Jaisinghpur Division
HPPWD Jaisinghpur