



Telephone No: 01782-233214

E-mail: eenh-ram-hp@nic.in

No. PW/EE/NH/RMP-CB-Tender /2023-24-
To

10/23


Dated:- 13-12-2023

The Executive Engineer, (IT)
Nigam Vihar Shimla-2.

Subject: - Publication of tender notice


Enclosed, please find herewith copy of tender notice in respect of tenders invited vide this office NIT No. PW/EE/NH/RMP/CB-Tender Notice/ 2023 - 24/10118-22 dated 13-12-2023 for uploading the same on department website for wide publicity.

DA:- Copy of NIT


Executive Engineer,
NH Division HPPWD,
Rampur Bushahr.

Certificate

Certified that the tenders of the works invited vide this office NIT
No. PW/EE/NH/RMP/CB-tender/2023-24- 10123 dated 13-12-2023 is of urgent
nature in exigency of public interest.

 Executive Engineer
NH Division HPPWD,
Rampur Bushahr.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

Sealed item rate tender(s) on PWD form No.6 & 8 are hereby invited by the Executive Engineer, NH- Division, HP.PWD, Rampur Distt. Shimla (H.P) on behalf of the Governor of H.P for the following works from the registered contractors/consultants in HP.PWD in appropriate class to reach in this office on **22.12.2023** up to 10.30 A.M. and will be opened on the same day at 11.00A.M. in the presence of Contractors/ consultants or their authorized representative who wish to be present at that time. The application for obtaining the tender form will be received on **21.12.2023** i.e. 11.00 AM to 1.00 PM and the tender form can be had from this office against this cash payment (Non- refundable) on the same day from 2.00P.M. to 5.00 P.M. No application shall be entertained without **earnest money** or through FAX.

Earnest money shall be in shape of NSC/FDR duly pledged in favour of Executive Engineer NH-Division HP.PWD Rampur Bushahr Distt. Shimla H.P. Ambiguous /Telegraphically/conditional tenders or tender through FAX shall not be entertained/ considered in any case.

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Time	Form No.	Cost of form
1	R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.57/870 to 57/880)	463811.00	9300.00	Two Months	6 & 8	350/-
2.	R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.66/240 to 66/247)	322104.00	6500.00	Two Months	6 & 8	350/-
3.	R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.66/247 to 66/254)	321972.00	6500.00	Two Months	6 & 8	350/-
4.	R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC B/wall at RD.70/868 to 70/881)	430315.00	8700.00	Two Months	6 & 8	350/-
5	R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC B/wall at RD.70/881 to 70/894)	430634.00	8700.00	Two Months	6 & 8	350/-
6	R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC B/wall at RD.70/894 to 70/907)	428487.00	8600.00	Two Months	6 & 8	350/-
7	R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.77/502 to 77/510)	459839.00	9200.00	Two Months	6 & 8	350/-
8	R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.77/510 to 77/518)	459858.00	9200.00	Two Months	6 & 8	350/-
9	R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.77/518 to 77/526)	459448.00	9200.00	Two Months	6 & 8	350/-
10	R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.78/419 to 78/425)	418318.00	8400.00	Two Months	6 & 8	350/-
11	R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.78/442 to 78/448)	355563.00	7200.00	Two Months	6 & 8	350/-
12.	R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.82/320 to 82/326.50)	455623.00	9200.00	Two Months	6 & 8	350/-
13	R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.82/326.50 to 82/333)	456280.00	9200.00	Two Months	6 & 8	350/-
14	R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.85/345 to 85/351.50)	372197.00	7500.00	Two Months	6 & 8	350/-
15	R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.85/351 to 85/358)	372847.00	7500.00	Two Months	6 & 8	350/-
16	R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.87/400 to 87/410)	460111.00	9300.00	Two Months	6 & 8	350/-

17	R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.89/480 to 89/490)	460645.00	9300.00	Two Months	6 & 8	350/-
18	R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.91/625 to 91/633)	373431.00	7500.00	Two Months	6 & 8	350/-
19	R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.89/490 to 89/496.50)	361161.00	7300.00	Two Months	6 & 8	350/-
20	R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.89/496.50 to 89/503)	361180.00	7300.00	Two Months	6 & 8	350/-
21	R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.93/010 to 93/018) (under FDR)	491700.00	9900.00	Two Months	6 & 8	350/-
22	R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.94/470 to 94/477)	483250.00	9700.00	Two Months	6 & 8	350/-
23	R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.77/663 to 77/672)	499925.00	9700.00	Two Months	6 & 8	350/-
24	R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.65/240 to 65/245)	470005.00	9400.00	Two Months	6 & 8	350/-
25	R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.80/224 to 80/228)	376297.00	7600.00	Two Months	6 & 8	350/-
26	R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.80/228 to 80/233)	470453.00	9500.00	Two Months	6 & 8	350/-
27	R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.80/233 to 80/238)	470631.00	9500.00	Two Months	6 & 8	350/-
28	R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O V-shape drain in PCC at Rd 81/800 to 82/320)	432483.00	8700.00	Two Months	6 & 8	350/-
29	R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O V-shape drain in PCC at Rd 82/380 to 82/960)	432227.00	8700.00	Two Months	6 & 8	350/-
30	R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- removal of slips, debris, muck etc. At Portion 89/380 to 89/530)	264606.00	5300.00	Two Months	6 & 8	350/-
31	A/R & MO on NH-05 KM.236/00 TO 368/00 (SH:- Cont. of PCC R/Wall at RD 298/070 to 298/078)	494950.00	9900.00	One Month	6 & 8	350/-
32	A/R & MO on NH-05 KM 236/00 TO 368/00 (SH:- C/O Wire crate B/wall at RD 302/235 to 302/265)	482174.00	9700.00	15 Days	6 & 8	350/-
33	A/R & MO on NH-05 KM 236/00 TO 368/00 (SH:- C/O Wire crate R/wall over existing wire crate R/wall at km 288/465 to 288/475 & 288/488 to 288/515)	480255.00	9700.00	15 Days	6 & 8	350/-
34	A/R & MO on NH-305 Sainj Luri Jalori banjar Aut Road Km. 0/00 to 97/00) (Sub Head:- Improvement of road geometrics by cutting of narrow reaches at RD 91/695 to 91/770)	408091.00	8200.00	Two months	6 & 8	350/-

SPECIAL CONDITIONS

1. The material shall be arranged by the contractor/ consultants himself.
2. The detail of documents to be attached with the application is given below.
 - i Latest copy of renewal enlistment/empanelment.
 - ii Copy of Pan Card.
 - iii Copy of GST No.

3. The offer of the tender shall be kept open for 90 days
4. Tender received after the specified time/date shall not be opened.
5. Executive Engineer NH-division HP.PWD Rampur Distt. Shimla H.P. reserves the right to reject any or all tender/s without assigning any reasons.
6. If due to any unforeseen reasons the office of the Executive Engineer NH-Division HP.PWD Rampur remain closed on the notified date of sale and receipt of tender, tender will be sold and received/opened the next working day of same specified time.
7. Tenderers may contact the Executive Engineer for any further information they may require during the working day/ office hours.
8. The contractor/ consultants are requested to insert the rate of each in words as well as in figures failing which Executive Engineer reserves the right to reject any or all tenders.
9. The labourcess shall allow/ deduction @ 2% TDS amount of GST (1% CGST and 1% SGST).
10. The labour cess @ 1% will be deducted from the gross amount of the bill
11. All the works are of urgent nature hence the contractor already having two works are not eligible to participate for the tendering.
12. A contractor enlisted in a particular class shall be eligible to tender for his own class and one step below as per Govt. notification No.PBW (B) 22-1/2002 dated 26-05-2015.
13. The Contractor/consultants will have to submit the proof of registration under Employees Provident Funds & Miscellaneous Provision Act.1952 before award of work.
14. Cement should be purchased from H.P. State Civil Supply Corporation
15. GST will be deducted from each bill as per latest instruction of the Government.

No.PW/EE/NH/RMP/CB-Tender Notice/2023-24-
Copy forwarded for information to the:-

1. Engineer-in-Chief, HP.PWD, Shimla
2. Chief Engineer (NH) HP.PWD, Shimla-1
3. Superintending Engineer, NH-Circle, HP.PWD, Shimla
4. All the Assistant Engineer working under this division
5. A/B & D/B in this office.
6. Notice board of this office.

10113-22

Executive Engineer,
NH Division, H.P.PWD,
Rampur Bushahr.

Dated:- 13-12-2023

Executive Engineer,
NH Division, H.P.PWD,
Rampur Bushahr

Schedule of Quantity

Name of work:- R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.57/870 to57/880)


Estimated Cost:- 463811.00

Earnest Money:- 9300.00

Time:- two months

S. No.	Descriptions	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work.. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensates by him at his own cost.	35.00			Per cubic meter.	
2	Providing concrete for plain/reinforced cement concrete in sub structure complete as per drawings and technical specifications. PCC Grade M15 using Batching plant , including all incidental charges. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensates by him at his own cost.	64.68			Per cubic meter.	
3	Providing weep holes in Brick masonry/Plain/ Reinforced concrete abutment, wing wall/ return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V :20H towards drawing face. Complete as per drawing and Technical Specifications including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensates by him at his own cost.	24.00			Per running meter.	


4	Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specification. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	16.00			Per cubic meter.	
Total Rs:-						


 Executive Engineer,
 N.H.Division,HP.PWD,
 Rampur Bsr.

Schedule of Quantity

Name of work:- R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.66/240 to 66/247)			Estimated Cost:-		322104.00	
			Earnest Money:-		6500.00	
			Time:-		two months	
S. No.	Descriptions	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work.. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	28.14			Per cubic meter.	
2	Providing concrete for plain/reinforced cement concrete in sub structure complete as per drawings and technical specifications. PCC Grade M15 using Batching plant , including all incidental charges. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	45.28			Per cubic meter.	
3	Providing weep holes in Brick masonry/Plain/ Reinforced concrete abutment, wing wall/ return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V :20H towards drawing face. Complete as per drawing and Technical Specifications including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	16.80			Per running meter.	


4	Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specification. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	9.59			Per cubic meter.
Total Rs:-					


 Executive Engineer,
 N.H.Division,HP.PWD,
 Rampur Bsr.

Draft Schedule of Quantity

Name of work:- R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.66/247 to 66/254)			Estimated Cost:-		321972.00	
			Earnest Money:-		6500.00	
			Time:-		two months	
S. No.	Descriptions	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work.. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	25.98			Per cubic meter.	
2	Providing concrete for plain/reinforced cement concrete in sub structure complete as per drawings and technical specifications. PCC Grade M15 using Batching plant , including all incidental charges. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	45.28			Per cubic meter.	
3	Providing weep holes in Brick masonry/Plain/ Reinforced concrete abutment, wing wall/ return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V :20H towards drawing face. Complete as per drawing and Technical Specifications including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	16.80			Per running meter.	

4	Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specification. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	10.01			Per cubic meter.
	Total Rs:-				


 Executive Engineer,
 N.H.Division,HP.PWD,
 Rampur Bsr.

Schedule of Quantity


Name of work:- R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC B/wall at RD.70/868 to 70/881)

Estimated Cost:- 430315.00

Earnest Money:- 8700.00

Time:- two months

S. No.	Descriptions	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Excavation for road way in soil by mechanical means i/c cutting and transporting the earth to site of embankment/dumping area with lead upto 1000 mtrs. i/c trimming bottom and side slopes in accordance with requirements of lines, grades and cross section. ntractor which shall have to be duly compansated by him at his own cost.	9.62			Per cubic meter.	
2	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	42.12			Per cubic meter.	
3	Plain/Reinforced Cement Concrete in Open Foundation complete as per Drawing and Technical Specifications. PCC Grade M15 including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	61.49			Per cubic meter.	
4	Providing weep holes in Brick masonry/Plain/ Reinforced concrete abutment, wing wall/ return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V :20H towards drawing foce. Complete as per drawing and Technical Specifications including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	32.50			Per running meter.	
Total Rs:-						



**Executive Engineer,
N.H.Division,HP.PWD,
Rampur Bsr.**

Schedule of Quantity


Name of work:- R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC B/wall at RD.70/881 to 70/894)

Estimated Cost:- 430634.00

Earnest Money:- 8700.00


Time:- two months

S. No.	Descriptions	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Excavation for road way in soil by mechanical means i/c cutting and transporting the earth to site of embankment/dumping area with lead upto 1000 mtrs. i/c trimming bottom and side slopes in accordance with requirements of lines, grades and cross section. ntractor which shall have to be duly compansated by him at his own cost.	8.71			Per cubic meter.	
2	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	44.33			Per cubic meter.	
3	Plain/Reinforced Cement Concrete in Open Foundation complete as per Drawing and Technical Specifications. PCC Grade M15 including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	61.49			Per cubic meter.	
4	Providing weep holes in Brick masonry/Plain/ Reinforced concrete abutment, wing wall/ return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V :20H towards drawing foce. Complete as per drawing and Technical Specifications including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	32.50			Per running meter.	
Total Rs:-						


 Executive Engineer,
 N.H.Division, HP.PWD,
 Rampur Bsr.

Schedule of Quantity


Name of work:- R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC B/wall at RD.70/894 to 70/907)			Estimated Cost:-		428487.00	
			Earnest Money:-		8600.00	
			Time:-		two months	
S. No.	Descriptions	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Excavation for road way in soil by mechanical means i/c cutting and transporting the earth to site of embankment/dumping area with lead upto 1000 mtrs. i/c trimming bottom and side slopes in accordance with requirements of lines, grades and cross section.ntractor which shall have to be duly compansated by him at his own cost.	14.69			Per cubic meter.	
2	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	29.64			Per cubic meter.	
3	Plain/Reinforced Cement Concrete in Open Foundation complete as per Drawing and Technical Specifications. PCC Grade M15 including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	61.49			Per cubic meter.	
4	Providing weep holes in Brick masonry/Plain/ Reinforced concrete abutment, wing wall/ return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V :20H towards drawing face. Complete as per drawing and Technical Specifications including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	32.50			Per running meter.	
Total Rs:-						


 Executive Engineer,
 N.H.Division, HP.PWD,
 Rampur Bsr.

Schedule of Quantity

Name of work:- R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.77/502 to 77/510)			Estimated Cost:- 459839.00			
			Earnest Money:- 9200.00			
			Time:- two months			
S. No.	Descriptions	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work.. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensates by him at his own cost.	39.44			Per cubic meter.	
2	Providing concrete for plain/reinforced cement concrete in sub structure complete as per drawings and technical specifications. PCC Grade M15 using Batching plant , including all incidental charges. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensates by him at his own cost.	64.66			Per cubic meter.	
3	Providing weep holes in Brick masonry/Plain/ Reinforced concrete abutment, wing wall/ return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V :20H towards drawing face. Complete as per drawing and Technical Specifications including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensates by him at his own cost.	19.20			Per running meter.	


4	Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specification. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	12.64			Per cubic meter.
	Total Rs:-				


 Executive Engineer,
 N.H.Division,HP.PWD,
 Rampur Bsr.

Schedule of Quantity

Name of work:- R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.77/510 to 77/518)			Estimated Cost:-		459858.00	
			Earnest Money:-		9200.00	
			Time:-		two months	
S. No.	Descriptions	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work.. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	40.16			Per cubic meter.	
2	Providing concrete for plain/reinforced cement concrete in sub structure complete as per drawings and technical specifications. PCC Grade M15 using Batching plant , including all incidental charges. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	64.66			Per cubic meter.	
3	Providing weep holes in Brick masonry/Plain/ Reinforced concrete abutment, wing wall/ return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V :20H towards drawing face. Complete as per drawing and Technical Specifications including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	19.20			Per running meter.	


4	Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specification. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	12.48			Per cubic meter.
	Total Rs:-				


 Executive Engineer,
 N.H.Division,HP.PWD,
 Rampur Bsr.

Schedule of Quantity

Name of work:- R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.77/518 to 77/526)			Estimated Cost:- 459448.00			
			Earnest Money:- 9200.00			
			Time:- two months			
S. No.	Descriptions	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work.. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	41.12			Per cubic meter.	
2	Providing concrete for plain/reinforced cement concrete in sub structure complete as per drawings and technical specifications. PCC Grade M15 using Batching plant , including all incidental charges. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	64.66			Per cubic meter.	
3	Providing weep holes in Brick masonry/Plain/ Reinforced concrete abutment, wing wall/ return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V :20H towards drawing face. Complete as per drawing and Technical Specifications including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	19.20			Per running meter.	


4	Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specification. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	11.92			Per cubic meter.	
	Total Rs:-					


 Executive Engineer,
 N.H.Division,HP.PWD,
 Rampur Bsr.

Schedule of Quantity

Name of work:- R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.78/419 to 78/425)			Estimated Cost:-		418318.00	
			Earnest Money:-		8400.00	
			Time:-		two months	
S. No.	Descriptions	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work.. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	41.10			Per cubic meter.	
2	Providing concrete for plain/reinforced cement concrete in sub structure complete as per drawings and technical specifications. PCC Grade M15 using Batching plant , including all incidental charges. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	59.27			Per cubic meter.	
3	Providing weep holes in Brick masonry/Plain/ Reinforced concrete abutment, wing wall/ return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V :20H towards drawing face. Complete as per drawing and Technical Specifications including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	17.40			Per running meter.	


4	Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specification. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	9.60			Per cubic meter.
Total Rs:-					


 Executive Engineer,
 N.H.Division,HP.PWD,
 Rampur Bsr.

Schedule of Quantity

Name of work:- R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.78/442 to 78/448.20)			Estimated Cost:-		355563.00	
			Earnest Money:-		7200.00	
			Time:-		two months	
S. No.	Descriptions	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work.. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	29.95			Per cubic meter.	
2	Providing concrete for plain/reinforced cement concrete in sub structure complete as per drawings and technical specifications. PCC Grade M15 using Batching plant , including all incidental charges. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	50.11			Per cubic meter.	
3	Providing weep holes in Brick masonry/Plain/ Reinforced concrete abutment, wing wall/ return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V :20H towards drawing face. Complete as per drawing and Technical Specifications including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	14.88			Per running meter.	


4	Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specification. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	9.30			Per cubic meter.
Total Rs:-					


 Executive Engineer,
 N.H.Division,HP.PWD,
 Rampur Bsr.

Schedule of Quantity

Name of work:- R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.82/320 to 82/326.50)			Estimated Cost:-		455623.00	
			Earnest Money:-		9200.00	
			Time:-		two months	
S. No.	Descriptions	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work.. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensates by him at his own cost.	35.30			Per cubic meter.	
2	Providing concrete for plain/reinforced cement concrete in sub structure complete as per drawings and technical specifications. PCC Grade M15 using Batching plant , including all incidental charges. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensates by him at his own cost.	64.21			Per cubic meter.	
3	Providing weep holes in Brick masonry/Plain/ Reinforced concrete abutment, wing wall/ return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V :20H towards drawing face. Complete as per drawing and Technical Specifications including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensates by him at his own cost.	18.85			Per running meter.	

4	Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specification. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	12.74			Per cubic meter.
	Total Rs:-				


 Executive Engineer,
 N.H.Division,HP.PWD,
 Rampur Bsr.

Schedule of Quantity

Name of work:- R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.82/326.50 to 82/333)


Estimated Cost:- 456280.00

Earnest Money:- 9200.00

Time:- two months

S. No.	Descriptions	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work.. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensates by him at his own cost.	36.92			Per cubic meter.	
2	Providing concrete for plain/reinforced cement concrete in sub structure complete as per drawings and technical specifications. PCC Grade M15 using Batching plant , including all incidental charges. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensates by him at his own cost.	64.21			Per cubic meter.	
3	Providing weep holes in Brick masonry/Plain/ Reinforced concrete abutment, wing wall/ return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V :20H towards drawing face. Complete as per drawing and Technical Specifications including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensates by him at his own cost.	18.85			Per running meter.	


4	Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specification. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	12.87			Per cubic meter.
Total Rs:-					


 Executive Engineer,
 N.H.Division, HP.PWD,
 Rampur Bsr.

Schedule of Quantity

Name of work:- R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.85/345 to 85/351.50)			Estimated Cost:- 372197.00			
			Earnest Money:- 7500.00			
			Time:- two months			
S. No.	Descriptions	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work.. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensates by him at his own cost.	33.54			Per cubic meter.	
2	Providing concrete for plain/reinforced cement concrete in sub structure complete as per drawings and technical specifications. PCC Grade M15 using Batching plant , including all incidental charges. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensates by him at his own cost.	52.54			Per cubic meter.	
3	Providing weep holes in Brick masonry/Plain/ Reinforced concrete abutment, wing wall/ return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V :20H towards drawing face. Complete as per drawing and Technical Specifications including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensates by him at his own cost.	15.60			Per running meter.	


4	Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specification. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	8.78			Per cubic meter.
	Total Rs:-				


 Executive Engineer,
 N.H.Division,HP.PWD,
 Rampur Bsr.

Schedule of Quantity

Name of work:- R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.85/351.50 to 85/358)			Estimated Cost:-		372847.00	
			Earnest Money:-		7500.00	
			Time:-		two months	
			Rate		Unit	Amount
S. No.	Descriptions	Qty.	In figure	In words.		
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work.. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensasated by him at his own cost.	36.47			Per cubic meter.	
2	Providing concrete for plain/reinforced cement concrete in sub structure complete as per drawings and technical specifications. PCC Grade M15 using Batching plant , including all incidental charges. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensasated by him at his own cost.	52.53			Per cubic meter.	
3	Providing weep holes in Brick masonry/Plain/ Reinforced concrete abutment, wing wall/ return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V :20H towards drawing face. Complete as per drawing and Technical Specifications including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensasated by him at his own cost.	15.60			Per running meter.	


4	Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specification. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	8.58			Per cubic meter.	
	Total Rs:-					


 Executive Engineer,
 N.H.Division,HP.PWD,
 Rampur Bsr.

Schedule of Quantity

Name of work:- R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.87/400 to 87/410)			Estimated Cost:- 460111.00			
			Earnest Money:- 9300.00			
			Time:- two months			
S. No.	Descriptions	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work.. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	40.20			Per cubic meter.	
2	Providing concrete for plain/reinforced cement concrete in sub structure complete as per drawings and technical specifications. PCC Grade M15 using Batching plant , including all incidental charges. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	64.68			Per cubic meter.	
3	Providing weep holes in Brick masonry/Plain/ Reinforced concrete abutment, wing wall/ return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V :20H towards drawing face. Complete as per drawing and Technical Specifications including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	24.00			Per running meter.	


4	Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specification. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	13.70			Per cubic meter.
	Total Rs:-				


 Executive Engineer,
 N.H.Division,HP.PWD,
 Rampur Bsr.

Schedule of Quantity

Name of work:- R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.89/480 to 89/490)			Estimated Cost:- 460645.00			
			Earnest Money:- 9300.00			
			Time:- two months			
S. No.	Descriptions	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work.. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	36.60			Per cubic meter.	
2	Providing concrete for plain/reinforced cement concrete in sub structure complete as per drawings and technical specifications. PCC Grade M15 using Batching plant , including all incidental charges. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	64.68			Per cubic meter.	
3	Providing weep holes in Brick masonry/Plain/ Reinforced concrete abutment, wing wall/ return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V :20H towards drawing face. Complete as per drawing and Technical Specifications including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	24.00			Per running meter.	


4	Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specification. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	15.00			Per cubic meter.
Total Rs:-					


 Executive Engineer,
 N.H.Division,HP.PWD,
 Rampur Bsr.

Schedule of Quantity

Name of work:- R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.91/625 to 91/633)			Estimated Cost:-		373431.00	
			Earnest Money:-		7500.00	
			Time:-		two months	
S. No.	Descriptions	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work.. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensates by him at his own cost.	27.52			Per cubic meter.	
2	Providing concrete for plain/reinforced cement concrete in sub structure complete as per drawings and technical specifications. PCC Grade M15 using Batching plant , including all incidental charges. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensates by him at his own cost.	51.74			Per cubic meter.	
3	Providing weep holes in Brick masonry/Plain/ Reinforced concrete abutment, wing wall/ return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V :20H towards drawing face. Complete as per drawing and Technical Specifications including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensates by him at his own cost.	19.20			Per running meter.	

4	Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specification. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	13.04			Per cubic meter.
	Total Rs:-				


 Executive Engineer,
 N.H.Division,HP.PWD,
 Rampur Bsr.

Schedule of Quantity

Name of work:- R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.89/490 to 89/496.50)


Estimated Cost:- 361161.00

Earnest Money:- 7300.00

Time:- two months

S. No.	Descriptions	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work.. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensatsed by him at his own cost.	32.05			Per cubic meter.	
2	Providing concrete for plain/reinforced cement concrete in sub structure complete as per drawings and technical specifications. PCC Grade M15 using Batching plant , including all incidental charges. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensatsed by him at his own cost.	52.54			Per cubic meter.	
3	Providing weep holes in Brick masonry/Plain/ Reinforced concrete abutment, wing wall/ return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V :20H towards drawing face. Complete as per drawing and Technical Specifications including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensatsed by him at his own cost.	15.60			Per running meter.	


4	Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specification. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	10.27			Per cubic meter.
	Total Rs:-				


 Executive Engineer,
 N.H.Division,HP.PWD,
 Rampur Bsr.

Schedule of Quantity

Name of work:- R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.89/496.50 to 89/503)			Estimated Cost:-		361180.00	
			Earnest Money:-		7300.00	
			Time:-		two months	
S. No.	Descriptions	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work.. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	32.63			Per cubic meter.	
2	Providing concrete for plain/reinforced cement concrete in sub structure complete as per drawings and technical specifications. PCC Grade M15 using Batching plant , including all incidental charges. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	52.54			Per cubic meter.	
3	Providing weep holes in Brick masonry/Plain/ Reinforced concrete abutment, wing wall/ return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V :20H towards drawing face. Complete as per drawing and Technical Specifications including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	15.60			Per running meter.	


4	Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specification. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	10.14			Per cubic meter.
Total Rs:-					


 Executive Engineer,
 N.H.Division,HP.PWD,
 Rampur Bsr.

Schedule of Quantity

Name of work:- R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.93/010 to 93/018) (under FDR)			Estimated Cost:-		491700.00	
			Earnest Money:-		9900.00	
			Time:-		two months	
S. No.	Descriptions	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work.. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	36.56			Per cubic meter.	
2	Providing concrete for plain/reinforced cement concrete in sub structure complete as per drawings and technical specifications. PCC Grade M15 using Batching plant , including all incidental charges. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	64.66			Per cubic meter.	
3	Providing weep holes in Brick masonry/Plain/ Reinforced concrete abutment, wing wall/ return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V :20H towards drawing face. Complete as per drawing and Technical Specifications including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	19.20			Per running meter.	


4	Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specification. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	12.96			Per cubic meter.
	Total Rs:-				


 Executive Engineer,
 N.H.Division,HP.PWD,
 Rampur Bsr.

Schedule of Quantity

Name of work:- R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.94/470 to 94/477)			Estimated Cost:-		483250.00	
			Earnest Money:-		9700.00	
			Time:-		two months	
S. No.	Descriptions	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work.. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	48.30			Per cubic meter.	
2	Providing concrete for plain/reinforced cement concrete in sub structure complete as per drawings and technical specifications. PCC Grade M15 using Batching plant , including all incidental charges. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	69.15			Per cubic meter.	
3	Providing weep holes in Brick masonry/Plain/ Reinforced concrete abutment, wing wall/ return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V :20H towards drawing face. Complete as per drawing and Technical Specifications including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	20.30			Per running meter.	


4	Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specification. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	7.35			Per cubic meter.
	Total Rs:-				


 Executive Engineer,
 N.H.Division,HP.PWD,
 Rampur Bsr.

Schedule of Quantity

Name of work:- R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.77/663 to 77/672)			Estimated Cost:- 499925.00			
			Earnest Money:- 9700.00			
			Time:- two months			
S. No.	Descriptions	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work.. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	43.83			Per cubic meter.	
2	Providing concrete for plain/reinforced cement concrete in sub structure complete as per drawings and technical specifications. PCC Grade M15 using Batching plant , including all incidental charges. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	72.75			Per cubic meter.	
3	Providing weep holes in Brick masonry/Plain/ Reinforced concrete abutment, wing wall/ return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V :20H towards drawing face. Complete as per drawing and Technical Specifications including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	21.60			Per running meter.	

4	Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specification. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	14.22			Per cubic meter.
Total Rs:-					


 Executive Engineer,
 N.H.Division,HP.PWD,
 Rampur Bsr.

Schedule of Quantity

Name of work:- R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.65/240 to 65/245)


Estimated Cost:- 470005.00

Earnest Money:- 9400.00

Time:- two months

S. No.	Descriptions	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work.. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	40.80			Per cubic meter.	
2	Providing concrete for plain/reinforced cement concrete in sub structure complete as per drawings and technical specifications. PCC Grade M15 using Batching plant , including all incidental charges. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	66.75			Per cubic meter.	
3	Providing weep holes in Brick masonry/Plain/ Reinforced concrete abutment, wing wall/ return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V :20H towards drawing face. Complete as per drawing and Technical Specifications including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	15.00			Per running meter.	


4	Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specification. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	10.10			Per cubic meter.
	Total Rs:-				


 Executive Engineer,
 N.H.Division,HP.PWD,
 Rampur Bsr.

Schedule of Quantity

Name of work:- R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.80/224 to 80/228)			Estimated Cost:-		376297.00	
			Earnest Money:-		7600.00	
			Time:-		two months	
S. No.	Descriptions	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work.. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	33.60			Per cubic meter.	
2	Providing concrete for plain/reinforced cement concrete in sub structure complete as per drawings and technical specifications. PCC Grade M15 using Batching plant , including all incidental charges. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	53.40			Per cubic meter.	
3	Providing weep holes in Brick masonry/Plain/ Reinforced concrete abutment, wing wall/ return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V :20H towards drawing face. Complete as per drawing and Technical Specifications including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	12.00			Per running meter.	


4	Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specification. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	8.08			Per cubic meter.
Total Rs:-					


 Executive Engineer,
 N.H.Division,HP.PWD,
 Rampur Bsr.

Schedule of Quantity

Name of work:- R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.80/228 to 80/233)			Estimated Cost:-		470453.00	
			Earnest Money:-		9500.00	
			Time:-		two months	
S. No.	Descriptions	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work.. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	43.50			Per cubic meter.	
2	Providing concrete for plain/reinforced cement concrete in sub structure complete as per drawings and technical specifications. PCC Grade M15 using Batching plant , including all incidental charges. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	66.75			Per cubic meter.	
3	Providing weep holes in Brick masonry/Plain/ Reinforced concrete abutment, wing wall/ return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V :20H towards drawing face. Complete as per drawing and Technical Specifications including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	15.00			Per running meter.	


4	Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specification. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	9.80			Per cubic meter.
	Total Rs:-				


 Executive Engineer,
 N.H.Division,HP.PWD,
 Rampur Bsr.

Schedule of Quantity

Name of work:- R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O PCC R/wall at RD.80/233 to 80/238)			Estimated Cost:-		470631.00	
			Earnest Money:-		9500.00	
			Time:-		two months	
S. No.	Descriptions	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work.. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensatsed by him at his own cost.	42.85			Per cubic meter.	
2	Providing concrete for plain/reinforced cement concrete in sub structure complete as per drawings and technical specifications. PCC Grade M15 using Batching plant , including all incidental charges. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensatsed by him at his own cost.	66.75			Per cubic meter.	
3	Providing weep holes in Brick masonry/Plain/ Reinforced concrete abutment, wing wall/ return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V :20H towards drawing face. Complete as per drawing and Technical Specifications including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensatsed by him at his own cost.	15.00			Per running meter.	

4	Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specification. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	10.10			Per cubic meter.
Total Rs:-					


 Executive Engineer,
 N.H.Division,HP.PWD,
 Rampur Bsr.

Schedule of Quantity


Name of work:- R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O V-shape drain in PCC at Rd 81/800 to 82/320)

Estimated Cost:- 432483.00

Earnest Money:- 8700.00

Time:- two months

S. No.	Descriptions	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work.. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	96.54			Per cubic meter.	
2	Providing concrete for plain/reinforced cement concrete in sub structure complete as per drawings and technical specifications. PCC Grade M15 using Batching plant , including all incidental charges. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	60.90			Per cubic meter.	
Total Rs:-						


 Executive Engineer,
 N.H.Division, HP.PWD,
 Rampur Bsr.

Schedule of Quantity


Name of work:- R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- C/O V-shape drain in PCC at Rd 82/380 to 82/960)

Estimated Cost:- 432227.00

Earnest Money:- 8700.00

Time:- two months

S. No.	Descriptions	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work.. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensates by him at his own cost.	95.70			Per cubic meter.	
2	Providing concrete for plain/reinforced cement concrete in sub structure complete as per drawings and technical specifications. PCC Grade M15 using Batching plant , including all incidental charges. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensates by him at his own cost.	60.90			Per cubic meter.	
Total Rs:-						


 Executive Engineer,
 N.H.Division,HP.PWD,
 Rampur Bsr.

Schedule of Quantity


Name of work:- R/R damages on Sainj Luri Jalori banjar Aut Road (NH 305) Km. 0/00 to 97/00) (Sub Head:- removal of slips, debris, muck etc. At Portion 89/380 to 89/530)

Estimated Cost:- 264606.00

Earnest Money:- 5300.00

Time:- two months

S. No.	Descriptions	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Clearance of land slides in soil and debries, muck etc from hill side by a dozer with in lift upto 1.5 mtrs. And lead upto 1000 mtrs as per technical specification.	1743.70			Per cubic meter.	
Total Rs:-						


 Executive Engineer,
 N.H.Division,HP.PWD,
 Rampur Bsr.

SCHEDULE OF QUANTITY


Name of work:- A/R & M/O on NH -05 Km 236/000 to 368/000 (SH:- C/O PCC R/wall at RD 298/070 tom 298/078)

Estimated cost:- 494950.00
Earnest money:- 9900.00

Time:- One month

Sr No.	Sub head/item of work	Quantity	Rate In Figure	Rate In words.	Unit	Amount
1		3	4	5	6	7
1	Earth work in excavation for structure in all depth as per drawing and technical specification Clause 304 of section 300 of MORTH specification in all kind of soils i.e pick work, Jumper work, blasting work in soft and hard rock and intermediate classification of soil including chiselling and wedging out of rock with in all depths and heights ,stacking the useful materials and disposal of unserviceable materials upto the indentified dumping site as per the direction of the Engineer-in-Charges with in all leads andlifts. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	24.00			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated cement concrete M-15 containing minimum contents of cement is 5.50 bags per cum in all heights and depth as per drawing and technical specifications in foundation of retaining walls complete as per MORTH specification No.1500,1700 & 2100 including carriage of all materials within all leads and lifts with all modes of transportation and equipment and cost of formwork required to complete the work to the satisfaction of the Engineer-in-Charge.	71.36			Per cubic metre	
3	Providing and laying 100mm diameter (Hundred milimeter) P. V.C. pipe in weep holes in R/wall in requisite slopes for drainages as per the direction of the Engineer-in-charges including carriage of materials in all leads and lifts with mechanical means.	23.20			Per running metre	

4	Providing and laying filter media with granular stone crushed aggregate to a thickness of not less than 600 mm(Six hundred milimetre) with smaller size towards the soil and bigger size towards the wall and provided over the entire surface behind wall in all heights and depths compacted to a firm condition complete satisfying the reqirment laid down in clause 710.1.4 of IRC:78 and 2200 MORTH Specifications (Latest revision) including carriage of materials by mechanical transport in all leads and lifts and as per direction of the Engineer-in-Charge.	13.52			Per cubic metre	
					Total:-	


 Executive Engineer,
 NH Division HPPWD,
 Rampur Bsr.

SCHEDULE OF QUANTITY


Name of work:- A/R & M/O on NH-05 Km 236/000 to 368/000 ((SH:- C/O wire crate B/wall at Km 302/235 to 302/265)

Estimated cost:- 482174.00

Earnest money:- 9700.00

Time:- 15 Days

Sr No.	Sub head/item of work	Quantity	Rate In Figure	Rate In words.	Unit	Amount
1	2	3	4	5	6	7
1	Providing and laying of boulder apron laid in wire crates with 4mm dia G.I. wire conforming to IS:280 and IS: 4826 in 100mmx100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25Kg each as per drawing and technical specifications Clause 1301 including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	172.80			Per cubic metre	
2	Providing and laying back filling behind Retaining walls satisfying the requirement as per drawing and technical specifications in all heights and depths compacted to a firm condition complete including carriage of materials by mechanical transport in all leads and lifts and as per direction of the Engineer-in-Charge.	4.50			Per cubic metre	
					Total:-	


Executive Engineer,
NH Division HPPWD,
Rampur Bsr.

SCHEDULE OF QUANTITY


Name of work:- A/R & M/O on NH-05 Km 236/000 to 368/000 ((SH:- C/O wire crate R/wall over existing wire crate R/wall at Km 288/465 to 288/475 & 288/488 to 288/515)

Estimated cost:- 480255.00

Earnest money:- 9700.00


Time:- 15 Days

Sr No.	Sub head/item of work	Quantity	Rate In Figure	Rate In words.	Unit	Amount
1	2	3	4	5	6	7
1	Providing and laying of boulder apron laid in wire crates with 4mm dia G.I. wire conforming to IS:280 and IS: 4826 in 100mmx100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25Kg each as per drawing and technical specifications Clause 1301 including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	165.34			Per cubic metre	
2	Providing and laying back filling behind Retaining walls satisfying the requirement as per drawing and technical specifications in all heights and depths compacted to a firm condition complete including carriage of materials by mechanical transport in all leads and lifts and as per direction of the Engineer-in-Charge.	10.88			Per cubic metre	
					Total:-	


Executive Engineer,
NH Division HPPWD,
Rampur Bsr.

SCHEDULE OF QUANTITY

NAME OF WORK:- A/R & M/O NH-305 Sainj Luri Aut Road Km. 0/00 to 97/00 (SH:- Improvement of road geometrices by cutting of nerrow reaches at Rd.91/695 to 91/770)				Estimated cost:- 408091.00 Earnest money:- 8200.00 Time:- Two month		
Sr, No.	Sub head/item of work	Quantity	Rate In Figure	Rate In words.	Unit	Amount
1	2	3	4	5	6	7
1	Excavation in soil in hilly area by mechnical means in all heights and depths, in all kinds of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiselling and wedging out of rock (where blasting is prohibited) including cutting and trimming of side slopes and disposing of excavated earth lift upto all heights and all leads as directed by the Engineer-in-Charge, in conformity with the requirement of technical specification of rural roads clause 1603.1. Minimum quantity of useful material such as stones, shingles, aggregates and slates etc. i.e 217.95 cubic metre, shall be sorted out and stacked along the road side properly, otherwise recovery @ Rs. 300/- per cubic metre shall be effected from the bills of the contractor. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	1228.34			Per Cubic metre	
					Total:-	


 Executive Engineer,
 NH Division HPPWD,
 Rampur Bsr.