

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

Sealed percentage basis tenders are hereby invited by Executive Engineer, NH Division, HP.PWD, Solan on behalf of Governor of Himachal Pradesh for the following works from the approved registered Contractors of appropriate class (D) enlisted with Himachal Pradesh Public Works Department, whose registration stood renewed as per revised instructions and also registered dealers under the Himachal Pradesh, General Sales Tax Act, 1968. The important dates of tender are as under:-

	Tender Schedule	Date	Time
1.	The last date for receipt of application for tender Form.	27/12/2023	4.00 PM
2.	The last date for issue of tender Form	28/12/2023	4.00 PM
3.	The last date for receipt of tender.	29/12/2023	10:30 AM
4.	The date of opening of tender.	29/12/2023	11:00 AM

The tender forms can be obtained against payment of Rs.350/- (Non refundable) and contractor will be required to produce documents of registration in appropriate class, list of completed works and GST registration certificate. The tenders shall be opened in presence of contractor or their authorized representative.

The earnest money in shape of National Saving Certificate/Time deposit account of nationalized saving or Saving Bank account in any of the post offices and F.D.R. of Nationalized Bank duly pledged in favour of the Executive Engineer, NH Division, HP.PWD, Solan must accompany with the tender offer. The exemption from depositing the earnest money with each tender earlier granted has been withdrawn under Govt. Notification No. PWE (B&R)(B)14(18) / 98-11 dated 4.11.2003 and accordingly the tender received without Earnest Money shall be rejected without assigning any reasons thereto and shall not be entertained.

The tenders will be issued only to them who qualify the criteria after the scrutiny of application Form. The tenders not accompanying the Earnest money shall be rejected at the time of opening. The contractor shall also indicate the detail of Earnest money in the tender document. The request on prescribed application should accompany the registration of appropriate class, GST registration No., work done certificate. The tenders shall be opened on schedule date and time in presence of contractor or in the presence of the authorized representative.

The validity of tenders has been given in the tender document. If any contractor/firm withdraw the offer within validity period then their earnest money shall be forfeited and shall finally be at the disposal of State Govt. The contractors are advised to write the percentage both in figures and in words, failing which the tender shall be rejected.

Conditional and incomplete tenders shall out rightly be rejected.

Application for obtaining the tender form must accompany the latest renewal of enlistment and proof of GST No/NOC from Excise and Taxation Department regarding Tax clearance. The offer shall be kept open for 15 days.

If due to any unforeseen reasons the office of the Executive Engineer, NH Division, HP.PWD, Solan remain closed on the notified date of sale and receipt of tender, the tender will be sold and received/opened on next working day at same specified time.

The Executive Engineer reserves the right to accept or reject the tender without assigning any reason.

Description of JOB:-


Sr. No.	Name of work	Estimated Cost (in Rs)	Earnest Money	Time
1	RR Damages (Kaithlighat to Dhalli Section) of NH 05 from km 131/00 to 145/100 & 0/00 to 13/00 (SH:- C/O R/Wall at Rd 11/295 to 11/300 on Shimla Bye Pass (Against NHAI Deposit)	Rs 4,75,716/-	Rs 10,000/-	Two Months
2	RR Damages (Kaithlighat to Dhalli Section) of NH 05 from km 131/00 to 145/100 & 0/00 to 13/00 (SH:- C/O R/Wall at Rd 11/270 to 11/275 on Shimla Bye Pass (Against NHAI Deposit)	Rs 4,87,162/-	Rs 10,000/-	Two Months

Term and Conditions:-

The contractor will have to produce following documents and attach attested copies of the same at the time of submitting application for issue of tender Form.

- Enlistment/renewal in appropriate class in HP.PWD.
- PAN Card issued by the Income Tax Department.
- Proof of valid GST Registration.
- Statement showing the ongoing works in HP.PWD.
- E.P.F registration.

Certified that the above work is of emergent nature in exigency of Public Interest.


Executive Engineer,
Solan NH Division,
HP.PWD., Solan.


Dated:- 21-12-23

No. NHD/CB/TA/NIT/2023-

5997-6022

Copy forwarded to the following for information and necessary action:-

1. The Engineer-in-Chief, HP.PWD, Shimla.
2. The Chief Engineer, NH, HP.PWD, Shimla.
3. The Superintending Engineer, NH Circle, HPPWD Shimla
4. The Deputy Commissioner, Solan, Distt Solan.
5. All the Assistant Engineers under this Division.
6. Various registered contractors working under this Division
7. Notice Board.
8. The Executive Engineer, IT Cell in the o/o Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.


Executive Engineer,
Solan NH Division,
HP.PWD., Solan.

SCHEDULE OF QUANTITY

Estimated Cost 475716 /only
 Earnest Money Rs. 10000 /only
 Time :- 2 Month

NAME OF WORK :- R.R. damages (Kaithlighat to Dhalli section) of NH-05 from Km 131/000 to Km 145/100, Km 0/00 to 13/00 (SH:- C/O R/ wall at Rd 11/295 to 11/300 on Shimla Bye pass)(Against NHAI Deposit)

Sr.No.	Description of items	Quantity	Rate in Figures	Rate in Words	Unit	Amount	Overall percentage to be quoted by the bidder above /below the estimated cost inclusive of GST) i.e. nearest two decimal places/amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sam on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All Kinds of Soil e.g Ordinary rock as per CPWD specification/SOR 2020 including carriage of materials within all leads and lifts by all means including mechanical transport and as per direction of the Engineer-in-Charge.	15.33 cum	182.25	Rs. one hundred eighty two and paise twenty five only	Per cum	2794	
2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, including the cost of centering, shuttering and finishing : 1:2:4 (1 Cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) including carriage of materials within all leads and lifts by all means including mechanical transport and as per direction of the Engineer-in-Charge.	60.46 CUM	7557.05	Rupees Seven thousand Hundred Fifty Seven and Paise five only	Per cum	456899	

3	Providing and laying of filter media with granular materials/stone satisfying the requirements laid down in clause 2504.2.2 of MoRT&H specifications to a thickness of not less than 600mm with smaller size towards the soil and bigger size towards the wall and provided over the entire surface behind abutment, wing wall and return wall to the full height compacted to a firm condition complete as per drawing and technical specification including carriage of materials within all leads and lifts by all means including mechanical transport and as per direction of the Engineer-in-Charge.	4.05	CUM	1979.6	Rupees Hundred ninety paise Sixty only	Per cum	8017	
4	Providing weep holes in brick masonry /plain/reinforced concrete abutment, wing wall/return wall with 100mm dia AC pipe, extending through the full width of the structure with slope of 1V:20H towards drawings face complete as per drawing and Technical Specifications including carriage of materials within all leads and lifts by all means including mechanical transport and as per direction of the Engineer-in-Charge.	42.00	RMT	190.60	Rupees One Hundred ninety paise Sixty only	Per Rmt	8005	
				Estimated Cost		475716		


 Executive Engineer,
 NH Division, HPPWD.,
 Solan

SCHEDULE OF QUANTITY

Estimated Cost 487162 /only
 Earnest Money Rs. 10000 /only
 Time :- 2 Month

NAME OF WORK :- R.R. damages (Kaithlighat to Dhalli section) of NH-05 from Km 131/000 to Km 145/100, Km 0/00 to 13/00 (SH:- C/O R/ wall at Rd 11/270 to 11/275 on Shimla Bye pass) (Against NHAI Deposit)

Sr.No.	Description of items	Quantity	Rate in Figures	Rate in Words	Unit	Amount	Overall percentage to be quoted by the bidder above /below the
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sam on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All Kinds of Soil e.g Ordinary rock as per CPWD specification/SOR 2020 including carriage of materials within all leads and lifts by all means including mechanical transport and as per direction of the Engineer-in-Charge.	24.37 cum	182.25	Rs. one hundred eighty two and paise twenty five only	Per cum	4441	
2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, including the cost of centering, shuttering and finishing : 1:2:4 (1 Cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) including carriage of materials within all leads and lifts by all means including mechanical transport and as per direction of the Engineer-in-Charge.	60.46 CUM	7557.05	Rupees Seven thousand Hundred Fifty Seven and Paise five only	Per cum	456899	

3	Providing and laying of filter media with ganular materials/stone satisfying the requirements laid down in clause 2504.2.2 of MoRT&H specifications to a thickness of not less than 600mm with smaller size towards the soil and bigger size towards the wall and provided over the entire surface behind abutment, wing wall and return wall to the full height compacted to a firm condition complete as per drawing and technical specification including carriage of materials within all leads and lifts by all means including mechanical transport and as per direction of the Engineer-in-Charge.	9.00	CUM	1979.6	Rupees Hundred ninety paise Sixty only	One Hundred ninety paise Sixty only	Per cum	17816	
4	Providing weep holes in brick masonry /plain/reinforced concrete abutment, wing wall/return wall with 100mm dia AC pipe, extending through the full width of the structure with slope of 1V:20H towards drawings face complete as per drawing and Technical Specifications including carriage of materials within all leads and lifts by all means including mechanical transport and as per direction of the Engineer-in-Charge.	42.00	RMT	190.60	Rupees One Hundred ninety paise Sixty only		Per Rmt	8005	
Estimated Cost									487162


 Executive Engineer,
 NH Division, HPPWD.,
 Solan