



Himachal Pradesh
Public Works Department
NOTICE INVITING TENDER

Sealed tenders on item rates on PWD form 6 & 7 are hereby invited by the Executive Engineer, Tauni Devi Division, and HPPWD Tauni Devi for the following works. The tender shall be received in this office on or before 28.12.2023 up to 11:00 AM and the same shall be opened on the same day at 11:30AM in the presence of the contractor/first. The application for the issue of tender document shall be received on dated 26.12.2023 upto 2:30PM and the tender form will be sold on cash payment (non refundable) on dated 27.12.2023 from 11.30 AM to 4:00 PM

Sr. No.	Name of Work	Estimated Cost (Rs.)	Earnest Money	Time Limit	Cost of form
1	R/R damages on link road from Charian –Di-Dhar Lambran –Di-Dhar via Bouru km 0/00 to 2/00 (SH:- C/o R/wall at RD 1/690 to 1/700)	365097/-	7300/-	Two Months	350.00
2	R/R damages on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road km 15/0 to 30/915 .(MDR-105) (SH:- C/O PCC R/wall at RD 18/100 to 18/112 (LHS of Road) & 18/110 to 18/117 (RHS Of road) (Near primary School Kakkar)	310845/-	6200/-	Two Months	350.00
3	R/R damages on Kakkar to Bakkar Khad via Ghodlamber km 0/00 to 2/200 (SH:- locking of sides of cement concrete pavement from RD 0/100 to 1/00) (B.H.S)	414929/-	8300/-	Two Months	350.00
4	R/R damages on various road under Kakkar Sub-Division (SH:- P/L kilometer stone ,sign boards and rumble strips on various roads under Kakkar-1 and Kakkar –II Section)	197138/-	3900/-	Two Months	350.00
5	R/R damages on link road Kakkar to Bakkar Khad via Ghodlamber km 0/00 to 2/650 (SH:- P/L stone soling from km 1/840 to 2/640)	489600/-	8900/-	Two Months	350.00
6	R/R damages on link road Kakkar to Bakkar Khad via Ghodlamber km 0/00 to 2/650 (SH:- C/O Maintenance of earthen shoulders from km 0/200 to 2/650 on BHS)	282240/-	5600/-	Two Months	350.00
7	C/o link road to village Chamaiania Di Khanauli km 0/00 to 4/00 (SH:- C/O 5/7 mtr.wide formation cutting at RD 1/770 to 1/921) (UNDER OTMNP)	496749/-	10000/-	Two Months	350.00
8	C/O link road to village Chamaiania Di Khanauli km 0/00 to 4/00 (SH:- C/O 5/7 mtr.wide formation cutting at RD 1/921 to 2/070) (UNDER OTMNP)	499833/-	10000/-	Two Months	350.00
9	R/R damages on Hamirpur Sujanpur road km 2/00 to 16/00 (SH:- C/O R/wall at RD 13/345 to 13/353 near house of Sh.Ravi Kumar) Deposit work	184605/-	3700/-	Two Months	350.00
10	R/R damages on Hamirpur Sujanpur road km 16/00 to 24/785 (SH:-C/O R/wall at RD 16/784 to 16/795 along with parapets at RD 16/768 to 16/795)	382697/-	7700/-	Two Months	350.00
11	R/R damages on Matial Tikker road km .0/00 to 2/030 (SH:- C/O R/wall at RD 1/360 to 1/375)	301399/-	6000/-	Two Months	350.00
12	R/R damages on Hamirpur Sujanpur road km 16/00 to 24/785 (SH:-C/O R/wall at RD 16/768 to 16/782)	436505/-	8700/-	Two Months	350.00
13	R/R damages on Hamirpur Sujanpur road km 16/00 to 24/785 (SH:-C/O B/wall at RD 23/967 to 23/975 near approach road to HP:PWD,Rest house Sujanpur)	366749/-	7300/-	Two Months	350.00
14	R/R damages on Banal to Chamiyana via Manghlehar Daddar road km .0/00 to 7/185 (SH:- C/O R/wall at RD 0/020 to 0/040)	328794/-	6600/-	Two Months	350.00
15	R/R damages on Banal to Chamiyana via Manghlehar Daddar road km .0/00 to 7/185 (SH:- C/O R/wall at RD 0/0 to 0/080)	323011/-	6500/-	Two Months	350.00

16	R/R damages on Hamirpur Sujanpur road km 0/00 to 24/785 (SH:-C/O B/wall at RD 23/958 to 23/967 near approach road to HPPWD Rest house Sujanpur)	394220/-	7900/-	Two Months	350.00
17	C/O link road Kalakhar bridge to Baharu Jhatour km 0/00 to 2/00 (C/O cement concrete pavement at RD 0/400 to 0/530) Under OTMNP	389498/-	7800/-	Two Months	350.00
18	C/O Junior Engineer office cum residence at Bharmeli (section Chabutra) HPPWD Sujanpur Distt Hamirpur (Sh:- P/F prepainted sheet windowsun shade ,brick masonry in 2 nd floor cup board and 60mm thick paver block court yard)	495391/-	9900/-	Two Months	350.00
19	R/R damages on Kasiri Duhak Chattruru raod km 0/00 to 8/00 (SH:- C/O R/wall from RD 5/915 to 5/920)	330122/-	6600/-	Two Months	350.00
20	R/R damages on Kasiri Duhak Chattruru raod km 0/00 to 8/00 (SH:- C/O R/wall from RD 5/910 to 5/915)	330122/-	6600/-	Two Months	350.00
21	R/R damages on Pohanj to Andral road km 0/00 to 3/695 (Sh:- C/O wire crate at RD 1/815 to 1/842.50)	492532/-	9900/-	Two Months	350.00
22	R/R damages on Uhal to Bagehra via Jandroo road km 0/0 to 27/00 (Sh:- Imp of curves at RD 20/270 to 20/310)	198881/-	4000/-	Two Months	350.00
23	R/R damages on Uhal to Bagehra via Jandroo road km 0/0 to 27/00 (Sh:- Imp of curves at RD 20/530 to 20/575)	470675/-	9400/-	Two Months	350.00
24	A/R & M/O on various roads under Tauni Devi Sub-Division (SH:- C/O various roads berms & road bed with earth filling in Jandroo section)	388440/-	7800/-	Two Months	350.00
25	R/R damages on Phonj to Andral km 0/0 to 3/695 (Sh:- C/O toe wall for protection brest wall at RD 1/122 to 1/153.75)	441751/-	8800/-	Two Months	350.00
26	R/R damages on Nanot to Bakkar Khad via Jamli road in km 0/00 to 4/00 (SH:- C/O R/wall at RD 1/415 to 1/425)	236619/-	4800/-	Two Months	350.00
27	C/O boundary wall & gate at Rest House Uhal Distt Hamirpur (SH:- C/O boundary wall and gate 0/058 at RD 0/128)	420054/-	8400/-	Two Months	350.00
28	C/O boundary wall at Rest House Uhal Distt Hamirpur (SH:- C/O boundary wall at RD 0/128 to 0/195 protection wall RHS of building 0/0 to 0/09)	426981/-	8500/-	Two Months	350.00
29	R/R damages on Utpur to Bakkar Khad via Kuthar Harizan Basti km 0/0 to 4/0 (SH:- C/O wire crate wall at RD .1/660 to 1/679)	476648/-	9500/-	Two Months	350.00
30	R/R damages on Utpur to Bakkar Khad via Kuthar Harizan Basti km 0/0 to 4/0 (SH:- C/O wire crate wall at RD .2/210 to 2/220 and 2/255 to 2/264.20)	481638/-	9600/-	Two Months	350.00
31	C/O link road from Bajrol to Chamrda via Lamber km 0/0 to 4/0 (SH:- Suppling and installation of one all in one computer and Multi- Function Laser printer and UPS for HP:PWD ,Sub Division Kakkar ,Division Tauni Devi Distt Hamirpur (HP)	308000/-	6200/-	Two Months	350.00
32	C/O link road Mehli Bridge to village Thathi and Plahi to village Pargana km 0/0 to 2/130 (SH:- Supplying and installation of 3No. Computer and Multi function laser printer and UPS for HP:PWD ,Division Tauni Devi Distt Hamirpur (HP)	462000/-	9200/-	Two Months	350.00
33	R/R damages on Uhal to Bakkar Khad via Parnali road 0/00 to 6/00 (SH:- C/O wire crate R/wall at RD 1/535 to 1/553)	472904/-	9500/-	Two Months	350.00
34	R/R damages on link road from Sangri Khad to Harizan basti Saphal km .0/0 to 2/00 (SH:- C/O R/wall from RD 0/00 to 0/015) Under SCSP	362678/-	7300/-	Two Months	350.00
35	R/R damages on various road under Kakkar Sub-Division HP:PWD,Tauni Devi (SH:- Hiring of JCB/front end loader for removal of slips,back filling of R/wall under Kakkar -1and Kakkar -II)	481000/-	9600/-	Two Months	350.00
36	R/R damages Hindu Di Dhar via Jandroo road km 0/0 to 9/00 (SH:- ROFD at km 3/195 to 3/255)	318488/-	6400/-	Two Months	350.00
37	R/R damages on Banal to Chamiana via Manglehar Daddar km 0/0 to 7/185.(SH:- C/O R/wall at RD .3/470 to 3/490)	469137/-	9400/-	Two Months	350.00
38	R/R damages on Banal to Chamiana via Manglehar Daddar km 0/0 to 7/185.(SH:- C/O R/wall at RD .1/817 to 1/828 and 4/080 to 4/095)	437551/-	8800/-	Two Months	350.00

39	C/O link road Kuthera to Chalokhar via Dei-Ka-Naun km .0/0 to 2/700 (SH:- P/L roller compacted concrete (M-30) grade at RD 2/115 to 2/242) (Under OTMNP)	493474/-	10000/-	Two Months	350.00
40	R/R damages on link road Ree to Gartholi via Balyana km 0/0 to 2/700.(SH:- C/O R/wall at RD 0/252 to 0/264)	494800/-	9800/-	Two Months	350.00
41	C/O link road Chaleli to Tikkar via Debra km .0/0 to 3/500 (SH:- C/O 900mm dia hume pipe culvert at RD 0/690 with both sides wing wall) (Under SCSP)	487289/-	9700/-	Two Months	350.00
42	C/O link road Chaleli to Tikkar via Debra km .0/0 to 3/500 (SH:- C/O 900mm dia hume pipe culvert at RD 1/165 with both sides wing wall) (Under SCSP)	490451/-	9800/-	Two Months	350.00
43	C/O Balance approach road for ITI building at Utpur . (SH:- F/C 5/7 mtr .wide road at RD 0/135 to 0/237) Deposit work	482751/-	9700/-	Two Months	350.00
44	R/R damages on Kakkar to Bakkar Khad via Ghodlamber km .0/00 to 2/650 (SH:- Hiring of hydraulic excavator /Polcain for removal of slips back filling of R/walls, clearing of drain)	497000/-	10000/-	Two Months	350.00
45	C/O Assistant Engineer Office cum Residence at Kakkar ,Tehsil Tauni Devi Distt Hamirpur (HP) (SH:- Site development) .	496743/-	10000/-	Two Months	350.00
46	C/O Assistant Engineer Office cum Residence at Kakkar ,Tehsil Tauni Devi Distt Hamirpur (HP) (SH:- Site development) .	497776/--	10000/-	Two Months	350.00
47	R/R damages on link road to Chaleli to Tikkar via Debra km 0/0 to 3/0 under Sujanpur Sub-Division (Chabutra Section) (Sh:- Hiring of JCB/front loader for removal of slips ,dressing of berms clearance of drains)	182000/-	3600/-	Two Months	350.00
48	R/R damages on link road from Jandroo road to Harizan Basti Dhar Baghera km 0/0 to 0/500 (SH:- C/O wire crates at RD .0/190 to 0/210) (LHS)	479380/-	9600/-	Two Months	350.00
49	R/R damages on link road from Sangri Khad to Harizan Basti Sapahal km 0/0 to 2/00 (Sh:- c/o R/wall from 0/015 to 0/027) Under SCSP	464703/-	9300/-	Two Months	350.00
50	R/R damages on Uhal to Bakkar Khad via Parnali road 0/00 to 6/00 (SH:- C/O wire crate R/Wall at RD 0/810 to 0/828.10)	478160/-	9600/-	Two Months	350.00

51	R/R damages Sujampur Sandhole road km 3/00 to 20/00 (MDR-38) (SH:- C/O solid causeway at Jakhoo at RD 11/500 and C.C pavement at RD 11/800)	489515/-	9800/-	Two Months	350.00
52	C/o motorable link road 5/7 mtr. Wide from Dosarka to village Roga (SH:- F/C from RD 0/0 to 0/165) (Deposit work)	141690/-	2800/-	Two Months	350.00
53	C/O Junior Engineer Office cum Residence at Bharmeli (Section Chabutra) HPPWD Sujampur Distt Hamirpur (HP) (SH:- P/F glazed and wire gauge shutter ,main gate ,boundary wall railing and fencing etc)	441649/-	8800/-	Two Months	350.00
54	R/R damages on link road Kakkar to Bakkar Khad via Ghodlambier km 0/00 to 2/650 (SH:- C/O PCC B/wall near the house of Smt.Rasmi Devi W.O Sanjay Kumar at RD 0/350 to 0/385) Deposit work	194885/-	3900/-	Two Months	350.00
55	C/O link road to village Chapted km 0/00 to 0/150 (SH:- F/C PCC R//wall and C.C pavement in km 0/00 to 0/120) (Deposit work)	378986/-	7600/-	Two Months	350.00
56	R/R damages on Hamirpur Sujampur road km .15/00 to 24/785 (SH:- C/O Alampur side wing wall of Alampur bridge at Beas River at RD 24/775 to 24/778)	439267/-	8800/-	Two Months	350.00
57	C/O link road Narwalan -Di-Dhar to Boursu via Lambran -Di- Dhar km 0/0 to 2/075. (SH:- F/C 5/7mtr. wide in km 2/001 to 2/045) Under OTMNP	472363/-	9500/-	Two Months	350.00
58	C/O link road Narwalan -Di-Dhar to Boursu via Lambran -Di- Dhar km 0/0 to 2/075. (SH:- F/C 5/7mtr. wide in km 1/945 to 2/00) Under OTMNP	450731/-	9000/-	Two Months	350.00

TERMS AND CONDITIONS:-

The tender documents shall be issued only to those contractors/firms who fulfill the following criteria and submit documents with the application. The valid enlistment/registration of contractor in appropriate class. Permanent Account Number (PAN). Earnest money in the shape of National saving certificate/Time deposit Account in any of the Post office in H.P./F.D.R from any Nationalized Bank (i/c Kangri Central Cooperative Bank) duly pledged in favour of the Executive Engineer. Other special terms and condition can be seen/obtain in the office on any working day. Any ambiguous/telegraphic conditional tenders by fax shall not be

Executive Engineer
TauniDevDivision,
HPPWD TauniDevi.

No. PW/TDD/GA/N.I.T./2023-24

15532-15590

Dated:- 21/12/2023


Copy forwarded for information & necessary action.

- 1 The Engineer-in-Chief, HP:PWD, Shimla.
- 2 The Chief Engineer (HZ), HP:PWD, Hamirpur.
- 3 The Superintending Engineer, 8th Circle, HP:PWD Hamirpur.
- 4 All the Superintending Engineers/Executive Engineers in HP:PWD.
- 5 The Deputy Commissioner, Hamirpur(HP)
- 6 The Director, Information and Public Relations, Suchna Avam Jan Sampark Bhawan, HP Shimla-2.
- 7 The Tehsildar, Tauni Devi.
- 8 The B.D.O Tauni Devi.
- 9 The Municipal Committee, Hamirpur(HP)
- 10 All the Assistant Engineers working under this Division.
- 11 Account Branch/Drawing Branch/Notice Board.
- 12 Lok Mitra, Tauni Devi.
- 13 Various Contractors/ Firms.

Excutive Engineer
TauniDevDivision,
HPPWD TauniDevi

CERTIFICATE

Certificate that the tender for JOB NO. 1 to 58 are called vide this office Letter NO. 15532-15590 dated 21-12-2023 are an urgent nature and in public interest .


Executive Engineer,
Tauni Devi Division,
H.P.W.D, Tauni Devi.

Schedule of Quantity

ITEM OF WORK:- Restoration of rain damages on link road from Chart-3, Di-Dhar to Lambhan Di-Dhar via Boursa I m. 0/00 to 1/700. (SR:- C/O R/Wall at RD. 1/690 to 1/700).

Estimated Cost:- Rs. 365097.00
Earnest Money:- Rs. 7300.00

Sr.No.	Description of Item	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
					Two Months	
2	Excavation work by mechanical means (Hydraulic excavator) manual means in foundation trenches or drains (not exceeding 1.5m (five feet) for width) in width or 10 days (ten square metre on plan) including clearing of sides and running of bottom, all upto 1.5 m. (five feet) for depth) including getting out the excavated soil and disposal of surplus excavated soils as decided, within a limit of 50 m (fifty metres) in per the direction of the Engineer-in-charge including entire cartage of material within all roads and its and other incidents. The rates are inclusive of octroi, royalty, Mahasul, toll tax, sale tax, good service tax or other taxes imposed by the Government.	36.48			Per cubic metre	
3	Providing and laying concrete concrete in retaining walls, return walls, walls (any thickness) including attached plastering, columns, piers, abutments, pillars, posts, caps, buttresses, string or facing courses, parapets, coping, foot blocks, anchor blocks, plain window sills, flat, harken floor etc., up to foot any level, including the cost of centering, shuttering and finishing 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (fourty millimeters nominal size) as per the direction of the Engineer-in-charge including entire cartage of material within all roads and its and other incidents. The rates are inclusive of octroi, royalty, Mahasul, toll tax, GST or other taxes imposed by the Government.	79.00			Per cubic metre	
4	Providing weep holes in brickwork masonry plain reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 100mm (one hundred ten millimeter) dia PVC pipe. De-shuttered weepers 400 having pressure 1kg per centimeter square. (four kilograms per centimeter square) extending through the full width of the structure with slopes of 1:1, 2:1, 3:1 towards drainage face complete as per drawing and technical specification clauses 414, 416, 418, 420 3.7 as per direction of Engineer-in-charge including entire cartage of material within all roads and its and other incidents. The rates are inclusive of octroi, royalty, Mahasul, toll tax, GST or other taxes imposed by the Government.	20.00			Each	
5	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and MRCO technical specifications clause 1204.2.8 as per direction of Engineer-in-charge, including entire cartage of material within all roads and its and other incidents. The rates are inclusive of octroi, royalty, Mahasul, toll tax, GST or other taxes imposed by the Government. The rates are inclusive of octroi, royalty, Mahasul, toll tax, GST or other taxes imposed by the Government.	15.46			Per cubic metre	
	Total				Total	

Terms and Condition

1. Work shall be executed as per PWD specification


 Executive Engineer,
 Tanged Devt Division,
 RPFWD, Tamil Nadu

Schedule of Quantity						
NAME OF WORK:- Restoration of rain drainages on Tandi Devi Ubad Kukkar Bajrol Jungle Beri road km. 15/0 to 30/9-5. (MDI-105) (SRI:- C/O PCC R/Wall at RD-18/100 to 18/112 (LHS of Road) & 18/110 to 18/117 (RHS of road) (Near primary School)				Estimated Cost:-	Rs. 310845.00	
				Earnest Money:-	Rs. 6200.00	
				Time:-	Two Months	
Sr.No.	Kakhar	Description of items	Qty.	Rate		Amount
				In Fig.	In Words	
1		Excavation work by mechanical means (Hydraulic excavatory) manual means in foundation trenches or drains (not exceeding 1.5 metre point five metre) in width or 10 sqm) ten square metre (in plan) including dressing of sides and ramming of bottom. All upto 1.5 m. (one point five metre) including getting out the excavated soil and deposit of surplus excavated soil as directed, within a lead of 50 multiply metre) as per the direction of the Engineer-in-charge including entire cartage of material within all leads and its and other incidentals. The rates are inclusive of cost, royalty, Malakana, soil tax, GST or other taxes imposed by the Government.	33.80			Per Cubic metre
2		Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached platform, columns, piers, abutments, pillars, posts, struts, buttresses, string or facing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, walls, surkim floor etc., up to floor any level, including the cost of concrete, shuttering and finishing, 1:5:10 (one cement : five coarse sand) : 1m graded stone aggregate 40 mm (forty millimeter nominal size) as per the direction of the Engineer-in-charge including entire cartage of material within all leads and its and other incidentals. The rates are inclusive of cost, royalty, Malakana, soil tax, GST or other taxes imposed by the Government.	69.48			Per Cubic metre
3		Providing weep holes in brickstone masonry pier reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 150mm one hundred ten millimeter dia PVC pipe (in-plastic) or vermic pipe having pressure 4kg per centimeter square, (four kilogram per centimeter square) extending through the full width of the structures with slopes of 1(V) : 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer-in-charge, including entire cartage of material within all leads and its and other incidentals. The rates are inclusive of cost, royalty, Malakana, soil tax, GST or other taxes imposed by the Government.	32.00			Each
						Total

Terms and Condition

1. Work shall be estimated as per IWD specifications.


 Executive Engineer,
 Tandi Devi Division
 RPPWD, Tandi Devi

Schedule of Quantity						
NAME OF WORK:- Restoration of rain damages on Kakkar to Bakkal: Khad via Ghodlamber km. 0/00 to 2/200.(SH:- locking of sides of cement concrete pavement from RD. 0/100 to 1/00).(B.H.S.)				Estimated Cost:-	Rs. 414929.00	
				Earnest Money:-	Rs. 4300.00	
				Time:-	Two Months	
Sr.No.	Description of Items	Qty.	In Fig.	Rate		Amount
				In Words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm/ ten square metre on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m (fifty metre) as per the direction of the Engineer-in-charge including entire cartage of material within all loads and fits and other incidentals The rates are inclusive octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	94.50			Per Cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:3:6 (one cement three sand six graded stone aggregated 20mm (twenty millimeter) nominal size, as per the direction of the Engineer-in-charge including entire cartage of material within all loads and fits and other incidentals The rates are inclusive octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	63.00			Per Cubic metre	
					Total	Total

Terms and Condition

1. Work shall be executed as per MWD specifications.

A. S. S. S.
Executive Engineer,
Tamil Nadu Division,
Tamil Nadu

Schedule of Quantity

NAME OF WORK:- Restoration of rain damage on various road under Kakkar Sub-Division, (SH:- Providing and laying Estimated Cost:- kilometre stone, sign boards and rumble strips on various roads under Kakkar-I and Kakkar-II Section) Earnest Money:-									
Sr. No.	Description of Items	Qty.	In Fig.	Rate		Unit	Amount	Rs.197138.00	
				In Words	Time:-			Two Months	Rs.3900.00
1	Reinforced cement concrete M-15 (M-Fifteen) grade kilometre stone/local stone of standard design as per IRC:8 fixing in position including painting and printing, etc. Ordinary Km Stone as per drawing and MORD technical specification Clause 1703 as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octroi, royalty, Malihana, toll tax, GST or other taxes imposed by the Government.	25.00				Each			
2	Providing and fixing of retro-reflectorised cautionary, mandatory and informative signs as per IRC: 67 made of encapsulated lens type (reflective sheeting vide clause 1701.2.3 fixed over aluminium sheeting, 1.5mm (one point five millimetre) thick supported on a mild steel angle iron post 75mmx75mmx6mm(seventy five millimetre into seventy millimetre into six millimetre) firmly fixed to the ground by means of properly designed foundation with M-15(M-fifteen) grade cement concrete 450mm x 450 mm x 600 mm (four hundred fiftyinto four hundred fifty into six hundred millimetre), 600 mm below ground below ground level) as per drawings and MORD technical specification Clause 801 (Retro-reflectorised Traffic Signs 900x900x900mm (nine hundred into nine hundred into nine hundred millimetre) triangular) as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malihana, toll tax, GST labour cess or other taxes imposed by the Government.	22.00				Each			
3	Providing and erecting direction and place identification retro-reflectorised sign with size 900x600mm(nine hundred into six hundred millimetre)as per IRC:67 made of encapsulated lens type reflective sheeting vide clause 1701.2.3, fixed over aluminium sheeting, 2mm(two millimetre) thick with area exceeding 0.9 sqm.(zero point nine squaremetre) supported on mild steel angle iron posts 75mmx75mmx6mm(seventy five into seventy five into six millimetre) 2(two)numbers firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete 450mmx 450mm x 600mm(four hundred fifty millimetre into four hundred fifty millimetre into six hundred millimetre) 600mm (six hundred millimetre) below ground level as per approved drawing and technical specification clause 1701 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malihana, toll tax, GST labour cess or other taxes imposed by the Government.	12.00				Each			

4	Providing and erecting direction and place identification retro-reflectivised sign with size 1200x900mm(One thousand two hundred into nine hundred millimetre)as per IRC:67 made of encapsulated lens type reflective sheeting side clause 1701.2.1, fixed over aluminium sheeting, 2mm(two millimetre) thick with area exceeding 0.9 sqm. (zero point nine square metre) supported on mild steel angle iron posts 75mmx75mmx6mm(seventy five into seventy five into six millimetre) 2numbers firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete 450mmx450mmx600mm(four hundred fifty millimetre into four hundred fifty millimetre into six hundred millimetre),600mm (six hundred millimetre), below ground level as per approved drawing and technical specification clause 1701 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate includes sale tax sector, royalty,malkhama toll tax,GST,labour cess or other taxes imposed by the Government.	11.00	3496.50	Rupees three thousand four hundred ninety six and paise fifty only.	Each
5	Provision of 15(fifteen) Nos. Rumble strips covered with premix bituminous carpet, 15-20mm (fifteen to twenty millimetre) high at centre, 250mm (two hundred fifty millimetre) wide placed at 1m (one metre) centre-to-centre at approved locations to control speed, marked with white strips of road marking paint as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate includes sale tax sector, royalty,malkhama toll tax,GST,labour cess or other taxes imposed by the Government.	50.00	177.20	Rupees one hundred seventy seven and paise twenty only.	Per Square metre
Terms and Condition					Total

1. Work shall be executed as per PWD specification.


Executive Engineer,
Tamil Devl Division,
HPPWD: Tamil Nadu.

Schedule of Quantity

Schedule of Quantity									
NAME OF WORK:- Restoration of rain damages on link road Kakkar to Bakkar Khad via Ghodlamber km. 0/00 to 2/650. (SH) - P/L									
Estimate voting from km. 1/940 to 2/640.									
Sr.No.	Description of Items	Qty.	Rate		Unit	Amount			
			In Fig.	In Words					
1	Stone setting properly hand packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and camber including spreading watering and rolling of binding materials medium or earth etc. complete as per H.P.W.D., specifications 100mm(one hundred millimeters) spread thickness (finished work including materials and labour) in all leads and lifts and dressing of sides and bottom (and as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	408.00			Per cubic metre				
Terms and Conditions						Total			

Terms and Condition

1. Work shall be executed as per PWD specifications.


 Executive Engineer,
 Tamsal Devl Division,
 H.P.W.D. Tamsal

Schedule of Quantity						
NAME OF WORK:- Restoration of rain damages on link road Kakkar to Bahkar Khad via Ghodlamber km. 0/00 to 4/650 (SH:- C/O Maintenance of earthen shoulders from Km.0/200 to 2/650 on BHS).						
Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Maintenance of earthen shoulder (filling with fresh selected soil). Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto all leads and lifts as per technical specification clause 1903, as per direction of Engineer- in -Charge, including cartage of materials within all leads and lifts and other incidents. The rates are inclusive of chrd, royalty, Mahanulol tax, GST or other taxes imposed by the Government.	5880.00			Per Square metre	
Total						Rs. 282240.00
						Rs. 5600.00
						Two Months


 Executive Engineer,
 Tamil Nadu Division,
 MPWD, Tamil Nadu

Terms and Condition
 1. Work shall be executed as per PWD specification.

Schedule of Quantity

NAME OF WORK:- C/O link road to village Chamaiyana Di Khamauli km. 0/00 to 4/00 (SH:- C/O 5/7 mtr. Wide formation cutting at RD. 1/770 to 1/921). (Under OTMNP).

Estimated Cost:- Rs. 496749.00

Earnest Money:- Rs. 10000.00

Time:- Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation in hilly areas in all heights and depths and in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling /wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the technical specification clause 302.1603.1.1603.2 sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un-useful material for filling in road ways, camber, embankment for grade improvement and disposal of all un-useful material to required width of the road or on approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and cartage of machineries materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and or labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including cartage of material within all leads and lifts. (Recovery of useful stone i.e. 170.99/- cubic metre shall be made from the contractor @ Rs. 300/- (three hundred only per cubic metre) amounting to Rs. 51,207/- only.	1103.20			Per cubic metre	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tanni Devi Division,
 HPPWD, Tanni D.A.

Schedule of Quantity

NAME OF WORK:- C/O link road to village Chumalyani Di Khanuli km. 0/00 to 4/00. (SH:- C/O 5/7mtr. Wide formation cutting at RD. 1/921 to 2/070). (Under OTMNP).					Estimated Cost:- Rs. 499833.00
					Rs. 10000.00
					Two Months
Sr.No.	Description of Items	Qty.	Rate		Amount
			In Fig.	In Words	
1	Excavation in hilly areas in all heights and depths and in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling /wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the technical specification clause 302.1603.1, 1603.2, sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un-useful material for filling in road ways, camber, embankment for grade improvement and disposal of all un-useful material to required width of the road or on approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and carriage of machineries materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and or labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. (Recovery of useful stone i.e. 172.05/- cubic metre shall be made from the contractor @ Rs. 300/- (three hundred only per cubic metre) amounting to Rs. 51,615/- only.	1110.00			Per cubic metre
					Total

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division,
 HPPWD, Tauni Dist.

Schedule of Quantities

NAME OF WORK:- Restoration of rain drainages on Hamirpur Sujajpur road km. 2/00 to 16/00 (SH- C/O R/W all at RD. 13/345 to 13/353 near house of Sh. Ravi Kumar) (Deposit Work).

Rs. 184605.80

Estimated Cost-
Earnest Money-

Rs. 3700.00

Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount.
			In Fig.	In Words		
1	Excavation work by mechanical means (hydraulic excavator) manual means in foundation trenches or drains just exceeding 1.50m (five feet) in width or 1.50m (five feet) in depth (including dressing of sides and watering of bottom, in upto 1.5 m, four point five metres) including getting out the excavated soil and disposal of surplus excavated soils at directed, within a limit of 50 m (fifty metres) in per the direction of the Engineer-in-charge including entire carriage of material within all loads and lifts and other incidentals. The rates are inclusive of petrol, royalty, Mahanagar tax, GST or other taxes imposed by the Government.	25.44			Per Cubic metre	
2	Providing and laying cement concrete in retaining walls, retaining walls (any thickness) including flagstones, pillars, piers, abutments, pillars, piers, buttresses, string or facing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, floors, surface floor etc., up to floor any level, including the cost of casting, shuttering and finishing 1:1.5:10 (one cement: one coarse sand: ten graded stone aggregate 40 mm (forty millimetres nominal size)) as per the direction of the Engineer-in-charge including entire carriage of material within all loads and lifts and other incidentals. The rates are inclusive of petrol, royalty, Mahanagar tax, GST or other taxes imposed by the Government.	39.92			Per Cubic metre	
3	Providing deep holes in brickwork masonry/ plain reinforced concrete abutment, wing wall, return wall, retaining walls and broad wall with 150mm (one hundred and fifty millimetres) dia PVC pipe. De-plastication/ venting pipe having pressure 4kg per centimetre square (four kilograms per centimetre square) extending through the full width of the structures with slopes of (1V: 20H) towards drawing floor complete as per drawing and technical specification clauses S14, 103, 1204.3.7 as per direction of Engineer-in-charge, including entire carriage of material within all loads and lifts and other incidentals. The rates are inclusive of petrol, royalty, Mahanagar tax, GST or other taxes imposed by the Government.	15.00			Each	
4	Providing and laying filter media with granular crushed aggregates as per specification to a thickness of not less than 300mm (one hundred millimetres) with smaller size towards the soil and bigger size towards the well and providing over the entire surface below abutment, wing wall, return wall to the full height, completed to firm condition complete as per drawing and technical specification clause 1204.3.6 as per direction of Engineer-in-charge, including entire carriage of material within all loads and lifts and other incidentals. The rates are inclusive of petrol, royalty, Mahanagar tax, GST or other taxes imposed by the Government.	5.52			Per cubic metre	
					Total	

Terms and Condition

1. Work shall be executed as per PWD specifications.

Arjun
Executive Engineer,
Tamil Dev Division,
HPPWD, Tamil Nadu

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Hamirpur Sejanpur road km. 16/00 to 24/785 (SH- C/O R/Wall at RD. 16/784) **Estimated Cost:-** Rs. 382497.69
in 16/795 along with parapets at RD. 16/768 to 16/795). **Barment Money:-** Rs. 7700.00

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation work by mechanical means (Hydraulic excavator) manual means in foundation trenches or drains (not exceeding 1.50m (five feet) in width or 10 sept. ten square metres or plan) including dressing of sides and widening of bottoms, up to 1.5 m (five feet) (see note) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a limit of 50 m (fifty metres) as per the direction of the Engineer-in-charge including entire carriage of material within all loads and lifts and other incidentals. The rates are inclusive of fuel, royalty, Maharsa and tax. GST or other taxes imposed by the Government.	58.08			Per Cubic metre	
2	Providing and laying cement concrete in retaining walls, retaining walls (dry, freeboard) including attached planters, columns, piers, abutments, pillars, posts, shafts, buttresses, string or facing courses, parapets, coping, footings, minor blocks, plain window sills, slabs, sunken floor etc. up to their any level, including the cost of erecting, shoring and bracing, 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (four millimetres nominal size) as per the direction of the Engineer-in-charge including entire carriage of material within all loads and lifts and other incidentals. The rates are inclusive of fuel, royalty, Maharsa and tax. GST or other taxes imposed by the Government.	82.93			Per Cubic metre	
3	Providing and laying brickwork (masonry) plain masonry concrete abutment, wing walls, abutment walls, retaining walls and breast wall with 110mm (one hundred ten millimetres) dia. PVC pipe. The plain brickwork masonry plain having perimeter 4kg per centimetre square (four kilograms per centimetre square) including through the full width of the structures with slopes of 1:1 (one vertical : 1 horizontal) facing face complete as per drawing and technical specification clauses 214, 703, 1204.3.7 as per direction of Engineer-in-charge including entire carriage of material within all loads and lifts and other incidentals. The rates are inclusive of fuel, royalty, Maharsa and tax. GST or other taxes imposed by the Government.	48.00			Each	
4	Providing and laying filter media with granular crushed aggregate as per specification to a thickness of not less than 600mm (six hundred millimetres) with smaller size towards the soil and larger size towards the wall and providing over the entire surface below abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification clause 1204.3.8 as per direction of Engineer-in-charge, including entire carriage of material within all loads and lifts and other incidentals. The rates are inclusive of fuel, royalty, Maharsa and tax. GST or other taxes imposed by the Government.	6.14			Per cubic metre	
Total						

Terms and Conditions

1. Work shall be executed as per PWD specifications.


 Executive Engineer,
 Tegal Beed Division
 Jharkhand, Jammu & Kashmir

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Matial Thicker road km. 0/00 to 2/030 (Sth:- C/O R/Wall at RD. 1/360 to 1/375).

Estimated Cost:-

Earliest Mouney:-

Time:-

Rs. 201399.00

Rs. 6000.00

Two Months

Sr.No.	Description of Items	Qty.	In Fig.	Rate		Unit	Amount
				In Words	In Words		
1	Excavation work by mechanical means (hydraulic excavator) manual means in foundation trenches or drains (not exceeding 1.5m (one point five meter) in width or 10 sqm (ten square meter) in area) including drawing of sides and leveling of bottom, up to 1.5 m, (one point five meter) including putting out the excavated soil and disposal of surplus excavated soil as directed, within a limit of 50 m (fifty meter) as per the direction of the Engineer-in-Charge including entire carriage of material within all loads and its and other incidents. The rates are inclusive of cart, royalty, Mahanadi tax, GST or other taxes imposed by the Government.	20.20				Per Cubic metre	
2	Providing and laying current concrete in retaining walls, retaining walls, with (per thickness) including attached pillars, columns, piers, abutments, pillars, posts, shafts, buttresses, wing or facing courses, parapets, coping, bed blocks, kerbs, blocks, plain window sills, flights, masonry box etc. up to four m (four meter) including the cost of formwork, shuttering and finishing 1:2:10 (one cement : two coarse sand) : ten graded stone aggregate 40 mm (forty millimeters nominal size), as per the direction of the Engineer-in-Charge including entire carriage of material within all loads and its and other incidents. The rates are inclusive of cart, royalty, Mahanadi tax, GST or other taxes imposed by the Government.	65.95				Per Cubic metre	
3	Providing and laying concrete in retaining walls, retaining walls, with (per thickness) including attached pillars, columns, piers, abutments, pillars, posts, shafts, buttresses, wing or facing courses, parapets, coping, bed blocks, kerbs, blocks, plain window sills, flights, masonry box etc. up to four m (four meter) including the cost of formwork, shuttering and finishing 1:2:10 (one cement : two coarse sand) : ten graded stone aggregate 40 mm (forty millimeters nominal size), as per the direction of the Engineer-in-Charge including entire carriage of material within all loads and its and other incidents. The rates are inclusive of cart, royalty, Mahanadi tax, GST or other taxes imposed by the Government.	20.00				Each	
4	Providing and laying filter media with granular crushed aggregates as per specification to a thickness of not less than 600mm (six hundred millimeters) with smaller size towards the soil and bigger size towards the wall and providing over the entire surface below abutment, wing wall, return wall to the full height connected to form corbation complete in per drawing and technical specification clause 1204.3.8 as per direction of Engineer-in-Charge, including entire carriage of material within all loads and its and other incidents. The rates are inclusive of cart, royalty, Mahanadi tax, GST or other taxes imposed by the Government.	10.50				Per cubic metre	
Total						Total	

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tantal Development Division,
 BPPWD, Tantal Development

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Hamirpur Sujanpur road km. 16/90 to 24/785 (SB:- C/O R/Wall at RD. 16/768

to 16/782).

Sl. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation work by mechanical means (hydraulic excavator) manual means in foundation trenches or drains (not extending 1 square point five meter) in width or 10 cent per square meter on plan including measuring of sides and opening of bottom, up to 1.5 m, (one point five meter) including putting out the excavated soil and disposal of surplus excavated soil as directed within a limit of 50 m (fifty meter) as per the direction of the Engineer-in-Charge including cartage of material within all loads and lifts and other incidentals. The rates are inclusive of cartage, royalty, Mahanadi tax, GST or other taxes imposed by the Government.	73.92			Per Cubic metre	
2	Providing and laying cement concrete in retaining walls, retaining walls (any thickness) including attached plinths, columns, piers, abutments, pillars, posts, etc., up to floor level including the cost of carting, chiselling and finishing 1:5:10 (one cement : five parts sand : ten parts coarse aggregate) 40 mm (four millimeters nominal size) as per the direction of the Engineer-in-Charge including cartage of material within all loads and lifts and other incidentals. The rates are inclusive of cartage, royalty, Mahanadi tax, GST or other taxes imposed by the Government.	03.20			Per Cubic metre	
3	Providing and laying brickwork masonry (solid) reinforced concrete abutment, wing walls, retaining walls and breast wall with 110mm (one hundred ten millimeter) dia PVC pipe (the-plasticized) section pipe having pressure 4kg per sq. centimetre (four kilograms per centimeter square) extending through the full width of the abutments with slopes of (1V) : 2(H) towards drawing face complete as per drawing and technical specification clauses 814, 700, 1204.3.17 as per direction of Engineer-in-Charge including cartage of material within all loads and lifts and other incidentals. The rates are inclusive of cartage, royalty, Mahanadi tax, GST or other taxes imposed by the Government.	62.00			Each	
4	Providing and laying filter media with granular crushed aggregate as per specification to a thickness of not less than 400mm (four hundred millimeter) with smaller size towards the soil and bigger size towards the well and providing over the entire surface behind abutment, wing wall, breast wall to the full height, completed to firm condition complete as per drawing and technical specification clause 1204.3.8 as per direction of Engineer-in-Charge, including cartage of material within all loads and lifts and other incidentals. The rates are inclusive of cartage, royalty, Mahanadi tax, GST or other taxes imposed by the Government.	7.81			Per Cubic metre	
					Total	

Terms and Condition

1. Work shall be executed as per PWD specification.

(Signature)

Executive Engineer,
Tauni Divl Division,
RPFWD, Tauni Divl

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Hamirpur Solanpur road km. 0/0 to 24/785 (SH: C/O B/W'Wall at RD, 23/967

Estimate No.:- Rs. 366749.00

Estimated Cost:- Rs. 7300.00

Earnest Money:- Two Months

Time:-

Sr. No.	Description of Items	Qty.	In Fig.	Rate		Unit	Amount
				In Words	In Words		
1	Excavation work by mechanical means (Hydraulic excavator) manual means in formation trenches or drains (not exceeding 1.50m depth) in width of 10 cm or less (not square more in plan) including dressing of sides and bottom of bottom, at least 1.5 m, (not less than 10 cm) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a limit of 50 m. (If the value is as per the direction of the Engineer-in-charge including entire carriage of material within all loads and its and other incidents. The rates are inclusive of cart, royalty, Mahanagar tax, GST or other taxes imposed by the Government.	49.20				Per cubic metre	
2	Providing and laying concrete 1:2:12 (one cement, two sand, twelve graded stone aggregate) casting complete including the cost of form work standardised concepts in retaining walls, small walls as per drawing and HPWD, typical specification, as per the direction of Engineer-in-charge including entire carriage of material within all loads and its and other incidents. The rates are inclusive of cart, royalty, Mahanagar tax, GST or other taxes imposed by the Government.	4.45				Per cubic metre	
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to 100 mm (one cement, two sand, eight graded stone aggregate) 40mm (80% minimum) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all loads and its and other incidents. The rates are inclusive of cart, royalty, Mahanagar tax, GST or other taxes imposed by the Government.	64.16				Per cubic metre	
4	Providing and laying in position cement concrete 1:2:12 (one cement, two sand, twelve graded stone aggregate) including the cost of centering and shuttering - All work up to 100 mm (one cement, two sand, eight graded stone aggregate) 40mm (80% minimum) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all loads and its and other incidents. The rates are inclusive of cart, royalty, Mahanagar tax, GST or other taxes imposed by the Government.	38.50				Each	
5	Providing and laying in position cement concrete 1:2:12 (one cement, two sand, twelve graded stone aggregate) including the cost of centering and shuttering - All work up to 100 mm (one cement, two sand, eight graded stone aggregate) 40mm (80% minimum) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all loads and its and other incidents. The rates are inclusive of cart, royalty, Mahanagar tax, GST or other taxes imposed by the Government.	23.20				Per cubic metre	
6	Providing and laying in position cement concrete 1:2:12 (one cement, two sand, twelve graded stone aggregate) including the cost of centering and shuttering - All work up to 100 mm (one cement, two sand, eight graded stone aggregate) 40mm (80% minimum) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all loads and its and other incidents. The rates are inclusive of cart, royalty, Mahanagar tax, GST or other taxes imposed by the Government.	5.00				Per unit	
						Total	

Terms and Condition

1. Work shall be executed as per PWV specification.


 Executive Engineer,
 Tunnel Devt Division,
 G.P.W.D. - Tamil Nadu

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Rainfall to Chamliana via Mangalchar Daddar road km. 0/00 to 7/185 (SIL- C/D)

Rs. 328794.69

Estimated Cost:-

Rs. 6600.00

Excess Moisture:-

Two Months

R/Wall at RD. 0/020 to 0/040)

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation work by mechanical means (hydraulic excavator) manual means in foundation (excavation) to extent not exceeding 1.50m (one point five metre) in width or 10 sqm (ten square metre) on plan including clearing of water and removing of debris, etc. upto 1.5 m (one point five metre) including putting soil and disposal of surplus excavated soil as directed, within a limit of 50 m (fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all loads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Maharashtra tax, GST or other taxes imposed by the Government.	41.60			Per cubic metre	
2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pillars, columns, piers, abutments, pillars, posts, arches, buttresses, sills or facing courses, parapets, coping, top blocks, ender blocks, plain concrete walls, etc., up to 100 mm (one hundred) including the cost of centering, shuttering and finishing. 1:2:4 (one cement : two parts sand : four parts stone aggregate 40 mm (forty millimetres nominal size) as per the direction of the Engineer-in-charge including entire carriage of material within all loads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Maharashtra tax, GST or other taxes imposed by the Government.	72.00			Per cubic metre	
3	Providing and laying concrete masonry (plain reinforced concrete abutment, wing walls, return walls, retaining walls and bonded wall with 110mm (one hundred ten millimetres) dia. PVC pipe. The (plaster) work is per running metre 400 (per centimetre) square (four kilograms per centimetre square) extending through the full width of the structure with slopes of (1V: 2H) towards drawing face complete as per drawing and technical specifications clause 814, 708, 1204.3.7 as per direction of Engineer-in-charge. Including entire carriage of material within all loads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Maharashtra tax, GST or other taxes imposed by the Government.	37.00			Each	
4	Providing and laying 150 mm (one hundred and fifty millimetres) dia. concrete (any thickness) as per specification to a thickness of not less than 150mm (one hundred and fifty millimetres) with smaller size towards the soil and larger size towards the wall and providing with the entire surface facing abutment, wing wall, return wall to the full height, completed to form condition complete as per drawing and technical specifications clause 1204.3.8 as per direction of Engineer-in-charge including entire carriage of material within all loads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Maharashtra tax, GST or other taxes imposed by the Government.	11.40			Per cubic metre	
					Total	

Terms and Condition

1. Work shall be executed as per PWD specifications.

A. K. K.
Executive Engineer,
Tamil Nadu Division,
RPPWD, Tamil Nadu

NAME OF WORK- Restoration of rail

Revenue and Contributions

Terms and Conditions
 * Work shall be executed as per PWD specifications.

Executive Engineer,
Tamil Nadu Division,
HAPPWD, Tamil Nadu

Schedule of Quantity

NAME OF WORK:-Restoration of rain damages on Hamirpur Solanpur road Km 0/0 to 24/785. (Sh:- Construction of breast wall at Estimated Cost:- Rs.394220.00 RD 23/958 to 23/967 near approach road to HPPWD Rest House Solanpur)							Earnest Money:- Rs.7000.00 Time:- Two Months	
Sr.No.	Description of Items	Qty.	Rate		Unit	Amount		
			In Fig.	In Words				
1.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a load of 50m(fifty metre) dressing of sides and bottom and backfilling in trenches with excavated suitable material (ordinary soil upto 3m(three metre) depth as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	55.35			Per cubic metre			
2.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering. All work up to plinth level 1:6:12 (one cement : six coarse sand/twelve graded stone aggregate 40 mm(forty millimetre) nominal size) as per the directions of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	5.04			Per cubic metre			
3.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering. All work up to plinth level 1:4:8 (one cement : four coarse sand : eight graded stone aggregate 40 mm(forty millimetre) nominal size) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	72.18			Per cubic metre			
4.00	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) dia PVC pipe Do place/ finish/ victrol having pressure 4kg per sqm (four kilogram) per square meter extending through the full width of the structures with slopes of (1V): 20(H)(twenty) towards drainage face complete as per drawing and technical specification clauses 614, 709, 7204.3.7 as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	42.00			Each			
5.00	Providing and laying filter media with granular crushed aggregates as per specification to a thickness of not less than 600mm(six hundred millimetre) with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	26.10			Per cubic metre			
	Total				Total			

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Town Devt Division,
 HPPWD, Tamil Nadu

Schedule of Quantity

NAME OF WORK:- C/O Bink road Kalakkur bridge to Baharu Jhatour km. 0/00 to 2/00. (SHE- E/Cement concrete pavement at RD. Estimated Cost:- Rs. 389490.00
 Earnest Money:- Rs. 7800.00
 Time:- Two Months

Sl. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation with by mechanical means (Hydraulic excavatory) manual means in foundation trenches or drains (not exceeding 1.5m/sore zone five metre) in width or 10 sqm/ ten square metre on plan) including dressing of sides and ramming of bottoms. If upto 1.5 m. (one point five metre) including gutting out the excavated soil and disposal of surplus excavated soils as directed, within a load of 50 m (fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Mahakamaili tax, GST or other taxes imposed by the Government.	25.71			Per Cubic metre	
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:2:4 (one cement : two coarse sand : four graded stone aggregate 20 mm nominal size) (twenty millimeters nominal size), as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Mahakamaili tax, GST or other taxes imposed by the Government.	48.56			Per Cubic metre	
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:3:6 (one cement : three sand : six graded stone aggregate 20mm (twenty millimeters) nominal size), as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Mahakamaili tax, GST or other taxes imposed by the Government.	27.79			Per Cubic metre	
	Total				Total	

Terms and Condition

Work shall be executed as per PWD specification.

Executive Engineer,
 Tamil Nadu Division,
 HPPWTD, Tamil Nadu

Schedule of Quantity

NAME OF WORK:- Construction of Junior Engineer Office cum residence at Bharmeli (section Chabutra) HPPWD, Estimated Cost:- Rs.495391.00

Sujanpur Dist, Hamirpur (SH:- Providing and fixing pre-painted sheet window sun shade, brick masonry in 2nd floor, Earnest Money:- Rs.4900.00)

cup board and 60mm thick paver block in court yard)

Time:- Two Months

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1.00	Steel (Tata/Sail) work welded in built up sections/ framed work, including cutting, bending, filing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In grating, frames, guard bar, ladder, railings, brackets, gates and similar works as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	631.36			Per Kilogram	
2.00	Providing and fixing pre-painted galvanized iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm(zero point fifty millimetre) (+ 0.05 %) total coated thickness with zinc coating 120gms (one hundred twenty grams) per sqm as per IS: 277, in 240 (two hundred forty) mpa steel grade, S-7(five to seven) microns epoxy primer on both side of the sheet and polyester top coat 15-18(fifteen to eighteen) microns. Sheet should have protective guard film of 25(twenty five) microns minimum to avoid scratches during transportation and should be supplied in single length upto 12m (twelve metre) or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling self tapping screws of size 5.5x 55 mm(five point five into fifty five millimetre) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purline, rafters and trusses and including cutting to size and shape wherever required as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	21.60			Per square metre	
3.00	Providing and fixing pre-coated galvanized steel sheet roofing accessories 0.50 mm (zero point fifty millimetre)(+0.05 %)(plus zero point zero five percentage)) total coated thickness, Zinc coating 120gms(one hundred twenty grams) per sqm as per IS: 277(two hundred seventy seven), in 240(two hundred forty) mpa steel grade, S-7(five to seven) microns epoxy primer on both side of the sheet and polyester top coat 15-18(fifteen to eighteen) microns using self drilling/ self tapping screws complete. Ridges plain (500 - 600mm)(five hundred to six hundred millimetre) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	36.00			Per running metre	
4.00	Providing and fixing M.S. RP Sheet 1.60mm(one point six millimetre) to 2mm(two millimetre) thick in eaves, house / fascia / soffits / ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete. [Both members of steel work shall be measured & paid separately in per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	38.42			Per square metre	

5.00	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (sevent point five) in superstructure above plinth level up to floor level second class of brick work in Cement mortar 1:6 (one cement : six coarse sand) as per the direction of the Engineer-in-Charge and carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	6.20			Per cubic metre
6.00	Providing and fixing cup board shutters 25 mm (twenty five millimetre) thick, with Pre-laminated flat pressed three layer particle board or graded wood particle board IS : 12823 marked, exterior grade (Grade 1 Type B), having one side decorative lamination and other side balancing lamination, including fluid class teak wood lipping of 25 mm (twenty five millimetre) wide x 12 mm (twelve millimetre) thick with necessary screws and bright finished stainless steel piano hinges, complete as per the direction of the Engineer-in-Charge and carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	25.43			Per square metre
7.00	Providing and fixing Pre-laminated flat pressed 3(three) layer (medium density) particle board or graded wood particle board IS : 3087 marked, with one side decorative and other side balancing lamination Grade 1, Type B exterior grade IS : 12823 marked, in shelves with screws and fittings wherever required, edges to be painted with polyurethane primer (fittings to be paid separately) 18 mm (eighteen millimetre) thick, as per the direction of the Engineer-in-Charge and carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	43.07			Per square metre
8.00	Providing and fixing 6mm (six millimetre) thick commercial ply conforming to IS : 1528 BWR type of action msa, Black, odora, green ply, but ply make plain lining with necessary screws/nails & bolts/ nails, including a coat of approved primer on one face, and fixed on wooden /steel frame work, complete as per direction of Engineer-in-charge (Frame work shall be paid for separately) as per the direction of the Engineer-in-Charge and carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	14.97			Per square metre
9.00	Providing & fixing decorative high pressure laminated sheet of plain / wood grain in glass / matt / suede finish with high density protective surface layer and reverse side of adhesive bonding quality conforming to IS : 2046 Type S, including cost of adhesive of approved quality 1.0 mm (one point zero millimetre) thick as per the direction of the Engineer-in-Charge and carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	25.43			Per square metre
10.00	Providing and fixing 2mm (two) class teak wood lipping / moulded beading or tal beading of size 1825 mm (eighteen into five millimetre) fixed with wooden adhesive of approved quality and screws/nails on the edges of the Pre-laminated particle board as per the direction of the Engineer-in-Charge and carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	30.00			Per running metre

11.00	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpaths, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm(fifty millimetre) thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete all 60mm(sixty millimetre) thick cement concrete paver block of M-35(M thirty five) grade with approved colour, design & pattern as per the direction of the Engineer-In-Charge and carriage of material within all loads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, godat service tax or other taxes imposed by the Government.	75.00				Per square metre
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.

A. J. Gov

Executive Engineer,
Tajaji Devi Division,
HPPWD, Tamil Nadu

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Kaisiri Dulaik Chattruru road Km 0/00 to 8/00. (SH- Construction of Retaining wall from RD 5/915 to 5/920)

Rs.339122.00

Estimated Cost:-

Rs.6600.00

Earnest Money:-

Two Months

Time:-

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 105.1 including setting out, construction of shoring and bracing, removal of stumps and other obstructions, material and disposal upto a lead of 50m(fifty metres) dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil upto 3m(three metre) depth as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents. The rates are inclusive of petrol, royalty, Malkanatali tax, GST or other taxes imposed by the Government.	14.40			Per cubic metre	
2.00	Providing and laying in position cement concrete of specified grade including the cost of containing and shuttering. All work up to plinth level 1:5:10 (one cement : five coarse sand) 100 graded coarse aggregate 40 mm(forty millimetre) nominal size(as per the direction of Engineer-in-charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive of petrol, royalty, Malkanatali tax, GST or other taxes imposed by the Government.	72.00			Per cubic metre	
3.00	Providing deep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 100mm (one hundred millimetre) dia PWC pipe. The plot/Holes/sockets having pressure 1kg per sqm (four kilogram) per square meter extending through the full width of the structures with slopes of 1(V): 20(H)(twenty) towards drawing face complete as per drawing and technical specification clauses 61.4, 709, 1204.3.7 and as per the direction of Engineer-in-charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive of petrol, royalty, Malkanatali tax, GST or other taxes imposed by the Government.	24.00			Each	
4.00	Providing and laying filter media with granular crushed aggregates as per specification to a thickness of not less than 600mm(six hundred millimetre) with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents. The rates are inclusive of petrol, royalty, Malkanatali tax, GST or other taxes imposed by the Government.	19.20			Per cubic metre	
Terms and Condition					Total	

Terms and Condition

1. Work shall be executed as per PWD specification.

Amal Kumar

Executive Engineer,
Tamil Nadu Division,
HPPWD, Tamil Nadu.

Schedule of Quantity						
NAME OF WORK:- Restoration of rain damages on Kalsiri Dubak Chattram road Km 0/00 to 8/00. (SH:- Construction of retaining wall from RD 5/910 to 5/915)				Estimated Cost:- Earnest Money:- Time:-	Rs.330122.00 Rs.6600.00 Two Months	
Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1.00	Earthwork in excavations for structures as per drawing and technical specifications Clause 305.1. including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a load of 50mm (fifty millimetre) dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil upto 3m (three metre) depth as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents. The rates are inclusive octroi, royalty, Mulhansoll tax, GST or other taxes imposed by the Government.	14.40			Per cubic metre	
2.00	Providing and laying in position concrete of specified grade including the cost of conveying and shunting. All work up to plinth level 1-5:150 (one cement : four coarse sand): ton graded stone aggregate 40 mm (forty millimetre) nominal size as per the direction of Engineer-in-charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octroi, royalty, Mulhansoll tax, GST or other taxes imposed by the Government.	72.00			Per cubic metre	
3.00	Providing deep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 100mm (one hundred millimetre) dia PCC pipe Do place /finches/venter having pressure 4kg per sqm (four kilogram) per square meter extending through the full width of the structures with slopes of 1V: 20H (twenty) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 and as per the direction of Engineer-in-charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octroi, royalty, Mulhansoll tax, GST or other taxes imposed by the Government.	24.00			Each	
4.00	Providing and laying filter media with granular crushed aggregates as per specification to a thickness of not less than 500mm (five hundred millimetre) with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, constructed to firm condition complete as per drawing and technical specification Clause 1204.3.8 as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents. The rates are inclusive octroi, royalty, Mulhansoll tax, GST or other taxes imposed by the Government.	19.20			Per cubic metre	
					Total	

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tamil Desi Division,
 HPPWD, Tamil Desi

1/842-501

	Estimated Cost	Earnest Money
B-49263 ± 00	\$15,990.00	
B-49263 ± 00	\$15,990.00	

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation work by mechanical means (hydraulic excavator) manual labour at foundation trenches at drains foot increasing 1 below post two metre) in width or 10 sqm (ten square metre (sq plan) including bunding of sides and forming of bottom, at upto 1.5 m (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a limit of 50 m (fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all limits and its use and other incidentals. The rates are inclusive octroi, mystery, Maharashtra tax, GST or other taxes imposed by the Government.	27.49			Per cubic metre	
2	Providing and laying laid at wire cables with 4mm four millimetre dia G.I. wire conforming to IS: 2640 and IS: 4026 in 1000x100mm (one hundred mm one hundred millimetre) mesh including ten percent extra for laps and joints laid with more boulders weighing not less than 20kg (twenty five kilogram) each as per drawing and technical specification of IS: 1161, as per the direction of the Engineer-in-charge including entire carriage of material within all limits and the use and other incidentals. This item are inclusive octroi, mystery, Maharashtra tax, GST or other taxes imposed by the Government.	159.13			Per cubic metre	
					Total	

© 2000 Blackwell Science Ltd *Journal of Internal Medicine* 247: 399–407

Executive Engineer,
Tamil Devl Division,
HDPWD, Tamil Devl

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Uhal to Bagehra via Jandroo road km. 0/0 to 27/00 (SH:- Imp. Of curves at RD. 20/270 to 20/310).				Estimated Cost:-	Rs. 198861.00
				Earnest Money:-	Rs. 4000.00
				Time:-	Two Months
Sl. No.	Description of Items	Qty.	Rate		Amount
			In Fig.	In Words	
1	Excavation in hilly areas in all heights and depths and in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling /wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the technical specification clause 302.1603.1, 1603.2 sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un-useful material for filling in road ways, camber, embankment for grade improvement and disposal of all un-useful material to required width of the road or on approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and carriage of machineries materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and or labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. (Recovery of useful stone i.e. 120.05/- cubic metre shall be made from the contractor @ Rs. 300/- (three hundred only per cubic metre) amounting to Rs. 36,015/- only.	509.05			Per cubic metre
					Total

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devl Division,
 HPPWD, Tauni De

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Uhal to Bagehra via Jandroo road km. 0/0 to 27/00. (SH- Imp. Of curves at RD. 20/530 to 20/575).					Estimated Cost:- Rs. 470675.00
					Earnest Money:- Rs. 9400.00
					Time:- Two Months
Sr. No.	Description of Items	Qty.	Rate		Amount
			In Fig.	In Words	
1	Excavation in hilly areas in all heights and depths and in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling /wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line. (where width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the technical specification clause 302.1603.1, 1603.2 sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un-useful material for filling in road ways, camber, embankment for grade improvement and disposal of all un-useful material to required width of the road or on approved dumping sites through all modes of transportation including hand load or animals transport or mechanical means along with its leveling fine dressing and carriage of machines materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and or labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. (Recovery of useful stone i.e. 251.47/- cubic metre shall be made from the contractor @ Rs. 300/- (three hundred only per cubic metre) amounting to Rs. 75,441/- only.	1371.57			Per cubic metre
					Total

Terms and Condition

A. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devt Division,
 HPPWD- Tauni Devt.

Schedule of Quantity						
NAME OF WORK:- A/R & M/O on various roads under Tauni Devi Sub-Division. (S.H.- C/O various roads berms & road bed with earth fillings in Jandiroo section).				Estimated Cost:- Earnest Money:- Time:-		Rs. 388440.00 Rs. 7800.00 Two Months
Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not in depth consolidation each deposited layers by ramming and watering, lead upto 50mtr. (fifty metre) and fill upto 1.5mtr. (one point five metre) Engineer-in-Charge including entire cartage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3120.00			Per Cubic metre	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.

Amit Kumar

Executive Engineer,
Tauni Devi Division,
HPPWD, Tauni Dist.

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Phum to Andral Km 0/0 to 3/695. (SH:- Construction of toe wall for protection breast wall at RD 1/122 to 1/153.75)						
Estimated Cost:-				Rs.441751.00		
Earnest Money:-				Rs.8800.00		
Time:-				Two Months		
Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a level of 50m(fifty metre) dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary and upto 3m(three metre) depth as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all loads, lifts and other incidents. The rates are inclusive octroi, royalty, Malkana/toll tax, GST or other taxes imposed by the Government.	70.84			Per cubic metre	
2.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (one cement : five coarse sand): ten graded stone aggregate 40 mm(forty millimetre) nominal sizes as per the direction of Engineer-in-Charge including entire carriage of material within all loads and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana/toll tax, GST or other taxes imposed by the Government.	100.49			Per cubic metre	
3.00	Providing wrap holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 100mm (one hundred millimetre) dia PVC pipe the plain /manhole/venter having pressure 4kg per sqm (four kilogram) per square metre extending through the full width of the structures with slopes of 1(V): 20(H)(twenty) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204-3.7 as per the direction of Engineer-in-Charge including entire carriage of material within all loads and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana/toll tax, GST or other taxes imposed by the Government.	5.80			Each	
Terms and Condition					Total	

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division,
 HPPWD, Tauni

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Nanot to Bakkar Khat via Jamli road in Km 0/00 to 4/00, (SIH- Construction of retaining wall at RD 1/415 to 1/425)							Estimated Cost:- Rs.236619.00
Estimated Cost:- Rs.48000.00							Two Months
Sr. No.	Description of Items	Qty.	Rate		Unit	Amount	
			In Fig.	In Words			
1.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other debris/loose material and disposal upto a limit of 30m(fifty metre) dressing of sides and bottom and backfilling in trenches with excavated suitable material, ordinary soil upto 3m(three metre) depth as directed by Engineer-in-Charge all kinds of soil including entire carriage of material within all loads, lifts and other incidents.The rates are inclusive octroi, royalty, Malhana,toll tax, GST or other taxes imposed thereon by the Government.	24.48			Per cubic metre		
2.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering. All work up to plinth level 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm(forty millimetre) nominal size) as per the direction of Engineer-in-Charge including entire carriage of material within all loads and lifts and other incidents.The rates are inclusive octroi, royalty, Malhana,toll tax, GST or other taxes imposed by the Government.	52.86			Per cubic metre		
3.00	Providing sweep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 100mm (one hundred ten millimeter) dia PVC pipe to plinth /finish level having pressure 4kg per sqm (four kilogram) per square meter extending through the full width of the structures with slopes of (V): 20(H)(twenty) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204,3.7 and as per the direction of Engineer-in-Charge including entire carriage of material within all loads and lifts and other incidents.The rates are inclusive octroi, royalty, Malhana,toll tax, GST or other taxes imposed by the Government.	10.00			Each.		
					Total		

Terms and Condition

1. Work shall be executed as per PWD specification.

A. D. O.

Executive Engineer,
Tamil Devl Division,
HPPWD, Tamil Devl

Schedule of Quantity

NAME OF WORK:- Construction of boundary wall & gate at Rest House Uhal Distt. Hamirpur. [SH:- Construction of Estimated Cost:-						
boundary wall and gate 0/058 at RD 0/128)						
Earliest Money:-						
Time:-						
Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1.00	Excavation work by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm(ten square metre) in plan), including dressing of sides and (mining of bottoms, lift upto 1.5 m(one point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within all leads (Ordinary rock) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive of netrol, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	0.90			Per cubic metre	
2.00	Providing form work with steel plates 3.15mm(three point fifteen millimetre) thick welded with angle iron in frame 30x30x5mm(thirty into thirty into five millimetre) so as to give a fair finish including centring, shuttering, strutting and propping etc. with wooden battens and battens, height of propping and centring below supporting floor to ceiling not exceeding 4 Mtrs.(four metres) and removal of the same for cast-in-place concrete & plain concrete work in Foundation, footings, basins of columns etc. and mass concrete as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive of netrol, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	14.92			Per cubic metre	
3.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering all works upto plinth level 1:1 1/2:3 (one Cement : one and half coarse sand : three graded stone aggregate 20 mm(twenty millimetre) nominal size) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive of netrol, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	3.87			Per cubic metre	
4.00	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level Mild steel and Medium Tensile steel bars as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive of netrol, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	255.00			Per kilogram	
5.00	Structural steel work in single section, fixed with or without connecting plate including cutting, bolting, fixing in position and applying a priming coat of approved steel primer all complete as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive of netrol, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	1600.00			Per kilogram	

6.00	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (seven point five) in superstructure above plinth level up to floor level second class of brick work in Cement mortar 1:6 (one cement : six coarse sand) as per the direction of the Engineer-in-Charge and carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	20.26			Per cubic metre
7.00	15mm(fifteen millimetre) cement lime plaster in single coat on the rough side of brick/concrete/stone walls for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm(eighteen millimetre) in girth and finished even and smooth in cement mortar 1:4 (one cement : four sand) as per the direction of the Engineer-in-Charge and carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	20.39			Per square metre
Terms and Condition					Total

1. Work shall be executed as per PWD specification.

A. S. Qureshi
Executive Engineer,
Tajni Devi Division,
HBPWD: Tauni Qdki.

Schedule of Quantity

NAME OF WORK:- Construction of boundary wall at Rest House Uhal Distt. Hamirpur. (Sl:- Construction of boundary wall at RD 0/128 to 0/145 protection wall RHS of building 0/0 to 0/99)					Estimated Cost:- Rs.426981.00
					Rs.8500.00
					Two Months
Sr. No.	Description of Items	Qty.	Rate		Amount
			In Fig.	In Words	
1.00	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one-point five metre) in width or 10 sqm(ten square metre) on plan)including drristing of sides and ramming of bottoms, lift upto 1.5 m(one point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within all leads (Ordinary rock)as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	15.43			Per cubic metre
2.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering. All work up to plinth level 1:5:10 (one cement : five coarse sand); ten graded stone aggregate 40 mm(forty millimetre) nominal size(as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	25.38			Per cubic metre
3.00	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) dia PVC pipe (ie. pipes /finches)vetus having pressure 4kg per sqm (four kilogram) per square meter extending through the full width of the structures with slopes of (1V): 20(1H)(twenty) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 and as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	12.00			Each
4.00	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (seven point five) in superstructure above plinth level (up to four lead second class of brick work in Cement mortar 1:5 (one cement : six coarse sand) as per the direction of the Engineer-in-Charge and carriage of material within all leads and lifts and other incidents.The rates are inclusive of octroi, royalty, Malkana, toll tax, side tax, good service tax or other taxes imposed by the Government.	19.38			Per cubic metre
5.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering, all works upto plinth level 1:1½:3 (one Cement : one and half coarse sand : three graded stone aggregate 20 mm(twenty millimetre) nominal size) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	2.47			Per cubic metre

6.00	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level Mild steel and Medium Tensile steel bars as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive of octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	60.00			Per kilogram	
7.00	Structural steel work in single section, fixed with or without connecting plate, including cutting, bolting, fixing in position and applying a priming coat of approved steel primer all complete as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive of octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	1030.95			Per kilogram	
8.00	15mm(fifteen millimetre) cement lime plaster in single coat on the rough side of brick/concrete/stone walls for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm(eighteen millimetre) in girth and finished even and smooth in cement mortar 1:4(one cement : four sand) as per the direction of the Engineer-in-Charge and carriage of material within all leads and lifts and other incidents. The rates are inclusive of octroi, royalty, Malkana toll tax, sale tax, good service tax or other taxes imposed by the Government.	92.16			Per square metre	
					Total	

Terms and Condition

1. Work shall be executed as per PWD specification.


Executive Engineer,
Tamil Nadu Division,
H.O. Taunai, Taunai.

NAME OF WORK:- Restoration of ruin damages on Uppur to Bankar Khad via Kuthar Harizan Basti km. 0/0 to 4/0.(SH:- C/O wire create wall at RD. 1/660 to 1/679).						
Schedule of Quantity						
Sr.No	Description of Items	Qty.	In Fig.	Rate		Amount
				In Words		
				Time:-		
				Estimated Cost:-	Rs. 476648.00	
				Earnest Money:-	Rs. 9500.00	
				Two Months		
1	Excavation work by mechanical means (Hydraulic excavator) means means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm/ten square metre on plan) including dressing of sides and carrying of bobbins, lift upto 1.5 m. (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a limit of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire cartage of material within all limits and its and other incidentals. The rates are inclusive of octroi, royalty, Maharaajali (as. GST or other taxes imposed by the Government).	51.06			Per cubic metre	
2	Providing and laying laid in wire cranes with 4mm (four millimeters) dia G.I. wire conforming to IS:200 and IS: 4328 in 100x100mm (one hundred into one hundred millimeters) mesh including ten percent extra for laps and joints laid with stone boulders weighing not less than 25kg. (twenty five kilograms) each as per drawing and technical specification clause 1301, as per the direction of the Engineer-in-charge including entire cartage of material within all limits and its and other incidentals. The rates are inclusive of octroi, royalty, Maharaajali (as. GST or other taxes imposed by the Government).	161.48			Per cubic metre	
Terms and Condition						Total

A. S. S. S.
 Executive Engineer,
 Taintal Dist Division,
 H.P.W.D. Taintal Dist.

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Utpur to Balikar Khad via Kufliar Harizan Basti km. 0/0 to 4/0 (SH- C/O wire crate wall at RD. 2/210 to 2/220 and 2/255 to 2/264.20).

Rs. 481630.00

Rs. 96000.00

Two Months

Estimated Cost:-

Estimated Money:-

Time:-

Sr. No.	Description of Items	Qty.	In Fig.	Rate		Unit	Amount
				In Words	In Words		
1	Excavation work by mechanical means (hydraulic excavator) manual means in foundation trenches or drains (not exceeding 1.5m/one point five metre) in width or 10 sqm/ten square metre on plan) including dressing of sides and shoring of bottom, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a head of 50 m./fifty metre) as per the direction of the Engineer-in-charge including entire cartage of material within all loads and lifts and other incidentals. The rates are inclusive octroi, royalty, Mahatma toll tax, GST or other taxes imposed by the Government.	51.60				Per cubic metre	
2	Providing and laying laid in wire crates with 4mm (four millimeter) dia G.I. wire conforming to IS:200 and IS: 4826 in 100x100mm (one hundred into one hundred millimeters) mesh including ten percent extra for laps and joints laid with stone boulders weighing not less than 25kg. (twenty five kilograms) each as per drawing and technical specification clause 1301, as per the direction of the Engineer-in-charge including entire cartage of material within all loads and lifts and other incidentals. The rates are inclusive octroi, royalty, Mahatma toll tax, GST or other taxes imposed by the Government.	163.17				Per cubic metre	
						Total	

Terms and Condition

1. Work shall be executed as per PWD specification.

Anil Kumar

Executive Engineer,
Tamil Devl Division,
HPPWD, Tamil Nadu

Schedule of Quantity

NAME OF WORK:- C/O link road from Bajrol to Chumarda via Lamber km. 6/9 to 4/9 (SI):- Supplying and Installation of One all in one computer and Multi-Function Laser printer and UPS for HP-PWD., Sub-Division Kakhar, Division Taunt Devi Distt. Hamirpur (HP).										Estimated cost:- Rs. 208000.00 Earnest Money:- Rs. 6200.00 Time:- Two Months
Sr.No.	Description of Items	Qty.	Rate		Unit	Amount				
			In Fig.	In Words						
1	All in one computer Desktop with Intel Core i7-10700-10th Generation Processor, 16 GB RAM (1TB HD Drive (7200 rpm), 512 GB SSD) LED color display with FHD (1920x1080) Integrated HD Graphics and Webcam, 2xusb 3.0,2xUSB, 2.0 card reader Auto Jack VGA/HDMI/DP port 10/100/1000 M IPv6 compliant LAN, USB keyboard and mouse, Intel speakers 1x802 1.1b/g/n/ac PL-Window 10 Pro 64 bit OS with three years onsite warranty.s per the direction of the Engineer-in-charge including entire carriage of material within all loads and its and other incidentals.The rates are inclusive octroi, royalty, Makana,tdt tax, GST or other taxes imposed by the Government.	2.00			Each					
2	Laser MFC Printer 135 MFW with print scan and copy and Fax with A4 size paper, printing speed 20PPM, resolution 600x600 DPI Memory 64 MB, ADF/ADF/Platen Wireless connectivity, paper tray capacity 150 pages, USB 2.0 port with one year warranty.s per the direction of the Engineer-in-charge including entire carriage of material within all loads and its and other incidentals.The rates are inclusive octroi, royalty, Makana,tdt tax, GST or other taxes imposed by the Government.	2.00			Each					
3	UPS 1 KVA.s per the direction of the Engineer-in-charge including entire carriage of material within all loads and its and other incidentals.The rates are inclusive octroi, royalty, Makana,tdt tax, GST or other taxes imposed by the Government.	2.00			Each					
					Total					

Terms and Condition

1. Work shall be executed as per PWD specifications.

Amit Kumar

Executive Engineer,

Taunt Devi Division,

Hamirpur, Taunt Devi Distt.

Schedule of Quantity

NAME OF WORK:- C/O link road Mehli Bridge to village Thathi and Plahi to village Pargana km. 0/0 to 2/130. (S/N:- Supplying and installation of 3No. Computer and multi function laser printer and UPS for HP-PWD, Division Taunt Devi Distt. Himachal P.R.).

Rs. 462000.00
Rs. 92000.00
Two Months

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Dell desktop i5 11th Generation processor & 8GB DDR4 RAM 512 GB SSD Win-11 office 2021 Anonymous 22" display monitor (FHD) USB keyboard mouse as per direction of Engineer-in-Charge including entire cartage of material within all leads and lifts and other incidentals.	3.00			Each	
2	Laser jet all in one printer scanning/photocopy state, as per direction of Engineer-in-Charge including entire cartage of material within all leads and lifts and other incidentals.	3.00			Each	
3	UPS 1 KVA, as per direction of Engineer-in-Charge including entire cartage of material within all leads and lifts and other incidentals.	3.00			Each	
Total						

Terms and Condition

1. Work shall be executed as per PWD specifications.

A. Singh

Executive Engineer,
Taunt Devi Division,
Himachal Pradesh
Taunt Devi

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Uhal to Bakkar Khad via Parnali road 0/00 to 6/00. (Slt.-Construction of wire crate retaining wall at RD 1/535 to 1/553)					
Sr. No.	Description of Items	Qty.	Rate		Per m
			In Fig.	In Words	
1.00	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm(thirty centimetre) in depth, 1.5 metre point five metre) in width as well as 10 sqm(ten squaremetre) on plan) including getting out and disposal of excavated earth upto 50 m (fifty metre) and lift upto 1.5 metre point five metre). Ordinary rock as per the direction of the Engineer-in-Charge and cartage of material within all loads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	74.49			
2.00	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia G.I wire conforming to IS:280 and IS:4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10(ten) per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg (twenty five kilogram) each as per drawing and technical specifications Clause 1301 as per drawing and technical specification clauses 614, 709, 1294.3.7 and as per the direction of Engineer-in-Charge including entire cartage of material within all loads and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	152.98			

Terms and Condition

1. Work shall be executed as per PWD specification.

© 2006 The Authors
Journal compilation © 2006 Blackwell Publishing Ltd

Rs. 7100.00
Two Months

[illegible]

A. S. Gamm
Executive Engineer,
Taunt Dev Division,
Taunt Dev. Apprb: Taunt Dev.

Schedule of Quantity						
NAME OF WORK:- Restoration of rain damages on various road under Kakkar Sub-Division HP-PWD., Tauni Devi.				Estimated Cost:-		Rs. 481000.00
SH:- Hiring of JCB/front end Loader for removal of slips, back filling of R/Wall under Kakkar-1 and Kakkar-II				Earnest Money:-		Rs. 9600.00
Section:-				Time:-		Two Months
Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Hiring of J.C.B. (front end loader 1 cum capacity with breaker) for widening of road, repair of berms, removal of slips and clearance of drains in all kinds of soil including breaking and chiselling with breaker of soft and hard rock as per direction of Engineer in charge. The JCB or breaker should be made available by the contractor as and when required even on Sunday and other holiday. JCB should be worked minimum 8.00 hours from 9.00AM to 5.00 PM daily and any loss to the public/private property or any accident etc. happened during the course of hiring period shall be the absolute responsibility of the JCB owner which shall have fully compensated by the contractor in all cases. The log book will be maintained at site which should be duly verified by the Engineer-in-charge.	370.00			Per hour	
Total						

Terms and Condition

1. The contractor shall be responsible for any kind of breakage in the machinery and accident happens during working hours.
2. Nothing shall be paid for idle hours
3. All bear and tear and POL charges are to be born by the contractor.

A. K. Singh
Executive Engineer,
Tauni Devi Division,
HP-PWD, Tauni Dist.

Schedule of Quantity

NAME OF WORK:- Restoration rain damages on Hindu Di Dhar via landroo road Km 0/0 to 9/00. (SIH-ROFD at Km 3/195 to 3/255)				Estimated Cost:-	Rs.318488.00
				Earnest Money:-	Rs.6400.00
				Time:-	Two Months
Sr. No.	Description of Items	Qty.	Rate		Amount
			In Fig.	In Words	
1	Excavation in hilly areas in all heights and depths and in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling /wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grades width turning and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the technical specification clause 302.1603.1,1603.2 sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un-useful material for filling in road ways, camber, embankment for grade improvement and disposal of all un-useful material to required width of the road or on approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling firm dressing and carriage of machineries materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and or labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. (Recovery of useful stone i.e. 87.68 cubic metre shall be made from the contractor @ Rs. 300/- per cubic metre amounting to Rs 24,504 /- only).	569.85			Per cubic metre
				Total	

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division,
 HPPWD Tauni Dhr.

Schedule of Quantity

NAME OF WORK:- Restoration of raila damages on Banaf to Chamliana via Munglehar Dudhhar km. 0/0 to 7/185.(SHE:- C/O R/Wall at RD. 3/470 to 3/490).

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1.	Excavation work by mechanical means (hydraulic excavator) manual means in foundation trenches or drains (not exceeding 1.5m deep) in width or 10 sqm (not square metre) or plan, including clearing of sides and running of bullocks, etc upto 1.5 m, (one point five metre) including getting rid of the excavated soil and disposal of surplus excavated soils as directed, within a limit of 50 m (fifty metres) as per the direction of the Engineer-in-charge including entire carriage of material within all heads and its and other incidentals. The rates are inclusive octroi, royalty, Mahanulal tax, GST or other taxes imposed by the Government.	63.80			Per Cubic metre	
2.	Providing and laying cement concrete in retaining walls, return walls, wells (any thickness) including attached platforms, columns, piers, abutments, pillars, posts, shafts, buttresses, string or facing openings, parapets, coping, lead blocks, anchor blocks, plain window sills, bluffs, window floor etc., up to floor any level, including the cost of cementing, shuttering and formwork, 1:5:10 (one cement, five coarse sand) : 100 graded stone aggregate 40 mm (forty millimetre nominal size) as per the direction of the Engineer-in-charge including entire carriage of material within all heads and its and other incidentals. The rates are inclusive octroi, royalty, Mahanulal tax, GST or other taxes imposed by the Government.	90.80			Per Cubic metre	
3.	Providing wood holes in load-bearing masonry/ plain reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 150mm (one hundred ten millimetre) dia PVC pipe (De-paint/Free/No) vector pipe having pressure 4kg per centimetre square (four kilogramme per centimetre square) extending through the full width of the structures with a slope of 1:10 (one towards drawing face) complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer-in-charge, including entire carriage of material within all heads and its and other incidentals. The rates are inclusive octroi, royalty, Mahanulal tax, GST or other taxes imposed by the Government.	55.00			Each	
4.	Providing and laying 150mm (one hundred ten millimetre) dia PVC pipe (De-paint/Free/No) vector pipe having pressure 4kg per centimetre square (four kilogramme per centimetre square) extending through the full width of the structures with a slope of 1:10 (one towards drawing face) complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer-in-charge, including entire carriage of material within all heads and its and other incidentals. The rates are inclusive octroi, royalty, Mahanulal tax, GST or other taxes imposed by the Government.	19.00			Per cubic metre	
					Total	

Terms and Conditions

1. Work shall be executed as per PWD specifications.


 Executive Engineer,
 Tansen Diesel Division,
 Bhopal-Tansen Diesel

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Banal to Chamla via Manglebar Daddar km. 0/0 to 7/185.(SH- C/O R/Wall at RD. 1/817 to 1/828 and 4/080 to 4/095).

Rs. 437551.00

Rs. 88900.00

Two Months

Estimated Cost:-

Estimated Money:-

Time:-

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation work by mechanical means (Hydraulic excavator) manual means is foundation trenches or drain (not exceeding 1.5m (one point five meter) in width or 10 sqm (ten square meter) on plan) including dressing of sides and carrying of bottom, up to 1.5 m, (one point five meter) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m (fifty meter) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Mahanadi tax, GST or other taxes imposed by the Government.	54.22			Per Cubic metre	
2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached piers, columns, piers, abutments, pillars, posts, stairs, buttresses, wing or facing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, custom floor etc., up to floor any level, including the cost of centering, shuttering and finishing 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (ten millimeters nominal size), as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Mahanadi tax, GST or other taxes imposed by the Government.	92.50			Per Cubic metre	
3	Providing weep holes in brickwork masonry (plain reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm (one hundred ten millimeter) dia PVC pipe. De-plasticized wet mix gun having pressure 4kg per centimeter square (four kilogramme per centimeter square) extending through the full width of the structures with slopes of (10: 20(H) towards drawing face complete as per drawing and technical specifications clauses 614, 758, 1204.3.7 as per direction of Engineer-in-charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Mahanadi tax, GST or other taxes imposed by the Government.	48.00			Each	
4	Providing and laying three leads with granular crushed aggregates as per specification to a thickness of not less than 500mm (one hundred millimeter) with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification clause 1204.3.8 as per direction of Engineer-in-charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Mahanadi tax, GST or other taxes imposed by the Government.	15.60			Per cubic metre	
					Total	

Terms and Condition:

1. Work shall be executed as per PWD specifications.


 Executive Engineer,
 Yamal Devi Division,
 Highway: Yamal Devi

Schedule of Quantity

NAME OF WORK:- C/D Hill Road Kuthera to Chalokhar via Del-Ka-Naan km. 0/0 to 2/700. (SH- P/L roller compacted concrete (M-30) grade at RD: 2/115 to 2/242). (Under GTMNP)

Estimated Cost:-
Rs. 49,474.60
Rs. 10060.00

Sr.No.	Description of Items	Qty.	In Fig.	Rate		Unit	Amount
				In	Wards		
1	Excavation work by mechanical means (hydraulic excavator) manual means in foundation trenches or drains (not exceeding 1 metre depth) in width or 10 sqm (ten square metres on plan) including dressing of sides and ramming of bottom, all upto 1.5 m (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a limit of 50 m (fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all lands and its, and other incidentals. The rates are inclusive of oil, royalty, Malabar, toll tax, GST or other taxes imposed by the Government.	11.43				Per Cubic metre	
2	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at CMC in mechanical mixer (Pug Mill), carriage of mixed material by tapper to site, laying in uniform layers in sub-base courses on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100 kN (eighty kilo Newton) weight to achieve the desired density including lighting, bankside and maintenance of diversion, as per Tables 400, 11 & 400.12 and Technical Specification Clause 406 by mechanical means in two layers, and as per direction of Engineer-in-charge including entire carriage of materials within all lands and its and other incidentals. The rates are inclusive of oil, royalty, Malabar, toll tax, GST or other taxes imposed by the Government.	11.43				Per Cubic metre	
3	Construction of roller compacted concrete pavement (RCCP) with coarse and fine aggregates conforming to IS 383, the size of coarse aggregate not exceeding 25mm (twenty five millimetre) with minimum aggregate content ratio of 5:1 mm (five : one) millimetre and with minimum cement content of 310 kg. (Three hundred ten kilograms) per cubic metre aggregate gradation to be as per table 602.2 after blending, mixing in concrete mixer at optimum moisture content, transporting to site, laying with wheel borrows or steel pans or with mechanical power, compacting with 80-100 kN smooth wheel, tandem vibratory roller, to achieve, the designed flexural strength, finishing and curing as per drawings and technical specification clause 1502, as per direction of Engineer-in-charge, including entire carriage of material within all lands and its and other incidentals. The rates are inclusive of oil, royalty, Malabar, toll tax, GST or other taxes imposed by the Government.	66.68				Per Cubic metre	
Total						Total	

Terms and Conditions

1. Work shall be executed as per PWD specifications.

Amit Kumar
Executive Engineer,
Tamil Nadu Division,
Haryana, Tamil Nadu

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on link road Rec to Garthbali via Balyana km. 0/0 to 2/700b (SH- C/O R/Wall RD, 0/252 to 0/264)

Estimated Cost:- Rs. 494850.00

Earnest Money:- Rs. 98962.50

Time:- Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation work by mechanical means (hydraulic excavator) manual means in foundation trenches or drains (not exceeding 1.5m/one point five metre) in width or 10 sqm/ten square metre on plan) including dressing of sides and rendering of bottoms, at upto 1.5 m. (one point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed within a limit of 50 m/fifty metre) as per the direction of the Engineer-in-charge including entire cartage of material within all leads and lifts and other incidentals The rates are inclusive octroi, royalty, Mahasabji tax, GST or other taxes imposed by the Government.	44.54			Per Cubic metre	
2	Providing and laying colour concrete in retaining walls, return walls, walls (any thickness) including attached pillars, columns, piers, abutments, pillars, posts, drains, buttresses, string or facing courses, parapets coping, lead blocks, anchor blocks, plain window sills, floors, sunken floor etc., up to floor any level, including the cost of centring, shuttering and finishing: 1:5:10 (one cement: five coarse sand): ten graded stone aggregate 40 mm (forty millimetres nominal size) as per the direction of the Engineer-in-charge including entire cartage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Mahasabji tax, GST or other taxes imposed by the Government.	113.76			Per Cubic metre	
3	Providing weep holes in brickwork masonry (plain) reinforced concrete abutments, wing walls, return walls, retaining walls and breast wall with 100mm (one hundred ten millimeter) dia PVC pipe. De-plasticized vescon pipe having pressure 4kg per centimeter square (four kilogram per centimeter square) extending through the full width of the structures with slopes of (V) 20(H) towards drawing face complete as per drawing and technical specification clauses 514, 709, 1204.3.7 as per direction of Engineer-in-charge, including entire cartage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Mahasabji tax, GST or other taxes imposed by the Government.	24.00			Each	
Totals and Conditions					Total	

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tamsil Road Division,
 HPPWD, Tamsil Road

NAME OF WORK: C/O Enis road Chatelet to Tilihar via Dehra Dun. 0/0 to 3/500. Sit. C/O 900mm dia maine pipe cover.

Terminated Conditions

Work shall be executed in per IWS specification.

Arif Khan
Executive Engineer,
Tamil Nadu Division,
Tamil Nadu Development

Schedule of Quantity

NAME OF WORK:- C/O Balance approach road for ITI building at Utpur. (SH:- F/C 5/7mtr. wide road at RD. 0/135 to 0/237).

(Deposit work).

Estimated Cost:- Rs. 487751.00

Earnest Money:- Rs. 97000.00

Time:- Two Months

Sr.No.	Description of Items	Qty.	In Fig.	Rate		Unit	Amount
				In Words			
1	Excavation in hilly areas in all heights and depths and in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling, wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the technical specification clause 302.1603.1.1603.2 sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un-useful material for filling in road ways, camber, embankment for grade improvement and disposal of all un-useful material to required width of the road or on approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and carriage of machineries materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and or labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. (Recovery of useful stone i.e. 124.61/- cubic metre shall be made from the contractor @ Rs. 300/- (three hundred only per cubic metre) amounting to Rs. 37,383/- only)	1038.33				Per cubic metre	
						Total	

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division,
 H.P.W.D. Tauni Devi

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Kakkar to Bakkar Khad via Ghodlamber km. 0/00 to 2/650 (SH:-
Hiring of hydraulic excavator/Poclain for removal of slips back filling of R/Walls, clearing of drain).

Estimated Cost:- Rs. 497000.00

Earliest Money:- Rs. 10000.00

Time:- Two Months

Sl. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Hiring of Excavator cum loader (Poclain/L&T) with 90-HP engine and lifting capacity of minimum 5000kgs-including P.O.L charges, shifting charges and other ancillary equipment as required of site of work for removal of slip in all kind of soil such as kanker, moorum single boulder decomposed or soft variety of soil such as spade work pick work, junger work soft hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-servicable material has to be done in the acquired width of the road to avoid damage to the properties of the people or incase any damages took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stone from removal of slips shall have to be neatly stacked along side on road burms. The work shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instruction of the Engineer-in-Charge. as per direction, including entire carriage of material within all leads and lifts and other incidentals.	142.00			Per Hour	
Total						

Terms and Condition

1. The contractor shall be responsible for any kind of breakage in the machinery and accident happens during working hours.
2. Nothing shall be paid for idle hours.
3. All bear and tear and P.O.L charges are to be born by the contractor.


Executive Engineer,
Traffic Devt Division,
HAWARI, Tamsi Dist.

Schedule of Quantity

NAME OF WORK:- C/O Assistant Engineer Office Cum Residence at Kaldkar, Tehsil Tauni Devi Distt.

Estimated Cost:- Rs. 496743.00

Location of Work:- (Site) Site - 1

Estimate No.:- 100/00

Unit:- as per schedule

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation in hilly areas in all heights and depths and in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling /wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the technical specification clause 302, 1803.1, 1803.2 setting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un-useful material for filling in road ways, camber, embankment for grade improvement and disposal of all un-useful material to required width of the road or on approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and carriage of machineries materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and or labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. (Recovery of useful stone i.e 121.95 /-cubic metre shall be made from the contractor @ Rs. 300/- (three hundred only per cubic metre) amounting to Rs. 36,585/- only.	813.00			Per cubic metre	
					Total	

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division,
 H.P.W.D. Tauni Devi

Schedule of Quantity

NAME OF WORK:- C/O Assistant Engineer Office Cam Residence at Kakkar, Tehsil Tauni Devi Distt. Hamirpur (HP) (SH- Site development).

Estimated Cost:-
Rs. 497776.00
Earnest Money:-
Rs. 10000.00
Time:-
Two Months

Sr.No.	Description of Items	Qty.	In Fig.	Rate		Unit	Amount
				In Words			
1	Excavation in hilly areas in all heights and depths and in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling /wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grades with cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the technical specification clause 302.1603.1, 1603.2 sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un-useful material for filling in road ways, camber, embankment for grade improvement and disposal of all un-useful material to required width of the road or on approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and cartage of machineries materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and or labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including cartage of material within all leads and lifts. (Recovery of useful stone i.e. 122.20 /-cubic metre shall be made from the contractor @ Rs. 300/- (three hundred only per cubic metre) amounting to Rs. 36,660/- only.	814.69				Per cubic metre	
						Total	

Terms and Condition

1. Work shall be executed as per PWD specification.

Amit Kumar
Executive Engineer,
Tauni Devt Division
H.P.W.D. Tauni Distt.

Schedule of Quantity						
NAME OF WORK:- Restoration of rain damages on link road to Chalelli to Tikkar via Debra Km 0/0 to 3/0 under Sujapur Sub-Division (Chabutra Section) [SH:- Hiring of JCB/Front loader for removal of slips, dressing of berms clearance of drains]				Estimated Cost:- Rs.182000.00 Earnest Money:- Rs.3600.00 Time:- Two Months		
Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1.00	Hiring of JCB (front end loader 1 cum(one cubic metre) capacity with breaker) for widening of road, repair of berms, removal of slips and clearance of drains in all kind of soil including breaking and chiselling with tumbler of soft and hard rock as per direction of Engineer in charge. The JCB or breaker should be made available by the contractor as and when required even on Sunday and other holiday. JCB should be worked minimum 8-00 hours from 9-00 AM to 5:00 PM daily and any loss to the public/private property or any accident etc. happened during the course of hiring period shall be the absolute responsibility of the JCB owner which shall have fully compensated by the contractor in all cases. The log book will be maintained at site which should be duly verified as per the direction of Engineer in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive of fuel, royalty, Mahanatal tax, GST or other taxes imposed by the Government.	140.00			Per Hour	
Total						

Terms and Condition

1. The contractor shall be responsible for any kind of breakage in the machinery and accident.
2. Nothing shall be paid for idle hours.
3. All bear and tear and POL charges are to be born by the contractor.

A. Singh
Executive Engineer,
Tangai Devi Division,
HPPWD, Tangai Devi

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on link road from Jandron road to Harizan Basti Dhar Baghara km. 0/70 to 500. (SR- C/O wire crates at RD. 0/190 to 0/210). (LHS)

Estimated Cost:- Rs. 479,386.00

Earnest Money:- Rs. 96,000.00

Time:- Two Months

S. No.	Description of Items	Qty.	In Fig.	Rate		Unit	Amount
				In Words	In Words		
1	Excavation work by mechanical means (Hydraulic excavator) natural means in foundation trenches or drains (not exceeding 1.5 metre deep five metre) in width or 10 sqm (ten square metre on plan) including dressing of sides and widening of bottom, up to 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m. (fifty metre) as per the direction of the Engineer-in-charge including cartage of material within all leads and its and other incidentals. This rates are inclusive of cartage, royalty, Mahanagar tax, GST or other taxes imposed by the Government.	31.25				Per cubic metre	
2	Providing and laying laid in wet drains with 4cm (four millimetre) dia G.I. wire conforming to IS: 280 and IS: 4026 # 100x10mm (one hundred x ten one hundred millimetre) mesh including ten percent extra for laps and joints laid with stone boulder weighing not less than 20kg. (twenty five kilogram) each as per drawing and technical specification clause 1301, as per the direction of the Engineer-in-charge including entire cartage of material within all leads and its and other incidentals. This rates are inclusive of cartage, royalty, Mahanagar tax, GST or other taxes imposed by the Government.	156.25				Per cubic metre	
						Total	

Terms and Condition

Work shall be executed as per PWD specifications.

A. N. Singh

Executive Engineer,
Tehsil Development Division,
Jalandhar, Punjab

Schedule of Quantity

NAME OF WORK:- Rectification of rain damages on link road from Sangri Khad to Hartian Basti Sapahad km. 0/00 to 2/00 (SH-1)
C/O 0/Wall from RD. 0/015 to 0/027.

Estimated Cost:- Rs. 46,470.00
Estimated Money:- Rs. 9,300.00
Time:- Two Months

Sl. No.	Description of Items	Qty.	In Fig	Rate		Unit	Amount
				In Words			
1	Excavation work by mechanical means (hydraulic excavator) manual means in foundation trenches or drains (not exceeding 1.50m wide) for rain water, width 1.50m, depth 1.50m, including clearing of soil and forming of trench, 1:1 slope, 1.5m, (not paid for) including cutting and disposal of surplus excavated soil as directed, within a limit of 50 m, (not paid for) as per the direction of the Engineer-in-charge and using entire design of masonry when at least and the soil of other materials. The rates are inclusive of all taxes, cesses, Mahanagar tax, GST or other taxes imposed by the Government.	3.314				Per cubic metre	
2	Reinforcing and laying concrete in retaining walls with width 1.50m, including structural elements, columns, piers, abutments, pillars, piers, buttresses, string, or facing concrete, parapet coping, bed blocks, arches, sills, piers, window sills, etc., within 1.50m, 1.50m, 1.50m, including the cost of forming, casting and finishing, 1:1.50 (not paid for) as per the direction of the Engineer-in-charge and using entire design of masonry when at least and the soil of other materials. The rates are inclusive of all taxes, cesses, Mahanagar tax, GST or other taxes imposed by the Government.	78.00				Per cubic metre	
3	Plastering work in retaining walls with width 1.50m, including structural elements, columns, piers, abutments, pillars, piers, buttresses, string, or facing concrete, parapet coping, bed blocks, arches, sills, piers, window sills, etc., within 1.50m, 1.50m, 1.50m, including the cost of forming, casting and finishing, 1:1.50 (not paid for) as per the direction of the Engineer-in-charge and using entire design of masonry when at least and the soil of other materials. The rates are inclusive of all taxes, cesses, Mahanagar tax, GST or other taxes imposed by the Government.	36.00				Each	
4	Painting work in retaining walls with width 1.50m, including structural elements, columns, piers, abutments, pillars, piers, buttresses, string, or facing concrete, parapet coping, bed blocks, arches, sills, piers, window sills, etc., within 1.50m, 1.50m, 1.50m, including the cost of forming, casting and finishing, 1:1.50 (not paid for) as per the direction of the Engineer-in-charge and using entire design of masonry when at least and the soil of other materials. The rates are inclusive of all taxes, cesses, Mahanagar tax, GST or other taxes imposed by the Government.	1.50				Per cubic metre	
	Total					Total	

Terms and Condition

a. Work shall be executed as per PWD specifications.


 Executive Engineer,
 Tarni Devd Division,
 H.P.P.D. Tarni Devd

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on (Uhal to Bakkar Khad via Parnali road 0/00 to 6/00. (SH--Construction Estimated Cost:- Rs.478160.00 of wire crate retaining wall at RD 0/810 to 0/828.10)					
Earmest Money:- Rs.9600.00					
Time:- Two Months					
Sr. No.	Description of Items	Qty.	Rate		Amount
			In Fig.	In Words	
1.00	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm(thirty centimetre) in depth, 1.5 m(one point five metre) in width as well as 10 sqm(ten squaremetre) on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty metre) and lift upto 1.5 m(one point five metre). Ordinary rock as per the direction of the Engineer-in-Charge and carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	75.32			Per cubic metre
2.00	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming of IS:280 and IS:4026 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10(ten) per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg (twenty five kilogram) each as per drawing and technical specifications Clause 1301as per drawing and technical specification clauses 614, 709, 1204.3.7 and as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	154.68			Per cubic metre
Terms and Condition			Total		

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devl Division,
 HPPWD, Tauni Dighi.

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages Solajpur Sandhole road km. 3/00 to 20/00 (MDR-38) (SR: C/O solid causeway at Jakhno at RD. 11/500 and C.C. pavement at RD. 11/800).					
Estimated Cost:-			Rs. 489515.00		
Earliest Money:-			Rs. 9800.00		
Time:-			Two Months		
Sr.No.	Description of Items	Qty.	Rate		Amount
			In Fig.	In Words	
1	Excavation work by mechanical means (Hydraulic excavator) manual means in bundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm(ten square metre on plan) including dressing of sides and rarming of bottoms, its upto 1.5 m, (one point five metre) including getting rid the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m (fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidents the rates are inclusive octroi, royalty, Mahana,toll tax, GST or other taxes imposed by the Government.	38.38		Per Cubic metre	
2	Stone spling properly hand packed filling interlocks with Khariya stone and consolidating with power road roller to the requested gradient and camber including spreading watering and rolling of bedding materials moorum or earth etc. complete as per HP-PWD. specification 100mm(one hundred millimeters) spread thickness (finished work including materials and labour) in all leads and lifts and dressing of sides and bottom and as per the direction of Engineer-in-charge including entire carriage of material within all leads and lifts and other incidents The rates are inclusive octroi, royalty, Mahana,toll tax, GST or other taxes imposed by the Government.	10.50		Per Cubic metre	
3	Providing and laying in position cement concrete of specified grade including the cost of confining and shuttering - All work up to plinth level 1:2.5 (one cement: three sand: six graded stone aggregated 20mm (twenty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidents The rates are inclusive octroi, royalty, Mahana,toll tax, GST or other taxes imposed by the Government.	13.13		Per Cubic metre	
4	Continuance of reinforcement plain cement concrete pavement thickness as per design after it prepared sub-base with 43 grade cement or all other type as per clause 1501.2.2.2 M-25 (twenty five) (grade) with minimum cement content not less than 400kg/cum (one design with plasticizer) coarse and fine aggregates conforming to IS. 383, maximum size of coarse aggregate not exceeding 25mm (twenty five millimeters) mixed in a concrete mass of not less than 0.25cum (zero point two cubic metre) capacity and appropriate weigh batching approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 425 micron thick polythene film, wedges, steel plates including leveling the formwork as per drawing, spreading the concrete with shovel rollers compacted using plate vibrators and finished in construction operation including provision of expansion and contraction joints curing of concrete slabs for 14 days with water, finishing to lines and grades as per drawing and technical specification Chapter 1501 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidents The rates are inclusive octroi, royalty, Mahana,toll tax, GST or other taxes imposed by the Government.	63.00		Per Cubic metre	
			Total		

Terms and Condition

1. Work shall be executed on per PWD specification.


 Executive Engineer,
 Tamil Desal Division,
 HPPWD, Tamil Nadu

Schedule of Quantity

NAME OF WORK:- C/O motorable link road 5.7 metr. Wide from Dusatarka to village Ropa.(SH- Formation cutting from RD. 0/00 to 0/165). (Deposit work).				Estimated Cost:- Rs. 141699.00	
				Earnest Money:- Rs. 2800.00	
				Time:- Two Months	
Sr.No.	Description of Items	Qty.	In Fig.	Rate In Words	Unit Amount
1	Excavation in hilly areas in all heights and depths and in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling /wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the technical specification clause 302.1803.1, 1803.2 sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un-useful material for filling in road ways, camber, embankment for grade improvement and disposal of all un-useful material to required width of the road or on approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its levelling line dressing and carriage of machineries materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and or labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including cartage of material within all leads and lifts. (Recovery of useful stone i.e. 50.41/- cubic metre shall be made from the contractor @ Rs. 300/- (three hundred only per cubic metre) amounting to Rs. 15,123/- only.	840.19			Per cubic metre
					Total

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tamsi Devl Division,
 W.P.W.D. Tamsi Devl

Schedule of Quantity

NAME OF WORK: Construction of Junior Engineer Office Cum Residence at Bharneli (section Chabutra) HPPWD Estimated Cost:- Rs.441649.00					
Sojanpur Distt. Hamirpur(HP), (SR:- Providing and fixing glazed and wire gauge) shutter, main gate, boundary wall Earnest Money:- Rs.8800.00					
Sr. No.	Description of Items	Qty.	Rate		Amount
			In Fig.	In Words	
					Two Months
1	Providing and fixing glazed shutters for doors, windows and clerestory windows using 4 mm (four millimetre) thick float glass panes, including ISI marked M.S. pressed butt hinges bright finished of required size with necessary screws. Second class teak wood 30 mm(thirty millimetre) thick as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	16.81			Per square metre
2	Providing and fixing wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm (one point four millimetre) in both directions with wire of dia 0.63 mm(zero point sixty three millimetre), for doors, windows and clerestory windows with hinges and necessary screws 35 mm(thirty five millimetre) thick shutters with ISI marked M.S. pressed butt hinges bright finished of required size. Second class teak wood as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	21.73			Per square metre
3	Providing and fixing M.S. Tubular frames for doors, windows, ventilators and cupboard with rectangular/ L Type sections, made of 1.60 mm(one point six zero millimetre) thick M.S. Sheet, joint's mitted, welded and grinded finish, with profiles of required size, including fixing of necessary butt hinges and screws and applying a priming coat of approved steel primer. Fixing with 15x3 mm(fifteen into three millimetre) lugs 10cm(ten centimetre) long embedded in cement concrete block 15x10x10 cm(fifteen into ten into ten centimetre) of cement concrete 1:3:6 (one Cement : three coarse sand : six graded stone aggregate 20 mm(twenty millimetre) nominal size) as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	648.30			Per kilogram
4	Providing and fixing 25mm (twenty five millimetre) dia stainless steel curtain pipe including bracket and side cover ornamental including fixing complete as as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	47.65			Per running metre
5	Providing and fixing curtain for door and window with cloths of size 6x7 size as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	92.00			Each

6	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fitting in position and applying a priming coat of approved steel primer oil complete as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	316.00			Per kilogram
7	Providing and fixing 4mm (four millimetre) thick corresponding to SWG-815cm * 15cm (eight hundred fifteen centimetre into fifteen centimetre) mesh with steel member (steel angle paid for separately) as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	150.00			Per square metre
8	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m one point five metre) in width or 10 sqm (ten square metre) on plan, including dressing of sides and ramming of bottoms, lift upto 1.5 m (one point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within all loads of 50m (fifty metre) (Ordinary rock) as per the direction of Engineer-in-Charge including entire carriage of material within all loads and lifts and other incidents. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	2.92			Per cubic metre
9	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering 1:4:8 (one cement : four coarse sand : eight graded stone aggregate) 40mm (forty millimetre) nominal size graded stone aggregate upto plinth level including entire carriage of materials in all loads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.92			Per cubic metre
Terms and Condition					Total

1. Work shall be executed as per PWD specification.

A. S. R.
Executive Engineer,
Tamil Nadu Division,
HPPWD, Tamil Nadu

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on link road Kakkar to Balikar Khad via Ghodilamber km. 0/00 to 2/650) (SB:-
F.O PCC B/Wall near the house of Smt. Hasina devi W.O. Sanjay Kumar at RD. 0/350 to 0/385) (Deposit work).

Rs. 194885.00

Rs. 3900.00

Two Months

Estimated Cost:-

Earnings Money:-

Time:-

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation work by mechanical means (hydraulic excavator) manual means in foundation trenches or drains (not exceeding 1.50sqm per line meter) in width or 10 sqm per square meter on plan) including dressing of sides and jacking of bottom, till upto 1.5 m, (one point five meter) including piling out the excavated soil and disposal of surplus excavated soils as directed, within a haul of 50 m. (offy meter) as per the direction of the Engineer-in-charge including entire cartage of material within all loads and its and other incidents. The rates are inclusive octroi, royalty, Mahanadi tax, GST or other taxes imposed by the Government.	18.04			Per Cubic metre	
2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pillars, columns, pipes, abutments, pillars, piers, abutments, string or facing courses, jetty walls, coping, bed blocks, arches blocks, plain window sills, drains, walling floor etc., up to floor any level, including the cost of centering, shading and finishing: 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (forty millimeters nominal size) as per the direction of the Engineer-in-charge including entire cartage of material within all loads and its and other incidents. The rates are inclusive octroi, royalty, Mahanadi tax, GST or other taxes imposed by the Government.	44.54			Per Cubic metre	
3	Providing sweep holes in brickwork masonry plain reinforced concrete abutment, wing walls, return walls, retaining walls and broad wall with 110mm (one hundred ten millimeter) dia PVC pipe (De-plasticized) vector pipe having pressure 4kg per centimeter square (four kilogram per centimeter square) extending through the full width of the structure with slopes of (1V: 20H) towards drawing face complete as per drawing and technical specification clauses 614, 706, 1204.3.7 as per direction of Engineer in - Charge, including entire cartage of material within all loads and its and other incidents. The rates are inclusive octroi, royalty, Mahanadi tax, GST or other taxes imposed by the Government.	10.00			Each	
					Total	

Terms and Condition

1. Work shall be executed as per PWD specification.

A. S. Chavhan

Executive Engineer,
Tashti Devi Division,
Hidnardi Taluk Dist.

Schedule of Quantity

NAME OF WORK:- Restoration of rains damages on Bamirpur Sujangpur road km. 16/00 to 24/705. (381 - C/O Alamgaur side wing wall of Alamgaur Bridge at Beas River at RD. 24/775 to 24/778).

Estimated Cost:-
Rs. 439267.00

Rs. 88000.00

Sr.No.	Description of Items	Qty.	In Fig.		Unit	Amount
			Base	In Words		
1	Excavation work by mechanical means (hydraulic excavator) manual means in foundation trenches or drains (not exceeding 1.50m depth) in width of 10 cm, in square metre (in plan) including shoring of sides and removing of bottom, in upto 1.5 m, (one paid two meter) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a limit of 50 m (fifty meter) as per the direction of the Engineer-in-Charge including cartage of material within all kinds and its and other incidentals. The rates are inclusive octroi, royalty, Mahasabai tax, GST or other taxes imposed by the Government.	28.28			Per Cubic metre	
2	Providing and laying cement concrete in masonry walls, retaining walls (any thickness) including attached pillars, columns, piers, abutments, pillars, foots, chisels, buttresses, string or facing (curtain, parapet coping, low breast, anchor blocks, plain window sills, etc., surface four or up to four any level, including the cost of setting, shoring and building 1:5:10 (one cement, two coarse sand) - for graded aggregate 40 mm (four millimetre) nominal size, as per the direction of the Engineer-in-Charge including cartage of material within all kinds and its and other incidentals. The rates are inclusive octroi, royalty, Mahasabai tax, GST or other taxes imposed by the Government.	2.90			Per Cubic metre	
3	Providing and laying in position concrete (curtain) of specified grade including the cost of excavating and shoring - All work up to 1.50 m (one meter) - from concrete (one course sand) in gabion stone aggregate 40 mm (four millimetre) nominal size, as per direction of Engineer-in-Charge including cartage of material within all kinds and its and other incidentals. The rates are inclusive octroi, royalty, Mahasabai tax, GST or other taxes imposed by the Government.	64.26			Per Cubic metre	
4	Steel reinforcement for RCC work including transportation, cutting, bending, placing in position and tying of complete slab with level as per direction of Engineer-in-Charge, including cartage of material within all kinds and its and other incidentals. The rates are inclusive octroi, royalty, Mahasabai tax, GST or other taxes imposed by the Government.	1500.00			Per kilogramme	
5	Providing wet set form in brick lining masonry (plain reinforced concrete) retaining wall, retaining wall, retaining wall and breast wall with 110mm (one hundred mm) nominal size PCC, type. In plain concrete retaining wall, retaining wall and breast wall. Near aggregate per centimeter (square) extending through the full width of the structure with slope of (1V: 20H) towards driving face complete as per drawing and technical specification clause 1014, 1051, 1204.3) as per direction of Engineer-in-Charge including cartage of material within all kinds and its and other incidentals. The rates are inclusive octroi, royalty, Mahasabai tax, GST or other taxes imposed by the Government.	27.20			Each	
6	Providing and laying filter media with granular crushed aggregate as per specification to a thickness of not less than 300mm (one hundred millimetre) with under size towards the soil and larger size towards the wall and providing over the entire surface breast abutment, wing wall, return wall to the full height, completed to firm condition complete in plan drawing and technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including cartage of material within all kinds and its and other incidentals. The rates are inclusive octroi, royalty, Mahasabai tax, GST or other taxes imposed by the Government.	318.28			Per cubic metre	
Total					Total	

Terms and Conditions

1. Work shall be executed as per PWD specifications.

2. Sheet will be issued separately.


 Executive Engineer,
 Tundla District Division,
 Aligarh, Uttar Pradesh

Schedule of Quantity

NAME OF WORK:- C/O link road Narwalan-Di-Dhar to Bouru via Lambran-di-Dhar km. 0/0 to 2/075 (SH- formation cutting 5/7mtr. Wide in km. 2/001 to 2/045). (Under OTMNP)					Estimated Cost:- Earnest Money:- Time:-	Rs. 472363.00 Rs.9500.00 Two Months
Sr No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation in hilly areas in all heights and depths and in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling /wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the technical specification clause 302,1603.1,1603.2 sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un-useful material for filling in road ways, camber, embankment for grade improvement and disposal of all unusu- l material to required width of the road or on approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and cartage of machines materials, tools, equipments and safety measures and incidental necessary to complete the work by mechanical means and or labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including cartage of material within all leads and lifts. (Recovery of useful stone i.e. 166.31% cubic metre shall be made from the contractor @ Rs. 300/- (three hundred only per cubic metre) amounting to Rs.49,893/- only.	1108.73			Per cubic metre	
					Total	

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tami Devi Division,
 HPPWD, Tami Devi

Schedule of Quantity

NAME OF WORK:- C/O link road Narwalan-Di-Dhar to Bouru via Lambrun-di-Dhar km. 0/0 to 2/075.5 (SH- formation cutting
Contract: Wide in km. 1/945 to 2/00). (Under OTMNP).

Estimated Cost:- Rs. 450731.00

Earnest Money:- Rs. 9000.00

Time:- Two Months

Sl. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
	Excavation in hilly areas in all heights and depths and in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling /wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grades with cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the technical specification clause 302.1503.1, 1603.2 setting out useful material and stacking the same in all loads and lifts in acquired width of the road and transportation of un-useful material for filling in road ways, canals, embankment for grade improvement and disposal of all un-useful material to required width of the road or on approved dumping sites through all modes of transportation including hand load or animals transport or mechanical means along with its loading, unloading, dressing and cartage of machineries materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and or labour if required. Any loss to the public/private property during the course of execution shall be the maximum responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including cartage of material within all loads and lifts. (Recovery of useful stone i.e. 158.761 cubic metre shall be made from the contractor @ Rs. 300/- (three hundred only per cubic metre) amounting to Rs. 47510/- only	1057.98			Per cubic metre	
						Total

Terms and Condition

Work shall be executed as per PWD specification.

Amit Chaur
 Executive Engineer,
 Tauni Devi Division,
 HPPWD, Tauni Devi