



Himachal Pradesh
Public Works Department
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

"SHORT TERM NOTICE INVITING TENDERS"

Sealed item rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Bhawarna Division HP.PWD. Bhawarna on behalf of the Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **13/12/2023** up to 11.00 AM. and the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) on **12/12/2023** up to 4.00 P.M and the application for issue of tender form shall be received on **11/12/2023** up to 12.00 noon.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Time Limit	Cost of Tender form
1	C/o Gallu Bhoda Shivanagar road Km. 0/0 to 7/0 (SW:- C/o R/Wall at Rd 0/982 to 0/995)	3,40,048/-	6800/-	Two Months	350/-
2	C/o Pharer to Thamba road (SW:- C/o Parapets in Km. 0/215 to 0/450)	98,335/-	2000/-	One Month	350/-
3	C/o link road from Salan to Katiyar Pharer road (SW:- Providing and laying Interlocking Concrete blocks in Km. 0/820 to 0/910)	4,38,960/-	8800/-	Two Months	350/-
4	C/o Pharer to Thamba road (SW:- C/o Retaining walls in Km. 2/015 to 0/026 and 2/030 to 2/038)	90,244/-	1800/-	One Month	350/-
5	Restoration of rain damages on Ballah to Ballah road (SW:- Breast wall in Km. 3/930 to 3/946)	1,75,938/-	3500/-	Two Months	350/-
6	Special repair of Assistant Engineer Residence at Sub Division Bhawarna, Tehsil Palampur, Distt. Kangra (HP) (SW:- P/L Paint work Tile work & Sanitary work)	3,11,944/-	6200/-	Three Months	350/-

Terms & Conditions:-

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor/firm have to produce the copy of latest enlistment and renewal enlisted in HP.PWD.
3. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.
5. The contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand.
6. Next tender will be issued only after completion of previous works in hand.

HIM SUCHANA AVM JAN SAMPARK

Executive Engineer
Bhawarna Division
HPPWD Bhawarna

(On behalf of Governor of Himachal Pradesh)

Dated:-

No. PWD/BWD/Tender/NIT/2023-24/-

Copy to following for information and necessary action:-

1. The Principal Secy.(PW) to the Govt. of H.P. Shimla.
2. The Engineer-in-Chief, HPPWD, Shimla.
3. The Chief Engineer (KZ), HPPWD, Dharamshala.
4. The Director, Information & Publications Department, HP Shimla.
5. The Executive Engineer (IT), Nigam Vihar Shimla. He is requested to upload the same on the department website.
6. The Superintending Engineer, 5th Circle, HPPWD, Palampur.
7. The Deputy Commissioner, Kangra at Dharamshala.
8. The Sub-Divisional Officer(Civil) Palampur.
9. All the S.E.s/E.E.s under Kangra Zone.
10. All the Assistant Engineers under this Division.
11. The Drawing /Accounts Branch in this office.
12. Notice Board.

Executive Engineer
Bhawarna Division
HPPWD Bhawarna

Schedule of quantity

Name of Work :- Construction of Gallu Bhoda Shivnagar road Km 0/0 to 7/0. (SH:- C/o R/wall at RD 0/982 to 0/995).

Estimate Cost :- Rs. 3,40,048/-

Earnest Money :- Rs. 6800/-

Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Excavation in foundation, trenches etcetera in earth work involving all classification of soil such as pick work, pick jumper work, blasting work, soft or hard rocks including chiseling/wedging out of rocks where blasting work is prohibited or any other mixed variety of intermediate soil, dewatering and removal of slush if arisen during course of construction and lifts upto all heights including stacking the excavated soil not more than three meters clear from the edge of the excavation and then returning the stacked soil in 15 cm (fifteen centimeter) thick layers when required into plinths, sides of foundation etcetera consolidating each deposited layer by ramming and watering and then disposing of all surplus excavation earth within all leads. lifts by any mode of transportation and other incidental, as per the direction and entire satisfaction of Engineer-in-Charge. Any loss to the private and public property during course of construction shall be absolute responsibility of the contractor. Rate inclusive royalty, malkana, toll tax, GST and other taxes imposed by the government.	39.78			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size including curing complete in parapets and the like etcetera including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	76.96			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	37.00			Each	
4	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	16.25			Per Cubic metre	

5	Construction of embankment with approved materials deposited at site from sand way cutting and excavation from drains and foundations of other structures or other sources graded and compacted to 200mm (two hundred millimeters) thickness in every layer and compacted with three Wheel Road Roller 80kN 100 (eighty hundred) K.N static weight roller to meet the requirement of tables 100.1 and 100.2 as per M.O.R.D. technical specification Clause 101 and 101.1.5 and as per the entire satisfaction and directions of the Engineer-in-Charge including carriage of materials within all local, state and other agencies. The rate is including octroi, royalty, Melikana, toll tax, C.S.I or other taxes imposed by the Government.	18.20			Per Cubic metre
Total :-					

Executive Engineer
Bharwana Division
HP PWD Bharwana

Schedule of quantity

Name of Work :-Construction of Pharer to Thamba road.

(SH:- C/o Parapets in Km 0/215 to 0/450).

Estimate Cost :-Rs. 98,335/-
Earnest Money :- Rs. 2000/-
Time Limit :- One Month

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Excavation in foundation, trenches etcetera in earth work involving all classification of soil such as pick work, pick jumper work, blasting work, soft or hard rocks including chiseling/wedging out of rocks where blasting work is prohibited or any other mixed variety of intermediate soil, dewatering and removal of slush if arisen during course of construction and lifts upto all heights including stacking the excavated soil not more than three meters clear from the edge of the excavation and then returning the stacked soil in 15 cm (fifteen centimeter) thick layers when required into plinths, sides of foundation etcetera consolidating each deposited layer by ramming and watering and then disposing of all surplus excavation earth within all leads, lifts by any mode of transportation and other incidental, as per the direction and entire satisfaction of Engineer-in-Charge. Any loss to the private and public property during course of construction shall be absolute responsibility of the contractor. Rate inclusive royalty, malkana, toll tax, GST and other taxes imposed by the government.	5.62			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement : four sand : eight graded crushed/ broken stone aggregate 40mm (forty millimetre) nominal size on ground or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification section 800, 900 and 1200 and as per the entire satisfaction and direction of the Engineer -in-Charge including carriage of materials within all lead, and lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	21.54			Per Cubic metre	
Total :-						

Executive Engineer
Bhawarna Division
HP PWD Bhawarna

Schedule of Quantity

Name of Work :- C/o link road from Salan to Katiyar Pharer road.

(SH:- Providing and laying Interlocking Concrete blocks in Km 0/820 to 0/910).

Estimate Cost :- Rs. 4,38,960/-
Earnest Money :- Rs. 8800/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm (Eighty millimetre) of approved make having compressive strength of M-50 as per drawings and MORD Technical Specification section 1500 including sand bedding, carriage of material within all leads and lifts, other incidentals. The rate is rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the government.	3.41			Per Square metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete Grade-M-20 (M-Twenty) nominal mix in open foundation design mix with cement contents not less than 320 kg (Three hundred twenty kilogram) per cubic metre as per drawing and M.O.R.D. technical specifications section 800, 900 and 1200, including the cost of form work, curing complete and hauling of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax or other taxes imposed by the Government.	279.00			Per Cubic metre	
Total :-						

Executive Engineer
Bhawarna Division
HP PWD Bhawarna

Schedule of quantity

Name of Work :- Construction of Pharer to Thamba road.

Estimate Cost :- Rs. 90,244/-

Earnest Money :- Rs. 1800/-

Time Limit :- One Month

(SH:- C/o Retaining walls in Km 2/015 to 0/026 and 2/030 to 2/038).

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Excavation in foundation, trenches etcetera in earth work involving all classification of soil such as pick work, pick jumper work, blasting work, soft or hard rocks including chiseling/wedging out of rocks where blasting work is prohibited or any other mixed variety of intermediate soil, dewatering and removal of slush if arisen during course of construction and lifts upto all heights including stacking the excavated soil not more than three meters clear from the edge of the excavation and then returning the stacked soil in 15 cm (fifteen centimeter) thick layers when required into plinths, sides of foundation etcetera consolidating each deposited layer by ramming and watering and then disposing of all surplus excavation earth within all leads. lifts by any mode of transportation and other incidental, as per the direction and entire satisfaction of Engineer-in-Charge. Any loss to the private and public property during course of construction shall be absolute responsibility of the contractor. Rate inclusive royalty, malkana, toll tax, GST and other taxes imposed by the government.	8.55			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size including curing complete in parapets and the like etcetera including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	19.19			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	15.00			Each	
4	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	10.07			Per Cubic metre	

5.	Construction of embankment with approved materials deposited at site from road way cutting and excavation from drains and foundations of other structures or other sources graded and compacted in 200mm(two hundred millimetres) thickness in every layers and compacted with three Wheel Road Roller 80-100 (eighty-hundred) KN static weight roller to meet the requirement of tables 300.1 and 300.2 as per M.O.R.D. technical specification Clause 301 and 1603.5 and as per the entire satisfaction and direction of the Engineer- In -Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	6.08			Per Cubic metre
Total :-					


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Restoration of rain damages on Ballah to Ballah road

Estimate Cost :- 1,75,938/-

Earnest Money :- 3500/-

(SH:- C/o Breast wall in Km 3/930 to 3/946).

Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	36.80			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	41.92			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, GST or other taxes imposed by the Government.	13.00			Each	
Total :-						

Schedule of Quantity

Name of Work :- Special repair of Assistance Engineer Residence at Sub Division Bhawarna, Tehsil Palampur, Distt. Kangra HP (SW:- P/L Paint work Tile work & Sanitary work).

Estimate Cost :- Rs. 3,11,944/-
Earnest Money :- Rs. 6200/-

Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Removing white wash or colour wash by steel wire brushing and/or scrapping sand papering and preparing the wall surface smooth including necessary repairs to scratches complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	246.75			Per Square metre	
2	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	246.75			Per Square metre	
3	Wall painting (two coats) with acrylic emulsion paint of approved brand and manufacture for interior grade on undecorated concrete/stone/plastered wall surfaces to give an even shade including thoroughly brushing the surface free from mortar dropping and other foreign matter and sand papered smooth including applying of putty a required for metting the surface. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	246.75			Per Square metre	
4	Providing and fixing 10mm (ten millimetre) thick antiskid water proof stain and impact resistant heavy duty vitrified tiles Kajaria/Nitco/AGL or equivalent 600x600x10mm (six hundred into six hundred into ten millimetre) manufactured of approved shade and colour in flooring treads of steps and landings laid over 12mm (twelve millimetre) thick cement mortar 1:3 (one cement : three sand) jointed with cement slurry mixed with pigment to match the shade of tiles as required complete as per specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	10.24			Per Square metre	
5	Providing and laying Duro stone vetrified tiles (300x300mmx8mm) (Three hundred into three hundred into eight millimetre) in grey/coloured of required shade in skirting, treads of steps and landing on 12mm thick cement mortar 1:3 (1 cement : 3 sand) laid over and jointed with neat cement slurry finished with flush pointing in white cement mixed with pigment of required shade to match the shade of tiles complete as per approved specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	22.63			Per Square metre	

6	15mm (fifteen millimetre) thick cement plaster in single coat on the rough side of brick/concrete/stone walls for interior plastering upto any floor level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm (eighty millimetre) in girth, in rough side with cement mortar 1:5 (one cement to five sand) complete including curing as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	25.67			Per Square metre
7	Providing and fixing 4 mm thick (four millimetre) plain asbestos cement sheet ceiling of approved quality with butt jointing and wood screws (frame work and cover fillets to be measured and paid for separately) complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	55.37			Per Square metre
8	Providing and fixing panelled glazed or panelled and glazed shutters for doors windows and clerestory windows i/c black enamelled in but hinges with necessary screws 40mm thick 2 nd class deodar wood .The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	1.80			Per Square metre
9	Providing and fixing glazing in aluminium door, window, ventilator shutters and partition etc. with PVC/Neoprens gasket etc. complete glazing with glass panes of 4mm thickness (weight not less than 10.00 kg/sqm. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	3.78			Per Square metre
10	Supplying and fixing Frosted Glass 4mm (Four millimetre) thick, panes with putty and nails including removal of broken glass panes wherever necessary. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	0.58			Per Square metre
11	Painting one coat (excluding priming coat) on previously painted steel and other metal surfaces with enamel paint brushing to give an even shade including cleaning of all dirt, dust and other foreign matter (With white enamel paint) Including carriage of material within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	21.96			Per Square metre
12	Painting one coat (excluding priming coat) on previously painted wood and wood surfaces with enamel paint brushing to give an even shade including cleaning of all dirt, dust and other foreign matter (With white enamel paint) Including carriage of material within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	34.20			Per Square metre

13.	Providing and fixing complete box of cup board shall be made of 19 mm (Nineteen millimeters) thick water proof termite resistance commercial board of uniply/ green ply/ century ply/ISI marked is No 1659 including self back side of cup board shall have 6/8 mm (six/ eight millimeters) thick water proof ply, all the cut portion of board shall have 6 mm (six millimeters) thick hard wood edging. The shutters all side shall also have 6/12 mm (six / twelve millimeters) thick hard wood edging to finished with mica lamination of approved shall as per detail drawing and specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	17.66			Per Square metre
14	Providing and fixing 25mm (twenty five millimetre) thick commercial board with sunmica water proof shutters for cup boards i/c fixing with nickel plated piano hinges with screws etc. complete. The cut portion of shutter shall be finished with 6mm hard wood edging. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	13.80			Per Square metre
15	Rubbing of existing floors with machine complete as per H.P.P.W.D. specifications, approved drawing, design, as per entire satisfaction including carriage of material within all leads, lifts and other incidentals as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	4.00			Per day
16	Providing and laying 2mm (two millimetre) thick PVC/Rubber tile flooring, plain, coloured, corbed, or mosaic or mottled finish. Laid with approved adhesive on sub floor complete (sub- floor including damp proofing treatment to be measured separately for payment) complete in all respect as per specifications approved drawing and design including cost and carriage of material with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	26			Per Square metre
17	Providing and fixing Bright finished M.S. hydraulic door closer ISI Marked with necessary screws complete including cost and carriage of material with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	2.00			Each
18	Providing and fixing bright finished brass helical door spring (superior quality) complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	2.00			Each
19	Providing and fixing Magnetic Catcher for cup boards shutter with necessary screws complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	14.00			Each
20	Providing and fixing 75mm (Seventy five millimeter) size coloured anodized aluminum handle anodized transparent or dyed to required shade or colour with necessary screws etcetera complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	3.00			Each
21	Providing and fixing 75mm (Seventy five millimetre) special quality chromium plated brass cupboard locks with six levers of approved quality including necessary screws etc. complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	3.00			Each

22	Providing and fixing vitreous china European type W.C. of star sr. No 20087 (S-50) of size 57x35x39 cm (fifty seven into thirty five into thirty nine centimeter) wash down water closet hindware/jaguar/cera of star white/ snow white including jet pressure integral P or S trap including jointing the trap with soil pipe in fixture (seat cover/ jet pressure to be paid seprately) including entire carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	1.00			Each
23	Providing and fixing heavy quality stainless steel kitchen sink of approved standard ISI marked with drain board and C.P. waste pipe C.I. or M.S. brackets painted white i/c cutting holes and making good the same including fitting 600x450x250 mm (six hundred into four hundred fifty into two hundred fifty millimetre) with bowl depth 20 mm (twenty millimetre) including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	1.00			Each
24	Providing and fixing CP Brass Single lever telephonic wall mixer of quality & make as approved specifications. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	2.00			Each
25	Providing and fixing 15 mm dia (Fifteen millimetre) mixer for kitchen sink and fittings including testing of joints with approved adhesive etcetera including carriage of materials within all leads and lifts complete within all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	1.00			Each
26	Providing and fixing 15mm (Fifteen millimetre) diameters Superior quality bib tap of continental series of Jaguar/ Classic series of Hindware/ Floral series of Cera/ Hindon series of Jal/ Vintage series of Kerovite as per specifications including carriage of material within all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	1.00			Each
27	Providing and fixing CP Brass Angle cock (15mm nominal size) including carriage of materials within all leads and lifts complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	3.00			Each
28	Providing and fixing chromium plated brass soap dish of ESS with C.P. brass brackets fixed with cleats with C.P. brass screws, within all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	3.00			Each
29	Providing and fixing C.P. brass towel rail size 600x20mm (Six hundred into twenty millimetre) of continental series of Jaguar/Classic of Hindware/Cera complete with C.P. brass brackets fixed to wooden plugs with C.P. brass socket including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	1.00			Each
30	Providing and fixing 600mmx450mm (six hundred millimeter into four hundred fifty millimeter) beveled edge mirror of superior glass mounted on 6mm (six millimeter) thick A.C. Sheet or plywood sheet and fixed to wooden plugs with C.P. screws and washers of Atul/Modi Guard/ Golden fish including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	2.00			Each
31	Providing and fixing CP brass bath shower 15mm (Fifteen millimeters) dia of era/Jal made including entire carriage of materials in all leads and lifts as per the direction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	2			Each

32.	Providing and fixing PVC waste pipe for wash basin or sink including necessary fitting and carriage of materials in all leads and lifts as per the direction of Engineer-in-Charge and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	1.00			Each	
33	Providing and fixing C.P. brass towel ring of continental series of Jaguar/Classic of Hindware/Cera complete with C.P. brass brackets fixed to wooden plugs with C.P. brass socket including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	1.00			Each	

~~Executive Engineer~~
Bhawarna Division
HP PWD Bhawarna