



**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

Tel.01899-299219.

eepwd-chowari@hp.gov.in

No. PWD-CHW/Tender /2023-24-

To

9957-59

Dated:- 8/12/23

The Executive Engineer (IT Cell)  
Nigam Bihar Shimla-2

**Subject: - Publishing of Tender Notice.**

**Dear Sir,**

Enclosed please find herewith the tender Notice of work as give in the Notice inviting Tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of Himachal Pradesh letter No. PBW-(B) A9 (3)1/2020 dated Shimla-2 the 16<sup>th</sup> July 2021 as the work mentioned in the tender notice are urgent in nature and public interest.

DA/ As above.

**Executive Engineer,  
Chowari Division,  
HPPWD, Chowari.**


Copy forwarded to the Superintending Engineer, 7<sup>th</sup> Circle, HPPWD, Dalhousie for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer, (IT Cell) Nigam Bihar Shimla-2 for information and further necessary action.

**Executive Engineer,  
Chowari Division,  
HPPWD, Chowari.**

**Certificate**

Certified that the tenders called vide this office letter No. PWD-CHW/Tender /2023-24~~5960~~~~100/10~~..dated. ~~8/12/22~~ is emergent nature and in Public interest.

  
Executive Engineer,  
Chowari Division,  
HPPWD, Chowari.



Tel.01899-299219.  
cepwd-chowari@hp.gov.in

## HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

### "NOTICE INVITING TENDERS"

Sealed percentage/item rate tender(s) on PWD from No 6 & 7/8 are hereby invited by the Executive Engineer, Chowari Division, HPPWD, Chowari on behalf of the Governor of HP for the following works from the approved and eligible contractor/firm of appropriate Class enlisted in HPPWD as per the latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening of the tender. The undersigned reserves the right to reject any or all the tender without assigning any reasons:-

1. Date of receipt of application for the tender

Form a/w requisite documents: -

15/12/2024

2. Date of issued/sale of tender form against

Cash payment (non refundable).

16/12/2024

The tender shall be received upto 11.00 AM on 18/12/2024 and will be opened on the same day at 12.00 PM in the presence of intending Contractor or their authorized representative who may like to be present. The tender can be had from this office against cash payment as shown below (Non refundable) during the working hours on 04/05/2023.

The Earnest Money in the shape of National Saving Certificate/Deposit at call/Time deposit/Account/in any Post Office/Nationalized Bank in HP duly pledged in favour of Executive Engineer, Chowari Division, HPPWD, Chowari must accompany with each application. Conditional tender and the tender received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 90 days. The XEN reserve the right to accept or reject the tender without assigning any reasons:-

S. No.	Name of work	Estimated cost	Earnest Money	Cost of tender	Time Limit	Class
1	Restoration of Rain Damage on Shahpur Sihunta Chowari Jot Chamba Road km 40/0 to 76/00 (SH:- C/o W/wall at RD 51/728.80 to 51/733.80 & 51/736.20 to 51/741.20)	460504/-	9210/-	Rs. 350/-	Three Month	Class-D & C
2	Restoration of rain damages on Link Road to village Bai Ka bag road km 0/0 to 1/500 (SH:- Hiring of Excavator cum loader for removal of slips)	495600/-	9912/-	Rs. 350/-	Three Month	Class-D & C
3	Restoration of rain damages on Patka to Dalhousie Road km 14/0 to 32/0 (SH:-Hiring of Excavator cum loader and Tipper for removal of slips km 14/0 to 32/0)	494325/-	9887/-	Rs. 350/-	Three Month	Class-D & C
4	Restoration of Rain Damage on Shahpur Sihunta Chowari Jot Chamba Road km 40/0 to 76/00 (SH:- C/o B/wall at RD 51/630 to 51/648)	455722/-	9114/-	Rs. 350/-	Three Month	Class-D & C
5	Restoration of rain damages on Link Road from Gatasani Pul to village Bhalog km 0/0 to 7/360 (SH:-Hiring of Excavator cum loader for removal of slips km 3/00 to 7/360)	496650/-	9933/-	Rs. 350/-	Three Month	Class-D & C
6	Restoration of rain damages on Link Road from Parchhore to village Nadal km 0/0 to 3/00 (SH:- Hiring of Excavator cum loader for removal of slips km 1/500 to 3/00)	498750/-	9975/-	Rs. 350/-	Three Month	Class-D & C
7	Restoration of Rain Damage on Shahpur Sihunta Chowari Jot Chamba Road km 40/0 to 76/00 (SH:- C/o Pusta for R/wall at RD 51/845 to 51/860)	455911/-	9118/-	Rs. 350/-	Three Month	Class-D & C



8	Restoration of rain damages Shahpur Sihunta Chowari Road km 24/00 to 40/00 (SH:- Repair to pot holes km 24/00 to 36/00)	499156/-	9983/-	Rs. 350/-	Three Month	Class-D & C
9	Restoration of Rain Damage on Nurpur Sanjhi Nallah Lahru Tunuhatti Road km 15/390 to 25/00 (SH:- C/o R/wall PCC at RD 16/654 to 16/662.50)	467846/-	9357/-	Rs. 350/-	Three Month	Class-D & C
10	Restoration of Rain Damage on Samote to Dramnallah Road km 0/0 to 12/435 (SH:- C/o R/wall PCC at RD 10/570 to 10/583)	427083/-	8542/-	Rs. 350/-	Three Month	Class-D & C
11	Restoration of rain damages on various Roads under Sihunta Sub-Division Thulel Section (Sub head:- Hiring of Poclain for removal of Slip/Debris/boulder etc)	498825/-	10000/-	Rs. 350/-	Three Month	Class-D & C
12	Restoration of Rain Damage on various Road under Chowari Sub-Division (SH:-Sub head:- Hiring of Tipper for shifting of muck /Debris/boulder etc)	277500/-	5550/-	Rs. 350/-	Three Month	Class-D & C
13	Restoration of rain damages on Patka Hathidhar Road km 0/0 to 10/400 24/00 to 40/00 (SH:-Formation cutting at RD 9/930 to 10/300 )	487142	9743/-	Rs. 350/-	Three Month	Class-D & C
14	Restoration of Rain Damage on Ghatasani Pul to Bhalog Road km 0/0 to 7/360 (SH:- C/o R/wall PCC at RD 0/585 to 0/595)	460586/-	9212/-	Rs. 350/-	Three Month	Class-D & C
15	Restoration of Rain Damage on Nurpur Sanjhi Nallah Lahru Tunuhatti Road km 15/390 to 25/00 (SH:- C/o R/wall at RD 22/480 to 22/486.30)	489534/-	9791/-	Rs. 350/-	Three Month	Class-D & C
16	Repair of Rest house at Sihunta (SH:- Painting & Distempering etc.)	229872/-	4597/-	Rs. 350/-	Three Month	Class-D & C
17	Restoration of Rain Damage on Chowari to Jot Road km 53/0 to 76/0 (SH:-Hiring of Excavator cum loader for removal of slips and Tipper for carriage of material)	491550/-	9831/-	Rs. 350/-	Three Month	Class-D & C
18	Restoration of rain damages on Nurpur Sanjhi Nallah Lahru Tunuhatti Road km 25/0 to 40/810 (SH:- C/o R/wall at RD 36/635 to 36/643, Parapets between RD 40/030 to 40/150 and extension of HP culvert at RD 36/655)	452948/-	9059/-	Rs. 350/-	Three Month	Class-D & C
19	Restoration of Rain Damage on Shahpur Sihunta Chowari Jot Chamba Road km 40/0 to 53/00 (SH:-Hiring of Excavator cum loader for removal of slips km 40/0 to 47/0)	491400/-	9828/-	Rs. 350/-	Three Month	Class-D & C
20	Restoration of Rain Damage on Nurpur Sanjhi Nallah Lahru Tunuhatti Road km 15/390 to 25/00 (SH:-Hiring of Excavator cum loader for removal of slips km 20/0 to 25/0)	494025/-	9881/-	Rs. 350/-	Three Month	Class-D & C
21	Restoration of Rain Damage on Shahpur Sihunta Chowari Jot Road km 40/0 to 76/00 (SH:- C/o R/wall with Pusta at RD 50/750 to 50/758)	470885/-	9418/-	Rs. 350/-	Three Month	Class-D & C
22	Restoration of rain damages on various roads under kakira Sub-Division under Balera Section (SH:-Hiring of Excavator cum loader for removal of slips)	495600/-	9912/-	Rs. 350/-	Three Month	Class-D & C
23	Restoration of rain damage on various roads under Kakira Sub Division ( SH:- Hiring of Hydraulic excavator cum loader for removal of slips).	498750	10000/-	Rs. 350/-	Three Month	Class-D & C

1. The tender forms will not be issued to those Contractors whose performance is not found satisfactory.
2. The Contractor should have executed two similar types of works 1/3 of each amount put to tender or single work of amount equal to the amount put to tender within list five year.

3. GST No./Earnest Money Tender Form cost, copy of enlistment should be accompanied with application.
4. Application without all documents will not be entertained.
5. Proxy application will not be entertained.

~~Executive Engineer,~~  
Chowari Division,  
HPPWD, Chowari.

No. PWD-CHW/Tender /2023-24-

9960-10010

Dated:-

8/12/23

Copy forwarded to the following for information and necessary action please:-

1. Engineer-in-Chief, HPPWD, Shimla.
2. All the Chief Engineer in HPPWD.
3. All SEs/EE in HPPWD.
4. All AEs/Contractor under this Division.
5. Deputy Commissioner, Chamba
6. The BDO Bhattiyat.
7. Sub Divisional Magistrate/B.D.O/Tehsildar Chowari.
8. Notice Board of this office.

/

Executive Engineer,  
Chowari Division,  
HPPWD, Chowari.

### Schedule of Quantity

Estimated Cost	Rs.460504/-
Earnest Money	Rs.9210/-
Time Limit	Three months

Name of work:-Restoration of Rein Damage on Shahpur Sihunia Chowari Jot Chamba Road km 40/0 to 76/00 (SH:- C/o Wing wall at RD 51/728.80 to 51/733.80 & 51/736.20 to 51/741.20)

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material. as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	34.10			Per cubic metre	
2	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	87.40			Per cubic metre	
3	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in Charge i/c carriage of materials with in all leads, lifts and other incidentals. The Rate including octroi Royalty Malkana Toll tax Sale tax or any other taxes imposed by the Govt.	17.70			Per cubic metre	
4	Providing weep holes in brick masonry/ stone masonry/ palin reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of ( IV ) : 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614,709,1204.3.7 asper the directions of the Engineer-incharge. i/c carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	30.00			Each	
<b>Total</b>						

**Executive Engineer**  
 Chowari Division  
 H.P. Chowari



(2)

## Schedule of Quantity

Name of work:-Restoration of rain damages on Link Road to village Bai Ka bag road km 0/0 to 1/500 (SH:-Hiring of Excavator cum loader for removal of silps)

		Estimate Cost :- Rs.		495600/-
		Earnest Money		9912/-
		Time Limit		Three months

Name of work:-Restoration of rain damages on Link Road to village Bai Ka bag road km 0/0 to 1/500 (SH:-Hiring of Excavator cum loader for removal of silps)						
<b><u>Schedule of Quantity</u></b>						
S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Hiring of JCB/ Excavator cum loader for cutting /widening work road or removal of silps in all kinds of soil and disposing of all excavated earth or unserviceable materials from the road surface upto any leads and lifts upto any height and depths as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be have to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also be borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge	472.00			Per hour	

**Executive Engineer**  
**Chowari Division**  
**PPWD, Chowari**

(3)

## Schedule of Quantity

Estimate Cost :- Rs.	494325/-
Earnest Money	9887/-
Time Limit	Three months

Name of work:- Restoration of rain damages on Patka to Dalhousie Road km 14/0 to 32/0 (SH:-Hiring of Excavator cum loader and Tipper for removal of slips km 14/0 to 32/0)

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Hiring of JCB/ Excavator cum loader for cutting /widening work road or removal of slips in all kinds of soil and disposing of all excavated earth or unserviceable materials from the road surface upto any leads and lifts upto any height and depths as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be have to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also be borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge	410.00			Per hour	
2	Hiring of Tipper having capacity 5.5 ( five decimal five zero ) cubic meter for carriage of all type of material upto any leads and lifts as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be have to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also are borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	115.00			Per hour	

**Executive Engineer**  
**Chowari Division**  
**HBPWD. Chowari**



4

### Schedule of Quantity

Name of work:- Restoration of Rain Damage on Shahpur Sihunta Chowari Jot Chamba Road km 40/0 to 76/00 (SH:- C/o B/wall at RD 51/630 to 51/648)

Schedule of Quantity				Estimated Cost	Rs. 455722/-
				Earnest Money	Rs. 9114/-
				Time Limit	Three months

Name of work:-Restoration of Rain Damage on Shahpur Sihunta Chowari Jot Chamba Road km 40/0 to 76/00 (SH:- C/o B/wall at RD 51/630 to 51/648)						
S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead , dressing of sides and bottom and backfilling in trenches with excavated suitable material . as per the direction of the Engineer in Charge. Including Carriage of material within all leadss and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt	29.45			Per cubic metre	
2	Providing and laying concrete for Plain/reinforced concrete 1:4:8 (one cement isto four sand isto eight graded/crushed stoneaggregate twenty five millimetre) size in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:4:8) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt	84.24			Per cubic metre	
3	Providing weep holes in brick masonry/ stone masonry/ pain reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of ( IV ) : 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614, 709, 1204.3.7 asper the directions of the Engineer-incharge. i/c carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	28.00			Each	
Total						

**Executive Engineer**  
 Chowari Division  
 Appwd Chowari

5

## Schedule of Quantity

Estimate Cost :- Rs.	496650/-
Earnest Money	9933/-
Time Limit	Three months

(SH:-Hiring of

Name of work:-Restoration of rain damages on Link Road from Gatasani Pul to village Bhalog km 0/0 to 7/360  
Excavator cum loader for removal of slip km 3/00 to 7/360)

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Hiring of JCB/ Excavator cum loader for cutting /widening work road or removal of slips in all kinds of soil and disposing of all excavated earth or unserviceable materials from the road surface upto any leads and lifts upto any height and depths as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be have to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also be borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge	473.00			Per hour	

**Executive Engineer**  
Chowari Division  
BPPWD, Chowari

## Schedule of Quantity

Estimate Cost :- Rs.	498750/-
Earnest Money	9975/-
Time Limit	Three months

Name of work:- Restoration of rain damages on Link Road from Parchore to village Nadai km 0/0 to 3/00 (SH:-Hiring of Excavator cum loader for removal of slips km 1/500 to 3/00)

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Hiring of JCB/ Excavator cum loader for cutting /widening work road or removal of slips in all kinds of soil and disposing of all excavated earth or unserviceable materials from the road surface upto any leads and lifts upto any height and depths as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be have to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also be borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge	475.00			Per hour	


Executive Engineer  
Chowari Division  
HPWD, Chowari

## Schedule of Quantity

Estimated Cost	Rs. 455911/-
Earnest Money	Rs. 9118/-
Time Limit	Three months

Name of work:- Restoration of Rain Damage on Shahpur Sihunta Chowari Jot Chamba Road km 40/0 to 76/00 (SH:- C/o Pusta for R/wall at RD 51/845 to 51/860)

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material. as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	64.73			Per cubic metre	
2	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Norminal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	90.00			Per cubic metre	
3	Providing weep holes in brick masonry/ stone masonry/ palin reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of ( IV ) : 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614, 709, 1204.3.7 asper the directions of the Engineer-incharge. i/c carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	10.00			Each	
<b>Total</b>						

  
**Executive Engineer**  
 Chowari Division  
 Ppawd Chowari



(2)

**DNT**

Estimated Cost: - Rs. 499156/-  
 Earnest Money :- Rs. 9983/-  
 Time Limit :- Three Months

Name of work: - Restoration of rain damages Shahpur Sihunta Chowari Road km 24/00 to 40/00  
 (SH: - Repair to pot holes km 24/00 to 36/00)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Repair of pot holes and removal of loose material, trimming of sides, cleaning of surface by providing and spreading @ 0.300 (Zero point three hundredkilogram) bituminous per square metre for tack coat, 1.46 kg ( one point four six kilograme ) bitumen per square for 20 mm (twenty millimetre) thick pre-mix carpet and 0.680 (zero point six eight kilograme) bitumen per square metre for seal coat as per MORD specification section 1900 and as per the direction of Engineer-in-Charge including carriage of material with in all leads ,lifts and other incidentials. The rate including the octroi, royalty, Malkana, toll tax,GST, sale tax or other taxes imposed by the Government.	1459.52	342.00	Three hundred forty two only	Per square metre	499156
						499156

**Executive Engineer**  
 Chowari Division  
 Hppwd Chowari


### Schedule of Quantity

Estimated Cost	Rs. 467846/
Earnest Money	Rs. 9357/-
Time Limit	Three months

Name of work:—Restoration of Rain Damage on Nurpur Sanjhi Nallah Lahru Tunuhatti Road km 15/390 to 25/00  
R/wall PCC at RD 16/654 to 16/662.50

(SH:- C/o

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material. as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	32.73			Per cubic metre	
2	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Normal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	88.40			Per cubic metre	
3	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORO technical specification clause 1204.3.8 or as directed by the Engineer-in Charge i/c carriage of materials with in all leads, lifts and other incidentals. The Rate including octroi Royalty Malkana Toll tax Sale tax or any other taxes imposed by the Govt.	17.60			Per cubic metre	
4	Providing weep holes in brick masonry/ stone masonry/ plain reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of ( IV ); 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614, 709, 1204.3.7 as per the directions of the Engineer-incharge. i/c carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	27.00			Each	
<b>Total</b>						

  
**Executive Engineer**  
 Chowari Division  
 Popwd Chowari


10

## Schedule of Quantity

Estimated Cost	Rs. 427083/-
Earnest Money	Rs. 8542/-
Time Limit	Three months

Name of work:-Name of work:-Restoration of Rain Damage on Samote to Drammallah Road km 0/0 to 12/435  
(SH:- C/o R/wall PCC at RD 10/570 to 10/583)

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material. as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	63.34			Per cubic metre	
2	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	76.83			Per cubic metre	
3	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in Charge i/c carriage of materials with in all leads, lifts and other incidentals. The Rate including octroi Royalty Malkana Toll tax Sale tax or any other taxes imposed by the Govt.	11.70			Per cubic metre	
4	Providing weep holes in brick masonry/ stone masonry/ palin reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of ( IV ) ; 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614,709,1204.3.7 asper the directions of the Engineer-incharge. i/c carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	27.00			Each	
<b>Total</b>						

  
**Executive Engineer**  
 Chowari Division  
 Hppwd Chowari

**Schedule of Quantity**

Estimated Cost	Rs. 498825/-
Earnest Money	Rs. 10000/-
Time Limit	Three months

Name of work :- Restoration of rain damages on various Roads under Sihunta Sub-Division Thulel Section (Sub head:- Hiring of Poclain for removal of Slip/Debris/boulder etc)

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Hiring of Poclain of removal of lips /Debris/Boulder in all kinds of soil and disposing of all excavated earth or unserviceable materials from the road surface upto any leads and lifts upto any height and depths as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be laved to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also be borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	135.00			Per Hours	
Total						

Executive Engineer  
Chowari Division  
Hppwd Chowari



(12)

## Schedule of Quantity

Name of work:- Restoration of Rain Damage on various Road under Chawari Sub-Division (SH:-Sub head:- Hiring of Tipper for shifting of muck /Debris/boulder etc)

Estimate Cost :- Rs.	277500/-
Earnest Money	5550/-
Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Hiring of Tipper having capacity 5.5 ( five decimal five zero ) cubic meter for cartage of all type of material upto any leads and lifts as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be have to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also are borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	500.00			Per hour	

**Executive Engineer**  
**Chowari Division**  
**HPRWD. Chowari**

13

### Schedule of Quantity

Estimated Cost	Rs. 487142/-
Earnest Money	Rs. 9743/-
Time Limit	Three months

**Name of work:-** Restoration of rain damages on Patka Hathidhar Road km 0/0 to 10/400 24/00 to 40/00  
**Formation cutting at RD 9/930 to 10/300 )**

(SH:-)

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual /mechanical means including saturated soil comprising of ordinary soil, ordinary rock ,soft rock,hard rock chiseling, wedging out rock Where blasting is prohibited )and their intermediate classification of soil complete including setting out true to the require lines, grades, width ,cutting and trimming of side slopes and levels as shown on the drawings and as directed by Engineer -In -Charge at site , according to the MORD Technical specification section 300 and 1600 and sorting out useful material and stacking the same within all leads and lifts in acquired width of road and transportation of un-usual materials for filling in roadways camber ,embankments for grade improvements and disposal of all surplus material to dumping site is to be selected by the contractor at his own level in private land only through all modes of transportation including head load or animal transport or mechanical means alongwith its levelling fine dressing and carriage of machineries , material , tools , equipment and safety measures and other incidental necessary to complete the work by contractor. Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor, which shall have to be compensated by him in all cases. The rate are including the octroi	1751.68			Per Cubic Metre	
<b>Total</b>						

**Executive Engineer**  
**Chowari Division**  
**Hdpwd Chowari**

74

### Schedule of Quantity

Name of work:- Restoration of Rain Damage on Chatasani Pul to Bhalog Road km 0/0 to 7/360  
PCC at RD 0/585 to 0/595

Estimated Cost	Rs. 460586/-
Earnest Money	Rs. 9212/-
Time Limit	Three months

(SH:- C/o R/wall)

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material. as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	35.00			Per cubic metre	
2	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	87.40			Per cubic metre	
3	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORO technical specification clause 1204.3.8 or as directed by the Engineer-in Charge i/c carriage of materials with in all leads, lifts and other incidentals. The Rate including octroi Royalty Malkana Toll tax Sale tax or any other taxes imposed by the Govt.	19.30			Per cubic metre	
4	Providing weep holes in brick masonry/ stone masonry/ palin reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of ( 1V ) : 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614, 709, 1204.3.7 as per the directions of the Engineer-incharge. i/c carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	28.00			Each	
Total						

Executive Engineer  
Chowari Division  
Hppwd Chowari

15

### Schedule of Quantity

Name of work:- Restoration of Rain Damage on Nurpur Sanjhi Nallah Lahru Tunuhatti Road km 15/390 to 25/00  
(SH:- C/o R/wall at RD 22/480 to 22/486.30)

Estimated Cost	Rs. 489534/-
Earnest Money	Rs. 9791/-
Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material. as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	34.78			Per cubic metre	
2	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	95.76			Per cubic metre	
3	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORO technical specification clause 1204.3.8 or as directed by the Engineer-in Charge i/c carriage of materials with in all leads, lifts and other incidentals. The Rate including octroi Royalty Malkana Toll tax Sale tax or any other taxes imposed by the Govt.	15.69			Per cubic metre	
4	Providing weep holes in brick masonry/ stone masonry/ palin reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of ( IV ); 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614, 709, 1204.3.7 as per the directions of the Engineer-incharge. i/c carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	20.00			Each	
Total						

Executive Engineer  
Chowari Division  
Hrppwd Chowari



### Schedule of Quantity

**Name of work:- Repair of Rest house at Sihunta (SH:- Painting & Distempering etc.)**

16

Estimated Cost Rs. 229872/-

Earnest Money Rs. 45971/-

Time Limit Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In Word		
1	Removing of white swash or colour wash by steel wire brushing and or scrapping sand papering and preparing the wall surface smooth including necessary repairs to scratches complete as per direction of Engineer-in-Charge including carriage of materials and other incidentals. The rates are including the octroi, royalty Malkana, Toll tax Sales tax, GST or any taxes imposed by the Govt.	158.31			Per square metre	
2	Distempering (two coats) with oil bound washable distemper of approved brand and manufacture and of required shade on undecorated wall surface to give an even shade over and including a priming coat with distemper primer of approved brand and manufacture after thoroughly brushing the surface free from mortar droppings and other foreign matter and also including preparing the surface even and sand papered smooth priming coat with distemper primer with in all leads and lifts complete, as per direction of Engineer-in-Charge including carriage of materials and other incidentals. The rates are including the octroi, royalty Malkana, Toll tax Sales tax, GST or any taxes imposed by the Govt.	524.96			Per square metre	
3	Removing of old paint or polish from wood and wood based surface with paint remover of approved brands and manufacture and making the surface even with paint remover of approved brand and manufacture complete with in all leads and lifts complete, as per direction of Engineer-in-Charge including carriage of materials and other incidentals. The rates are including the octroi, royalty Malkana, Toll tax Sales tax, GST or any taxes imposed by the Govt.	312.98			Per square metre	
4	Painting two coats (excluding priming coat) on new wood and wood based surfaces, with readymixed paint, brushing to give an even shade including cleaning of all dirt, dust and other foreign matter sand papering and stopping readymixed paint other then whitewash in all leads and lifts complete, as per direction of Engineer-in-Charge including carriage of materials and other incidentals. The rates are including the octroi, royalty Malkana, Toll tax Sales tax, GST or any taxes imposed by the Govt.	386.23			Per square metre	
5	Polishing two coats with Malamine polish of required shade on new wood and wood based surface to give an even surface including cleaning the surface of all dirt, dust and sand papered smooth and including a coat of wood filler with in all leads and lifts complete, as per direction of Engineer-in-Charge including carriage of materials and other incidentals. The rates are including the octroi, royalty Malkana, Toll tax Sales tax, GST or any taxes imposed by the Govt.	108.72			Per square metre	

6	Applying birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface with in all leads and lifts complete, as per direction of Engineer-in-Charge including carriage of materials and other incidentals. The rates are including the octroi, royalty Malkana, Toll tax Sales tax, GST or any taxes imposed by the Govt.	35.37				Per square metre	
7	Finishing wall with weather proof exterior grade emulsion of approved design (apexultima) or its equalised on undecorated wall surfaces (two coats ) to give an even after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc including sand paper smooth complete with in all leads and lifts complete, as per direction of Engineer-in-Charge including carriage of materials and other incidentals. The rates are including the octroi, royalty Malkana, Toll tax Sales tax, GST or any taxes imposed by the Govt.	324.25				Per square metre	
8	Painting two coats (excluding priming coat) on previously painted steel and other metal surfaces, with enamel paint, brushing to give an even shade including cleaning of all dirt, dust and other foreign matter sand papering and stopping readymixed paint other then whitewash in all leads and lifts complete, as per direction of Engineer-in-Charge including carriage of materials and other incidentals. The rates are including the octroi, royalty Malkana, Toll tax Sales tax, GST or any taxes imposed by the Govt.	450.00				Per square metre	
Total:-							

Executive Engineer  
Chowari Division  
Hppwd Chowari

17

## Schedule of Quantity

Estimate Cost :- Rs.	491550/-
Earnest Money	9831/-
Time Limit	Three months

Name of work:- Restoration of Rain Damage on Chowari to Jot Road km 53/0 to 76/0 (SH:- Hiring of Excavator cum loader for removal of silps and Tipper for carriage of material)

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Hiring of JCB/ Excavator cum loader for cutting /widening work road or removal of silps in all kinds of soil and disposing of all excavated earth or unserviceable materials from the road surface upto any leads and lifts upto any height and depths as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be have to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also be borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge	410.00			Per hour	
2	Hiring of Tipper having capacity 5.5 ( five decimal five zero ) cubic meter for carriage of all type of material upto any leads and lifts as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be have to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also are borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	110.00			Per hour	

**Executive Engineer**  
 Chowari Division  
 HPPWD. Chowari



### Schedule of Quantity


Estimated Cost	Rs. 452948/-
Earnest Money	Rs. 9059/-
Time Limit	Three months
	(SH:- C/o

**NAME OF WORK:-** Restoration of rain damages on Nurpur Sanjha Nallah Lahru Tunuhatti Road km 25/0 to 40/810  
**R/wall at RD 36/635 to 36/643, Parapets between RD 40/030 to 40/150 and extension of HP culvert at RD 36/655)**

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material, as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt	49.49			Per cubic metre	
2	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:3:6) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	0.94			Per cubic metre	
3	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:2.5:5) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	0.38			Per cubic metre	
4	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:2:4) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	0.37			Per cubic metre	
5	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:2.5:5) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	16.24			Per cubic metre	
6	Providing and laying (to level or slope) 900mm dia (Nine thousand millimeters) diameter reinforced cement concrete heavy duty non pressure pipes IS Class NP-2 for culverts in single row including fixing collar with cement mortar 1 : 2 ( One cement : two sand) but excluding the cost of excavation, protection works, back filling, bedding concrete or first class bedding and masonry work in head walls and parapets as per drawing and MORD technical specifications section 11080, including hauling of materials in all leads and lifts and other incidental. The rate including Octroi, Royalty, Malkana, Toll Tax, Sale Tax, GST or other taxes imposed by the Government	2.50			Per running metre	
7	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	58.40			Per cubic metre	



8	Providing weep holes in brick masonry/ stone masonry/ palin reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of ( IV ); 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614,709,1204.3.7 as per the directions of the Engineer-in-charge. i/c carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	21			Each	
9	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in Charge i/c carriage of materials with in all leads, lifts and other incidentals. The Rate including octroi Royalty Malkana Toll tax Sale tax or any other taxes imposed by the Govt.	15.36			Per cubic metre	

  
 Executive Engineer,  
 Chowari Division,  
 H.P.W.D. Chowari

## Schedule of Quantity

Name of work:- Restoration of Rain Damage on Shahpur Sihunta Chowari Jot Chamba Road km 40/0 to 53/00 (SH:-Hiring of Excavator cum loader for removal of silps km 40/0 to 47/0)

		Estimate Cost :- Rs.		491400/-	
		Earnest Money		9828/-	
		Time Limit		Three months	

Name of work:- Restoration of Rain Damage on Shahpur Sihunta Chowari Jot Chamba Road km 40/0 to 53/00 (SH:-Hiring of Excavator cum loader for removal of silps km 40/0 to 47/0)					
<u>Schedule of Quantity</u>					
S.No.	Description	Quantity	Rate	Unit	Amount
			in Fig.	in Word	
1	Hiring of JCB/ Excavator cum loader for cutting /widening work road or removal of silps in all kinds of soil and disposing of all excavated earth or unserviceable materials from the road surface upto any leads and lifts upto any height and depths as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be lave to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also be borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge	468.00		Per hour	

**Executive Engineer**  
**Chowari Division**  
**HPWD, Chowari**

(20)

## Schedule of Quantity


Estimate Cost :- Rs. 494025/-

Earnest Money 9881/-

Time Limit Three months

**Name of work:- Restoration of Rain Damage on Nurpur Sanjha Nallah Lahru Tunuhatti Road km 15/390 to 25/00 (SH:-Hiring of Excavator cum loader for removal of silps km 20/0 to 25/0)**

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Hiring of JCB/ Excavator cum loader for cutting /widening work road or removal of silps in all kinds of soil and disposing of all excavated earth or unserviceable materials from the road surface upto any leads and lifts upto any height and depths as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be have to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also be borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge	415.00			Per hour	
2	Hiring of Tipper having capacity 5.5 ( five decimal five zero ) cubic meter for carriage of all type of material upto any leads and lifts as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be have to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also are borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	105.00			Per hour	

  
**Executive Engineer**  
 Chowari Division  
 RPPWD. Chowari


(291)

### Schedule of Quantity

Estimated Cost	Rs. 470885/-
Earnest Money	Rs. 9418/-
Time Limit	Three months

Name of work:- Restoration of Rain Damage on Shahpur Silhunta Chowari Jot Road km 40/0 to 76/00  
(SH:- C/o R/wall with Pusta at RD 50/750 to 50/758)

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material. as per the direction of the Engineer in Charge. Including Carriage of material within all leads and lifts and other incidental The Rate including octroi, royalty, Malkana Toll tax sale tax or other taxes imposed by the Govt.	25.96			Per cubic metre	
2	Providing and laying concrete for Plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202, and 1203 (P.C.C Nominal size 1:5:10) within all leads and lifts as per the direction of Engineer in Charge including carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	92.64			Per cubic metre	
3	Back filling with granular material behind abutments return walls, wing walls and retaining walls complete as per drawing and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in Charge i/c carriage of materials with in all leads, lifts and other incidentals. The Rate including octroi Royalty Malkana Toll tax Sale tax or any other taxes imposed by the Govt.	12.72			Per cubic metre	
4	Providing weep holes in brick masonry/ stone masonry/ plain reinforced abutment wing wall, return wall with hundred mm dia PVC pipe extending through the full width of the structures with slope of ( IV ); 20 (H) towards drawings face complete as per drawing & technically specifications clauses 614.709, 1204.3.7 as per the directions of the Engineer-incharge. i/c carriage of materials with in all leads, lifts and other incidentals. The rate i/c the octroi royalty, Malkana toll tax, sales tax or ay other taxes imposed by the Govt.	26.00			Each	
<b>Total</b>						

  
**Executive Engineer**  
 Chowari Division  
 Hppwd Chowari




## Schedule of Quantity

Name of work:- Restoration of rain damages on various roads under kakira Sub-Division Balera Section  
removal of silps)

(SH:-Hiring of Excavator cum loader for

Estimate Cost	495600/-
Earnest Money	9912/-
Time Limit	Three months

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Hiring of JCB/ Excavator cum loader for cutting /widening work road or removal of silps in all kinds of soil and disposing of all excavated earth or unserviceable materials from the road surface upto any leads and lifts upto any height and depths as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be lave to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also be borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	472.00			Per hour	

  
 Executive Engineer  
 Chowari Division  
 HPPWD, Chowari

53

### Schedule of Quantity

Name of work:- Restoration of rain damage on various roads under Kakira sub-Division ( SH:- Hiring of Hydraulic Excavator cum Loader for removal of slips)

Estimated Cost	Rs. 498750/-
Earnest Money	Rs. 10000/-
Time Limit	One month

S.No.	Description	Quantity	Rate		Unit	Amount
			in Fig.	in Word		
1	Hiring of JCB/ Excavator cum loader for cutting /widening work road or removal of slips in all kinds of soil and disposing of all excavated earth or unserviceable materials from the road surface upto any leads and lifts upto any height and depths as per direction and entire satisfaction of Engineer-in-Charge. Any loss to the Public/private property or any accident etc. happened during the course hiring period/execution shall be absolute responsibility of the JCB owner which shall be have to fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare watch and ward of machine also be borne by the contractor /Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge .The rate is including royalty, Malkana,Toll tax, GST or other taxes imposed by the Government.	475.00			Per hour	
Total						

Executive Engineer  
Chowari Division  
Hppwd Chowari