



Office of the
Executive Engineer,
Hamirpur Division (B&R), HPPWD Hamirpur,
Tel: +911972-222510 Fax: +911972-222510
Email: ee-ham-hp@nic.in.

No:-PW/Hamirpur/CB/GA-1/Tender/2023-24- **12538-548**
To

Dated:- **29.11.2023**

The Executive Engineer (IT Cell),
Nigam Vihar, HP Shimla-2.

Subject:- Publication of Tender Notice.

Sir,

Enclosed please find herewith the Tender Notice of various works as given in the Notice Inviting Tender, As per Notification Pr. Secy (PW) to the Govt. of Himachal Pradesh letter No. PBW(B)A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the works mentioned in the tender Notice are of urgent nature and in public interest, the same may be uploaded on the departmental website.


DA/- Notice Inviting Tender/Scheduled of Quantity
And "A" Certificate.


Executive Engineer
Hamirpur Division HPPWD
Hamirpur Hamirpur.

Copy forwarded with its enclosures for information to:-

1. The Engineer-in-Chief, H.P.W.D., Shimla-2.
2. The Chief Engineer (HZ), H.P.W.D., Hamirpur.
3. The Superintending Engineer, 8th Circle, HPPWD, Hamirpur.
4. The Assistant Engineer, Sub Division, HPPWD Hamirpur/Lamblao & Nadaun.
5. Drawing Branch in this office.
6. Accounts Branch in this office.
7. Supdt of C Branch in this office.
8. Notice Board.


Executive Engineer
Hamirpur Division HPPWD
Hamirpur Hamirpur.



Office of the
Executive Engineer,
Hamirpur Division (B&R), HPPWD Hamirpur.
Tel: +911972-222510 Fax: +911972-222510
Email: ee-ham-hp@nic.in

CERTIFICATE

Certified that the works are of urgent in nature and for larger public interest so there is exigencies/emergency in calling these tenders without press vide this office letter No. PW/Hamirpur/CB/GA-1/Tender/2023-24- 12538-548 dated 29/11/2023


Executive Engineer
Hamirpur Division HPPWD
Hamirpur Hamirpur.



Office of the
Executive Engineer,
Hamirpur Division (B&R), HPPWD Hamirpur.
Tel: +911972-222510 Fax: +911972-222510
Email: ee-ham-hp@nic.in

NOTICE INVITING TENDER.

Sealed item rate tender on form 6 & 8 are hereby invited by the Executive Engineer Hamirpur Division HPPWD Hamirpur on behalf of Governor of HP, from the approved eligible contractors enlisted in HPPWD for the following works; so as to reach this office on 13.12.2023 up to 10.30 A.M. and same will be opened on the same day at 11.00 A.M. in presence of the interested contractors or their authorized representative. The application will be received in this office on dated 08.12.2023 upto 3.00 P.M. The tender form can be had from the office of Executive Engineer Hamirpur Division HPPWD Hamirpur on cash payment (Non-refundable) on 11.12.2023 during office hours till 1.00 P.M. The application must be accompanied with earnest money in shape of NSD/FDR/Time deposit etc. of any post office of HP, or Nationalized Bank duly pledged in the name of Executive Engineer Hamirpur Division HPPWD Hamirpur cash order will not be entertained, it may be ensure that the earnest money shall have to be prepared work wise otherwise forms will not be issued. The offer of tender shall be kept upon for 60 days. The conditional tender or tender received by post will also be rejected. The undersigned reserves the right to reject any or all tenders without assigning any reason. All the approved eligible contractors should bring copy of their valid enlistment/renewal/exemption from earnest money with them. The tender documents will be issued only to those who fulfill the eligibility conditions. The contractor should be registered as dealer under GST Act, Valid copy of Registration as required, Copy of PAN Card, EPF failing which no tender form will be issued to him.

HIM SUCHANA AVAM JAN SAMPARK.

Executive Engineer
Hamirpur Division HPPWD
Hamirpur Hamirpur.
On behalf of Governor of Himachal Pradesh.

PRESS TENDER NOTICE (Offline)

Sr. No.	Name of Work	Estimated Cost (in Rs.)	Earnest Money (in Rs.)	Time
1	Improvement of Black spot on link road Patta to Jalari km 0/0 to 4/650. (SH:- C/o R/wall at RD 4/300 to 4/312).	471557.00	9500.00	One Month
2	Improvement of black spot on link road Mansoli Maloti Sasan to Rainthal km 0/0 to 1/520. (SH:- C/o R/wall at RD 0/245 to 0/258).	358189.00	7200.00	One Month
3	Improvement of black spot on NH Har Sukrala road km 0/0 to 7/165. (SH:- C/o R/wall at RD 0/095 to 0/107).	471557.00	9500.00	One Month
4	Improvement of black spot on link road Lahar to Rattian km 0/0 to 2/200. (SH:- C/o R/wall at RD 1/0 to 1/012).	471267.00	9500.00	One Month
5	Improvement of black spot on Dodlu Garyali road km 0/0 to 3/520. (SH:- C/o R/wall at RD 2/275 to 2/293).	471717.00	9500.00	One Month
6	Improvement of black spot on NH-70 Kohla Kaloor Bilvkaleshwar road km 0/0 to 10/600. (SH:- C/o R/wall at RD 0/300 to 0/331).	489650.00	9800.00	One Month
7	Improvement of black spot on Choru Bhou Jeehan road km 0/0 to 6/0. (SH:- C/o R/wall at RD 2/300 to 2/328).	477115.00	9600.00	One Month
8	Improvement of black spot on Nadaun Sujampur road MDR-36 km 0/0 to 14/600. (SH:- C/o R/wall at RD 13/900 to 13/930).	475565.00	9600.00	One Month
9	Improvement of black spot on Nadaun Sujampur road MDR-36 km 0/0 to 14/600. (SH:- C/o R/wall at RD 0/750 to 0/781).	491100.00	9600.00	One Month
10	Improvement of black spot on Har Holwin Har road km 0/0 to 2/0. (SH:- C/o Retaining wall at RD 1/0 to 1/012).	473007.00	9500.00	One Month
11	Improvement of black spot on NH-03 Shaloya to village Badwal km 0/0 to 1/800. (SH:- C/o Retaining wall at RD 0/870 to 0/882).	470687.00	9500.00	One Month
12	Improvement of black spot on Dangri Tutroo road km 0/0 to 2/500. (SH:- C/o R/wall at RD 1/885 to 1/897).	471847.00	9500.00	One Month
13	A/R & M/O various road under Nadaun Sub-Division. (SH:- Bush cutting, maintenance of earthen shoulder on various road in Bara Section)	249147.00	5000.00	One Month
14	A/R & M/O various road under Nadaun Sub-Division. (SH:- Bush cutting, maintenance of earthen shoulder on various road in Rangas Section)	249209.00	5000.00	One Month
15	A/R & M/O Tiyaie Da Ghat to Patta via Draundla km 0/0 to 3/300. (SH:- C/o Retaining wall/Edge wall at RD 2/695 to 2/715).	155958.00	3200.00	One Month
16	A/R & M/O District and Session Court Building at Hamirpur. (SH:- Painting of existing boundary wall, C/o drain and other General repair work in courtyard area).	292474.00	5900.00	One Month
17	A/R & M/O Assistant Engineer Residence Nadaun Tehsil Nadaun Distt. Hamirpur (HP). (SH:- Painting, P/F Cupboard Shutter, P/F door and windows shutter	276819.00	5700.00	One Month

18	A/R & M/O Sub-Division Office Building at Nadaun Tehsil Nadaun Distt. Hamirpur (HP). (SH:- Repair to plaster patches, painting, P/F Cupboard shutter, P/F Glazed shutter, P/F curtain Rods & Sanitary etc).	278365.00	5700.00	One Month
19	Restoration of rain damages on Bhumpal Sadwan road km 0/0 to 4/975. (SH:- Dismantling of existing interlocking tiles & P/L cement concrete & 80mm thick interlocking paver blocks at RD 4/390 to 4/470).	285462.00	5600.00	One Month
20	Restoration of rain damages on link road from Balhi to Samad km 0/0 to 0/400. (SH:- C/o 900mm dia Hume pipe culvert at RD 900mm dia hume pipe culvert at RD 0/180).	280693.00	5700.00	One Month
21	Restoration of rain damages on link road Patta to Jalari km 0/0 to 4/650. (SH:- C/o U-Shape drain at RD 2/240 to 2/298 & V-Shape drain at RD 2/298 to 2/533).	499688.00	10000.00	Two Months
22	Restoration of rain damages on link road Patta to Jalari km 0/0 to 4/650. (SH:- C/o U-Shape drain at RD 4/239 to 4/375 & V-Shape drain at RD 3/855 to 4/063).	499475.00	10000.00	Two Months
23	Restoration of rain damages on link road Patta to Jalari km 0/0 to 4/650. (SH:- C/o U-Shape drain at RD 1/900 to 2/035 & V-Shape drain at RD 2/035 to 2/240).	499210.00	10000.00	Two Months
24	Restoration of rain damages on link road Harzan Basti Chiggar km 0/0 to 0/180. (SH:- C/o PCC Retaining wall at RD 0/114 to 0/121.50 under MMGSY).	478508.00	9600.00	One Month
25	Restoration of rain damages on Hamirpur Jahu road km 3/690 to 8/0. (SH:- C/o Breast wall between km 7/047 to 7/067).	252180.00	5100.00	One Month
26	Repair and maintenance of Janj Ghar to village Jangal in GP Putrail Tehsil Nadaun Distt. Hamirpur. (SH:- P/L Steel Truss roofing etc.).	313182.00	6300.00	One Month
27	Repair and maintenance of existing Court Complex building at Nadaun, Distt. Hamirpur (HP). (SH:- Demolishing existing roofing sheet, providing and fixing new prepainted steel, built up section work in fascia and soffit, fixing BP in fascia and soffit).	499500.00	10000.00	One Month
28	Repair and maintenance of existing Court Complex building at Nadaun, Distt. Hamirpur (HP). (SH:- Providing and laying painting work).	126528.00	2600.00	One Month
29	Repair and maintenance of existing Court Complex building at Nadaun, Distt. Hamirpur (HP). (SH:- Demolishing existing roofing sheet, providing and fixing new prepainted steel, built up section work in fascia and soffit, fixing BP in fascia and soffit.).	499376.00	10000.00	One Month
30	Special repair to ECH Poly Clinic building at Hamirpur. (SH:- Providing and laying Interlocking paver block in leftout space in front side of building used as parking, U-Shape Drain along the road).	318541.00	6400.00	Two Months
31	C/o Boundary wall and Gate at Govt. Sr. Sec. School at Jalari Tehsil Nadaun Distt. Hamirpur (HP).	457328.00	9200.00	One Month

32	Construction of Residential Accommodation Type-IV Qtrs. 1 No. Type-III Qtrs. 4 Nos and Type-II Qtrs 12 Nos of SV & ACB in Police Line Hamirpur at Dosarka. (SH- C/o Retaining wall for approach road to SV & ACV Residence and Police Station 0/015.10 to 0/022.70).	425865.00	9900.00	One Month
33	C/o Combined office building (Mini Secretariat) at Nadaun in Distt. Hamirpur (HP). (SH- C/o balance work of half and full brick work, wall panelling and wooden ceiling work, polishing, ceiling work in SDM Office etc.).	447956.00	9000.00	One Month
34	C/o Combined office building (Mini Secretariat) at Nadaun in Distt. Hamirpur (HP). (SH- C/o balance work of half and full brick work, wall panelling and wooden ceiling work, polishing ceiling work in MLA Office etc.).	442136.00	9000.00	One Month
35	C/o link road from Sasan to Jhanjari via 1HM, Sidh Baba km 0/0 to 2/0 (SH- P/L 80mm thick cement concrete paver block km 0/90 to 0/144).	498098.00	10000.00	One Month
36	C/o link road from Sasan to Jhanjari via 1HM, Sidh Baba km 0/0 to 2/0 (SH- P/L 80mm thick cement concrete paver block km 0/210 to 0/263).	488972.00	9800.00	One Month
37	Restoration of rain damages on Kallar to Kesari Bridge im 0/0 to 1/560. (SH- Repair of Pot Holes at various RDs).	300000.00	6000.00	One Month
38	Restoration of rain damages on link road to village Ghurar road km 0/0 to 1/390. (SH- Construction of Wire Crate, Retaining wall at RD 0/095.80 to 0/116.60).	499872.00	10000.00	One Month
39	Restoration of rain damages on link road to village Ghurar road km 0/0 to 1/390. (SH- Construction of Wire Crate, Retaining wall at RD 0/075 to 0/095.80).	499872.00	10000.00	One Month
40	Restoration of rain damages on Aghar Mehal road km 0/0 to 4/0. (SH- construction of wire crates at RD2/415 to 2/421 and filling at RD 2/393 to 2/421).	172540.00	3500.00	One Month
41	Detailed Project Report for link road (i) Dhaned to Talasi from km 0/0 to 5/670. (ii) C/o link road from Galot to Har via Gugga Mandir from km 0/0 to 3/0 including 1 No. bridge under NABARD (SH- Preparation of detailed project report). (iii) C/o bridge over Dugh Khad at Rd 1/765 on link road Bari to Harizen basti Dug km 0/0 to 2/0. (SH- Preparation of Hydraulic data report and drawing complete including consultancy service for topographical survey).	381695.00	7700.00	One Month
42	C/o link road from Jatheri to Balh Bhalana in GP Sasan km 0/0 to 1/0. (SH- Providing and laying WMM and complete Metalling/Tarring in km 0/0 to 0/300).	497755.00	10000.00	One Month
43	Repair and maintenance of various bridges under HPPWD Hamirpur Sub Division. (SH- (i) Repair of bridge of Masyana to Bhatwara road at Rd 1/900. (ii) Repair of bridge on Sasan Baleta road at Rd 5/0).	498194.00	10000.00	One Month

44	Restoration of rain damages on link road Patta to Jalari km 0/0 to 4/650. (SH:- Construction of U-Shape drain at RD 1/508 to 1/641 & V-Shape drain at RD 1/641 to 1/868).	499012.00	10000.00	One Month
45	Restoration of rain damages on link road Patta to Jalari km 0/0 to 4/650. (SH:- Construction of U-Shape drain at RD 1/375 to 1/508 & V-Shape drain at RD 1/030 to 1/060 and 1/180 to 1/375).	498194.00	10000.00	One Month


 Executive Engineer,
 Hamirpur Division,
 HPPWD Hamirpur.

DRAFT SCHEDULE OF QUANTITY

Name Of Work:- Improvement of Black spot on link road Patta to Jalari km 0/0 to 4/650. (SH:- C/o R/wall at RD 4/300 to 4/312).				Estimated Cost-Rs. 471557.00 Earnest Money:- Rs.9500.00 Time Limit:- One Month		
Sr. No.	Description of Items	Qty.	Fig.	Rate in		Amount
				Words	Unit	
1	Excavation work by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms within all leads including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads and lifts ordinary rock and all kinds of soil including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	36.72	300.00	Rupees Three Hundred and Paise Zero Only	Per cubic metre	11016.00
2	Providing and laying in position cement concrete of specified grade 1:5:10 (one cement: five coarse sand: ten graded stone aggregate) 40mm (forty millimetre) nominal size graded stone aggregate in retaining wall, breast wall, walls of any thickness and like structures excluding the cost of centering and shuttering including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	107.64	4200.00	Rupees Four Thousand Two Hundred and Paise Zero Only	Per cubic metre	452088.00
3	Providing weep holes in brick masonry / Stone masonry / plain/reinforced concrete in retaining walls, breast walls and the like with 110mm (One hundred ten millimetre) dia PVC pipe Finolex/Supreme having pressure not less than 4.00 Kg/Cm ² (four kilogramme) per centimetre square extending through the full width of the structure with slope of 1(V) 20(H) (one vertical: twenty horizontal) towards drawing face complete including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	25.00	290.00	Rupees Two Hundred Ninety and Paise Zero Only	Per Running metre	7250.00
4	Providing and fixing Geo-Textile membrane behind RCC and PCC retaining walls Ocean Non woven Geotextile 3mm (Three millimetre) thickness including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	7.29	165.00	Rupees One Hundred Sixty Five and Paise Zero Only	Per square metre	1203.00
Total						471557.00

Condition

- The work will be strictly executed as per HPPWD specifications
- The contractor will procure cement at their own level from Civil Supply Depot. After the approval of permit from the competent authority and other material from market as per Department specification issued by the Additional Chief Secretary PW to the Govt. of HP vide No. PSW (B) C (17) 2/2012 dated 07 August 2018 and all other condition are liable & carriage will be born by the contractor
- The bills of all materials procured by the contractor M-form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill.

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS. 471557/-

Rupees Four Lakhs Seventy One Thousand Five Hundred Fifty Seven and Paise Zero Only

Executive Engineer,
Hamirpur Division,
HPPWD, Hamirpur

144 N
283

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Improvement of Black spot on Har Holwin Har road Km 0/0 to 2/0
(SH:- C/O retaining wall at RD 1/00 to 1/012)

Estimated Cost:-Rs.473007.00
Earnest Money:- Rs.9500.00
Time Limit:- One Month

Sr. No.	Description of Items	Qty.	Rate in Fig.	Words		Unit	Amount
1	Excavation work by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, up to 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soil in ordinary rock and Pick work and jumper work including entire carriage of materials within 80 leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	36.72	300.00	Rupees Three Hundred and Paise Zero Only		Per cubic metre	11016.00
2	Providing and laying in position concrete of specified grade 1:1.5:10 (one cement five coarse sand ten graded stone aggregate) 40mm (forty millimetre) nominal size graded stone aggregate in retaining wall, breast wall, walls of any thickness and like structures excluding the cost of centering and shuttering including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	107.64	4200.00	Rupees Four Thousand Two Hundred and Paise Zero Only		Per cubic metre	452088.00
3	Providing and fixing Single socketed pipes 110mm (one hundred ten millimetre) dia of Supreme/Endox/Vectus make on wall face unplasticised Rigid PVC rain water pipes conforming to IS: 13592 Type A, including jointing with seal ring conforming to IS: 5382, leaving 10 mm (ten millimetre) gap for thermal expansion complete upto all floor level including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	30.00	260.00	Rupees Two Hundred Ninety and Paise Zero Only		Per Running Metre	8700.00
4	Providing and fixing Geo-Textile membrane behind RCC and PCC retaining walls Ocean Non woven Geotextile 3mm (Three millimetre) thickness including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	7.29	165.00	Rupees One Hundred Sixty Five and Paise Zero Only		Per square metre	1203.00
Total							473007.00

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS.473007/-
Rupees Four Lakhs Seventy Three Thousand Seven and Paise Zero Only

- The work will be strictly executed as per HPPWD specifications
- The contractor will procure cement at their own level from Civil Supply Depot. After the approval of permit from the competent authority and other material from market as per Department Specification issued by the Additional Chief Secretary PW to the Govt. of H.P. vide No. PBW (B) C (17) 2/2012 dated 07 August 2018 and all other condition are liable & carriage will be born by the contractor
- The bills of all materials procured by the contractor in form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill


 Executive Engineer,
 Hamirpur Division,
 HPPWD, Hamirpur

145 N
290

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Improvement of Black spot on Dodlu Garyali road Km 0/0 to 3/520
(SH:- C/O retaining wall at RD 2/275 to 2/293)

Estimated Cost:-Rs.471717.00
Earnest Money:- Rs.9500.00
Time Limit:- One Month

Sr. No.	Description of Items	Qty.	Rate in Fig.	Words	Unit	Amount
1	Excavation work by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and rammings of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soil in ordinary rock and Pick work and jumper work including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	36.90	300.00	Rupees Three Hundred and Paise Zero Only	Per cubic metre	11070.00
2	Providing and laying in position cement concrete of specified grade 1:5:10 (one cement : five coarse sand : ten graded stone aggregate) 40mm (forty millimetre) nominal size graded stone aggregate in retaining wall, breast wall, walls of any thickness and like structures excluding the cost of centering and shuttering including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	107.32	4200.00	Rupees Four Thousand Two Hundred and Paise Zero Only	Per cubic metre	450744.00
3	Providing and fixing Single socketed pipes 110mm (one hundred ten millimetre) dia of Supreme/Fenolax/ Vectus make on wall face ungalvanized Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm (ten millimetre) gap for thermal expansion complete upto all floor level including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	30.00	290.00	Rupees Two Hundred Ninety and Paise Zero Only	Per Running Metre	8700.00
4	Providing and fixing Geo-Textile membrane behind RCC and PCC retaining walls Ocean Non woven Geotextile 3mm (Three millimetre) thickness including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	7.29	165.00	Rupees One Hundred Sixty Five and Paise Zero Only	Per square metre	1203.00
Total						471717.00

Condition

1 The work will be strictly executed as per HPPWD specifications

2 This contractor will procure cement at their own level from Civil Supply Depot. After the approval of permit from the competent authority and other material turn market as per Department specification issued by the Additional Chief Secretary PW to the Govt. of HP vide No. PSW (B) C (17) 200112 dated 07 August 2016 and all other condition are liable & carriage will be born by the contractor

3 The bills of all materials procured by the contractor M-form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill.

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS.471717/-
Rupees Four Lakhs Seventy One Thousand Seven Hundred Seventeen and Paise Zero Only


 Executive Engineer
 Hamirpur Division
 HPPWD Hamirpur

1467 H
289

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Improvement of Black spot on NH-70 Kohla Kaloor Bilkaleshwar road Km 0/0 to 10/600
(SH:- C/O retaining wall at RD 0/300 to 0/331)

Estimated Cost:-Rs.489650.00
Earnest Money:- Rs.9800.00
Time Limit:- One Month

Sr. No.	Description of Items	Qty.	Rate in Fig.	Words	Unit	Amount
1	Excavation work by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soil in ordinary rock and Pick work and jumper work including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	35.96	300.00	Rupees Three Hundred and Paise Zero Only	Per cubic metre	10788.00
2	Providing and laying in position cement concrete of specified grade 1:5:10 (one cement : five coarse sand : ten graded stone aggregate) 40mm (forty millimetre) nominal size graded stone aggregate in retaining wall, breast wall, walls of any thickness and like structures excluding the cost of centering and shuttering including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	111.45	4200.00	Rupees Four Thousand Two Hundred and Paise Zero Only	Per cubic metre	468990.00
3	Providing and fixing Single socketed pipes 110mm (one hundred ten millimetre) dia of Supreme/Endotax/ Vedus make on wall face unplasticized Rigid PVC rain water pipes conforming to IS : 15592 Type A, including jointing with seal ring conforming to IS : 5362, leaving 10 mm (ten millimetre) gap for thermal expansion complete upto all floor level including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	30.00	290.00	Rupees Two Hundred Ninety and Paise Zero Only	Per Running Metre	8700.00
4	Providing and fixing Gao-Tex/Geotextile membrane behind RCC and PCC retaining walls Ocean Non woven Geotextile 3mm (Three millimetre) thickness including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	12.56	165.00	Rupees One Hundred Sixty Five and Paise Zero Only	Per square metre	2072.00
Total						489650.00

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS.489650/-
Rupees Four Lakhs Eighty Nine Thousand Six Hundred Fifty and Paise Zero Only

- The work will be strictly executed as per HPPWD specifications.
- The contractor will procure cement at their own level from Civil Supply Depot. After the approval of permit from the competent authority and other material turn market as per Department specification issued by the Additional Chief Secretary PW to the Govt of HP vide No. PBW (R) C (17) 2/2012 dated 07 August 2018 and all other condition are liable & carriage will be born by the contractor.
- The bills of all materials procured by the contractor M-form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill.

Executive Engineer
Hamirpur Division
HPPWD, Hamirpur

147
286

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Improvement of Black spot on Choru Bhou Jeehan road Km 0/0 to 6/0
(SH:- C/O retaining wall at RD 2/300 to 2/328)

Estimated Cost:-Rs.474115.00
Earnest Money:- Rs.5500.00
Time Limit:- One Month

Sr. No.	Description of Items	Qty.	Rate in Fig.	Words	Unit	Amount
1	Excavation work by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten square metre) or plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soil in ordinary rock and Pick work and jumper work, including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge, including all incidental. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	34.80	300.00	Rupees Three Hundred and Paise Zero Only	Per cubic metre	10440.00
2	Providing and laying in position concrete of specified grade 1:5:10 (one cement, five coarse sand, ten graded stone aggregate) 40mm (forty millimetre) nominal size graded stone aggregate in retaining wall, breast wall, walls of any thickness and the structures excluding the cost of centering and shuttering, including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge, including all incidental. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	107.85	4200.00	Rupees Four Thousand Two Hundred and Paise Zero Only	Per cubic metre	452970.00
3	Providing and fixing Single socketed pipes 110mm (one hundred ten millimetre) dia of Supreme/Enolux/Vectus make on wall face unclassified Rigid PVC rain water pipes conforming to IS : 13582 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm (ten millimetre) gap for thermal expansion complete upto all floor level, including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge, including all incidental. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	30.00	290.00	Rupees Two Hundred Ninety and Paise Zero Only	Per Running Metre	8700.00
4	Providing and fixing Geo-Textile membrane behind RCC and PCC retaining walls Ocean Non woven Geotextile 3mm (Three millimetre) thickness including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge, including all incidental. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	12.15	165.00	Rupees One Hundred Sixty Five and Paise Zero Only	Per square metre	2005.00
Total						474115.00

Condition

- The work will be strictly executed as per HPPWD specifications
- The contractor will procure cement at their own level from Civil Supply Depot. After the approval of permit from the competent authority and other material from market as per Department specification issued by the Assistant Chief Secretary PW to the Govt. of HP vide No. PBW (B) C (17) 2020/2 dated 07 August 2018 and all other condition are liable & carriage will be born by the contractor
- The bills of all materials procured by the contractor M-form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS.474115/-
Rupees Four Lacks Seventy Four Thousand One Hundred Fifteen and Paise Zero Only

Executive Engineer,
Hamirpur Division
HPPWD, Hamirpur

148
285

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Improvement of Black spot on Nadaun Sujapur road MDR-36 Km 0/0 to 14/600
(SH:- C/O retaining wall at RD 13/900 to 13/930)

Estimated Cost:- Rs.475565.00
Earnest Money:- Rs.9600.00
Time Limit:- One Month

Sr. No.	Description of Items	Qty.	Rate in Fig.	Words	Unit	Amount
1	Excavation work by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ranning of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soil in ordinary rock and Pick work and Jumper work including entire carriage of materials within at leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	34.80	300.00	Rupees Three Hundred and Paise Zero Only	Per cubic metre	10440.00
2	Providing and laying in position cement concrete of specified grade 1:1.5:10 (one cement : five coarse sand : ten graded stone aggregate) 40mm (forty millimetre) nominal size graded stone aggregate in retaining wall, breast wall, walls of any thickness and like structures excluding the cost of centering and shuttering including entire carriage of materials within at leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	107.85	4200.00	Rupees Four Thousand Two Hundred and Paise Zero Only	Per cubic metre	452970.00
3	Providing and fixing Single socketed pipes 110mm (one hundred ten millimetre) dia of Supreme/Endox/Vectus make on wall face unplastered Rigid P-Vc ren water pipes conforming to IS : 13592 Type A, including joining with seal ring conforming to IS : 5382, leaving 10 mm (ten millimetre) gap for thermal expansion complete upto all floor level including entire carriage of materials within at leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	35.00	290.00	Rupees Two Hundred Ninety and Paise Zero Only	Per Running Metre	10150.00
4	Providing and fixing Geo-Textile membrane behind ROC and PCC retaining walls Ocean Non woven Geotextile 3mm (Three millimetre) thickness including entire carriage of materials within at leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	12.15	165.00	Rupees One Hundred Sixty Five and Paise Zero Only	Per square metre	2005.00
Total						475565.00

- Condition**
- The work will be strictly executed as per HPPWD specifications
 - The contractor will procure cement at their own level from Civil Supply Depot. After the approval of permit from the competent authority and other material from market as per Department specification issued by the Additional Chief Secretary PW to the Govt. of HP vide No. PW (B) C (17) 2020/2 dated 07 August 2018 and all other condition are liable & carriage will be born by the contractor
 - The bills of all materials procured by the contractor in form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill.

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS.475565/-
Rupees Four Lakhs Seventy Five Thousand Five Hundred Sixty Five and Paise Zero Only


 Executive Engineer
 Hamirpur Division
 HPPWD, Hamirpur

1497 N
284

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Improvement of Black spot on Nadaun Sujampur road MDR-36 Km 0/0 to 14/500
(SH:- C/O retaining wall at RD 0/750 to 0/781)

Estimated Cost-Rs.491000.00
 Earnest Money:- Rs.9900.00
 Time Limit:- One Month

Sr. No.	Description of Items	Qty.	Rate in Fig.	Words	Unit	Amount
1	Excavation work by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soil in ordinary rock and Pick work and jumper work including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	35.96	300.00	Rupees Three Hundred and Paise Zero Only	Per cubic metre	10788.00
2	Providing and laying in position cement concrete of specified grade 1:1.5:10 (one cement : five coarse sand : ten graded stone aggregate) 40mm (forty millimetre) nominal size graded stone aggregate in retaining wall, breast wall, walls of any thickness and like structures excluding the cost of centering and shuttering including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	111.45	4200.00	Rupees Four Thousand Two Hundred and Paise Zero Only	Per cubic metre	468090.00
3	Providing and fixing Single socketed pipes 110mm (one hundred ten millimetre) dia of Supreme/Enallax/Vectus make on wall face ungalvanized Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm (ten millimetre) gap for thermal expansion complete upto all floor level including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	35.00	290.00	Rupees Two Hundred Ninety and Paise Zero Only	Per Running Metre	10150.00
4	Providing and fixing Geo-Textile membrane behind RCC and PCC retaining walls Ocean Non woven Geotextile 3mm (Three millimetre) thickness including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	12.56	165.00	Rupees One Hundred Sixty Five and Paise Zero Only	Per square metre	2072.00
Total						491100.00

Condition
 The work will be strictly executed as per HPPWD specifications

The contractor will procure cement at their own level from Civil Supply Depot. After the approval of permit from the competent authority and other material from market as per Department specification issued by the Additional Chief Secretary PW to the Govt. of HP vide No. PBW (B) C (17) 202012 dated 07 August 2018 and all other condition are liable & carriage will be born by the contractor

The bills of all materials procured by the contractor in form of billing materials used for execution of work must be submitted to the authority concerned alongwith contractor bill

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS.491100.
 Rupees Four Lakhs Ninety One Thousand One Hundred and Paise Zero Only


 Executive Engineer,
 ✓ Haripur Division,
 HPPWD, Haripur

159
282
N

DRAFT SCHEDULE OF QUANTITY						
Name Of Work:- Improvement of black spot on NH-03 Shaloya to village Badwal km 0/0 to 1/800. (SH:- Construction of R/Wall at RD 0/870 to 0/882).			Estimated Cost:-Rs. 470687.00 Earnest Money:- Rs.9500.00 Time Limit:- One Month			
Sr. No.	Description of Items	Qty.	Rate in		Unit	Amount
			Fig.	Words		
1	Excavation work by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads and lifts ordinary rock and all kinds of soil including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidents. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	36.72	300.00	Rupees Three Hundred and Paise Zero Only	Per cubic metre	11016.00
2	Providing and laying in position cement concrete of specified grade 1:5:10 (one cement: five coarse sand: ten graded stone aggregate) 40mm (forty millimetre) nominal size graded stone aggregate in retaining wall, breast wall, walls of any thickness and like structures including the cost of centering and shuttering, including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidents. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	107.64	4200.00	Rupees Four Thousand Two Hundred and Paise Zero Only	Per cubic metre	452088.00
3	Providing weapholes in brick masonry / stone masonry / lean reinforced concrete abutment, wing wall, return wall with 110 mm (One hundred ten millimetre) dia PVC pipe of SupremeFinolex/Vectus extending through the full width of the structures with slope of 1 in 20 (H) towards drainage faces complete as per drawing and technical specification clauses B14, 709, 1204.3.7 complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidents. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	22.00	290.00	Rupees Two Hundred Ninety and Paise Zero Only	Per running metre	6380.00
4	Providing and fixing Geo-Textile membrane behind RCC and PCC retaining wall Ocean Non woven Geotextile 3mm (Three millimetre) thickness including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidents. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	7.29	165.00	Rupees One Hundred Sixty Five and Paise Zero Only	Per cubic metre	1203.00
Grand Total						470687.00

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS. 470687.-

Rupees Four Lakhs Seventy Thousand Six Hundred Eighty Seven and Paise Zero Only

Condition

- The work will be strictly executed as per MORD specifications
- The Contractor will procure cement at their own level from Civil Supply Depot, after the approval of permit from the competent authority and other material from market as per Department specification/ Notification issued by the Additional Chief Secretary PW to the Govt. of HP vide No. PWSW (B) C (17) 2012 dated 07 August 2016 & carriage will be born by the contractor
- The bills of all materials procured by the contractor and VWX form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill

Executive Engineer,
Hamirpur Division,
HPPWD, Hamirpur.

163/281 W

DRAFT SCHEDULE OF QUANTITY

Name Of Work:- Improvement of black spot on Mansoli Maloti Sasan to Rainthel km 0/0 to 1/520. (SH)- Construction of R/Wall at RD 0/245 to 0/253).						Estimated Cost:-Rs. 470687.00 Earnest Money:- Rs.6900.00 Time Limit:- One Month	
Sr. No.	Description of Items	Qty.	Rate in		Unit	Amount	
			Fig.	Words			
1	Excavation work by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads and lifts ordinary rock and all kinds of soil including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, mahana, toll tax, sale tax, GST or other taxes imposed by the Government.	26.65	300.00	Rupees Three Hundred and Paise Zero Only	Per cubic metre	7995.00	
2	Providing and laying in position cement concrete of specified grade 1:5:10 (one cement : five coarse sand : ten graded stone aggregate) 40mm (forty millimetre) nominal size graded stone aggregate in retaining wall, breast wall, walls of any thickness and like structures including the cost of centering and shuttering including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, mahana, toll tax, sale tax, GST or other taxes imposed by the Government.	78.01	4200.00	Rupees Four Thousand Two Hundred and Paise Zero Only	Per cubic metre	327642.00	
3	Providing weapholes in brick masonry / stone masonry (plan reinforced concrete abutment, wing wall, return wall with 110 mm (One hundred ten millimetre) dia PVC pipe of Supreme/Finolex/Vectus extending through the full width of the structures with slope of 1(V) 20(H) towards drawing face complete as per drawing and technical specification clauses 814, 708, 1204, 3.7 complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, mahana, toll tax, sale tax, GST or other taxes imposed by the Government.	20.00	290.00	Rupees Two Hundred Ninety and Paise Zero Only	Per running metre	5800.00	
4	Providing and fixing Geo-Textile membrane behind RCC and PCC retaining wall Ocean Non woven Geotextile 3mm (Three millimetre) thickness including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, mahana, toll tax, sale tax, GST or other taxes imposed by the Government.	4.05	165.00	Rupees One Hundred Sixty Five and Paise Zero Only	Per cubic metre	668.00	
Grand Total						342105.00	

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS. 342105/-
Rupees Three Lakhs Forty Two Thousand One Hundred Five and Paise Zero Only

Condition

- The work will be strictly executed as per MORD specifications
- The Contractor will procure cement at their own level from Civil Supply Depot, after the approval of permit from the competent authority and material from market as per Department specification/ Notification issued by the Additional Chief Secretary PW to the Govt. of HP vide No. PSW (B) C (17) 202012 dated 07 August 2018 & carriage will be born by the contractor
- The bills of all materials procured by the contractor and VMS form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill

Executive Engineer,
Hamirpur Division,
HPPWD, Hamirpur

143 N
280

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Improvement of Black spot on Dangri Tutroo road Km 0/0 to 2/500
(SH:- C/O retaining wall at RD 1/885 to 1/897)

Estimated Cost-Rs.471847.00

Earnest Money:- Rs.9500.00

Time Limit:- One Month

Sr. No.	Description of Items	Qty.	Rate in Fig.	Words	Unit	Amount
1	Excavation work by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, up to 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soil in ordinary rock and Pick work and Jumper work including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	36.72	300.00	Rupees Three Hundred and Paise Zero Only	Per cubic metre	11016.00
2	Providing and laying in position cement concrete of specified grade 1:5:10 (one cement : five coarse sand : ten graded stone aggregate) 40mm (forty millimetre) nominal size graded stone aggregate in retaining wall, breast wall, walls of any thickness and like structures excluding the cost of centering and shuttering including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	107.64	4200.00	Rupees Four Thousand Two Hundred and Paise Zero Only	Per cubic metre	452088.00
3	Providing and fixing Single socketed pipes 110mm (one hundred ten millimetre) dia of Supwin/Fenolax/Vectus make on wall face unplasticized Rigid PVC rain water pipes conforming to IS : 13582 Type A, including paring with seal ring conforming to IS : 5382 leaving 10 mm (ten millimetre) gap for thermal expansion complete upto all floor level including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	26.00	290.00	Rupees Two Hundred Ninety and Paise Zero Only	Per Running Metre	7540.00
4	Providing and fixing Geo-Textile membrane behind ROC and PCC retaining walls Ocean Non woven Geotextile 3mm (Three millimetre) thickness including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	7.29	165.00	Rupees One Hundred Sixty Five and Paise Zero Only	Per square metre	1203.00
Total						471847.00

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS.471847/-
Rupees Four Lakhs Seventy One Thousand Eight Hundred Forty Seven and Paise Zero Only

Executive Engineer,
Hampi Division,
HPPWD, Hampi

1 The work will be strictly executed as per HPPWD specifications
2 The contractor will procure cement at their own level from Civil Supply Deptt. After the approval of permit from the competent authority and other material from market as per Department specification issued by the Additional Chief Secretary PW to the Govt. of H.P. vide No. PSW (B) C (17)/2012 dated 07 August 2018 and all other condition are table & carriage will be born by the contractor.

3 The bills of all materials procured by the contractor M-form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill.

138-4
247

DRAFT SCHEDULE OF QUANTITY

Name Of Work:- Improvement of black spot on link road Lahar to Rattian km 0/0 to 2/200. (SH:- C/o R/wall at RD 1/0 to 1/012).						
Estimated Cost:-Rs. 471267.00						
Earnest Money:- Rs.9500.00						
Time Limit:- One Month						
Sr. No.	Description of Items	Qty.	Fig.	Rate in		Amount
				Words	Unit	
1	Excavation work by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms within all leads including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads and lifts ordinary rock and all kinds of soil including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	36.72	300.00	Rupees Three Hundred and Paise Zero Only	Per cubic metre	11016.00
2	Providing and laying in position cement concrete of specified grade 1:5:10 (one cement: five coarse sand: ten graded stone aggregate) 40mm (forty millimetre) nominal size graded stone aggregate in retaining wall, breast wall, walls of any thickness and like structures excluding the cost of centering and shuttering, including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	107.64	4200.00	Rupees Four Thousand Two Hundred and Paise Zero Only	Per cubic metre	452088.00
3	Providing weep holes in brick masonry / Stone masonry / plain/reinforced concrete in retaining walls, breast walls and the like with 110mm (One hundred ten millimetre) dia PVC pipe Finolex/ Supreme having pressure not less than 4.00 Kg/Cm ² (four kilogramme) per centimetre square extending through the full width of the structure with slope of 1(V) 20(H) (one vertical: twenty horizontal) towards drawing face complete including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	24.00	290.00	Rupees Two Hundred Ninety and Paise Zero Only	Per Running metre	6960.00
4	Providing and fixing Geo-Textile membrane behind RCC and PCC retaining walls Ocean Non woven Geotextile 3mm (Three millimetre) thickness including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	7.29	165.00	Rupees One Hundred Sixty Five and Paise Zero Only	Per square metre	1203.00
	Total					471267.00

Condition

- The work will be strictly executed as per HPPWD specifications.
- The contractor will procure cement at their own level from Civil Supply Depot. After the approval of permit from the competent authority and other material from market as per Department specification issued by the Addition Chief Secretary PW to the Govt. of HP vide No. PSW (B) C (17) 2/2012 dated 07 August 2018 and all other condition are liable & carriage will be born by the contractor.
- The bills of all materials procured by the contractor M-form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill.

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS. 471267/-
Rupees Four Lakhs Seventy One Thousand Two Hundred Sixty Seven and Paise Zero Only


Executive Engineer,
Hamirpur Division,
HPPWD, Hamirpur.

139
249
N

DRAFT SCHEDULE OF QUANTITY

Name Of Work:- Improvement of black spot on NH Har Sukrala road km 0/0 to 7/165). (SH:- C/o R/wall at RD 0/095 to 0/167).				Estimated Cost:- Rs. 471557.00 Earnest Money:- Rs. 9500.00 Time Limit:- One Month	
Sl. No.	Description of Items	Qty.	Fig.	Rate in	
				Words	Unit
1	Excavation work by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms within all leads including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads and lifts ordinary rock and all kinds of soil including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government	36.72	300.00	Rupees Three Hundred and Paise Zero Only	Per cubic metre
2	Providing and laying in position cement concrete of specified grade 1:5:10 (one cement : five coarse sand : ten graded stone aggregate) 40mm (forty millimetre) nominal size graded stone aggregate in retaining wall, breast wall, walls of any thickness and like structures excluding the cost of centering and shuttering including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government	107.84	4200.00	Rupees Four Thousand Two Hundred and Paise Zero Only	Per cubic metre
3	Providing weep holes in brick masonry / Stone masonry / plain/reinforced concrete in retaining walls, breast walls and the like with 110mm (One hundred ten millimetre) dia PVC pipe Finolex/ Supreme having pressure not less than 4.00 Kg/Cm ² (four kilogramme) per centimetre square extending through the full width of the structure with slope of 1(V) 20(H) (one vertical : twenty horizontal) towards drawing face complete including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government	25.00	290.00	Rupees Two Hundred Ninety and Paise Zero Only	Per Running metre
4	Providing and fixing Geo-Textile membrane behind RCC and PCC retaining walls Ocean Non woven Geotextile 3mm (Three millimetre) thickness including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government	7.29	165.00	Rupees One Hundred Sixty Five and Paise Zero Only	Per square metre
Total					
					471557.00

Condition

- The work will be strictly executed as per HPPWD specifications
- The contractor will procure cement at their own level from Civil Supply Depot. After the approval of permit from the competent authority and other material from market as per Department specification issued by the Additional Chief Secretary PW to the Govt. of HP vide No. P&W (B) C (17) 2/2012 dated 07 August 2018 and all other condition are liable & carriage will be born by the contractor
- The bills of all materials procured by the contractor M-form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS. 471557/-
Rupees Four Lakhs Seventy One Thousand Five Hundred
Fifty Seven and Paise Zero Only

Executive Engineer,
Planning Division,
HPPWD, Haridwar

276
137

DRAFT SCHEDULE OF QUANTITY

Name Of Work:- Restoration of rain damages on link road Pattia to Jalari km 0/0 to 4/650. (SH:- Construction of U-Shape drain at RD 1/375 to 1/508 & V-Shape drain at RD 1/030 to 1/060 and 1/180 to 1/375).					Estimated Cost:-Rs. 498194.00		
					Earnest Money:- Rs.10000.00		
					Time Limit:- One Month		
Sr. No.	Description of Items	Qty.	Fig.	Words	Unit	Amount	
1	Earth work in excavation by mechanical means (Hydraulic excavator/breaker)/manual means over areas (exceeding 30 cm (Thirty centimetres) in depth, 1.5 m (One point five metre) in width as well as 10 sqm(Ten square metre) on plan) including getting out and disposal of excavated earth in all leads and lifts in ordinary rock and all kinds of soil including chiseling of hard rocks where blasting is prohibited including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	123.58	300.00	Rupees Three Hundred and Paise Zero Only	Per cubic metre	37074.00	
2	Providing and laying cement concrete 1:3:6 (One cement, three coarse sand, six graded stone aggregate) 20 mm (Twenty millimetre) nominal size in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or facing courses, parapets, coping, bed blocks, anchor blocks, plan window sills, fillets, sunken floor etc etc etc including the cost of centering, shuttering and finishing as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	83.84	5500.00	Rupees Five Thousand Five Hundred and Paise Zero Only	Per cubic metre	461120.00	
		Total				498194.00	

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS. 498194.-
Rupees Four Lakhs Ninety Eight Thousand One Hundred
Ninety Four and Paise Zero Only

Executive Engineer,
Hamirpur Division,
HPPWD, Hamirpur

Condition

- The work will be strictly executed as per HPPWD specifications
- The contractor will procure cement at their own level from Civil Supply Depot. After the approval of permit from the competent authority and other material from market as per Department specification issued by the Addition Chief Secretary PW to the Govt. of HP vide No. PSW (B) C (17) 2/2012 dated 07 August 2018 and all other condition are liable & carriage will be born by the contractor
- The bills of all materials procured by the contractor M-form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill

142 N
202

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on link road Patta to Jalari Km 0/0 to 4/650
(SH:- C/O U-shape drain at RD 4/239 to 4/375 & V-shape drain at RD 3/855 to 4/063)

Estimated Cost:- Rs.499475.00
Earnest Money:- Rs.10000.00
Time Limit:- One Month

Sr. No.	Description of Items	Qty.	Rate in Fig.	Words		Unit	Amount
1	Excavation work by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soil in ordinary rock and Pick work and jammer work including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	124.55	300.00	Rupees Three Hundred and Paise Zero Only		Per cubic metre	37365.00
2	Providing and laying in position cement concrete 1:3:6 (One Cement : three coarse sand : six graded stone aggregate 20 mm (Twenty millimetre) nominal size of specified grade including the cost of centering and shuttering - All work up to plinth level including entire carriage of material with in all leads and lifts and as per drawings and technical specifications and the direction of Engineer-in-Charge including other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	84.02	5500.00	Rupees Five Thousand Five Hundred and Paise Zero Only		Per Cubic metre	462110.00
Total							499475.00

Condition

1 The work will be strictly executed as per HPPWD specifications

2 The contractor will procure cement at their own level from Civil Supply Depot. After the approval of permit from the competent authority and other material from market as per Department specification issued by the Additional Chief Secretary PW to the Govt. of MP vide No. PBW (B) C (17) 2/2012 dated 07 August 2018 and all other condition are liable & carriage will be born by the contractor.

3 The bills of all materials procured by the contractor M-form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill.

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS.499475/-
Rupees Four Lakhs Ninety Nine Thousand Four Hundred Seventy Five and Paise Zero Only


 Executive Engineer,
 Haripur Division,
 HPPWD, Haripur

140
875

DRAFT SCHEDULE OF QUANTITY

Name Of Work:- Restoration of rain damages on link road Patta to Jalari km 0/0 to 4/650. (SH:- Construction of U-Shape drain at RD 1/508 to 1/541 & V-Shape drain at RD 1/641 to 1/868).							Estimated Cost:-Rs. 499012.00		Earnest Money:- Rs.10000.00		Time Limit:- One Month	
Sr. No.	Description of Items	Qty.	Fig.	Rate in		Unit	Amount					
				Words	Words							
1	Earth work in excavation by mechanical means (Hydraulic excavator/breaker)/manual means over areas (exceeding 30 cm (Thirty centimetres) in depth, 1.5 m (One point five metre) in width as well as 10 sqm(Ten square metre) on plan) including getting out and disposal of excavated earth in all leads and lifts in ordinary rock and all kinds of soil including chiseling of hard rocks where blasting is prohibited including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	123.74	300.00	Rupees Three Hundred and	Paise Zero Only	Per cubic metre	37122.00					
2	Providing and laying cement concrete 1:3:6 (One cement : three coarse sand : six graded stone aggregate) 20 mm (Twenty millimetre) nominal size in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etcetera including the cost of centering, shuttering and finishing as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	83.98	5500.00	Rupees Five Thousand Five Hundred and	Paise Zero Only	Per cubic metre	461890.00					
Total							499012.00					

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS. 499012/-
Rupees Four Lakhs Ninety Nine Thousand Twelve and Paise Zero Only

Executive Engineer,
Hamirpur Division,
HPPWD, Hamirpur.

Condition

- 1 The work will be strictly executed as per HPPWD specifications
- 2 The contractor will procure cement at their own level from Civil Supply Depot. After the approval of permit from the competent authority and other material from market as per Department specification issued by the Additional Chief Secretary P.W. to the Govt. of HP vide No. PBW (B) C (17) 2/2012 dated 07 August 2018 and all other condition are liable & carriage will be born by the contractor.
- 3 The bills of all materials procured by the contractor M-form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill.

DRAFT SCHEDULE OF QUANTITY

Name Of Work:- Restoration of rain damages on link road Patta to Jalari km 0.0 to 4/650 (SH:- C/O U-shape drain at RD 2/240 to 2/298 & V-shape drain at RD 2/298 to 2/533).

Estimated Cost:-Rs. 499688.00
Earnest Money:- Rs.10000.00
Time Limit:- One Month

Sr. No.	Description of Items	Qty.	Fig.	Rate in Words	Unit	Amount
1	Excavation work by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms within all leads including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads and lifts ordinary rock and all kinds of soil including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	123.61	300.00	Rupees Three Hundred and Paise Zero Only	Per cubic metre	37083.00
2	Providing and laying cement concrete 1:3:6 (One cement, three coarse sand, six graded stone aggregate) 20 mm (Twenty millimetre) nominal size in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or facing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc. etc. etc. including the cost of centering, shuttering and finishing as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	84.11	5500.00	Rupees Five Thousand Five Hundred and Paise Zero Only	Per cubic metre	462605.00
Grand Total						499688.00

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS. 499688-
Rupees Four Lakhs Ninety Nine Thousand Six Hundred Eighty Eight and Paise Zero Only

Condition

- The work will be strictly executed as per MORD specifications.
- The Contractor will procure cement at their own level from Civil Supply Depot. after the approval of permit from the competent authority and other material from market as per Department specification/ Notification issued by the Additional Chief Secretary PW to the Govt. of HP vide No. PBW (B) C (17) 2/2012 dated 07 August 2018 & carriage will be born by the contractor.
- The bills of all materials procured by the contractor and WIX form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill

Executive Engineer,
Hamirpur Division,
HPPWD, Hamirpur.

157/293

DRAFT SCHEDULE OF QUANTITY

Name Of Work:- Restoration of rain damages on link road Patta to Jalari km 0/0 to 4/650 (SH:- C/O U-shape drain at RD 1/900 to 2/035 & V-shape drain at RD 2/035 to 2/240).

Estimated Cost:-Rs. 499210.00
Earnest Money:- Rs.10000.00
Time Limit:- One Month

Sr. No.	Description of Items	Qty.	Fig.	Rate in		Unit	Amount
				Words			
1	Excavation work by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms within all leads including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads and lifts ordinary rock and all kinds of soil including entire carriage of materials in all leads and lifts as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	122.75	300.00	Rupees Three Hundred and Paise Zero Only		Per cubic metre	36825.00
2	Providing and laying cement concrete 1:3:6 (One cement three coarse sand six graded stone aggregate) 20 mm (Twenty millimetre) nominal size in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or facing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, filets, surken floor etcetera including the cost of centering, shuttering and finishing as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	84.07	5500.00	Rupees Five Thousand Five Hundred and Paise Zero Only		Per cubic metre	462385.00
Grand Total							499210.00

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS 499210/-
Rupees Four Lakhs Ninety Nine Thousand Two Hundred Ten and Paise Zero Only

Condition

- The work will be strictly executed as per MORD specifications
- The Contractor will procure cement at their own level from Civil Supply Depot, after the approval of permit from the competent authority and other material from market as per Department specification/ Notification issued by the Additional Chief Secretary PW to the Govt. of HP vide No. PBW (B) C (17) 2/2012 dated 07 August 2018 & carriage will be born by the contractor.
- The bills of all materials procured by the contractor and W/X form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill


 Executive Engineer,
 Hamirpur Division,
 HPPWD, Hamirpur.

16/30)N

DRAFT SCHEDULE OF QUANTITY

Work:- A/R & M/O Various road under Nadaun Sub-Division (SH:- Bush cutting , Maintenance of earthen road on various road in Rangas Section)

Estimated Cost:-Rs. 249209.00

Earnest Money:- Rs. 5000.00

Time Limit:- One Month

Description of Items	Qty.	Rate in		Unit	Amount
		Fig.	Words		
Clearing of Jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30cm (thirty centimetres) measured at a height of 1mtr (one metres) above ground and removal of rubbish upto a distance of all leads and lifts out side the periphery of the area cleared including entire carriage of material with in all leads and lifts and as per drawings and technical specifications and the direction of Engineer-in-Charge including other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	6095.00	9.76	Rupees Nine and Paise Seventy Six Only	Per square metre	59487.00
making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC complete including entire carriage of material within all leads, lifts, drawings, technical specifications as per direction by Engineer-in-Charge including other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3745	50.66	Rupees Fifty and Paise Sixty Six Only	Per Running Metre	189722.00
total					249209.00

condition

The work will be strictly executed as per HPPWD specifications

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS. 249209.00 only

Rupees Two Lakhs Forty Nine Thousand Two Hundred Nine and Paise Zero Only


Executive Engineer,
Hamirpur Division,
HPPWD, Hamirpur

162-3027 N

510

DRAFT SCHEDULE OF QUANTITY						
Name Of Work:- A/R & M/O Various road under Nadaun Sub-Division (SH:- Bush cutting , Maintenance of earthen shoulder on various road in Bara Section)				Estimated Cost:-Rs. 249148.00		
				Earnest Money:- Rs. 5000.00		
				Time Limit:- One Month		
Sr. No.	Description of Items	Qty.	Fig.	Rate in		Amount
				Words	Unit	
1	Clearing of Jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30cm (thirty centimetres) measured at a height of 1mtr (one metres) above ground and removal of rubbish upto a distance of all leads and lifts out side the periphery of the area cleared including entire carriage of material with in all leads and lifts and as per drawings and technical specifications and the direction of Engineer-in-Charge including other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax GST or other taxes imposed by the Government.	5716.67	9.76	Rupees Nine and Paise Seventy Six Only	Per square metre	55795.00
2	Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC complete including entire carriage of material within all leads, lifts, drawings, technical specifications as per direction by Engineer-in-Charge including other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3815.67	50.66	Rupees Fifty and Paise Sixty Six Only	Per Running Metre	193353.00
Total						249148.00

Condition
The work will be strictly executed as per HPPWD specifications

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS. 249148/-only
Rupees Two Lakhs Forty Nine Thousand One Hundred Forty Eight and Paise Zero Only

Executed Engineer,
Manipur Division,
HPPWD, Manipal

DRAFT SCHEDULE OF QUANTITY

Name Of Work:-Repair and maintenance of Janij Ghar to Village Jangal in GP Putnal Tehsil Nadaun Distt. Hamirpur
(Providing and laying Steel truss roofing etc.)

Estimated Cost:-Rs. 313182.00
Earnest Money:- Rs.6300.00

Time Limit:- One Month

Sr. No.	Description of items	Qty.	Fig.	Rate in		Unit	Amount
				Words	Zero Only		
1	Providing and fixing 110mm (one hundred ten millimetre) dia G.I pipe complete with G.I fitting including trenching and refilling including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	42.00	1100.00	Rupees One Thousand One Hundred and Paise Zero Only		Per Running metre	46200.00
2	Steel work welded in built up sections (TATA/JINDAL/SAIL/ JAI BHARAT Make), trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint upto all floor level in all heights in grating frames, framed guard bars, ladders, railings, brackets and similar works including entire carriage of material with in all leads, lifts, drawings, technical specifications as per the direction of Engineer-in-Charge and other incidentals The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1468.54	115.00	Rupees One Hundred Fifteen and Paise Zero Only		Per Kilogram	168882.00
3	Providing and fixing pre-coated galvanized iron profile sheets (TATA/SAIL/JSW make) (size, shape and pitch of corrugation as approved by Engineer-in-Charge) 0.50 mm (zero point five zero millimetre) + 0.05 % (zero point zero five percentage) total coated thickness with zinc coating 120 (one hundred twenty) grams per square metre as per IS. 277, in 240 (two hundred forty) mpa steel grade, 5-7 (five to seven) microns epoxy primer on both side of the sheet and polyester top coat 15-18 (fifteen to eighteen) microns. Sheet should have protective guard film of 25 (twenty five) microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 (twelve) metre or as desired by Engineer-in-Charge. The sheet shall be fixed using self drilling self tapping screws of size 5 x 35 mm (five point into fifty five millimetre) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of puling, rafters and trusses and including cutting to size and shape wherever required including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	70.00	1350.00	Rupees One Thousand Three Hundred Fifty and Paise Zero Only		Per square metre	94500.00
4	Providing and fixing Ridges or hips Plain 500 x 600mm (five hundred to six hundred millimetre) Pre-coated Galvanized steel sheet roofing accessories of TATA/SAIL/JSW Make 0.60 mm (zero point six zero millimetre) + 0.05 % (Plus zero point zero five percent) total coated thickness, Zinc coating 120 (one hundred twenty) grams per square metre as per IS. 277, in 240 (two hundred forty) mpa steel grade, 5-7 (five to seven) microns epoxy primer on both side of the sheet and polyester top coat 15-18 (fifteen to eighteen) microns using self drilling self tapping screws complete upto all floor level including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	14.40	250.00	Rupees Two Hundred Fifty and Paise Zero Only		Per Square metre	3600.00
Total							313182.00

Condition

- The work will be strictly executed as per HPPWD specifications.
- The contractor will procure cement at their own level from Civil Supply Depot. After the approval of permit from the competent authority and other material from market as per Department specification issued by the Additional Chief Secretary P.W. to the Govt. of H.P vide No. PWS (B) C (17) 2/2012 dated 07 August 2018 and all other condition are liable & carriage will be born by the contractor.
- The bills of all materials procured by the contractor M-form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill.

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS.313182/- only
Rupees Three Lakhs Thirteen Thousand One Hundred Eighty Two and Paise Zero Only

Executive Engineer,
Hamirpur Division
HPPWD, Hamirpur

106-N


DRAFT SCHEDULE OF QUANTITY

Sr. No.		Description of Items	Qty.	Rate in		Unit	Amount
				Fig.	Words		
1		Excavation work by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms within all leads including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads and lifts ordinary rock and all kinds of soil including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	63.00	300.00	Rupees Three Hundred and Paise Zero Only	Per cubic metre	18900.00
2		Providing and laying cement concrete 1:3:6 (One cement : three coarse sand : six graded stone aggregate) 20 mm (Twenty millimetre) nominal size in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etcetera including the cost of centering, shuttering and finishing as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	27.83	5200.00	Rupees Five Thousand Two Hundred and Paise Zero Only	Per cubic metre	144715.00
3		Construction of Roller Compacted Concrete Pavement (RCCP) of M-25 (M-Twenty Five) grade design mix with coarse and fine aggregate conforming to IS 383, the size of coarse aggregate not exceeding 20mm (Twenty millimetre) with minimum cement content not less than 390kg per cum (Three hundred ninety kilogram per cubic metre), aggregate gradation to be as per table 602.2 after blending, mixing the concrete mixer at optimum moisture content, transporting to site, laying with wheel barrows or steel pan or with mechanical paver, compacting with 80-100 KN smooth wheel tandem vibratory roller to achieve the designed flexural strength, finishing and curing including entire carriage of materials within all leads and lifts as per the direction of Engineer-in-Charge and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	42.00	7200.00	Rupees Seven Thousand Two Hundred and Paise Zero Only	Per cubic metre	302400.00
		Grand Total					466016.00

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS 466016/-only
Rupees Four Lakhs Sixty Six Thousand Sixteen and Paise Zero Only

Condition

- The work will be strictly executed as per MORD specifications
- The Contractor will procure cement at their own level from Civil Supply Depot, after the approval of permit from the competent authority and other material from market as per Department specification/ Notification issued by the Additional Chief Secretary PW to the Govt. of HP vide No. PBW (B) C (17) 2/2012 dated 07 August 2018 & carriage will be born by the contractor.
- The bills of all materials procured by the contractor and W/X form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill.


Executive Engineer,
Hamirpur Division,
HPPWD, Hamirpur.

164 N
203

α No 5

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Bhupal Sadwan road Km 0/0 to 4/975 (SH: Dismantling of existing interlocking tiles & providing and laying cement concrete & 80mm thick interlocking paver block at RD 4/390 to 4/470)

Estimated Cost -Rs. 285452.00

Earnest Money:- Rs. 5800.00

Time Limit:- One Month

Sr. No.	Description of Items	Qty.	Fig.	Rate in		Unit	Amount
				Words			
1	Dismantling the work in floors and roofs laid in cement mortar including stacking material within all lead for thickness of tiles 25 mm to 40 mm (Twenty five millimetre to forty millimetre) including entire carriage of material with in all leads, lifts, drawings, technical specifications as per direction by Engineer-in-Charge including other incidentals The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	150.00	80.00	Rupees Eighty and Paise Zero Only		Per square metre	12000.00
2	Preparation and consolidation of sub grade with power road roller of 8 to 12 (Eight to twelve) tonne capacity after excavating earth to an average of 22.5 cm (Twenty two point five centimetre) depth, dressing to camber and consolidating with road roller including making good the undulations etcetra and re-rolling the sub grade and disposal of surplus earth with upto all leads including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	240.00	120.00	Rupees One Hundred Twenty and Paise Zero Only		Per square metre	28800.00
3	Construction of granular sub base by providing well graded material spreading in uniform layers with tractor mount grader on prepared surface mixing by mix in place method with rotavator at OMC and compacting with smooth wheel roller to achieve the desired density complete Grading-II material (Plan mix) as per technical specification clause 301.5 as per the direction of Engineer-in-Charge including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax or other taxes imposed by the Government	36.00	1800.00	Rupees One Thousand Eight Hundred and Paise Zero Only		Per cubic metre	64800.00
4	Providing and laying in position cement concrete of 1:2:4 (One cement : Two coarse sand) : four graded stone aggregate 20 mm (Twenty millimetre) nominal size for All work up to plinth level excluding the cost of centering and shuttering, including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	4.07	6600.00	Rupees Six Thousand Six Hundred and Paise Zero Only		Per cubic metre	26862.00
5	Providing and laying factory made 80mm (Eighty millimetre) thick cement concrete paver block of M-40 (M-forty) grade with approved colour, design and pattern (MTC make & ISI marked or its equivalent) chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etcetra of required strength, thickness and size/ shape, made by table vibratory method using PU mould, laid in required colour and pattern over 50mm thick (fifty millimetre) compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand complete all as per direction of Engineer-in-Charge including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	90.00	1400.00	Rupees One Thousand Four Hundred and Paise Zero Only		Per square metre	126000.00

164/2024

B	Laying of old 80mm (Eighty millimetre) paver block complete all as per direction of Engineer-in-Charge including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	150.00	180.00	Rupees One Hundred Eighty and Paise Zero Only	Per square metre	27000.00
	Total					285462.00

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS.285462/-
Rupees Two Lakhs Eighty Five Thousand Four Hundred Sixty Two and Paise Zero Only

Condition
1 The work will be strictly executed as per HPPWD specifications

2 The contractor will procure cement of their own level from Civil Supply Depot. After the approval of permit from the competent authority and other material from market as per Department specification issued by the Addition Chief Secretary PW to the Govt. of HP vide No. PBW (B) C (17) 2/2012 dated 07 August 2018 and all other condition are liable & carriage will be born by the contractor.

3 The bills of all materials procured by the contractor in form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill

Executive Engineer
Mamrupur District
HPPWD, Hamirpur

DRAFT SCHEDULE OF QUANTITY

Name Of Work:- C/o Combined office building (Mini Secretariat) at Nadaun in Distt. Hamirpur (HP). (SH:- C/o balance work of half and full brick work, wall panelling and wooden ceiling work, polishing ceiling work in MLA Office etc.).

Estimated Cost:-Rs. 442136.00
Earnest Money:- Rs. 9000.00
Time Limit:- One Month

Sr. No.	Description of Items	Qty.	Fig.	Rate in		Unit	Amount
				Words			
1	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (seven point five) in super structure above plinth level up to all floor levels in all shapes and sizes with Cement mortar 1:6 (one cement : six coarse sand) including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	0.52	8505.60	Rupees Eight Thousand Five Hundred Five and Paise Sixty Only		Per cubic metre	5273.00
2	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (seven point five) in super structure above plinth level up to all floor level in cement mortar 1:4 (one cement : four coarse sand) including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	16.53	1103.80	Rupees One Thousand One Hundred Three and Paise Eighty Only		Per square metre	18246.00
3	15 mm (fifteen millimetre) cement plaster on rough/fair side of single or half brick wall of max 1:6 (one cement : six coarse sand) upto all floor level including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	38.96	268.50	Rupees Two Hundred Sixty Eight and Paise Fifty Only		Per square metre	10451.00
4	Steel work welded in built up sections (TATA/ SAIL/ Apollo/ JSW Make) in framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etcetra as required in grillings, door and window frames, guard bar, ladder, railings, brackets, gates and similar works complete upto all floor level including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	114.66	122.60	Rupees One Hundred Twenty Two and Paise Sixty Only		Per Kilogram	14057.00
5	Providing wood work in frames of false ceiling, partitions etc. sawn and fixed position upto all floor level Kail wood including entire carriage of material with in all leads, lifts, drawings, technical specifications as per direction by Engineer-in-Charge including other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	0.50	80118.50	Rupees Eighty Thousand One Hundred Eighteen and Paise Fifty Only		Per cubic metre	40059.00
6	Providing and fixing 8mm (Eight millimetre) thick commercial ply conforming to IS : 1326 BWR type of Action Tessa/Black Cobra/Green Ply/Kur Ply/Century Ply/Minerino ply make plain lining with necessary screws/nuts and bolts/ nails, including a coat of approved primer on one face, and fixed on wooden /steel frame work, complete (Frame work shall be paid for separately) including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	56.22	1445.50	Rupees One Thousand Four Hundred Forty Five and Paise Fifty Only		Per square metre	81266.00

7	Providing and fixing PVC flexible foam sheet 2mm (two millimetre) thick on existing door shutters (bathroom and WC door), behind wall lining, under wooden flooring complete including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	139.00	703.60	Rupees Seven Hundred Three and Paise Sixty Only	Per square metre	97800.00
8	Providing and fixing in wall lining 6mm (six millimetre) thick HDHMR (high density high moisture resistant board) of (Action Tesa/Century ply/Kit ply/Green ply or its equivalent) both side plain without lamination, with necessary fixing arrangement and screws etc. complete including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	86.14	969.00	Rupees Nine Hundred Sixty Nine and Paise Zero Only	Per square metre	83470.00
9	Providing and fixing pine wood 12mm (Twelve millimetre) thick, wooden plank ceiling with tongued and grooved jointing and wood screws (frame work and cover filets to be measured and paid for separately) etc. complete including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	56.22	1223.40	Rupees One Thousand Two Hundred Twenty Three and Paise Forty Only	Per square metre	68780.00
10	Polishing wood work with French spirit polishing. Two or more coats on new works including a coat of wood filler complete including entire carriage of material in all leads and lifts as per direction of Engineer-in-Charge including other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	56.22	404.20	Rupees Four Hundred Four and Paise Twenty Only	Per Running metre	22724.00
Condition		Total				442136.00

1 The work will be strictly executed as per HPPWD specifications

2 The contractor will procure cement at their own level from Civil Supply Depot. After the approval of permit from the competent authority and other material from market as per Department specification issued by the Additional Chief Secretary PW to the Govt. of HP vide No. PBW (B) C (17) 2/2012 dated 07 August 2018 and all other condition are liable & carriage will be born by the contractor.

3 The bills of all materials procured by the contractor M-form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill.

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS. 442136/-
Rupees Four Lakhs Forty Two Thousand One Hundred Thirty Six and Paise Zero Only


Executive Engineer,
Hamirpur Division,
HPPWD, Hamirpur

DRAFT SCHEDULE OF QUANTITY

DRAFT SCHEDULE OF QUANTITIES						Estimated Cost:-Rs. 447956.00
Name Of Work:- C/o Combined office building (Mini Secretariat) at Nadaun in Distt. Hamirpur (HP). (SH:- C/o balance work of half and full brick work, wall panelling and wooden ceiling work, polishing, ceiling work in SDM Office etc.).						Earnest Money:- Rs. 9000.00
						Time Limit:- One Month
Sr. No.	Description of Items	Qty.	Fig.	Rate in	Unit	Amount
				Words		
1	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (seven point five) in super structure above plinth level up to all floor levels in all shapes and sizes with Cement mortar 1:6 (one cement, six coarse sand) including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	0.4	8505.60	Rupees Eight Thousand Five Hundred Fifty and Paise Sixty Only	Per cubic metre	3402.00
2	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (seven point five) in super structure above plinth level up to all floor level in cement mortar 1:4 (one cement, four coarse sand) including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.92	1103.80	Rupees One Thousand One Hundred Three and Paise Eighty Only	Per square metre	3223.00
3	15 mm (fifteen millimetre) cement plaster on rough/fair side of single or half brick wall of mix 1:6 (one cement, six coarse sand) upto all floor level including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	15.11	268.50	Rupees Two Hundred Sixty Eight and Paise Fifty Only	Per square metre	4057.00
4	Steel work welded in built up sections (TATAJ SAIL/ Apollo/ JSW Make) in framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc/extra as required in gratings, door and window frames, guard bar, ladder, railings, brackets, gates and similar works complete upto all floor level including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	138.55	122.60	Rupees One Hundred Twenty Two and Paise Sixty Only	Per Kilogram	16886.00
5	Providing wood work in frames of false ceiling, partitions etc. sawn and fixed position upto all floor level Kail wood including entire carriage of material with in all leads, lifts, drawings, technical specifications as per direction by Engineer-in-Charge including other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	0.73	80118.50	Rupees Eighty Thousand One Hundred Eighteen and Paise Fifty Only	Per cubic metre	58487.00
6	Providing and fixing 8mm (Eight millimetre) thick commercial ply conforming to IS : 1328 BWR type of Action Tessa/Black Cobra/Green Ply/Kit Ply/Century Ply/Merino ply make plain lining with necessary screws/nuts and bolts/ nails, including a coat of approved primer on one face, and fixed on wooden /steel frame work, complete (Frame work shall be paid for separately) including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	58.12	1445.50	Rupees One Thousand Four Hundred Forty Five and Paise Fifty Only	Per square metre	84012.00

7	Providing and fixing PVC flexible foam sheet 2mm (two millimetre) thick on existing door shutters (bathroom and WC door), behind wall lining, under wooden flooring complete including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	135.99	703.60	Rupees Seven Hundred Three and Paise Sixty Only	Per square metre	95683.00
8	Providing and fixing in wall lining 6mm (six millimetre) thick HDHMR (high density high moisture resistant board) of (Action Tesa/Century ply/Kit ply/Green ply or its equivalent) both side plain without lamination, with necessary fixing arrangement and screws etc. complete including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	90.31	989.00	Rupees Nine Hundred Sixty Nine and Paise Zero Only	Per square metre	87510.00
9	Providing and fixing pine wood 12mm (Twelve millimetre) thick, wooden plank ceiling with tongued and grooved jointing and wood screws (frame work and cover fillets to be measured and paid for separately) etc. complete including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	58.12	1223.40	Rupees One Thousand Two Hundred Twenty Three and Paise Forty Only	Per square metre	71104.00
10	Polishing wood work with French spirit polishing. Two or more coats on new works including a coat of wood filler complete including entire carriage of material in all leads and lifts as per direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	58.12	404.20	Rupees Four Hundred Four and Paise Twenty Only	Per Running metre	23492.00
Total						447956.00

Condition

- The work will be strictly executed as per HPPWD specifications
- The contractor will procure cement at their own level from Civil Supply Depot. After the approval of permit from the competent authority and other material from market as per Department specification issued by the Additional Chief Secretary PW to the Govt. of HP vide No. PWD (B) C (17) 2/2012 dated 07 August 2018 and all other condition are liable & carriage will be born by the contractor.
- The bills of all materials procured by the contractor M-form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill.

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS. 443956/-
Rupees Four Lakhs Forty Seven Thousand Nine Hundred
Fifty Six and Paise Zero Only


Executive Engineer,
Hamirpur Division,
HPPWD, Hamirpur

DRAFT SCHEDULE OF QUANTITY

Estimated Cost-Rs. 252180.00
Earnest Money:- Rs. 5100.00
Time Limit:- One Month

Name Of Work:- Restoration of rain damages Hamirpur Jahu road km 2/690 to 910. (SH:- Construction of Breast wall between km

7/047 to 7/067).

Sr. No.	Description of Items	Rate in		Qty	Unit	Amount
		Fig	Words			
1	Excavation work by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms within all leads including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads and lifts ordinary rock and all kinds of soil including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	46.20	Rupees Three Hundred and Paise Zero Only	46.20	Per cubic metre	13860.00
2	Providing and laying in position cement concrete of specified grade 1:5:10 (one cement, five coarse sand, ten graded stone aggregate) 40mm (forty millimetre) nominal size graded stone aggregate in retaining wall, breast wall, walls of any thickness and like structures including the cost of centering and shuttering including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	55.50	Rupees Four Thousand Two Hundred and Paise Zero Only	55.50	Per cubic metre	233100.00
3	Providing weep holes in brick masonry / Stone masonry / plain/reinforced concrete in retaining walls, breast walls and the like with 110mm (One hundred ten millimetre) dia PVC pipe Finolex/ Supreme having pressure not less than 4.00 Kg/Cm ² (four kilogramme) per centimetre square extending through the full width of the structure with slope of 1(V):20(H) (one vertical, twenty horizontal) towards drawing face complete including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	18.00	Rupees Two Hundred Ninety and Paise Zero Only	18.00	Each	5220.00
Grand Total						252180.00

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS. 252180 only
Rupees Two Lakhs Fifty Two Thousand One Hundred Eighty and Paise Zero Only

Condition

- The work will be strictly executed as per MORD specifications
- The Contractor will procure cement at their own level from Civil Supply Depot, after the approval of permit from the competent authority and other material from market as per Department specifications/ Notification issued by the Additional Chief Secretary PW to the Govt. of HP vide No. PBW (B) C (17) 2/2012 dated 07 August 2018 & carriage will be born by the contractor.
- The bills of all materials procured by the contractor and WX form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill.


 Executive Engineer
 Hamirpur Division
 Approved _____

140 Hml

DRAFT SCHEDULE OF QUANTITY

Name Of Work:- Detailed Project Report for Link road Dhanded to Talasi from Km 0/0 to 5/570 2. C/O link road from Gafot to Har via Gugga mandir from KM 0/0 to 3/0 i/c 1 Nos bridge under NABARD (H.P) (SH:- Preparation of Detailed Project Report). 3. C/O bridge over Dug Khad at RD 1765 on link road Bari to Harizen bast Dalg Km 0/0 to 2/0 (SH:- Preparation of Hydraulic data report and drawing complete including consultancy service for topographical survey.)		Estimated Cost:-Rs. 381695.00				Earnest Money:- Rs. 7700.00		Time Limit:- One Month	
		Qty.	Fig.	Rate in Words		Unit	Amount		
Sr. No.	Description of items								
1	Preparation of Detailed Project Report of road as per scope of work mentioned below:- (a) Topography survey by digital total station with two second accuracy, showing all features like tree, culverts, bridges, electric poles, telephone pole, hand pumps, school, habitations village etcetera. (b) Preparation of geometric plan of the road to the NABARD specifications showing all the provisions to be made in the DPR commensurate to the site conditions. (c) Preparation of L-Section and X-Section (at 10.00 mtr (Ten metre) intervals) showing the HLS and FRL of the road. (d) Detailed BOQ of all including cost estimation as per SOQ including entire cartage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	8 670	28500.00	Rupees Twenty Eight Thousand Five Hundred and Paise Zero Only		Per Kilometre	247095.00		
2	Preparation/Update of detail project for the work construction of 210.00m span bridges over Kunah Khad at RD 0/822 on Gafot to Har via Gugga Mandir (Under Nabard) i.e. substructure, super structure alongwith both side approaches in manuscript form and get checked from the competent authority, and if any amendment/correction desired by the competent authority be made, after the approval of the same should be fared out and submitted in triplicate for its further submission to high office complete including entire cartage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1 Job	95000.00	Rupees Ninety Five Thousand and Paise Zero Only		Lump Sum	48000.00		
3	Preparation of Hydraulic data report and drawing complete including consultancy service for topographical survey etc. in manuscript form and submission of the same in higher office for approval. If any correction/ amendment is required by the higher office the same may be corrected to the satisfaction of Engineer-in charge complete in all projects. After approval of the same from the S.E. office, GAD should be submitted in three copies in a fair manner and complete in all respects. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax or other taxes imposed by the Government.	1.00	86600.00	Rupees Eighty Six Thousand Six Hundred and Paise Zero Only		Per Bridge	86600.00		
	Total						381695.00		

Condition

- The work will be strictly executed as per HPPWD specifications

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS.381695/-
Rupees Three Lakhs Eighty One Thousand Six Hundred Ninety Five and Paise Zero Only

Executive Engineer,
Hamirpur Division,
HPPWD, Hamirpur

152-N
307

DRAFT SCHEDULE OF QUANTITY

Name Of Work:- Repair and maintenance of existing Court Complex building at Nadaun, Distt. Hamirpur (HP).				Estimated Cost:-Rs. 499376.00	
(SH:- Demolishing existing roofing sheet, providing and fixing new pre-painted steel, built up section work in fascia and soffit, fixing BP in fascia and soffit).				Earnest Money:- Rs. 10000.00	
				Time Limit:- One Month	
Sr. No.	Description of Items	Qty.	Fig.	Rate in Words	
				Unit	Amount
1	Dismantling roofing including ridges, hips, valleys, gutters, G.S. sheet elcetra stacking the serviceable materials and disposal of un-serviceable materials within all leads and lifts complete and stacking them including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	227.25	120.00	Rupees One Hundred Twenty and Paise Zero Only	27270.00
2	Providing and fixing pre-coated galvanised iron profile sheets (TATA/SAIL/JSW make) (size, shape and pitch of corrugation as approved by Engineer-in-Charge) 0.50 mm (zero point five zero millimetre) + 0.05 % (zero point zero five percentage) total coated thickness with zinc coating 120 (one hundred twenty) grams per square metre as per IS: 277, in 240 (two hundred forty) mpa steel grade, 5-7 (five to seven) microns epoxy primer on both side of the sheet and polyester top coat 15-18 (fifteen to eighteen) microns. Sheet should have protective guard film of 25 (twenty five) microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 (twelve) metre or as desired by Engineer-in-Charge. The sheet shall be fixed using self drilling /self tapping screws of size 5.5x 55 mm (five point into fifty five millimetre) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces excluding the cost of purins, rafters and trusses and including cutting to size and shape wherever required including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	227.25	1300.00	Rupees One Thousand Three Hundred and Paise Zero Only	295425.00
3	Providing and fixing Ridges or hips Plain 500 - 600mm (five hundred to six hundred millimetre) Pre-coated Galvanised steel sheet roofing accessories of TATA/SAIL/JSW Make 0.60 mm (zero point six zero millimetre) + 0.05 % (plus zero point zero five percent) total coated thickness, Zinc coating 120 (one hundred twenty) grams per square metre as per IS: 277, in 240 (two hundred forty) mpa steel grade, 5-7 (five to seven) microns epoxy primer on both side of the sheet and polyester top coat 15-18 (fifteen to eighteen) microns using self drilling/ self tapping screws complete upto all floor level including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	21.25	700.00	Rupees Seven Hundred and Paise Zero Only	14875.00


152-N
307

4	Providing and fixing MS BP Sheet 1.68mm to 2.00mm (One point six six to two millimetre) thick of TATA/Sail make in eaves board/ fascia/ soffits/ ceiling including cutting fixing and welding to steel roof members and applying a coat of red lead primer complete upto all heights as per instruction of Engineer in Charge (base members of steel work shall be measured and paid separately) including entire carriage of material with in all leads and lifts and as per drawings and technical specifications and the direction of Engineer-in-Charge including other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	35.06	1850.00	Rupees One Thousand Eight Hundred Fifty and Paise Zero Only	Per square metre	64861.00
5	Steel work welded in built up sections (TATA/ SAIL/ Apollo/ JSW Make) in framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etcetra as required in gratings, door and window frames, guard bar, ladder, railings, brackets, gates and similar works complete upto all floor level including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	843.00	115.00	Rupees One Hundred Fifteen and Paise Zero Only	Per Kilogram	96945.00
Total						499376.00

Condition

- 1 The work will be strictly executed as per HPPWD specifications
- 2 The contractor will procure cement at their own level from Civil Supply Depot. After the approval of permit from the competent authority and other material from market as per Department specification issued by the Additional Chief Secretary P.W. to the Govt. of HP vide No. FBW (B) C (17) 2/2012 dated 07 August 2018 and all other condition are liable & carriage will be born by the contractor.
- 3 The bills of all materials procured by the contractor M-form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill.

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS. 499376/-
Rupees Four Lakhs Ninety Nine Thousand Three Hundred
Seventy Six and Paise Zero Only


Executive Engineer,
Hamirpur Division,
HPPWD, Hamirpur

153-306 N

DRAFT SCHEDULE OF QUANTITY

DRAFT SCHEDULE OF QUANTITY							Estimated Cost:-Rs. 499500.00	
Name Of Work:- Repair and maintenance of existing Court Complex building at Nadaun, Distt. Hamirpur (HP).							Earnest Money:- Rs. 10000.00	
(SH:- Demolishing existing roofing sheet, providing and fixing new pre-painted steel, built up section work in fascia and soffit, fixing BP in fascia and soffit).							Time Limit:- One Month	
Sr. No.	Description of Items	Qty.	Rate in		Unit	Amount		
			Fig.	Words				
1	Dismantling roofing including ridges, hips, valleys, gutters, G.S. sheet etcetra stacking the serviceable materials and disposal of un-serviceable materials within all leads and lifts complete and stacking them including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	227.30	120.00	Rupees One Hundred Twenty and Paise Zero Only	Per square metre	27276.00		
2	Providing and fixing pre-coated galvanised iron profile sheets (TATA/SAIL/JSW make) (size: shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (zero point five zero millimetre) + 0.05 % (zero point zero five percentage) total coated thickness with zinc coating 120 (one hundred twenty) grams per square metre as per IS: 277, in 240 (two hundred forty) mpa steel grade, 5-7 (five to seven) microns epoxy primer on both side of the sheet and polyester top coat 15-18 (fifteen to eighteen) microns. Sheet should have protective guard film of 25 (twenty five) microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 (twelve) metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size 5.5x 55 mm (five point into fifty five millimetre) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	227.30	1300.00	Rupees One Thousand Three Hundred and Paise Zero Only	Per square metre	295490.00		
3	Providing and fixing Ridges or hips Plain 500 - 600mm (five hundred to six hundred millimetre) Pre-coated Galvanised steel sheet roofing accessories of TATA/SAIL/JSW Make 0.60 mm (zero point six zero millimetre) + 0.05 % (Plus zero point zero five percent) total coated thickness, Zinc coating 120 (one hundred twenty) grams per square metre as per IS: 277, in 240 (two hundred forty) mpa steel grade, 5-7 (five to seven) microns epoxy primer on both side of the sheet and polyester top coat 15-18 (fifteen to eighteen) microns using self drilling/ self tapping screws complete upto all floor level including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	21.25	700.00	Rupees Seven Hundred and Paise Zero Only	Per Running m	14875.00		

4	Providing and fixing MS BP Sheet 1.66mm to 2.00mm (One point six six to two millimetre) thick of TATA/Sail make in eaves board/ fascia/ soffits/ ceiling including cutting fixing and welding to steel roof members and applying a coat of red lead primer complete upto all heights as per instruction of Engineer in Charge (base members of steel work shall be measured and paid separately) including entire carriage of material with in all leads and lifts and as per drawings and technical specifications and the direction of Engineer-in-Charge including other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	35.06	1850.00	Rupees One Thousand Eight Hundred Fifty and Paise Zero Only	Per square metre	64861.00
5	Steel work welded in built up sections (TATA/ SAIL/ Apollor JSW Make) in framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel electro as required in gratings, door and window frames, guard bar, ladder, railings, brackets, gates and similar works complete upto all floor level including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	843.46	115.00	Rupees One Hundred Fifteen and Paise Zero Only	Per Kilogram	96598.00
	Total					499500.00

Condition

- 1 The work will be strictly executed as per HPPWD specifications
- 2 The contractor will procure cement at their own level from Civil Supply Depot. After the approval of permit from the competent authority and other material from market as per Department specification issued by the Additional Chief Secretary PW to the Govt. of HP vide No. PAW (B) C (17) 2/2012 dated 07 August 2018 and all other condition are liable & carriage will be born by the contractor
- 3 The bills of all materials procured by the contractor M-form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS. 499500/-
Rupees Four Lakhs Ninety Nine Thousand Five Hundred and Paise Zero Only


Executive Engineer,
Hamirpur Division
HPPWD, Hamirpur

154
308

DRAFT SCHEDULE OF QUANTITY

DRAFT SCHEDULE OF QUANTITY							Estimated Cost:-Rs. 126526.00	
Name Of Work:- Repair and maintenance of existing Court Complex building at Nadaun, Distt. Hamirpur (HP).							Earnest Money:- Rs. 2600.00	
Time Limit:- One Month								
Sr. No.	Description of Items	Qty.	Fig.	Rate in		Unit	Amount	
				Words				
1	Brick work with common burnt clay F P S. (non modular) bricks of class designation 7.5 (seven point five) in super structure above plinth level up to all floor levels in all shapes and sizes with Cement mortar 1:6 (one cement : six coarse sand) including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	6.04	9280.60	Rupees Nine Thousand Two Hundred Eighty and Paise Sixty Only		Per cubic metre	56055.00	
2	Providing and laying cement concrete 1:3:6 (One cement : three coarse sand : six graded stone aggregate) 20 mm (Twenty millimetre) nominal size in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or facing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etcetera including the cost of centering, shuttering and finishing as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.01	5491.00	Rupees Five Thousand Four Hundred Ninety One and Paise Zero Only		Per cubic metre	11037.00	
3	Repair to plaster of thickness 12mm to 20mm (Twelve millimetre to twenty millimetre) in patches of area 2.50 sqm (Two point five zero square metre) and under including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground with cement mortar 1:4 (One cement : four fine sand) complete including entire carriage of material with in all leads, lifts, drawings, technical specifications as per direction by Engineer-in-Charge including other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	47.50	335.50	Rupees Three Hundred Thirty Five and Paise Fifty Only		Per square metre	15936.00	
4	Providing and applying white Cement Based Putty of average thickness 1 mm (one millimetre) of approved brand and manufacturer (J K White/ Birla White) over the plastered wall surface to prepare the surface even and smooth complete upto all floor level including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	47.50	105.00	Rupees One Hundred Five and Paise Zero Only		Per square metre	4988.00	

5	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content. With water thinnable cement primer on wall surface having VOC content less than 50 grams/litre (fifty grammes per litre) including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	47.50	105.70	Rupees One Hundred Five and Paise Seventy Only	Per square metre	5021.00
6	Finishing walls with Acrylic Smooth Exterior Paint of ASIAN- APEX ULTIMA of required shade on old work (One or more coat applied @ 1.67 ltr/10 sqm (at the rate of one point six seven litre per ten square metre) over and including priming coat of exterior primer applied @ 0.90 kg/sqm (at the rate two point two zero kilogram per ten square metre) complete upto all floor level including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	47.50	100.20	Rupees One Hundred and Paise Twenty Only	Per square metre	4760.00
7	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm (at the rate of zero point nine zero per ten square metre) over an under coat of primer applied @ 0.80 ltr/ 10 sqm (at the rate of zero point eight zero per ten square metre)/(ASIAN/NEROLAC/ICI-DULUX) of approved brand and manufacture including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	70.12	117.30	Rupees One Hundred Seventeen and Paise Thirty Only	Per square metre	8225.00
8	Providing and fixing Single socketed pipes 110mm (one hundred ten millimetre) dia of Supreme/Fenolax/ Vectus make on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm (ten millimetre) gap for thermal expansion complete upto all floor level including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	26.40	365.60	Rupees Three Hundred Sixty Five and Paise Sixty Only	Per Running metre	9652.00

9	Providing and fixing 110 mm (One hundred ten millimetre) diameter unplasticised PVC pipe clips of approved design to unplasticised PVC rain water pipes (Finolex/ Supreme) by means of 50x50x50mm (fifty into fifty into fifty) millimetre hard wood plugs, screwed with mild steel screws of required length, including cutting brick work and fixing in cement mortar 1:4 (one cement: four sand) and making good the wall including entire carriage of material with in all leads and lifts and as per drawings and technical specifications and the direction of Engineer-in-Charge including other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	24.00	368.20	Rupees Three Hundred Sixty Eight and Paise Twenty Only	Each	8837.00
10	Providing and fixing Plain bend 87 5 degree 110mm (one hundred millimetre) dia of Supreme/Finolex/O-plast/ vectus make on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	8.00	251.90	Rupees Two Hundred Fifty One and Paise Ninety Only	Each	2015.00
	Total					126526.00

Condition

- 1 The work will be strictly executed as per HPPWD specifications
- 2 The contractor will procure cement at their own level from Civil Supply Depot. After the approval of permit from the competent authority and other material from market as per Department specification issued by the Addition Chief Secretary PW to the Govt. of HP vide No. PBW (B) C (17) 2/2012 dated 07 August 2018 and all other condition are liable & carriage will be born by the contractor.
- 3 The bills of all materials procured by the contractor M-form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill.

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS. 126526/-
Rupees One Lakh Twenty Six Thousand Five Hundred
Twenty Six and Paise Zero Only


Executive Engineer,
Hamirpur Division,
HPPWD, Hamirpur.

09/10/2012

GGL

DRAFT SCHEDULE OF QUANTITY						
Name Of Work:- Restoration of rain damages on link road to village Ghurat road km 0/0 to 1/390. (SH:- Construction of Wire Gate, Retaining wall at RD 0/075 to 0/095.80)				Estimated Cost:-Rs. 499872.00		
				Earnest Money:- Rs. 10000.00		
				Time Limit:- One Month		
Sr. No.	Description of Items	Qty.	Rate in		Unit	Amount
			Fig.	Words		
1	Excavation work by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms within all leads including getting out the excavated soil and disposal of surplus excavated soil as directed within all leads and lifts ordinary rock and all kinds of soil including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	36.19	300.00	Rupees Three Hundred and Paise Zero Only	Per cubic metre	10857.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetres) dia G.I wire conforming to IS 280 and IS 4826 in 100mmx100mm (One hundred into one hundred millimetre) mesh (woven diagonally) including 10% (Ten percent) extra for laps and joints laid with stone boulders weighing not less than 25kg (Twenty five kilogramme) each as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	119.80	2850.00	Rupees Two Thousand Eight Hundred Sixty and Paise Zero Only	Per cubic metre	342628.00
3	Back filling behind abutment, wing walls and return walls complete as per drawings & MORD technical specification Clause 1204.3.8 granular material as per direction of Engineer-in-Charge including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	172.22	850.00	Rupees Eight Hundred Fifty and Paise Zero Only	Per cubic metre	146387.00
		Total		499872.00		

Condition

- 1 The work will be strictly executed as per HPPWD specifications
- 2 The contractor will procure cement at their own level from Civil Supply Depot. After the approval of permit from the competent authority and other material from market as per Department specification issued by the Addition Chief Secretary PW to the Govt. of HP vide No. PBW (B) C (17) 2/2012 dated 07 August 2018 and all other condition are table & carriage will be born by the contractor
- 3 The bills of all materials procured by the contractor M-form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS. 499872/-
Rupees Four Lakhs Ninety Nine Thousand Eight Hundred
Seventy Two and Paise Zero Only


Executive Engineer,
Hamirpur Division,
HPPWD, Hamirpur

16110

65 L

DRAFT SCHEDULE OF QUANTITY

Name Of Work:- Restoration of rain damages on link road to village Ghurar road km 0/0 to 1/390. (SH:- Construction of Wire Crata, Retaining wall at RD 0/095.80 to 0/116.60)		Estimated Cost:-Rs. 499872.00		Earnest Money:- Rs. 10000.00		Time Limit:- One Month	
Sr. No.	Description of Items	Qty.	Fig.	Rate in		Unit	Amount
				Words			
1	Excavation work by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms within all leads including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads and lifts ordinary rock and all kinds of soil including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	36.19	300.00	Rupees Three Hundred and Paise Zero Only		Per cubic metre	10857.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetres) dia G.I wire conforming to IS-280 and IS-4826 in 100mmx100mm (One hundred into one hundred millimetre) mesh (woven diagonally) including 10% (Ten percent) extra for laps and joints laid with stone boulders weighing not less than 25kg (Twenty five kilograms) each as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax or other taxes imposed by the Government.	119.80	2850.00	Rupees Two Thousand Eight Hundred Sixty and Paise Zero Only		Per cubic metre	342628.00
3	Back filling behind abutment, wing walls and return walls complete as per drawings & MORD technical specification Clause 1204.3.8 granular material as per direction of Engineer-in-Charge including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	172.22	850.00	Rupees Eight Hundred Fifty and Paise Zero Only		Per cubic metre	145387.00
Total							499872.00

Condition

- The work will be strictly executed as per HPPWD specifications.
- The contractor will procure cement at their own level from Civil Supply Depot. After the approval of permit from the competent authority and other material from market as per Department specification issued by the Addition Chief Secretary PW to the Govt. of HP vide No. PSW (B) C (17) 2/2012 dated 07 August 2018 and all other condition are liable & carriage will be born by the contractor.
- The bills of all materials procured by the contractor in form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill.

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS. 499872/-
 Rupees Four Lakhs Ninety Nine Thousand Eight Hundred
 Seventy Two and Paise Zero Only


 Executive Engineer,
 Hamirpur Division,
 HPPWD, Hamirpur

18/10

15/1 N
295

DRAFT SCHEDULE OF QUANTITY

Name Of Work:- Restoration of rain damages on link road from Balhi to Samad Km 0/0 to 0/600. (SH):- C/o 900mm dia Hume Pipe Culvert at RD 0/180).						Estimated Cost:-Rs. 280667.00	
						Earnest Money:- Rs. 5700.00	
						Time Limit:- One Month	
Sr. No.	Description of Items	Qty.	Rate in		Unit	Amount	
			Fig.	Words			
1	Excavation work by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms within all leads including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads and lifts ordinary rock and all kinds of soil including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	43.98	212.75	Rupees Two Hundred Twelve and Paise Seventy Five Only	Per cubic metre	9337.00	
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering 1:4:8 (one cement : four coarse sand : eight graded stone aggregate) 40mm (forty millimetre) nominal size graded stone aggregate for all works upto plinth level including the cost of centering and shuttering including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.26	5073.60	Rupees Five Thousand Seventy Three and Paise Sixty Only	Per cubic metre	11466.00	
3	Providing and laying cement concrete 1:3:6 (One cement : three coarse sand : six graded stone aggregate) 20 mm (Twenty millimetre) nominal size in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, filets, sunken floor etcetera including the cost of centering, shuttering and finishing as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	19.22	5459.10	Rupees Five Thousand Four Hundred Sixty Nine and Paise Ten Only	Per cubic metre	105116.00	
4	Providing and laying in position cement concrete of specified grade 1:5:10 (one cement : five coarse sand : ten graded stone aggregate) 40mm (forty millimetre) nominal size graded stone aggregate in retaining wall, breast wall, walls of any thickness and like structures including the cost of centering and shuttering including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	22.99	4535.00	Rupees Four Thousand Five Hundred Thirty Six and Paise Zero Only	Per cubic metre	104283.00	
5	Providing and laying 900mm (Nine hundred millimetre diameter) (to level and slopes) reinforced cement concrete non pressure pipe (S.I class NP-3 (Medium duty) for culverts on 1st class bedding of granular material in single row including collar with cement mortar 1:2 (One cement : two coarse sand) but excluding the cost of excavation protection work, back filling, concrete and masonry work in head walls and parapets as per drawing and MORD technical specification and as per direction of Engineer-in-Charge including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	7.50	5432.80	Rupees Five Thousand Four Hundred Thirty Two and Paise Eighty Only	Per Running metre	40746.00	


1501 N
295

6	Back filling behind abutment, wing walls and return walls complete as per drawings & MORD technical specification. granular material as per direction of Engineer-in-Charge including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	5.40	1250.00	Rupees One Thousand Two Hundred Fifty Nine and Paise Zero Only	Per cubic metre	6799.00
7	Providing weep holes in brick masonry / Stone masonry / plain/reinforced concrete in retaining walls, breast walls and the like with 110mm (One hundred ten millimetre) dia PVC pipe Finotex/ Supreme having pressure not less than 4.00 Kg/Cm ² (four kilogramme) per centimetre square extending through the full width of the structure with slope of 1(V):20(H) (one vertical : twenty horizontal) towards drawing face complete including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	10.00	290.00	Rupees Two Hundred Ninety and Paise Zero Only	Each	2900.00
	Total					280667.00

Condition

- The work will be strictly executed as per HPPWD specifications
- The contractor will procure cement at their own level from Civil Supply Depot. After the approval of permit from the competent authority and other material from market as per Department specification issued by the Addition Chief Secretary PW to the Govt. of HP vide No. HPW (B) C (17) 20012 dated 07 August 2018 and all other condition are liable & carriage will be born by the contractor
- The bills of all materials procured by the contractor M-form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS.280667/-
Rupees Two Lakhs Eighty Thousand Six Hundred Sixty Seven and Paise Zero Only


Executive Engineer
✓ Hemapur Division
HPPWD Hamirpur

138 Hme
288

DRAFT SCHEDULE OF QUANTITY

Name of Work:- C/O link road from Jhanyari Via IHM Sidh Baba Km 0/0 to 2/0

(SH:- Providing and laying 80mm thick cement concrete Paver block Km 0/900 to 0/144)

Estimated Cost:- Rs.498098.00

Earnest Money:- Rs.10000.00

Time Limit:- One Month

Sr. No.	Description of Items	Qty.	Rate in		Unit	Amount
			Fig.	Words		
1	Excavation work by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soil in ordinary rock and Pick work and junper work, including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	7.01	300.00	Rupees Three Hundred and Paise Zero Only	Per cubic metre	2103.00
2	Providing and laying in position cement concrete of 1:2:4 (One cement : Two coarse sand) : four graded stone aggregate 20 mm (Twenty millimetre) nominal size for All work up to plinth level excluding the cost of centering and shuttering, including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	10.51	6500.00	Rupees Six Thousand Five Hundred and Paise Zero Only	Per cubic metre	68315
3	Providing and laying factory made 80mm (Eighty millimetre) thick cement concrete paver block of M-40 (M-forty) grade with approved colour, design and pattern (NTC make & ISI marked or its equivalent) chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etcetra of required strength, thickness and size/ shape, made by table vibratory method using PU mould, laid in required colour and pattern over 50mm thick (fifty millimetre) compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand complete all as per direction of Engineer-in-Charge including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	237.60	1800.00	Rupees One Thousand Eight Hundred and Paise Zero Only	Per square metre	427680
Total						498098.00

Condition

1 The work will be strictly executed as per HPPWD specifications

2 The contractor will procure cement at their own level from Civil Supply Depot. After the approval of permit from the competent authority and other material from market as per Department specification issued by the Addn. Chief Secretary P&W to the Govt. of HP vide No. P&W (B) C (17) 2/2012 dated 07 August 2012 and at other condition are liable & carriage will be born by the contractor

3 The bills of all materials procured by the contractor in form of running materials need for execution of work must be submitted to the authority concerned alongwith contractor bill

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS.498098.

Rupees Four Lakhs Ninety Eight Thousand Ninety Eight and Paise Zero Only


 Executive Engineer
 Hamirpur Division
 HPPWD Hamirpur

DRAFT SCHEDULE OF QUANTITY

Name of Work:- C/O link road from Jhanyari Via IHM Sidh Baba Km 0/0 to 2/0
(SH:- Providing and laying 80mm thick cement concrete Paver block Km 0/210 to 0/263)

Estimated Cost:-Rs.488972.00
 Earnest Money:- Rs.9800.00
 Time Limit:- One Month

Sr. No.	Description of Items	Qty.	Fig.	Rate in		Unit	Amount
				Words			
1	Excavation work by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soil in ordinary rock and Pick work and jumper work including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	6.89	300.00	Rupees Three Hundred and Paise Zero Only		Per cubic metre	2067.00
2	Providing and laying in position cement concrete of 1:2:4 (One cement : Two coarse sand) : four graded stone aggregate 20 mm (Twenty millimetre) nominal size for All work up to plinth level excluding the cost of centering and shuttering, including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	10.33	6500.00	Rupees Six Thousand Five Hundred and Paise Zero Only		Per cubic metre	67145
3	Providing and laying factory made 80mm (Eighty millimetre) thick cement concrete paver block of M-40 (M-forty) grade with approved colour, design and pattern (NTC make & ISI marked or its equivalent) chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking elcetra of required strength, thickness and size/ shape, made by table vibratory method using PU mould, laid in required colour and pattern over 50mm thick (fifty millimetre) compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator. Filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand complete all as per direction of Engineer-in-Charge including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	233.20	1800.00	Rupees One Thousand Eight Hundred and Paise Zero Only		Per square metre	419750
Total							488972.00

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS.488972/-
 Rupees Four Lakhs Eighty Eight Thousand Nine Hundred Seventy Two and Paise Zero Only

- 1 The work will be strictly executed as per HPPWD specifications.
- 2 The contractor will procure cement at their own level from Civil Supply Depot. After the approval of permit from the competent authority and other material from market as per Department specification issued by the Additional Chief Secretary PW to the Govt. of HP vide No. PBW (B) C-1773/2012 dated 07 August 2018 and all other condition are liable & carriage will be born by the contractor.
- 3 The bills of all materials procured by the contractor M-form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill.

Executive Engineer,
 Haripur Division
 HPPWD, Haripur

1374 H
 287

147 N
310

DRAFT SCHEDULE OF QUANTITY

DRAFT SCHEDULE OF QUANTITY						
Name Of Work:- A/R & M/O Assistant Engineer Residence Nadaun Tehsil Nadaun Distt. Hamirpur (HP). (SH:- Painting, P/F Cupboard Shutter, P/F door and windows shutter & Sanitary etc.).			Estimated Cost:-Rs. 280653.00 Earnest Money:- Rs.5700.00 Time Limit:- One Month			
Sr. No.	Description of Items	Qty.	Rate in		Unit	Amount
			Fig.	Words		
1	Repair to plaster of thickness 12mm to 20mm (Twelve millimetre to twenty millimetre) in patches of area 2.50 sqm (Two point five zero square metre) and under including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground with cement mortar 1:4 (One cement : four fine sand) complete including entire carriage of material with in all leads, lifts, drawings, technical specifications as per direction by Engineer-in-Charge including other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	112.32	347.40	Rupees Three Hundred Forty Seven and Paise Forty Only	Per square metre	39020.00
2	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface (Asian/Nerolac/ICI Dulux) complete including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	112.32	49.90	Rupees Forty Nine and Paise Ninety Only	Per square metre	5605.00
3	Removing dry or oil bound distemper, water proofing cement paint and the like by scraping and sand papering the wall surface smooth including necessary repairs to scratches complete including entire carriage of material with in all leads, lifts, drawings, technical specifications as per direction by Engineer-in-Charge including other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	184.71	15.40	Rupees Fifteen and Paise Forty Only	Per square metre	2845.00
4	Wall painting Two coats with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre (Fifty grams per litre) of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour complete including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	184.71	108.80	Rupees One Hundred Eight and Paise Eighty Only	Per square metre	20096.00
5	Finishing walls with Acrylic Smooth Exterior Paint of ASIAN- APEX ULTIMA of required shade on old work (One or more coat applied @ 1.87 lt/10 sqm (at the rate of one point six seven litre per ten square metre) over and including priming coat of exterior primer applied @ 0.90 kg/sqm (at the rate two point zero zero kilogram per ten square metre) complete upto all floor level including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	107.42	153.00	Rupees One Hundred Fifty Three and Paise Zero Only	Per square metre	16435.00

6	Providing and fixing 19mm (Nineteen millimetre) thick water proof commercial board both side laminated HDHMR (Action Tesa/Kitply/Century ply make) in shelves/box for cup board with butt joints and fixing with nails and screws etcetera complete including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	6.51	4015.90	Rupees Four Thousand Fifteen and Paise Ninety Only	Per square metre	26144.00
7	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade on old work (two or more coats) including a coat of approved steel primer but excluding a coat of mordant solution (Asian/Nerolac/ICI Dulux) complete including entire carriage of material with in all leads, lifts, drawings, technical specifications as per direction by Engineer-in-Charge including other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	120.51	79.36	Rupees Seventy Nine and Paise Thirty Six Only	Per square metre	9564.00
8	Providing and fixing 35 mm (Thirty five millimetre) thick shutters Second class teak wood panelled or panelled and grazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, excluding panelling which will be paid for separately including entire carriage of material with in all leads, lifts, drawings, technical specifications as per direction by Engineer-in-Charge including other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	17.99	4500.00	Rupees Four Thousand Five Hundred and Paise Zero Only	Per square metre	80955.00
9	Providing and fixing Float glass panes of nominal thickness 4 mm (four millimetre) make of Modiguard/ Saint Gobain/ Asahi (weight not less than 10kg/sqm (ten kilogram per square metre) of renewing glass panes with putty and nails wherever necessary including racking out the old putty complete upto all floor level including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	14.70	850.00	Rupees Eight Hundred Fifty and Paise Zero Only	Per square metre	12495.00
10	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat (Hindware/Parryware/Cera make) and lid, 10 litre (Ten litre) low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) W.C. pan with ISI marked white solid plastic soft closing seat and lid conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required as per direction of Engineer-In-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.00	5500.00	Rupees Five Thousand Five Hundred and Paise Zero Only	Each	5500.00
11	Providing and fixing 20mm (Twenty millimetre) nominal bore C.P. brass bib cock of Jaquar (CON-047KN) with wall flange approved quality conforming to IS 8931 make of Jaquar/ Parryware/Hindware including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	4.00	1300.00	Rupees One Thousand Three Hundred and Paise Zero Only	Each	5200.00

12	Providing and fixing wash basin with C.I. brackets, 15 mm (fifteen millimetre) diameter single hole basin mixer of approved quality and make of JalJaquar/Parryware/Hindware C.P. brass pillar taps, 32 mm (thirty two millimetre) C.P. brass waste of standard pattern (Hindware or Jaquar), including painting of fittings and brackets, cutting and making good the walls wherever required White Vitreous China Wash basin size 630x450 mm (six hundred thirty into four hundred fifty millimetre) with a 15 mm (fifteen millimetre) CP Brass single hole basin mixer of Hindware or Jaquar make (OPAL SERIES) including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.00	4500.00	Rupees Four Thousand Five Hundred and Paise Zero Only	Each	9000.00
13	Providing and fixing galvanized iron inlet connection for flushing pipe with W.C. pan including entire carriage of material with in all leads, lifts, technical specifications as per the direction by Engineer-in-Charge and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	8.00	535.02	Rupees Five Hundred Thirty Six and Paise Two Only	Each	4288.00
14	Providing and fixing 15mm (fifteen millimetre) dia nominal bore G.I. pipes complete with G.I. fittings and clamps, including cutting and making good the walls etc. Internal work - Exposed on wall including entire carriage of material with in all leads, lifts, technical specifications as per the direction by Engineer-in-Charge and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	30.00	301.88	Rupees Three Hundred One and Paise Eighty Eight Only	Per Running metre	9056.00
15	Providing and fixing P.V.C. waste semi rigid pipe for sink or wash basin including P.V.C. waste fittings complete of 32mm (thirty two millimetre) dia of Supreme /Fenolax make including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.00	120.00	Rupees One Hundred Twenty and Paise Zero Only	Each	240.00
16	Providing and fixing 15mm (Fifteen millimetre) nominal bore C.P. brass Stop Cock of Jaquar (OP-CHR-15053 PM) with wall flange for basin mixer and geyser points of approved quality conforming to IS 8931 including entire carriage of material with in all leads, lifts, drawings, technical specifications as per direction by Engineer-in-Charge including other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	12.00	950.00	Rupees Nine Hundred Fifty and Paise Zero Only	Each	11400.00
17	Providing and fixing 8 mm (Eight millimetre) dia C.P. / S.S. Jet with flexible tube upto 1 (One) metre long with S.S. triangular plate to European type W.C. of quality of ESCO (ALE-547) and make including entire carriage of material with in all leads, lifts, drawings, technical specifications as per direction by Engineer-in-Charge including other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.00	400.00	Rupees Four Hundred and Paise Zero Only	Each	400.00
18	Providing and fixing solid plastic seat with lid for pedestal type W.C. pan White solid plastic seat with lid complete Jaquar/Hindware/ Parryware make including entire carriage of material with in all leads, lifts, technical specifications as per the direction by Engineer-in-Charge and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.00	607.16	Rupees Six Hundred Seven and Paise Sixteen Only	Each	607.00

19	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm (one hundred millimetre) sand cast iron P or S trap, 10 (ten) litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required White Vitreous china Orissa pattern W.C. pan of size 580x440 mm (five hundred eighty into four hundred forty) with integral type foot rests Hindware/Cera Universal Pan No. 2071 (two thousand seventy one) including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.00	5500.00	Rupees Five Thousand Five Hundred and Paise Zero Only	Each	5500.00
20	Providing and fixing white glazed fire clay kitchen sink of size 600x450x 250 mm (Six hundred into four hundred fifty into two hundred fifty millimetre) kitchen sink with C.I. brackets, C.P. brass chain with rubber plug, 40 mm (Forty millimetre) C.P. brass waste complete, including painting the fittings and brackets, cutting and making good the walls wherever required including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.00	3161.99	Rupees Three Thousand One Hundred Sixty One and Paise Ninety Nine Only	Each	3162.00
21	Providing and fixing 12mm (twelve millimetre) dia. chromium plated brass curtain rod having wall thickness of 1.25mm (one point two five millimetre) with two chromium plated brass brackets fixed with C.P. brass screws and PVC sleeves etcetera wherever necessary complete including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	24.25	290.05	Rupees Two Hundred Ninety and Paise Five Only	Per Running metre	7034.00
22	Providing and fixing 150x10mm (One hundred fifty into ten millimetre) nominal size ISI marked oxidised M.S. tower bolt black finish, (Barrel type) with necessary screws etcetra complete including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	14.00	111.58	Rupees One Hundred Eleven and Paise Fifty Eight Only	Each	1562.00
23	Providing and fixing 100mm (One hundred millimetre) ISI marked oxidised M.S. handles conforming to IS 4992 with necessary screws etcetra complete including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	10.00	71.07	Rupees Seventy One and Paise Seven Only	Each	711.00
	Total					276819.00

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS. 276819/-
Rupees Two Lakhs Seventy Six Thousand Eight Hundred Nineteen and Paise Zero Only

Condition

- The work will be strictly executed as per HPPWD specifications.
- The contractor will procure cement at their own level from Civil Supply Depot. After the approval of permit from the competent authority and other material from market as per Department specification issued by the Addition Chief Secretary PW to the Govt. of HP vide No. PBW (B) C (17) 2/2012 dated 07 August 2018 and all other condition are liable & carriage will be born by the contractor.
- The bills of all materials procured by the contractor M-form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill.


Executive Engineer,
Hamirpur Division,
HPPWD, Hamirpur

150-N
309

DRAFT SCHEDULE OF QUANTITY

Name Of Work:- A/R & M/O Sub-Division Office Building at Nadaun Tehsil Nadaun Distt. Hamirpur (HP). (SH:- Repair to plaster patches, painting, P/F Cupboard shutter, P/F Glazed shutter, P/F curtain Rods & Sanitary etc).					Estimated Cost:-Rs. 278365.00		
					Earnest Money:- Rs.5600.00		
					Time Limit:- One Month		
Sr. No.	Description of Items	Qty.	Fig.	Rate in		Unit	Amount
				Words			
1	Repair to plaster of thickness 12mm to 20mm (Twelve millimetre to twenty millimetre) in patches of area 2.50 sqm (Two point five zero square metre) and under including cutting the patch in proper shape raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground with cement mortar 1:4 (One cement : four fine sand) complete including entire carriage of material with in all leads, lifts, drawings, technical specifications as per direction by Engineer-in-Charge including other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	115.27	347.40	Rupees Three Hundred Forty Seven and Paise Forty Only		Per square metre	40045.00
2	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface (Asian/Norlac/ICI Dulux) complete including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	115.27	49.90	Rupees Forty Nine and Paise Ninety Only		Per square metre	5752.00
3	Removing dry or oil bound distemper water proofing cement paint and the like by scraping and sand papering the wall surface smooth including necessary repairs to scratches complete including entire carriage of material with in all leads, lifts, drawings, technical specifications as per direction by Engineer-in-Charge including other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	251.74	15.40	Rupees Fifteen and Paise Forty Only		Per square metre	3877.00
4	Wall painting Two coats with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/litre (Fifty grams per litre) of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour complete including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	251.74	108.80	Rupees One Hundred Eight and Paise Eighty Only		Per square metre	27389.00
5	Finishing walls with Acrylic Smooth Exterior Paint of ASIAN- APEX ULTIMA of required shade on old work (One or more coat applied @ 1.67 ltr/10 sqm (at the rate of one point six seven litre per ten square metre) over and including priming coat of exterior primer applied @ 0.90 kg/sqm (at the rate two point two zero kilogram per ten square metre) complete upto all floor level including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	115.44	153.00	Rupees One Hundred Fifty Three and Paise Zero Only		Per square metre	17662.00

150 N
809

6	Providing and fixing 19mm (Nineteen millimetre) thick water proof commercial board both side laminated HDHMR (Action Tesa/Kitply/Century ply make) in shelves/box for cup board with built joints and fixing with nails and screws etcetera complete including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.10	4051.90	Rupees Four Thousand Fifty One and Paise Ninety Only	Per square metre	8509.00
7	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade on old work (two or more coats) including a coat of approved steel primer but excluding a coat of mordant solution (Asian/Nerolac/ICI Dulux) complete including entire carriage of material with in all leads, lifts, drawings, technical specifications as per direction by Engineer-in-Charge including other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	47.50	79.36	Rupees Seventy Nine and Paise Thirty Six Only	Per square metre	3770.00
8	Providing and fixing 35 mm (Thirty five millimetre) thick shutters Second class teak wood panelled or panelled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, excluding panelling which will be paid for separately including entire carriage of material with in all leads, lifts, drawings, technical specifications as per direction by Engineer-in-Charge including other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	5.34	4500.00	Rupees Four Thousand Five Hundred and Paise Zero Only	Per square metre	24030.00
9	Providing and fixing Float glass panes of nominal thickness 4 mm (four millimetre) make of Modiguard/ Saint Gobain/ Asahi (weight not less than 10kg/sqm (ten kilogram per square metre) of renewing glass panes with putty and nails wherever necessary including racking out the old putty complete upto all floor level including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	12.60	850.00	Rupees Eight Hundred Fifty and Paise Zero Only	Per square metre	10710.00
10	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat (Hindware/Parryware/Cera make) and 10 litre (Ten litre) low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) W.C. pan with ISI marked white solid plastic soft closing seat and lid, conforming to IS: 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.00	5500.00	Rupees Five Thousand Five Hundred and Paise Zero Only	Each	5500.00
11	Providing and fixing 20mm (Twenty millimetre) nominal bore C.P. brass bib cock of Jaquar (CON-047KN) with wall flange approved quality conforming to IS 8931 make of Jaquar/ Parryware/Hindware including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	4.00	1300.00	Rupees One Thousand Three Hundred and Paise Zero Only	Each	5200.00

150/- N
309

12	Providing and fixing wash basin with C.I. brackets, 15 mm (fifteen millimetre) diameter single hole basin mixer of approved quality and make of Jai/Jaquar/Parryware/Hindware) C.P. brass pillar taps, 32 mm (thirty two millimetre) C.P. brass waste of standard pattern (Hindware or Jaquar), including painting of fittings and brackets, cutting and making good the walls wherever required White Vitreous China Wash basin size 630x450 mm (six hundred thirty into four hundred fifty millimetre) with a 15 mm (fifteen millimetre) CP Brass single hole basin mixer of Hindware or Jaquar make (OPAL SERIES) including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.00	4500.00	Rupees Four Thousand Five Hundred and Paise Zero Only	Each	9000.00
13	Providing and fixing galvanized iron inlet connection for flushing pipe with W.C. pan including entire carriage of material with in all leads, lifts, technical specifications as per the direction by Engineer-in-Charge and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	8.00	536.02	Rupees Five Hundred Thirty Six and Paise Two Only	Each	4288.00
14	Providing and fixing 15mm (fifteen millimetre) dia nominal bore G.I. pipes complete with G.I. fittings and clamps, including cutting and making good the walls etc. Internal work - Exposed on wall including entire carriage of material with in all leads, lifts, technical specifications as per the direction by Engineer-in-Charge and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	40.00	301.88	Rupees Three Hundred One and Paise Eighty Eight Only	Per Running metre	12075.00
15	Providing and fixing P.V.C. waste semi rigid pipe for sink or wash basin including P.V.C. waste fittings complete of 32mm (thirty two millimetre) dia of Supreme/Fenolax make including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.00	120.00	Rupees One Hundred Twenty and Paise Zero Only	Each	240.00
16	Providing and fixing 15mm (Fifteen millimetre) nominal bore C.P. brass Stop Cock of Jaquar (OPP-CHR-15053 PM) with wall flange for basin mixer and geyser points of approved quality conforming to IS 8931 including entire carriage of material with in all leads, lifts, drawings, technical specifications as per direction by Engineer-in-Charge including other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	15.00	950.00	Rupees Nine Hundred Fifty and Paise Zero Only	Each	14250.00
17	Providing and fixing 8 mm (Eight millimetre) dia C.P. / S.S. Jet with flexible tube upto 1 (One) metre long with S.S. triangular plate to European type W.C. of quality of ESSCO (ALE-547) and make including entire carriage of material with in all leads, lifts, drawings, technical specifications as per direction by Engineer-in-Charge including other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.00	400.00	Rupees Four Hundred and Paise Zero Only	Each	400.00
18	Providing and fixing solid plastic seat with lid for pedestal type W.C. pan White solid plastic seat with lid complete Jaquar/Hindware/ Parryware make including entire carriage of material with in all leads, lifts, technical specifications as per the direction by Engineer-in-Charge and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.00	607.16	Rupees Six Hundred Seven and Paise Sixteen Only	Each	607.00

150 N
309

19	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm (one hundred millimetre) sand cast iron P or S trap, 10 (ten) litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required White Vitreous china Orissa pattern W.C. pan of size 580x440 mm (five hundred eighty into four hundred forty) with integral type foot rests Hindware/Cera Universal Pan No. 2071 (two thousand seventy one) including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.00	5500.00	Rupees Five Thousand Five Hundred and Paise Zero Only	Each	5500.00
20	Providing and fixing white glazed fire clay kitchen sink of size 600x450x 250 mm (Six hundred into four hundred fifty into two hundred fifty millimetre) kitchen sink with C.I. brackets, C.P. brass chain with rubber plug, 40 mm (Forty millimetre) C.P. brass waste complete, including painting the fittings and brackets, cutting and making good the walls wherever required including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.00	3161.99	Rupees Three Thousand One Hundred Sixty One and Paise Ninety Nine Only	Each	3162.00
21	Providing and fixing 12mm (twelve millimetre) dia chromium plated brass curtain rod having wall thickness of 1.25mm (one point two five millimetre) with two chromium plated brass brackets fixed with C.P. brass screws and PVC sleeves etcetera wherever necessary complete including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	16.10	290.05	Rupees Two Hundred Ninety and Paise Five Only	Per Running metre	4670.00
22	Providing and fixing 150x10mm (One hundred fifty into ten millimetre) nominal size ISI marked oxidised M.S. tower bolt black finish, (Barrel type) with necessary screws etcetra complete including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	10.00	111.58	Rupees One Hundred Eleven and Paise Fifty Eight Only	Each	1116.00
23	Providing and fixing 100mm (One hundred millimetre) ISI marked oxidised M.S. handles conforming to IS:4992 with necessary screws etcetra complete including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	10.00	71.07	Rupees Seventy One and Paise Seven Only	Each	711.00
24	Providing and fixing 100mm (one hundred millimetre) dia nominal size soil, waste and vent pipes sand cast iron socket and spigot (S&S) pipe as per IS: 3989 including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	50.00	1056.12	Rupees One Thousand Fifty Six and Paise Twelve Only	Per running metre	52806.00

150 N
309

25	Providing and fixing white vitreous china flat back half stall urinal of size 500x380x350 mm (Five hundred eighty into three hundred eighty into three hundred fifty millimetre) with white PVC automatic flushing cistern, with fittings, standard size C.P. brass flush pipe, spreaders with unions and clamps (all in C.P. brass) with waste fitting as per IS 2556, C.I. trap with outlet grating and other couplings in C.P. brass, including painting of fittings and cutting and making good the walls and floors wherever required Range of four half stall urinals with 10 litre (Ten litre) P.V.C. automatic flushing cistern complete including entire carriage of material with in all leads, lifts, drawings, technical specifications as per direction by Engineer-in-Charge including other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.00	8548.15	Rupees Eight Thousand Five Hundred Forty Eight and Paise Fifteen Only	Each	17096.00
Total						278365.00

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS. 278365/-
Rupees Two Lakhs Seventy Eight Thousand Three Hundred Sixty Five and Paise Zero Only

Condition

1. The work will be strictly executed as per HPPWD specifications
2. The contractor will procure cement at their own level from Civil Supply Depot. After the approval of permit from the competent authority and other material from market as per Department specification issued by the Additional Chief Secretary PW to the Govt. of HP vide No. PBW (B) C (17) 2/2012 dated 07 August 2018 and all other condition are liable & carriage will be born by the contractor
3. The bills of all materials procured by the contractor M-form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill


Executive Engineer,
Hamirpur Division
✓ HPPWD, Hamirpur

66 L

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Kallar to Kesari Bridge im 0/0 to 1/550. (SH:- Repair of Pot Holes at various RDs).

Name of Work:- Restoration of rain damages on Kallar to Kesarl Bridge im 0/0 to 1/550. (SH:- Repair of Pot Holes at various RDs).				Estimated Cost:- Earnest Money:- Time:- One Month.	Rs. 300000.00 only Rs. 17100.00 only	
No	Description of Items	Qty.	Rate in		Unit	Amount
			Fig.	Words		
1	Repair to patch/pot holes (any depth) in connection with repainting including sweeping free from dust and mud, scoring sunken surfaces in road, paths etcetera cutting around edges to atleast 25mm (Twenty five millimetres) in depth and removal of loose material, trimming of sides, cleaning of surface and making good by providing tack coat with emulsion bitumen @ 0.300kg/sqm (Zero point three zero zero kilogramme per square metre) and then providing 20mm (Twenty millimetres) thick premix carpet using VG-10 bitumen @1.46kg/sqm (One point four six kilogramme per square metre) and seal coat type-B with VG-10 bitumen @0.68kg/sqm (Zero point six eight kilogramme per square metre) as per technical specification clause 1904.2, 503 and 508.2 including entire carriage of material with in all leads, lifts, drawings, technical specifications as per direction by Engineer-in-Charge including other incidentals. The rates are inclusive of octroi, royalty, matikana, toll tax, sale tax, GST or other taxes imposed by the Government.	869.564	345, 70	Rupees Three Hundred	Per square metrie	300000.00
						300000.00

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS. 300000/-only
Rupees Three Lakhs Zero and Paise Zero Only

Conditions:-

- The work will be strictly executed as per HPPWD specifications
- The contractor will procure Cement from Civil Supply Depot, VG-30 & Emulsion RS-1 & SS-1 from HPCL/IOCL/BPCL at their own level after the approval of permit from the competent authority and other material from market as per Department specification issued by the Addition Chief Secretary PW to the Govt. of HP vide No. PBW (B) C (17) 2/2012 dated 07 August 2018 and all other condition are liable & carriage will be born by the contractor.
- The bills of all materials procured by the contractor M-form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill.


Executive Engineer,
Hamirpur Division
HPPWD, Hamirpur

141-11112
205

DRAFT SCHEDULE OF QUANTITY

Time Of Work:- A/R & M/O District Session Court Building at Hamirpur (SH):- Painting of existing boundary wall, C/o
in any other general repair work in courtyard area).

Estimated Cost:-Rs. 492499.00

Earnest Money:- Rs.9900.00

Time Limit:- One Month

S. No.	Description of Items	Qty.	Fig.	Rate in		Unit	Amount
				Words			
1	Excavation work by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms within all leads including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads and lifts ordinary rock and all kinds of soil including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	4.10	300.00	Rupees Three Hundred and Paise Zero Only		Per cubic metre	1230.00
2	Providing and laying cement concrete 1:3:6 (One cement : three coarse sand : six graded stone aggregate) 20 mm (Twenty millimetre) nominal size in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etcetera including the cost of centering, shuttering and finishing as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	15.58	5200.00	Rupees Five Thousand Two Hundred and Paise Zero Only		Per cubic metre	81016.00
3	Repairs to plaster of thickness 12 mm to 20 mm (Twelve millimetre to twenty millimetre) in patches of area 2.5 sq metre (Two point five square metre) and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground with cement mortar 1:4 (One cement : four fine sand), all complete including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	90.00	300.00	Rupees Three Hundred and Paise Zero Only		Per square metre	27000.00
4	Providing and applying white Cement Based Putty of average thickness 1 mm (one millimetre) of approved brand and manufacturer (J K White/ Birla White) over the plastered wall surface to prepare the surface even and smooth complete upto all floor level including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	90	90.00	Rupees Ninety and Paise Zero Only		Per square metre	8100.00
5	Finishing walls with Deluxe Multi Surface Paint of required shade. Two or more coats applied on walls @ 1.25 ltr/10 sqm (at the rate of one point two five per ten square metre) over an under coat of primer applied @0.75 ltr/10 sqm (at the rate of zero point seven five per ten square metre) (ASIAN-Apex Ultima) of approved brand and manufacture including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	873.34	110.00	Rupees One Hundred Ten and Paise Zero Only		Per square metre	96067.00

6	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm (at the rate of zero point nine zero litre per ten square metre) over an under coat of primer applied @ 0.80 ltr/ 10 sqm (at the rate of zero point eight zero litre per ten square metre) of approved brand and manufacture (ASAIN/NEROLAC/ICI-DULUX) complete upto all floor level including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	339.06	90.00	Rupees Ninety and Paise Zero Only	Per square metre	30515.00
7	Steel work welded in built up sections (TATA/ SAIL/ Apollo/ JSW Make) in framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etcetra as required in gratings, door and window frames, guard bar, ladder, railings, brackets, gates and similar works complete upto all floor level including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	300.00	115.00	Rupees One Hundred Fifteen and Paise Zero Only	Per Kilogram	34500.00
8	Demolishing brick tile covering in terracing including stacking of serviceable material and disposal of unserviceable material including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	10.05	50.00	Rupees Fifty and Paise Zero Only	Per square metre	503.00
9	Providing and laying 600x600 mm (six hundred into six hundred millimetre) Full Body matt finished Double Charged Vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% (zero point zero eight percent) and conforming to IS: 15622. of Orient bell/ Kazania/ AGU/ RAK /Johnson & Johnson approved make, in all colours and shades, laid on 20mm (twenty millimetre) thick cement mortar 1:4 (one cement : four coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm(Three point three kilogramme per square metre) including grouting the joints with white and matching pigment etcetra complete in pattern finish approved by the Engineer-in-Charge upto all floor level including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	10.05	1250	Rupees One Thousand Three Hundred Fifty and Paise Zero Only	Per square metre	13568.00
Grand Total						292499.00


DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS 262459/-only
Rupees Two Lakhs Ninety Two Thousand Four Hundred Ninety Nine and Paise Zero Only

Condition

The work will be strictly executed as per MORD specifications

The Contractor will procure cement at their own level from Civil Supply Depot. after the approval of permit from the competent authority and other material from market as per Department specification/ Notification issued by the Additional Chief Secretary PW to the Govt. of HP vide No. PBW (B) C (17) 2/2012 dated 07 August 2018 & carriage will be born by the contractor.

The bills of all materials procured by the contractor and W/X form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill.


Executive Engineer,
Hamirpur Division,
✓ HPPWD, Hamirpur.

DRAFT SCHEDULE OF QUANTITY

Name Of Work:- Special repair to ECH Poly Clinic building at Hamirpur. (SH:- Providing and laying Interlocking paver block in leftout space in front side of building used as parking, U-Shape Drain along the road).

Estimated Cost:-Rs. 318541.00

Earnest Money:- Rs. 6400.00

Time Limit:- Two Months

Sr. No.	Description of Items	Qty.	Rate in		Unit	Amount
			Fig.	Words		
1	Excavation work by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms within all leads including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads and lifts ordinary rock and all kinds of soil including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	6.84	300.00	Rupees Three Hundred and Paise Zero Only	Per cubic metre	2052.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering 1:4:8 (one cement : four coarse sand : eight graded stone aggregate) 40mm (forty millimetre) nominal size graded stone aggregate for all works upto plinth level including the cost of centering and shuttering including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	4.76	4800.00	Rupees Four Thousand Eight Hundred and Paise Zero Only	Per cubic metre	22848.00
3	Providing and laying cement concrete 1:3:6 (One cement : three coarse sand : six graded stone aggregate) 20 mm (Twenty millimetre) nominal size in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etcetera including the cost of centering, shuttering and finishing as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.58	5200.00	Rupees Five Thousand Two Hundred and Paise Zero Only	Per cubic metre	8216.00
4	Cement concrete flooring 1:2:4 (One cement : two coarse sand : four graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etcetera complete as per direction of Engineer-in-Charge including entire carriage carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.85	350.00	Rupees Three Hundred Fifty and Paise Zero Only	Per square metre	998.00

Providing and laying factory made 60mm (Sixty millimetre) thick cement concrete paver block of M-30 (M-Thirty) grade with approved colour, design and pattern (NTC make ISI marked) chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etcetra of required strength, thickness and size/ shape, made by table vibratory method using PU mould, laid in required colour and pattern over 50mm thick (fifty millimetre) compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete all as per direction of Engineer-in-Charge including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals The rates are inclusive of octroi, royalty, maikana, toll tax, sale tax, GST or other taxes imposed by the Government	166.75	1400.00	Rupees One Thousand Four Hundred and Paise Zero Only	Per square metre	233450.00
Steel work welded in built up sections (TATA/ SAIL/ Apollo/ JSW Make) in framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etcetra as required in gratings, door and window frames, guard bar, ladder, railings, brackets, gates and similar works complete upto all floor level including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals The rates are inclusive of octroi, royalty, maikana, toll tax, sale tax, GST or other taxes imposed by the Government	443.28	115.00	Rupees One Hundred Fifteen and Paise Zero Only	Per Kilogram	50977.00
Grand Total					318541.00

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS 318541/-only
Rupees Three Lakhs Eighteen Thousand Five Hundred Forty One and Paise Zero Only

Condition

The work will be strictly executed as per MORD specifications.
The Contractor will procure cement at their own level from Civil Supply Depott. after the approval of permit from the competent authority and other material from market as per Department specification/ Notification issued by the Additional Chief Secretary PW to the Govt. of HP vide No. PBW (B) C (17) 2/2012 dated 07 August 2018 & carriage will be born by the contractor.
The bills of all materials procured by the contractor and W/X form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill.


Executive Engineer,
Hamirpur Division,
HPPWD, Hamirpur.

DRAFT SCHEDULE OF QUANTITY

Name Of Work:- Restoration of rain damages on Aghar Mehal road km 0/0 to 4/0. (SH:- construction of wire crates at RD/2/415 to 2/421 and filling at RD 2/393 to 2/421)

Estimated Cost:-Rs. 172540.00
Earnest Money:- Rs. 3500.00
Time Limit:- One Month

Sr. No.	Description of Items	Qty.	Rate in		Unit	Amount
			Fig.	Words		
1	Excavation work by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and raiming of bottoms within all leads including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads and lifts ordinary rock and all kinds of soil including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malakana, toll tax, sale tax, GST or other taxes imposed by the Government.	10.70	300.00	Rupees Three Hundred and Paise Zero Only	Per cubic metre	3210.00
2	Back filling behind abutment , wing walls and return walls complete as per drawings & MORD technical specification Clause 1204.3.8 granular material as per direction of Engineer-in-Charge including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malakana, toll tax, sale tax, GST or other taxes imposed by the Government.	105.00	850.00	Rupees Eight Hundred Fifty and Paise Zero Only	Per cubic metre	89250.00
3	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetres) dia G.I wire conforming to IS 280 and IS 4826 in 100mmx100mm (One hundred into one hundred millimetre) mesh (woven diagonally) including 10% (Ten percent) extra for laps and joints laid with stone boulders weighing not less than 25kg (Twenty five kilogramme) each as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malakana, toll tax, sale tax or other taxes imposed by the Government.	28.00	2850.00	Rupees Two Thousand Eight Hundred Sixty and Paise Zero Only	Per cubic metre	80080.00
	Total					

Condition

- The work will be strictly executed as per HPPWD specifications
- The contractor will procure cement at their own level from Civil Supply Depot. After the approval of permit from the competent authority and other material from market as per Department specification issued by the Addition Chief Secretary PW to the Govt. of HP vide No. PSW (B) C (17) 2/2012 dated 07 August 2016 and all other condition are liable & carriage will be born by the contractor
- The bills of all materials procured by the contractor M-form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS. 172540/-
Rupees One Lakh Seventy Two Thousand Five Hundred Forty and Paise Zero Only


 Executive Engineer,
 Hamirpur Division,
 HPPWD, Hamirpur

9/11/16

139
291 HMR

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on link road Harizan Basti Chiggar Km 0/0 to 0/180 (SH:- C/O retaining wall at RD 0/114 to 0/121.50) under MMGSY					Estimated Cost:-Rs.474409.00	
					Earnest Money:- Rs.9509.00	
					Time Limit:- One Month	
Sr. No.	Description of Items	Qty.	Rate in Fig.	Words	Unit	Amount
1	Excavation work by mechanical means (hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ransing of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soil in ordinary rock and Pick work and jumper work including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	25.54	300.00	Rupees Three Hundred and Paise Zero Only	Per cubic metre	7652.00
2	Providing and laying in position concrete of specified grade 1:5:10 (one cement, five coarse sand, ten graded stone aggregate) 40mm (forty millimetre) nominal size graded stone aggregate in retaining wall, breast wall, walls of any thickness and like structures excluding the cost of centering and shuttering including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	102.01	4500.00	Rupees Four Thousand Five Hundred and Paise Zero Only	Per cubic metre	459045.00
3	Providing and fixing Single socketed pipes 110mm (one hundred ten millimetre) dia of Supreme/Fendolax/Vedus make on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including joining with seal ring conforming to IS : 5382, leaving 10 mm (ten millimetre) gap for thermal expansion complete upto all floor level including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	23.80	290.00	Rupees Two Hundred Ninety and Paise Zero Only	Per Running Metre	6902.00
4	Providing and fixing Geo Textile membrane behind RCC and PCC retaining walls Ocean Non woven Geotextile 3mm (Three millimetre) thickness including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	5.16	155.00	Rupees One Hundred Fifty Five and Paise Zero Only	Per square metre	800.00
Total						474409.00

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS.474409/-

Rupees Four Lakhs Seventy Four Thousand Four Hundred Nine and Paise Zero Only

- The work will be strictly executed as per HPPWD specifications
- The contractor will procure cement at their own level from Civil Supply Depot. After the approval of permit from the competent authority and other material from market as per Department specification issued by the Additional Chief Secretary PW to the Govt. of HP vide No. PSW (B) C (17) 220/12 dated 07 August 2018 and all other condition are liable & carriage will be born by the contractor
- The bills of all materials procured by the contractor in form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill

Executive Engineer,
Haripur Division,
HPPWD, Haripur

✓

27 NOV

165 N
3.11

DRAFT SCHEDULE OF QUANTITY

Name Of Work:- Restoration of rain damages on Boundary wall and gate at Sr. Sec. School at Jalari Tehsil Nadaun
stt. Hamirpur.

Estimated Cost:-Rs. 457328.00

Earnest Money:- Rs. 9200.00

Time Limit:- One Month


Sr. No.	Description of Items	Qty.	Rate in		Unit	Amount
			Fig.	Words		
1	Excavation work by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms within all leads including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads and lifts ordinary rock and all kinds of soil including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	17.91	300.00	Rupees Three Hundred and Paise Zero Only	Per cubic metre	5373.00
2	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (seven point five) in super structure above plinth level up to all floor levels in all shapes and sizes with Cement mortar 1:6 (one cement: six coarse sand) including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	32.84	8800.00	Rupees Eight Thousand Eight Hundred and Paise Zero Only	Per cubic metre	288992.00
3	1:5 mm (fifteen millimetre) cement plaster on rough side of single or half brick wall of mix 1:6 (one cement: six coarse sand) upto all floor level including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	165.60	300.00	Rupees Three Hundred and Paise Zero Only	Per square metre	49680.00
4	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface (Asian/Nerolac/Dulux) complete including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	165.60	90.00	Rupees Ninety and Paise Zero Only	Per square metre	14904.00
5	Wall painting Two coats with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/litre (Fifty grams per litre) of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour complete including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	165.60	130.00	Rupees One Hundred Thirty and Paise Zero Only	Per square metre	21528.00
6	Providing and laying in position specified grade of reinforced cement concrete, 1:1.5:3 (one cement: one point five coarse sand: three graded stone aggregate 20 mm (twenty millimetre) nominal size) in Foundation footings bases of columns and the like and mass concrete excluding the cost of centering, shuttering, finishing and reinforcement upto plinth level including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.00	7200.00	Rupees Seven Thousand Two Hundred and Paise Zero Only	Per cubic metre	14400.00

	Steel reinforcement (TATA/SAIL / JINDAL PANTHER/ Shyam steel make) for reinforced cement concrete work including straightening, cutting, bending, placing in position and binding all complete work including cost of binding wire upto all floor level mild steel and medium tensile steel bars of grade Fe-500D (Five hundred) or more including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	199.80	95.00	Rupees Ninety Five and Paise Zero Only	Per Kilogram	18981.00
8	Structural steel work riveted, bolted or welded in built up sections, trusses, purlins, rafters, railings and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete (Apollo/Jai Bharat/Tata) including entire carriage of material with in all leads and lifts and as per drawings and technical specifications and the direction of Engineer-in-Charge including other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	378.00	115.00	Rupees One Hundred Fifteen and Paise Zero Only	Per kilogram	43470.00
	Grand Total					457328.00

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS 457328/- only
Rupees Four Lakhs Fifty Seven Thousand Three Hundred Twenty Eight and Paise Zero Only

Condition

- The work will be strictly executed as per MORD specifications
- The Contractor will procure cement at their own level from Civil Supply Depot. after the approval of permit from the competent authority and other material from market as per Department specification/ Notification issued by the Additional Chief Secretary PW to the Govt. of HP vide No. PBW (B) C (17) 2/2012 dated 07 August 2018 & carriage will be born by the contractor.
- The bills of all materials procured by the contractor and W/X form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill.


Executive Engineer,
Hamirpur Division,
HPPWD, Hamirpur.

136/296 H

136/296 H

DRAFT SCHEDULE OF QUANTITY

Name Of Work:- Construction of Residential Accommodation Type-IV Qtrs. 1 Nos. Type-III Qtrs. 4 Nos. and Type-II Qtrs. 12 Nos. of SV & ACB in Police Line Hamirpur at Dosarka. (SH:- C/o Retaining wall for approach road to SV & ACB residence and Police Station 0/015.10 to 0/022.70).						
Estimated Cost:-Rs. 425885.00 Earnest Money:- Rs.8600.00 Time Limit:- One Month						
Sr. No.	Description of items	Qty.	Fig.	Rate in Words	Unit	Amount
1	Excavation work by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms within all leads including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads and lifts ordinary rock and all kinds of soil including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	37.32	300.00	Rupees Three Hundred and Paise Zero Only	Per cubic metre	11196.00
2	Providing and laying in position cement concrete of specified grade 1:5:10 (one cement : five coarse sand : ten graded stone aggregate) 40mm (forty millimetre) nominal size graded stone aggregate in retaining wall, breast wall, walls of any thickness and like structures excluding the cost of centering and shuttering including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	102.60	4000.00	Rupees Four Thousand and Paise Zero Only	Per cubic metre	410400.00
3	Providing weep holes in brick masonry / Stone masonry / plain/reinforced concrete in retaining walls, breast walls and the like with 110mm (One hundred ten millimetre) dia PVC pipe Finolex/ Supreme having pressure not less than 4.00 Kg/Cm ² (four kilogramme) per centimetre square extending through the full width of the structure with slope of 1(V):20(H) (one vertical : twenty horizontal) towards drawing face complete including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	13.20	290.00	Rupees Two Hundred Ninety and Paise Zero Only	Per Running metre	3828.00
4	Providing and fixing Geo-Textile membrane behind RCC and PCC retaining walls Ocean Non woven Geotextile 3mm (Three millimetre) thickness including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	2.67	165.00	Rupees One Hundred Sixty Five and Paise Zero Only	Per square metre	441.00
Total						425885.00

Condition

- The work will be strictly executed as per HPPWD specifications
- The contractor will procure cement at their own level from Civil Supply Depot. After the approval of permit from the competent authority and other material from market as per Department specification issued by the Additional Chief Secretary PW to the Govt. of HP vide No. P&W (B) C (17) 2/2012 dated 07 August 2016 and all other condition are liable & carriage will be born by the contractor
- The bills of all materials procured by the contractor M-form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS. 425885/-
Rupees Four Lakhs Twenty Five Thousand Eight Hundred Sixty Five and Paise Zero Only


Executive Engineer,
Hamirpur Division,
HPPWD, Hamirpur

DRAFT SCHEDULE OF QUANTITY

Name Of Work:- Repair and maintenance of various bridges under HPPWD Hamirpur Sub Division. (SH:- (i) Repair of bridge of Masyana to Bhatwara road at Rd 1/900. (ii) Repair of bridge on Sasan Baleta road at Rd 5/0).										Estimated Cost:-Rs. 498194.00		Earnest Money:- Rs. 10000.00		Time Limit:- One Month	
Sr. No.	Description of Items	Qty.	Fig.	Rate in		Unit	Amount								
				Words											
1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade on old work (one or more coats) including a coat of approved steel primer but excluding a coat of mordant solution (Asian/Nerolac/ICI Dulux) complete including entire carriage of material with in all leads, lifts, drawings, technical specifications as per direction by Engineer-in-Charge including other incidentals The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	209.21	90.00	Rupees Ninety and Paise Zero Only		Per square metre	18829.00								
2	Providing and applying tack coat using bitumen emulsion conforming to IS.8887, using emulsion pressure distributor including preparing the surface and cleaning with mechanical broom. With medium setting bitumen emulsion -On W.B.M / W.M.M. @ 0.4kg/sqm (Zero point four kilogramme per square metre) including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	407.97	25.00	Rupees Twenty Five and Paise Zero Only		Per square metre	10199.00								
3	Providing and laying 25 mm (Twenty five millimetre) thick bitumen mastic wearing course (as per specifications) with industrial bitumen of grade 85/25 (Eighty oblique twenty five) conforming to IS : 702, prepared by using mastic cooker and laid to required level and slope, including providing antiskid surface with bitumen precoated fine grained hard stone chipping of approved size at the rate of 0.005 cum per 10 sqm (Zero point zero five cubic metre per ten square metre) and at approximate spacing of 10 cm (Ten centimetre) centre to centre in both directions, pressed into surface protruding 1 mm to 4 mm (One millimetre to four millimetre) over mastic surface, including cleaning the surface, removal of debris etcetera all complete. (Considering bitumen using 10.2% (Ten point two percent) as per MORTH specification) including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government	407.97	1150.00	Rupees One Thousand One Hundred Fifty and Paise Zero Only		Per square metre	469168.00								
Total							498194.00								
Condition															

1 The work will be strictly executed as per HPPWD specifications

2 The contractor will procure cement/steel at their own level from Civil Supply Depot. After the approval of permit from the competent authority and other material from market as per Department specification issued by the Addition Chief Secretary P.W to the Govt. of HP vide No. PBW (B) C (17) 2/2012 dated 07 August 2018 and all other condition are liable & carriage will be born by the contractor.

3 The bills of all materials procured by the contractor M-form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill.

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS.498605/- only
Rupees Four Lakhs Ninety Eight Thousand One Hundred Ninety Four and Paise Zero Only


Executive Engineer,
Hamirpur Division,
HPPWD, Hamirpur

DRAFT SCHEDULE OF QUANTITY

Name Of Work:- C/o link road from Jatheri to Balh Bhalana in GP Sasan km 0/0 to 1/0. (SH:- Providing and laying WMM and complete Metalling/Tarring in km 0/0 to 0/300).

Estimated Cost:-Rs. 497755.00

Earnest Money:- Rs. 10000.00

Time Limit:- One Month

Sr. No.	Description of Items	Qty.	Fig.	Rate in		Unit	Amount
				Words			
1	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) (fifty three millimetres to zero point seven five millimetres) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all levels & lifts, laying in uniform layers with mechanical paver finisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne (eight to ten tonne) capacity to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge as per direction of Engineer-in-Charge including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	96.07	1900.00	Rupees One Thousand Nine Hundred and Paise Zero Only		Per cubic metre	182533.00
2	Providing and applying tack coat using hot straight run bitumen of grade VG - 10 (Viscosity Grade Ten) including heating the bitumen, spraying the bitumen with mechanically operated spray unit fitted on bitumen boiler, cleaning and preparing the existing road surface as per specifications On W.B.M. @ 0.75 Kg / sqm (zero point seven five kilogramme per squaremetre) including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	137.25	85.00	Rs Forty six & paise sixty five only.		Per Square meter	11666.00
3	Providing and applying tack coat using bitumen emulsion conforming to IS-8847 using emulsion pressure distributor including preparing the surface and cleaning with mechanical broom. With medium setting bitumen emulsion-On W.B.M / W.M.M. @ 0.4kg/sqm (Zero point four kilogramme per square metre) including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	137.25	25.00	Rupees Twenty Five and Paise Zero Only		Per square metre	3431.00
4	Providing and laying Bituminous concrete 30mm (Thirty millimetre) compacted thickness with bitumen of grade VG-30 (VISCOSITY GRADE-THIRTY) @ 5.5% (Five point five percent) (percentage by weight of total mix) and lime filler @ 2% (Two percent) (percentage by weight of Aggregate) using crushed stone aggregates of specified grading, premixed with bituminous binder and filler prepared in batch Type Hot Mix Plant of 100-120 (Hundred two One hundred twenty) TPH capacity, transporting the hot mix to work site by tippers, laying with paver finisher equipped with electronic sensor to the required grade, level and alignment and rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction and density as per specification complete and as per directions of Engineer-in-Charge including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	24.01	12500.00	Rupees Twelve Thousand Five Hundred and Paise Zero Only		Per cubic metre	300125.00
Grand Total							497755.00

Condition

The work will be strictly executed as per MCRD specifications.
The contractor will procure Cement from Civil Supply Depot, VG-30/VG-10 & Emulsion RS-1 & SS-1 from HPCL/IOCL/BPCL at their own level after the approval of permit from the competent authority and other material from market as per Department specification issued by the Additional Chief Secretary PW to the Govt. of HP vide No: PBW (B) C (17) 202012 dated 07 August 2018 and all other condition are liable & carriage will be born by the contractor.
The bills of all materials procured by the contractor and Wix form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS. 497955/-only
Rupees Four Lakhs Ninety Seven Thousand Seven Hundred Fifty Five and Paise Zero Only


Executive Engineer,
Hamirpur Division,
HPPWD, Hamirpur.

DRAFT SCHEDULE OF QUANTITY

Name Of Work:- Restoration of rain damages on link road Patta to Jalari km 0/0 to 4/650. (SH:- Construction of U-shape drain at RD 1/375 to 1/508 & V-Shape drain at RD 1/030 to 1/060 and 1/180 to 1/375).

Estimated Cost:-Rs. 498194.00

Earnest Money:- Rs.10000.00

Time Limit:- One Month

Sr. No.	Description of Items	Qty.	Fig.	Words	Unit	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator/breaker)/manual means over areas (exceeding 30 cm (Thirty centimetres) in depth, 1.5 m (One point five metre) in width as well as 10 sqm(Ten square metre) on plan) including getting out and disposal of excavated earth in all leads and lifts in ordinary rock and all kinds of soil including chiseling of hard rocks where blasting is prohibited including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	123.58	300.00	Rupees Three Hundred and Paise Zero Only	Per cubic metre	37074.00
2	Providing and laying cement concrete 1:3:6 (One cement : three coarse sand : six graded stone aggregate) 20 mm (Twenty millimetre) nominal size in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etcetera including the cost of centering, shuttering and finishing as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	83.84	5500.00	Rupees Five Thousand Five Hundred and Paise Zero Only	Per cubic metre	461120.00
Total						498194.00

Condition

1 The work will be strictly executed as per HPPWD specifications

2 The contractor will procure cement at their own level from Civil Supply Depot. After the approval of permit from the competent authority and other material from market as per Department specification issued by the Addition Chief Secretary PW to the Govt. of HP vide No. PBW (B) C (17) 2/2012 dated 07 August 2018 and all other condition are table & carriage will be born by the contractor

3 The bills of all materials procured by the contractor M-form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS. 498194/-
Rupees Four Lakhs Ninety Eight Thousand One Hundred Ninety Four and Paise Zero Only


 Executive Engineer,
 Hamirpur Division,
 HPPWD, Hamirpur.

DRAFT SCHEDULE OF QUANTITY

Name Of Work:- Restoration of rain damages on link road Patta to Jalari km 0/0 to 4/650. (SH:- Construction of U-shape drain at RD 1/508 to 1/641 & V-Shape drain at RD 1/641 to 1/868).

Estimated Cost:-Rs. 499012.00
Earnest Money:- Rs.10000.00
Time Limit:- One Month


Sr. No.	Description of Items	Qty.	Fig.	Rate in		Unit	Amount
				Words			
1	Earth work in excavation by mechanical means (Hydraulic excavator/breaker)/manual means over areas (exceeding 30 cm (Thirty centimetres) in depth, 1.5 m (One point five metre) in width as well as 10 sqm(Ten square metre) on plan) including getting out and disposal of excavated earth in all leads and lifts in ordinary rock and all kinds of soil including chiseling of hard rocks where blasting is prohibited including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	123.74	300.00	Rupees Three Hundred and Paise Zero Only		Per cubic metre	37122.00
2	Providing and laying cement concrete 1:3:6 (One cement : three coarse sand : six graded stone aggregate) 20 mm (Twenty millimetre) nominal size in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or facing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, filets, sunken floor etcetera including the cost of centering, shuttering and finishing as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	83.98	5500.00	Rupees Five Thousand Five Hundred and Paise Zero Only		Per cubic metre	461890.00
Total							499012.00

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS. 499012/-

Rupees Four Lakhs Ninety Nine Thousand Twelve and Paise Zero Only

Condition

- The work will be strictly executed as per HPPWD specifications
- The contractor will procure cement at their own level from Civil Supply Depot. After the approval of permit from the competent authority and other material from market as per Department specification issued by the Addition Chief Secretary PW to the Govt. of HP vide No. PBW (B) C (17) 2/2012 dated 07 August 2018 and all other condition are liable & carriage will be born by the contractor.
- The bills of all materials procured by the contractor M-form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill


Executive Engineer,
Hamirpur Division,
HPPWD, Hamirpur.