



Office of
Executive Engineer B&R Division HP.PWD. Joginder Nagar
Himachal Pradesh Public Works Department, Mandi-175015
Phone & Fax No. 01908-222033 E-Mail:- ee-jog-hp@nic.in

"NOTICE INVITING TENDER"

Sealed item rate tender for the following works are hereby invited by the Executive Engineer, B&R Division HP.PWD., Joginder Nagar District Mandi (H.P.) from the eligible contractors of the appropriate class registered in HP.PWD. as per revised enlistment rules so as to reach in the office of under signed ON 18-12-2023 up to 11:30 A.M. and will be opened on the same day at (12:00 noon) in the presence of intending contractors. The tender application will be received in this office on 15-12-2023 up to 10.00 A.M. to 12:30 P.M. and tender form can be had from this office on 16-12-2023 from 2.00 P.M. to 5.00 P.M. The earnest money as shown against each in the shape of F.D.R. of any bank in Himachal Pradesh duly pledged in the name of the under signed must accompany with each tender. The tender form will be issued to contractor giving proof of enlistment, GST. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors in the office of the under signed on any working day during the office hours.

Sr. No.	Name of work	Amount put to tender/ Estimated cost	Earnest Money	Cost of tender form	Eligible Class of Contractor	Time
1	Construction of Samudayak Bhawan SC Bsti Dhelu Muhal G.P. Dhelu under Deposit (SH:- Balance work of Samudayak Bhawan).	Rs.1,60,570/-	Rs. 3,200/-	Rs.350/-	Class "D"	Three Months
2	Construction of Galu Bhatwari Lahla Malan Nakehar Kangwan road km. 0/00 to 5/00 under SCSP (SH:- Construction of U-Shape drain in km. 0/675 to 0/735).	Rs. 94,271/-	Rs.1,900/-	Rs. 350/-	Class "D"	Two Months
3	Construction of road from Kuthera Kurati to Banwar i/c Metalling and Tarring km. 0/00 to 4/00 (SH:- Providing and laying WBM G-I at km. 2/070 to 0/0165).	Rs.86,797 /-	Rs. 1,700/-	Rs.350/-	Class "D"	Three months
4	Special repair to State Level Revenue Training Institute at Joginder Nagar Distt. Mandi (H.P.) (SH:- Painting work & W.S. & S.I. work repair of window on girls hostel 40 Nos. Trainee) Under Deposit).	Rs. 4,23,771/-	Rs. 8,500/-	Rs. 350/-	Class "D"	Three Months
5	Special repair to State Level Revenue Training Institute at Joginder Nagar Distt. Mandi (H.P.) (SH:- Providing Painting work/P/F GI Metal Ceiling to Administrative Block)	Rs. 3,55,316/-	Rs. 7,100/-	Rs. 350/-	Class "D"	Three Months
6	Restoration of Damages due to OFC eable on Joignder Nagar Sarkaghat Ghumarwin road km. 0/00 to 34/300 (SH:- C/O Breast wall to protect Radha Swami Satsang Bhawan at km. 1/540 to 1/547).	Rs. 88,714/-	Rs.1,800/-	Rs.350/-	Class "D"	Two months
7	Restoration of Damages due to OFC eable on Joignder Nagar Sarkaghat Ghumarwin road km. 0/00 to 34/300 (SH:- C/O Breast wall to protect Radha Swami Satsang Bhawan at km. 1/530 to 1/538).	Rs. 99,935/-	Rs.2,000/-	Rs.350/-	Class "D"	Two months
8	Construction of Jeepable link road from Bella to Shamshan Ghat Gharli km. 0/00 to 0/700 in G.P. Bhadyara Bhulla under Deposit (SH:- Formation cutting in km. 0/700 to 0/810).	Rs. 1,76,992/-	Rs.3,500/-	Rs.350/-	Class "D"	Three months
9	Restoration of damages due to laying of OFC on Joginder Nagar Sarkaghat Ghumarwin road km. 0/0 to 21/00 (SH:- Construction of Breast wall at km. 13/290 to 13/300).	Rs. 1,30,362/-	Rs.2,600/-	Rs.350/-	Class "D"	Three months
10	Restoration of damages due to laying of OFC on Gagal Simus road km. 0/00 to 5/00 (SH:- Construction of Taining wall at km. 0/855 to 0/860).	Rs. 1,42,834/-	Rs.2,900/-	Rs.350/-	Class "D"	Three months
11	Restoration of damages due to laying of OFC on Jogidner Nagar Sarkaghat Ghumarwin road km. 0/00 to 34/300 (SH:- C/O U-Shape drain in km. 0/523 to 0/583).	Rs. 93,987/-	Rs.1,900/-	Rs.350/-	Class "D"	Two Months
12	Construction of Link road from Joginder Nagar Sarkaghat Ghumarwin road upto Nag Joad via Kufridhar upper Samohli G.P. Bulha Bhadyara (Under MPLAD Rajya Sabha)(SH:- C/O Retaining wall at km. 0/240 to 0/255).	Rs. 1,62,692/-	Rs.3,300/-	Rs.350/-	Class "D"	Three months
13	Construction of link road from Joginder Nagar Sarkaghat Ghumarwin road upto Naag Joad via Kufridhar upper samohli G.P. Bulha Bhadyara (Under MPLAD Rajya Sabha) (SH:- C/O Retaining wall at km. 0/560 to 0/570).	Rs. 1,77,242/-	Rs.3,500/-	Rs.350/-	Class "D"	Three months
14	Construction of Road Se Basti Zim Zima to Upper Zim Zima G.P. Zim Zima under deposit (SH:- Construction of Retaining/edge wall at km. 0/005 to 0/010 and Cement Concrete Pavement at km. 0/00 to 0/040) (Under MPLAD Rajya Sabha).	Rs. 1,58,453/-	Rs.3,200/-	Rs.350/-	Class "D"	Three months

15	Restoration of Damages due to Laying of OFC on Bajinath Lad Bharol Kandapattan road km. 0/00 to 46/0 (SH:- Construction of 900mm dia Hume Pipe Culvert alongwith wing wall at km. 12/365).	Rs. 4,13,501/-	Rs.8,300/-	Rs.350/-	Class "D"	Three Months
16	Construction of link road from Joginder Nagar Sarkaghat Ghumarwin road upto Naag Joad via Kufridhar upper Samohli G.P. Bulha Bhadyara (Under MPLAD Rajya Sabha) (SH:- C/O Retaining wall at km. 0/440 to 0/443.50).	Rs. 83,672/-	Rs.1,700/-	Rs.350/-	Class "D"	Two Months
17	Construction of Cement Concrete pavement Link road to Mata Kanya Devi Mandir G.P. Vata Ri Bihun under Deposit (SH:- Providing and laying Kharanja Stone Soling & Cement Concrete pavement at km. 0/00 to 0/027).	Rs.85,224/-	Rs.1,700/-	Rs.350/-	Class "D"	Two Months
18	Construction of Cement Concrete pavement Link road to Mata Kanya Devi Mandir G.P. Vata Ri Bihun under Deposit (SH:- Providing and laying Kharanja Stone Soling & Cement Concrete pavement at km. 0/28 to 0/055).	Rs.85,224/-	Rs.1,700/-	Rs.350/-	Class "D"	Two Months
19	Construction of various road under Joginder Nagar Sub Division (Harabag Section) under Deposit (SH:- Extension of 600mm dia hume pipe culvert at km. 1/530, C/O Retaining wall at km. 1/528 to 12/535.50 & Construction of U-shape drain at km. 1/525 to 1/600 on Shanar Harabag Road).	Rs.2,60,380/-	Rs.5,200/-	Rs.350/-	Class "D"	Three Months
20	Construction of road Mokshdham Siyun Banader in GP Maman (SH:- Formation cutting in km. 0/000 to 0/120).	Rs.89,299/-	Rs.1,800/-	Rs.350/-	Class "D"	Three Months
21	Construction of road Mokshdham Siyun Banader in G.P. Maman (SH:- Formation cutting in km. 0/120 to 0/165).	Rs.82,816/-	Rs.1,700/-	Rs.350/-	Class "D"	Three Months
22	Construction of link road Batolu to Kharon Under Deposit (SH:- Removal of formation Deficiency at km. 0/100 to 0/0135).	Rs.82,432/-	Rs.1,600/-	Rs.350/-	Class "D"	Two Months
23	Balance work construction of Additional Accommodation for Govt. High School Building at Khaddar Tehsil Lad Bharol Distt. Mandi (H.P.) (SH:- Providing and Fixing angle Iron Stair).	Rs.37,646/-	Rs.800/-	Rs.350/-	Class "D"	One month
24	A/R & M/O to various Non Residential Buildings under Joginder Nagar Division HP PWD, Joginder Nagar (SH:- Construction of Boundary wall at RD. 0/00 to 0/030.45 on Section office Ladruhin (Dohag).	Rs.96,233/-	Rs.1,900/-	Rs.350/-	Class "D"	Two months
25	A/R & M/O to various Non Residential Buildings under Joginder Nagar Division HP PWD, Joginder Nagar (SH:- Dismantling doors, windows and Providing & fixing aluminum work for door & window etc. in HP PWD, Rest House at Joginder Nagar).	Rs.4,97,764/-	Rs.10,000/-	Rs.350/-	Class "D"	Three months
26	Restoration of damages due to laying of OFC on Ahju Basai road km. 0/00 to 12/00 (SH:- Purchase of Computer, Printer and UPS for Chauntra Section).	Rs.92,292/-	Rs.1,800/-	Rs.350/-	Class "D"	Two Months
27	Restoration of damages due to laying of OFC on Joginder Nagar Sarkaghat Ghumarwin road (Makriri Section) (SH:- Hiring of excavator cum loader for removal of slips, dressing of berms, clearing of road side drains, debris and C/o road side katcha drains etc).	Rs. 99,060/-	Rs.2,000/-	Rs. 350/-	Class "D"	Two Months
28	Restoration of damages due to laying of OFC on Joginder Nagar Sarkaghat Ghumarwin road (Makriri Section) (SH:- Hiring of Tipper for shifting and carriage of various type of materials etc.	Rs. 99,000/-	Rs.2,000/-	Rs. 350/-	Class "D"	Two Months
29	Restoration of damages due to laying of OFC on Joginder Nagar Sarkaghat Ghumarwin road (Makriri Section) (SH:- Hiring of excavator cum loader for removal of slips, dressing of berms, clearing of road side drains, debris and C/o road side katcha drains etc).	Rs. 99,060/-	Rs. 2,000/-	Rs. 350/-	Class "D"	Two months
30	Restoration of damages due to laying of OFC on Joginder Nagar Sarkaghat Ghumarwin road (Makriri Section) (SH:- Hiring of excavator cum loader for removal of slips, dressing of berms, clearing of road side drains, debris and C/o road side katcha drains etc).	Rs. 99,060/-	Rs. 2,000/-	Rs. 350/-	Class "D"	Two months
31	A/R & M/O Chauntra to Lower Chauntra road km. 0/00 to 2/200 (SH:- Providing and laying Granular Sub Base on both side berms at km. 0/100 to 0/570).	Rs. 98,976/-	Rs.2,000/-	Rs.350/-	Class "D"	Two months
32	A/R & M/O on various Non Residential Buildings Under HP PWD Division Joginder Nagar (SH:- Supplying of various Office articles for Division office HP PWD Joginder Nagar	Rs. 98,527/-	Rs.2,000/-	Rs.350/-	Class "D"	Two months

33	Construction of Ambulance road Jhamehar Muhai in G.P. Dhar km. 0/00 to 0/350 Under MPLAD Cement (SH:- Providing and laying Khairanja Stone Soling & Cement concrete pavement at km. 0/00 to 0/65).	Rs. 1,68,411/-	Rs. 3,400/-	Rs. 350/-	Class "D"	Three Months
34	Restoration of damages due to laying of O/FC on Baljnath Lad Bhrol Kandapattan road (Tullah Section) (SH:- Hiring of excavator cum loader for removal of slips, dressing of berms, clearing of road side drains, debris and C/O road side katcha drains etc.).	Rs. 99,060/-	Rs. 2,000/-	Rs. 350/-	Class "D"	Two Months
35	Restoration of Damages due to laying of OFC on Ahju Bashai Road km. 0/00 to 19/200 (SH:- C/O Retaining wall at km. 5/625 to 5/632.80)	Rs. 98,770/-	Rs. 2,000/-	Rs. 350/-	Class "D"	Two Months
36	Restoration of Damages due to laying of OFC on Ahju Bashai Road km. 0/00 to 19/200 (SH:- C/O Retaining wall at km. 5/670 to 5/677)	Rs. 62,988/-	Rs. 1,300/-	Rs. 350/-	Class "D"	Two Months
37	Restoration of Makchhyal Ropari Trembali road km. 0/00 to 10/00 (SH:- Providing and laying Cement concrete pavement at km. 5/405 to 5/455 & 5/525 to 5/575).	Rs. 2,70,040/-	Rs. 5,400/-	Rs. 350/-	Class "D"	Three Months
38	Construction of road from Panjalag to Harizan Bati Katoun via Nichala Panjalag km. 0/0 to 2/0 under SCSP (SH:- Providing and laying Cement concrete pavement at km. 1/088 to 1/140).	Rs. 1,48,201/-	Rs. 3,000/-	Rs. 350/-	Class "D"	Three Months

1. Certified that tender of above works are being called of emergent nature in exigency of public interest

Terms and conditions:-

1. The contractor should produce a copy of enlistment / renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/Firm shall have his registration and GST No, the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer B&R Division HPPWD., Joginder Nagar & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
5. No tender form will be issued to the contractor without producing the work done certificate from the Executive Engineer concerned.
6. The contractor/firms are requested to insert the rate of each item in words as well as in figures falling which XEN reserves the right to accept/reject any tender without assigning any reason at any stage.
7. The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar.
District Mandi (HP) for on behalf of
Governor of Himachal Pradesh
Ph. 01908-222033

No. PW-JND-B&R-EA-I/NIT/Press/2023-24- 23910-23957 Dated:- 7-11-2023.

1. Copy to the F.C. Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
2. The Engineer-in-Chief, HPPWD, Shimla.
3. The Chief Engineer (MZ), HPPWD, Mandi.
4. The Superintending Engineer, Joginder Nagar Circle HPPWD, Joginder Nagar.
5. All the Assistant Engineer working under this Division.
6. All the Contractor working under this Division.
7. Drawing Branch in this office.
8. Notice Board.
9. The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar.

SCHEDULE OF QUANTITY

Name of work : Construction of Samudayak Bhawan SC Basti Dhehu Muhaf GP Dhehu under Deposit (SH: Balance work of Samudayak Bhawan)					Estimate Cost: 1,60,570.00 Earnest Money : 3,200.00 Time Limit : Three Months		
Sl. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Providing and fixing panelled glazed or panelled and glazed shutter for doors windows and eleventh story windows including black enameled iron butt hinges with necessary screws 35 mm (thirty five millimeter) thick in 2nd class deodar wood. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	5.92	Per Square metre				
2	Providing and fixing 300x16mm (Three hundred by sixteen millimeter) size anodized aluminium sliding door bolt anodized colour and shade with bolts and nuts screws etc. complete as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.00	Each				
3	Providing and fixing 300x10mm (Three hundred by ten millimeter) size aluminium tower bolts (borel type) anodized trans parent or dyed to required shade and colour with screws etc. complete as per PWD specification complete in all respect including haulage of material in all leads and lifts by all modes of transportation and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.00	Each				
4	Providing and fixing 100x10mm (One hundred by ten millimeter) size aluminium tower bolts (borel type) anodized trans parent or dyed to required shade and colour with screws etc. complete as per PWD specification complete in all respect including haulage of material in all leads and lifts by all modes of transportation and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	18.00	Each				
5	Providing and fixing anodized aluminium handle anodized transparent or dyed to required shade or colour with necessary screws etcetera complete. 12.5mm (one hundred twenty five millimeter) size as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	2.00	Each				

Sl. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
6	Providing and fixing anodized aluminum handle anodized transparent or dyed to required shade or colour with necessary screws etcetera complete. 100 mm (one hundred millimeter) size as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	12.00	Each			
7	15mm (Fifteen millimeter) cement plaster in single coat on the rough side in cement mortar 1:6 (one Cement isto six Sand). of brick concrete stone walls for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and or rounded angles not exceeding 80mm in girth and finished even and smooth. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	63.64	Per Square Metre			
8	6mm (six millimeter) cement plaster 1:3 (one cement isto three sand) in ceiling complete including curing complete as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	33.74	Per Square Metre			
9	Providing and laying cement concrete 1:5:10 (one Cement isto five Sand isto ten graded stone aggregate 40mm (forty millimeter) nominal size) and curing complete excluding cost of cementing and shuttering in foundation and plinth. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	2.27	Per cubic metre			
10	Providing and laying vitrified floor tiles of size 600x600 mm (six hundred by six hundred millimeter) (thickness to be specified by the manufacturer) with water absorption less than 0.08% (zero point zero eight percent) and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm (twenty millimeter) thick cement mortar 1:4 (one cement isto four coarse sand), jointing with grey cement slurry at 3.3 kg/sqm (three point three kilogramme per square meter) including grouting the joints with white cement and matching pigments etc., complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	24.60	Per Square Metre			

Description of work

	No. or Qty.	Unit	Rate		AMOUNT Rs. P
			Figures	Words	
11 Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level Cement mortar 1:4 (one cement to four coarse sand). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	2.81	Per cubic metre			
12 Providing and applying white cement based putty of average thickness 1 mm. (one millimeter) of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete complete in all respect including haulage of material in all leads and lifts by all modes of transportation and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	97.38	Per Square Metre			
13 Distempering with oil bound washable distemper of approved brand and manufacture on New work (two or more coats) over and including water thinable priming coat with cement primer to give an even shade complete including carriage of materials within all leads, lift and other incidental charges. The rate is inclusive all taxes levy by the government time to time excluding GST.	97.38	Per Square Meter			
14 Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied at 0.00 ltr 10 sqm (zero point nine liter per ten square meter) over an under coat of primer applied at 0.75 ltr 10 sqm (zero point seven five liter per ten square meter) of approved brand and manufacture complete in all respect including haulage of material in all leads and lifts by all modes of transportation and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	8.92	Per Square Metre			
15 Making plinth protection 50mm (fifty millimeter) thick of cement concrete 1:3:6 (one cement isto three coarse sand isto six graded stone aggregate 20 mm twenty millimeter) nominal size) over 75mm (seventy five millimeter) thick bed of dry brick ballast 40 mm (fourty millimeter) nominal size, well rammed and consolidated and grouted with fine sand, including necessary excavation, levelling & dressing & finishing the top snowth including carriage of materials within all leads, lifts and other incidental charges. The rate is inclusive all taxes levy by the government time to time excluding GST.	6.94	Per square metre			

Description of work		No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
16	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand) : 3 graded stone aggregate 20 mm nominal size), complete in all respect including haulage of material in all leads and lifts by all modes of transportation and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	3.39	Per cubic metre			
17	Providing mild steel/For steel reinforcement for R.C.C. work including bending, binding and placing in position complete upto floor two level as per drawing and technical specification as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	203.40	Per Kilogramme			
Total						


 Executive Engineer
 B & R Division H.P.P.W.D.
 Jodhpur Nagard

SCHEDULE OF QUANTITY

Name of Work : Construction of Galu Bhatwari Lahla Malan Nakehar Kangwan road km 0/00 to 5/00 Under SCSP (Sub Head:- Construction of U Shape Darin in km 0/675 to 0/735)				Estimate Cost: 94,271.00 Earnest Money: 1,900.00 Time Limit : Two Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	23.40	Per cubic metre			
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete Grade M-10 complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time excluding GST.	13.50	Per cubic metre			
	Total					

Executive Engineer

B & R Division HP.PWD,

Joginder Nagar,

SCHEDULE OF QUANTITY

Name of Work : Construction of road from Kuthera kurati to Banwar i/c Metalling and tarring km 0/00 to 4/00 (Sub Head:- Providing and laying WBM G-1 at km 2/070 to 0/165)					Estimate Cost: 86,797.00 Earnest Money: 1,700.00 Time Limit : Two Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Preparation of sub grade by dressing to camber (Earth work for cutting involved for sub grade to paid for separately depending upon the classification of soil completed as per HPPWD specifications complete within all leads, lifts, carriage of material and other incidentals charges and to the entire satisfaction and direction of Engineer - in- Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	319.20	Per square metre			
2	Consolidation of sub grade with road roller including making good the undulation etc. with earth or quarry soil etc. and rerolling the sub grade complete as per HPPWD Specifications complete within all leads, lifts, carriage of material and other incidentals charges and to the entire satisfaction and direction of Engineer - in- Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	319.20	Per square metre			
3	Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness . hand packing. rolling with three wheel 80-100 kN (eighty-hundred kilo newton) static roller in stages to proper grade and camber applying and brooming , stone screening / binding materials to fillup the interstics of course aggregate watering and compacting to the required density Grading -1 (one) as per technical specification clause -405 complete within all leads , lifts, carriage of material and other incidentals charges and to the entire satisfaction and direction of Engineer - in- Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	31.92	Per cubic metre			
Total						


 B & R Division HP.PWD.
 Jodhpur

SCHEDULE OF QUANTITY

Name of Work : Special Repair to State Level Revenue Training Institute at Joginder Nagar Distt. Mandi (HP) (S.H. : Painting work & WS & SI work , Repair of Windows on Girls Hostel 40 Nos. Trainee) Under Deposit					Estimate Cost: Earnest Money: Time Limit :			4,23,771.00 8,500.00 Three Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate		Figures	Words	AMOUNT Rs. P
1	Painting One coat (excluding priming coat.) on previously painted steel & other metal surfaces with readymixed paint,brushing oil, grease to give an even shade including cleaning the surface of all dirt,dust and other foreign matter With white readymixed paint.The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.The rate is inclusive all taxes levy by the government time to time excluding GST.	653.12	Per square metre					
2	Painting two coats (excluding priming coat)on previously painted wood and wood based surfaces with enamel paint to given and even shade including cleaning of all dirt,dust and other foreign matter sand papering and stopping With white enamel paint The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1086.25	Per square metre					
3	Wall painting (two coats) with plastic emulsion paint of approved brand and manufacture on undecorated wall surfaces to give an even shade including thoroughly brushing the surface free from mortar droppings and other foreign matter and sand papered smooth including applying of putty as required for making the surface.The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1089.38	Per square metre					
4	Distemping (Two coats) with oil bound washable distemper of approved brand and manufacture and of required shade on decorated wall surfaces to give an even shade over and including a priming coat with distemper primer of approved brand and manufacture after thoroughly brushing the surface free from mortar droppings and other foreign matter and also including preparing the surface even and sand papered smooth. Priming coat with distemper primer.The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	641.62	Per square metre					

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
5	Finishing wall with weather proof exterior grade emulsion of approved design (Apexultima) or its equivalent on undecorated wall surfaces (three coats) to give an even shade and final after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc including sand paper smooth complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	237.27	Per square metre			
6	Painting two or more coats on G.I Sheets with readymix paint red shade of approved brand and manufacture on new work to give an even shade. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	360.23	Per square metre			
7	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, 15 mm (fifteen millimeter) nominal outer dia Pipes having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	322.70	Per Running metre			
8	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, 20 mm (twenty millimeter) nominal outer dia Pipes having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	180.00	Per Running metre			
9	Providing and fixing controlled flush, 10 litre (full flush) capacity white low level cistern made of vitreous china with all fittings complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	17.00	Each			
10	Providing and fixing aluminium tower bolts, 300x 10mm (three hundred by ten millimeter) ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	100.00	Each			

Description of work		No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
Providing and fixing ISI marked M.S. pressed butt hinges bright finished with necessary screws etc. complete 100x58x1.90 mm (One hundred by fifty eight by one point nine millimeter) The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.		50.00	Each			
12 Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 (three) ply veneering with vertical grains or cross bands and face veneers on both faces of shutters 25 (twenty five) mm thick (for cupboard) including ISI marked nickel plated bright finished M.S. piano hinges with necessary screws. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.		2.40	Per square metre			
13 Providing and fixing 35 (thirty five) mm thick panelled or panelled and glazed shutters for doors, windows and clerestory, windows fixing with butt hinges of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per direction of Engineer-In-Charge. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.		3.71	Per square metre			
Total						


 Executive Engineer
 B & R Division HP.PWD.
 Joginder Nigam

SCHEDULE OF QUANTITY

Name of Work : Special Repair to State Level Revenue Training Institute at Joginder Nagar Distt. Mandi (HP) (S.H. : Providing Painting work , Providing and Fixing GI-Metal Celling to Administrative Block) Under Deposit					Estimate Cost:	3,55,316.00
					Earnest Money:	7,100.00
					Time Limit :	Three Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT
				Figures	Words	
1	Applying Brush finished of Altek harmony of NCI altek and secular exterior paint containing pure acrylic binder of international standard good quality additives colour pigments with chemicals to resist algae and funds to be applied in two coats directly on clean wall overall a coat of Altek primer or equivalent of approved shade to give final matter finish to the surface complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	595.35	Per square metre			
2	Distempering (Two coats) with oil bound washable distemper of approved brand and manufacture and of required shade on decorated wall surfaces to give an even shade over and including a priming coat with distemper primer of approved brand and manufacture after thoroughly brushing the surface free from mortar droppings and other foreign matter and also including preparing the surface even and sand papered smooth. Priming coat with distemper primer. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	2577.59	Per square metre			
3	Painting (One coat (excluding priming coat) on previously painted steel & other metal surfaces with readymixed paint,brushing oil, grease to give an even shade including cleaning the surface of all dirt,dust and other foreign matter With white readymixed paint. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	635.68	Per square metre			
4	Painting two coats (excluding priming coat)on previously painted wood and wood based surfaces with enamel paint to given and even shade including cleaning of all dirt,dust and other foreign matter sand papering and stopping With white enamel paint The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	148.98	Per square metre			
5	Painting two or more coats on G.I Sheets with readymix paint red shade of approved brand and manufacture on new work to give an even shade. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	623.54	Per square metre			

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
6.	Providing and fixing false ceiling of specified materials of size 595x595 mm (Five hundred ninety five by five hundred ninety five) in true horizontal level, suspended on inter locking metal grid of hot dipped galvanized steel sections (galvanized @ 120 grams/ sqm. (one hundred twenty gramme per Square meter) both side inclusive) consisting of main "T" runner with suitably spaced joints to get required length and of size 24x25 mm (twenty four by thirty eight millimeter) made from 0.30 mm (zero point three) thick (minimum) sheet, spaced at 1200 mm (one thousand two hundred millimeter) center to center and cross "T" of size 24x25 mm (twenty four by twenty five millimeter) made of 0.30 mm (zero point three) thick (minimum) sheet, 1200 mm (one thousand two hundred millimeter) long spaced between main "T" at 600 mm (six hundred millimeter) center to center to form a grid of 1200x600 mm (twelve hundred millimeter by six hundred millimeter) and secondary cross "T" of length 600 mm (six hundred millimeter) and size 24x25 mm (twenty four by twenty five millimeter) made of 0.30 (zero point three millimeter) mm thick (minimum) sheet to be interlocked at middle of the 1200x600 mm (twelve hundred millimeter by six hundred millimeter) panel to form grids of 600x600 mm (Six hundred millimeter by six hundred millimeter) and wall angle of size 24x24x0.3 mm (twenty four by twenty four by zero point three millimeter) and laying false ceiling tiles of approved texture in the grid including, required cutting making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc. Main "T" runners to be suspended from ceiling using GI slotted cleats of size 27 x 37 x 2.5 x 1.6 mm (thirty by twenty five by one point six millimeter) fixed to ceiling with 12.5 mm (twelve point five) dia and 50 mm (fifty millimeter) long dash fasteners. 4 mm (four millimeter) GI adjustable rods with galvanised butterfly level clips of size 85 x 30 x 0.8 mm (eighty five by thirty by zero point three millimeter) spaced at 1200 mm (twelve hundred millimeter) center to center along main T, bottom exposed width of 24 mm (twenty four millimeter) of all T- sections shall be pre-painted with polyester paint, all complete for all heights as per specifications, drawings and as directed by Engineer-in-charge. GI Metal Ceiling Lay in plain Tegular edge Global white color tiles of size 595x595 mm. (five hundred ninety five millimeter by five hundred ninety five millimeter) and 0.5 mm (zero point five millimeter) thick with 8 mm (eight millimeter) drop made of GI sheet having galvanizing of 100 gms sqm (one hundred gramme per square meter) (both sides inclusive) and electropolyester powder coated of thickness 60 microns (minimum), statically including factory painted after bending. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	75.60	Per square metre			
Total						

Executive Engineer
B & R Division HP, PWD.
Joginder Kumar

SCHEDULE OF QUANTITY

Name of Work : Restoration of Damages due to laying of OFC cable on Joginder Nagar Sarkaghat Chumarwin road km 0/00' to 34/300 (SH: Construction of Breast wall to protect Radha Swami Satsang Bhawan at km 1/540 to 1/547)				Estimate Cost: Earnest Money: Time Limit :		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	8.40	Per cubic metre			
2	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	5.39	Per cubic metre			

88,714.00
1,800.00
Two Months

	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	16.52	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time excluding GST.	5.00	Each			
	Total					


 Executive Engineer
 B & R Division HP.PWD,
 Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work : Restoration of Damages due to laying of OFC cable on Joginder Nagar Sarkaghat Ghumarwin road m 0/00 to 34/300 (SH: Construction of Breast wall to protect Radha Swami Satsang Bhawan at km 1/530 to 1/538)				Estimate Cost: Earnest Money: Time Limit :			AMOUNT Rs. P
Sr. No.	Description of work	No. or Qty.	Unit	Figures	Rate	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	9.60	Per cubic metre				
2	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	6.16	Per cubic metre				

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	18.88	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time excluding GST.	5.00	Each			
	Total					


 Executive Engineer
 B & R Division HP.PWD,
 Joginder Nagar

SCHEDULE OF QUANTITY


Name of Work: Construction of Jeepable link road from Bella to Shamshan Ghat Gharli km 0/00 to 0/700 in G.P. Bhaḍyara Bhulla Under Deposit (SH: Formation Cutting in km 0/700 to 0/810)				Estimate Cost: Earnest Money: Time Limit :		1,76,992.00 3,500.00 Three Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 54.58 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	839.58	Per cubic metre			
Total						


 Executive Engineer
 B & R Division HP.PWD.
 Jalandhar Nagar

SCHEDULE OF QUANTITY

Name of Work : Restoration of Damages Due to laying of OFC on Joginder Nagar Sarkaghat Ghumarwin road km 0/60 to 21/00 (SH: Construction of Breast wall at km 13/290 to 13/300)				Estimate Cost: Earnest Money: Time Limit :			1,30,362.00 2,600.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P		
				Figures	Words			
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	17.10	Per cubic metre					
2	Earth work in excavation for structures in all depths as per drawing and M.O.R.D technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	7.10	Per cubic metre					

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals . The rate is inclusive all taxes levy by the government time to time excluding GST.	23.50	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge . The rate is inclusive all taxes levy by the government time to time excluding GST.	12.00	Each			
	Total					


 Executive Engineer
 B & R Division HP.PWD.
 Jalandhar Nagar

SCHEDULE OF QUANTITY

Name of Work : Restoration of damages due to laying og OGC on Gagal Simus road km 0/00 to 5/00 (SH: Construction of Retaining wall at km 0/855 to 0/860)					Estimate Cost: Earnest Money: Time Limit :			1.42,834.00 2,900.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		Figures	Words	AMOUNT	
								Rs.	P
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	15.00	Per cubic metre						
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty-millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	26.45	Per cubic metre						

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	3.00	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1(v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	12.00	Each			
Total						


 Executive Engineer
 B & R Division HP.PWD.
 Jodhpur Nagar

SCHEDULE OF QUANTITY

Name of Work : Restoration of damages due to laying of OFC on Joginder Ngar Sarkaghat Ghumarwin Road km 0/00 to 34/300 (Sub Head:- Construction of U-Shape Darin in km 0/523 to 0/583)				Estimate Cost: 93.987.000 Earnest Money: 1,900.000 Time Limit : Two Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	23.40	Per cubic metre			
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete Grade M-10 complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	13.50	Per cubic metre			
	Total					


 Engineer
 B & R Division HP.PWD,
 Joginder Nagar

DRAFT SCHEDULE OF QUANTITY

Name of Work : Cnstruction of Link road from Joginder Nagar Sarkaghat Gumnarwin road upto Naag Joad via Kufidhar upper samohli GP Bulha Bhadyara (Under MPLAD Rajya Sabha) (SH: Construction of Retaining wall at km 0/240 to 0/255)					Estimate Cost: 1,62,497.00
					Earnest Money: 3,300,000
					Time Limit : Three Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate	
				Figures	Words
AMOUNT					
Rs. P					
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	8.40	Per cubic metre		
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	29.10	Per cubic metre		

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3.	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	5.63	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D. technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	15.00	Each			
	Total					


 Executive Engineer
 B & R Division HP.PWD.
 Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work : Cnstruction of Link road from Joginder Nagar Sarkaghat Gunmarwin road upto Naag Joad via Kufridhar upper samohli GP Bulha Bhadyara (Under MPLAD Rajya Sabha) (SH: Construction of Retaining wall at km 0/560 to 0/570)					Estimate Cost: 1,77,242.00 Earnest Money: 3,500.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P	
				Figures	Words		
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	10.75	Per cubic metre				
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights,depths including cost of form work as per drawings and MORID technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	31.70	Per cubic metre				

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads. lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	6.70	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	12.00	Each			
Total						


 Executive Engineer
 B & R Division HP.P.W.D.
 Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work : Construction of Road Sc Basti ZimZima to Upper ZimZima G.P. Zimzima under Deposit (SH:-Construction of Reatining/ edge wall-at km-0/005 to 0/010 and Cement Concrete Pavement at km 0/00 to 0/040) (Under MPLAD Rajya Sabha)					Estimate Cost: 1,58,453.00 Earnest Money: 3,200.00 Time Limit : Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	3.18	Per cubic metre			
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	9.46	Per cubic metre			
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	2.63	Per cubic metre			

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
4	Providing weep holes in brick masonry/stone masonry plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D. technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	4.00	Each			
5	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and combor including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (one hundred millimeter) spread thickness (finished work including materials and labour) and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST.	16.50	Per Cubic metre			
6	Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints, over a prepared sub base, with 4.5 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade coarse and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	11.00	Per Cubic metre			
	Total					


 Executive Engineer
 B & R Division HP.PWD.
 Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work : Restoration of Damages due to Laying of OFC on Baijnath Lad Bharol Kandapattan Road km 0/00 to 46/00 (Sub Head:- Construction of 900mm dia Hume Pipe Culvert alongwith wing wall at km 12/365)					Estimate Cost: Earnest Money: Time Limit :		
Sr. No.	Description of work	No. or Qty.	Unit		Rate	AMOUNT	
					Figures	Words	Rs. P
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	56.80	Per cubic metre				4,13,501.00 8,300.00 Three Months
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802.803.1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded stone aggregate 40mm (forty millimetre) nominal size) complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time excluding GST.	5.91	Per cubic metre				
3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802. 803. 1202 & 1203. Plain cement concrete Grade M-10 complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time excluding GST.	11.42	Per cubic metre				

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
4	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification. Rubble stone laid in cement mortar 1:5 (one cement : five sand) complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	0.49	Per cubic metre			
5	Providing and laying 900mm (nine hundred millimetre) diameter reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	7.50	Per running metre			
6	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	47.68	Per cubic metre			
7	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204,3.7 including carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	30.00	Each			
8	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	15.36	Per cubic metre			
	Total					


 Executive Engineer
 B & R Division HP.PWD,
 Jalandhar

SCHEDULE OF QUANTITY

Name of Work : Cnstruction of Link road from Joginder Nagar Sarkaghat Gummarwin road upto Naag Joad via Kufridhar upper samohli GP Bulha Bhadyara (Under MPLAD Rajya Sabha) (SH: Construction of Retaining wall at km 0/440 to 0/443.50)					Estimate Cost: Earnest Money: Time Limit :		83,672.00 1,700.00 Two Months
Sr. No.	Description of work	No. or Qty.	Unit	Figures	Rate		AMOUNT Rs. P
					Words	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D. technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	5.85	Per cubic metre				
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	14.60	Per cubic metre				

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause J 204.3.8 Granular material complete within all leads. lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	5.15	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry plain or reinforced concrete abutment. wing-wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	5.00	Each			
	Total					


 Executive Engineer
 B & R Division HP.PW.D.
 Joginder Nagaur

SCHEDULE OF QUANTITY

Name of Work : Construction of Cement Concrete Pavement Link road to Mata Kanya Devi Mandir G.P. Vata Ri Bihun under Deposit (S.H. : Providing and laying Kharanja Stone Soling & Cement Concrete pavement at km 0/00 to 0/027)				Estimate Cost: Earnest Money: Time Limit :			85,224.00 1,700.00 Two Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (one hundred milimeter) spread thickness (finished work including materials and labour) and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST.	11.14	Per Cubic metre				
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five milimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	9.28	Per Cubic metre				
Total							


 Executive Engineer
 B & R Division HP.PWD.
 Jalandhar Nagar

SCHEDULE OF QUANTITY

Name of Work : Construction of Cement Concrete Pavement Link road to Mata Kanya Devi Mandir G.P. Vata Ri Bihun under Deposit (S.H. : Providing and laying Kharanja Stone Soling & Cement Concrete pavement at km 0/028 to 0/055)				Estimate Cost: 85,224.00 Earnest Money: 1,700.00 Time Limit : Two Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (one hundred milimeter) spread thickness (finished work including materials and labour) and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST.	11.14	Per Cubic metre			
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383. maximum size of coarse aggregate not exceeding 25 mm (twenty five milimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	9.28	Per Cubic metre			
Total						


 Executive Engineer
 B & R Division HP.PWD.
 Jalandhar Nagar

SCHEDULE OF QUANTITY

Name of Work : Construction of Various Roads under Joginder Nagar Sub Division (Harabag Section) Under Deposit (SH: Extension of 600mm dia hume pipe culvert at km 1/530, Construction of Retaining wall at km 1/528 to 1/535.50 & Construction of U-Spahe Drain at km 1/525 to 1/600 on Shanan Harabag Road)				Estimate Cost: Earnest Money: Time Limit :			2,60,380.00 5,200.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	Rs.	P
				Figures	Words			
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	43.20	Per cubic metre					
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete Grade M-10 complete within all leads, lifts carriage of material and other incidentials. The rate is inclusive all taxes levy by the government time to time excluding GST.	17.18	Per cubic metre					

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	22.99	Per cubic metre			
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	4.13	Per cubic metre			
5	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification. Rubble stone laid in cement mortar 1:5 (one cement : five sand) complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	0.49	Per cubic metre			
6	Providing and laying 600mm (six hundred millimetre) diameter reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	2.50	Per running metre			
7	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment . wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614.709.1204.3.7 including carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	14.00	Each			
	Total					


 Executive Engineer
 B & R Division HP.PWD,
 Jalandhar Nagar

SCHEDULE OF QUANTITY

Name of Work: Construction of road Mokshdham Siyun Banander in GP Maman (SH:-Formation Cutting in km 0/000 to 0/120)				Estimate Cost: 89,299.00 Earnest Money: 1,800.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 58.11 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	337.08	Per cubic metre			
	Total					


Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

(21)

SCHEDULE OF QUANTITY

Name of Work: Construction of road Mokshdham Siyun Banander in GP Maman (SH: Formation Cutting in km 0/120 to 0/165)				Estimate Cost: Earnest Money: Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 58.98 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	298.92	Per cubic metre			
Total						


Executive Engineer
B & R Division HP.P.W.D.
Joginder-Nagar

Name of Work: Construction of Link road Batolu to Kharon Under Deposit	Estimate Cost:	82,432.00
(SH: Removal of Formation Deficiency at km 6/100 to 0/135)	Earnest Money:	1,600.00


Executive Engineer
B & R Division HP, PWD,
Jalandhar Nagar

SCHEDULE OF QUANTITY

Name of Work:- Balance work Construction of Additional Accomodation for Govt. High School Building at Khddar The. Lad Bharol Dist. Mandi (H.P.) (S.H. : Providing and Fixing angle Iron Stair)					Estimate Cost: 37,646.00	
					Earnest Money: 800.00	
					Time Limit : 03 Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Steel work welded in built up sections including cutting, hoisting, fixing In gratings framed guard bars, ladders, railings, brackets and similar work including cutting, hoisting, fixing in position & applying a priming coat of red lead paint complete including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	341.00	Per Kilogramme			
	Total					


 Executive Engineer
 B & R Division HP, PW D.
 Jodhpur Nagar

SCHEDULE OF QUANTITY

Name of work : A/R & M/O to various Non Residential Buildings under Joginder Nagar Division HPPWWD Joginder Nagar (SH: Construction of Boundary wall at RD 0/00 to 0/030.45 on Section office Ladruhin (Dohag)					Estimate Cost: 96,233.00		
					Earnest Money: 1,900.00		
					Time Limit : Two Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	4.87	Per cubic metre				
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth leve in 1:4:8 (one Cement isto four coarse sand) isto eight graded stone aggregate 40 mm (fourty milimeter) nominal size). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	4.87	Per cubic metre				
3	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level Cement mortar 1:4 (one cement isto four coarse sand). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	54.81	Per Square Meter				

No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
4	15mm (Fifteen millimeter) cement plaster in single coat on the Rough side in cement mortar 1:6 (one Cement : six Sand) of brick concrete stone walls for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	109.62	Per Square Metre			
	Total					


 Executive Engineer
 B & R Division HP.PWD.
 Joginder Nagar

SCHEDULE OF QUANTITY

Name of work : A/R & M/O to various Non-Residential Buildings under Joginder Nagar Division HPPWD Joginder Nagar (SH: Dismantling doors, windows and Providing & fixing aluminium work for door & window etc. in HPPWD Rest House at Joginder Nagar)				Estimate Cost: Earnest Money : Time Limit :			4,97,764.00 10,000.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate			AMOUNT	
				Figures	Words	P	Rs.	P
1	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 (fifty) metres lead Of area 3 (three) sq. metres and below. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	15.00	Each					
2	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) For fixed portion Powder coated aluminium (minimum thickness of powder coating 50 (fifty micron). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	455.81	Per Kilogramme					
2	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) For shutters of doors, windows & ventilators including providing and fixing hinges pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber neoprene gasket require (Fittings shall be paid for separately) Powder coated aluminium (minimum thickness of powder coating 50 (fifty micron) The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	564.98	Per Kilogramme					

Sl. No.	Description of work	No. or Qty.	Unit	Rate			AMOUNT
				Figures	Words	RS. P	
3.	Providing and fixing glazing-in-aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge. ((Cost of aluminium snap beading shall be paid in basic item). With float glass panes of 4.0 mm (four millimeter) thickness (weight not less than 10 (ten) kg/ sqm). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	31.05	Per Square Meter				
3.	Providing and fixing 12 mm thick pre-laminated particle board Pre-laminated particle board with decorative lamination on one side and balancing lamination on other side flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminium doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer- in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	6.62	Per Square Meter				
4	Providing and fixing anodised aluminium grill (anodised transparent or dyed to required shade according to IS: 1868 with minimum anodic coating of grade AC 15) of approved design/pattern, with approved standard section and fixed to the existing window frame with C.P. brass/ stainless steel screws @ 200 mm centre to centre, including cutting the grill to proper opening size for fixing and operation of handles and fixing approved anodised aluminium standard section around the opening, all complete as per requirement and direction of Engineer-in-charge. (Only weight of grill to be measured for payment). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the government time to time excluding GST.	31.05	Per Kilogramme				
4	Providing and fixing fly proof galvanised 1.5. wire gauge of 1.5. gauge designation 85G with wire of dia 0.56 mm to window and clerestory windows. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	37.67	Per Square Metre				
6	Providing and fixing 250x16mm (two hundred fifty by sixteen millimeter) Size anodized aluminium sliding door bolt anodized colour and shade with bolts and nuts screws etc. complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	6.00	Each				
11	Providing and fixing anodized aluminium lower bolts (barrel type) anodized transparent or dyed to required shade and colour with screws etcetra complete 250x16mm (two hundred fifty into ten millimeter) size. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	6.00	Each				

No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
11	Providing and fixing anodized aluminum tower bolts (barrel type) anodized transparent or dyed to required shade and colour with screws etcetera complete 150x10mm (one hundred fifty into ten millimeter) size. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	72.00	Each			
19	Providing and fixing anodized aluminium handle anodized transparent or dyed to required shade or colour with necessary screws etcetera complete. 125mm (one hundred twenty five millimeter) size as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	6.00	Each			
19	Providing and fixing anodized aluminium handle anodized transparent or dyed to required shade or colour with necessary screws etcetera complete. 100mm (one hundred twenty millimeter) size as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	72.00	Each			
	Total					


 B & R Division H.P.P.W.D.
 Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work : Restoration of damages due to laying of OFC on Ahju Bashai Road km 0/00 to 12/00 (SH: Purchase of Computer, printer and UPS for Chauntra Section)					Estimate Cost: 92,292.00	
					Earnest Money: 1,800.00	
					Time Limit : Two Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT
				Figures	Words	
1	Supply and Installation of HP All in One PC with Intel i 3-12th Gen Processor / 8 GB Ram/ Win 11 pro/ 512GB SSD/20/22' LED Keyboard & Mouse / MS office including as per the direction of Engineer. -in-charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	1.00	Each			
2	Supplying of HP Laserjet M 126 MFP Printer including as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	1.00	Each			
3	Supplying of UPS 600VA Microtek as per the direction of Engineer -in-charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	1.00	Each			
Total						


 B & R Division HP.PWD.
 Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work: Restoration of damages due to laying of OFC on Joginder Nagar Sarkaghat Ghumarwin Road (Makriri Section) (SH:- Hiring of excavator cum loader for removal of slips, dressing of berms, clearing of road side drains, debris and C/O road side katcha drains)				Estimate Cost: 99,060.00 Earnest Money: 2,000.00 Time Limit : Two Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Hiring of Hydraulic Excavator having capacity of 1.00 (one point zero) cubic meter loader capacity for construction unlined drain & dressing of berms i/c cost of fuel oil lubricants and wages of operating staff, any repair/breakage during operation will be carried out by the contractor owner at his own risk shifting machinery from one place to other place will be absolute responsibility of the contractor, only actual working hour will be accounted for the payment. Earth cutting in all kind of soils i/c loading in to tipper/truck within all leads and lifts to the entire satisfaction of Engineer-In-Charge. The payment will be made on the submission of the copy of log book duly signed/checked by the concerned Engineer-in-Charge. The rate is inclusive all taxes including GST levy by the government time to time.	78.00	Per working hour			
Total						


 Executive Engineer
 B & R Division HP, PWD.
 Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work: Restoration of damages due to laying of OFCon Joginder Nagar Sarkaghat Ghumarwin Road. (Makriri Section) (SH:- Hiring of Tipper for Shifting and carriage of various type of material etc.)				Estimate Cost: 99,000.00 Earnest Money: 2,000.00 Time Limit : Two Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Hire charges of tipper for carriage/shifting of soling stone earth, moorum, premix material, seal coat etc. having capacity of 5.50 (five point five zero) cubic metre per trip and covering 70 (seventy) kilometers per day (9AM to 5PM), the contractor/owner of tipper shall bear the expensive of POL charges, repair of machineries including driver and helper wages. Any accident and other damages to private and Govt property occur during the working hours in the work shall be the responsibility of the contractor and disposal of excavated material/ slips debris with in all leads and lifts as per the direction of Engineer-in-Charge. The rates are inclusive of all taxes including GST levy by the Govt. time to time.	22.00	Per Working Day			
Total						


 Executive Engineer
 B & R Division HP.PWD.
 Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work: Restoration of damages due to laying of OF Con-Joginder Nagar Sarkaghat Ghumarwin Road (Makriri Section) (SH:- Hiring of excavator-cum loader for removal of slips, dressing of berms, clearing of road side drains, debris and C/O road side katcha drains)					Estimate Cost: 99,060.00		
					Earnest Money: 2,000.00		
					Time Limit : Two Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT- Rs. P	
				Figures	Words		
1	Hiring of Hydraulic Excavator having capacity of 1.00 (one point zero) cubic meter loader capacity for construction unlined drain & dressing of berms i/c cost of fuel oil lubricants and wages of operating staff, any repair/breakage during operation will be carried out bt the contractor/owner at his own risk,shifting machinery from one place to other place will be absolute responsibility of the contractor, only actual working hour will be accounted for the payment. Earth cutting in all kind of soils i/c loading in to tipper/truck within all leads and lifts to the entire satisfaction of Engineer-In-Charge. The payment will be made on the submission of the copy of log book duly signed/checked by the concerned Engineer-in-Charge.The rate is inclusive all taxes including GST levy by the government time to time.	78.00	Per working hour				
		Total					



Executive Engineer
 B & R Division HP.PWD.
 Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work:- Restoration of damages due to laying of OFC on Joginder Nagar Sarkaghat Ghumarwin Road (Makiri Section) (SH:- Hiring of excavator-cum loader for removal of slips, dressing of berms, clearing of road side drains, debris and C/O road side katcha drains)				Estimate Cost: Earnest Money: Time Limit :		
				Two Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Hiring of Hydraulic Excavator having capacity of 1.00 (one point zero) cubic meter loader capacity for construction unlined drain & dressing of berms i/c cost of fuel oil lubricants and wages of operating staff, any repair/breakage during operation will be carried out by the contractor/owner at his own risk, shifting machinery from one place to other place will be absolute responsibility of the contractor, only actual working hour will be accounted for the payment. Earth cutting in all kind of soils i/c loading in to tipper/truck within all leads and lifts to the entire satisfaction of Engineer-In-Charge. The payment will be made on the submission of the copy of log book duly signed/checked by the concerned Engineer-in-Charge. The rate is inclusive all taxes including GST levy by the government time to time.	78.00	Per working hour			
Total						



Executive Engineer

B & R Division HP.PWD.

Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work : A/R & M/O Chauntra to Lower Chauntra road km 0/00 to 2/200				Estimate Cost: 98,976.00	
Sub Head:- Providing and laying Granular Sub Base on both side berms at km 0/100 to 0/570)				Earnest Money: 2,000.00	
				Time Limit : Two Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate	
				Figures	Words
1	Construction of granular sub -base by providing well graded material , spreading in uniform layers with Tractor mount grader on prepared surface , mixing by mix in place method with pretavator at OMC, and compacting with smooth wheel roller to achieve the desired density , complete as per technical specification clause 405 complete within all leads , lifts, carriage of material and other incidentals charges. The rate is inclusive all taxes levy by the government time to time excluding GST.	49.35	Per cubic metre		
Total					
				AMOUNT	
				Rs.	P


 Executive Engineer
 B & R Division HP.PWD.
 Jalandhar Nagar

SCHEDULE OF QUANTITY

Name of work : A/R & M/O on various Non Residential Buildings Under HPPWD Division HPPWD Joginder Nagar (SH: Supplying of Various Office articles for division office HPPWD Joginder Nagar)				Estimate Cost: Earnest Money: Time Limit :			98,527.00 2,000.00 Two Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs.	P	
				Figures	Words			
1	Supplying Revolving metal chair with high back upholstered Seat Of Size 360x360mm (three hundred sixty by three hundred sixty millimeter) and back 725x475 mm (seven hundred twenty five by four hundred seventy five millimeter) having castor unit with hydraulic system with 5 (Five) numbers PVC wheels. Seat/back cushion should be made of flexible polyurethane foam having density of 28 kg/m (twenty eight kg/m) and indentation hardness shall be 18 to 25 kg per cum (eighteen to twenty five kilogramme per cubic meter) covered with best quality leather foam furnishing cloth with push back spring having double action i.e. fixed and pushed back Seat should be fitted with shoulder action complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	3.00	Each					
2	Supplying Steel Almirah door and shelves made of 1 mm (one millimeter) thick and body made of 0.8mm (zero point eight millimeter thick) thick M.S sheets of size 1980x1010x530mm (one thousand nine hundred eighty by one thousand ten by five hundred thirty millimeter) with 4 (four) shelves 5 (five) compartment shall be painted With synthetic enamel paint on inside and spray hammer tone paint from outside in silver ash, olive green or as requested by the indenter complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.00	Each	- /				
3	Supplying Office Writing Tables 900mmx1200mmx 760mm (Nine hundred by twelve hundred ten by seven hundred sixty millimeter) made Of mild steel sq. pipe of section 25x25x1 25mm (twenty five by twenty five by one point two five millimeter) painted with synthebe enamel paint with 3 (three) drawers on the right side with beking device in mild steel sq. pipe of section 25x25x1 25 mm (twenty five by twenty five by one point two five millimeter). The drawers of cup board made of 0.8mm (zero point eight millimeter) thick sheet. Table top should be Of 18 mm (eighteen millimeter) thick pre-laminated Board(MDF) complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	5.00	Each					
4	Supplying of HP Laserjet A11005 M1 P Printer Copy Print Scan. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	2.00	Each					
	Total							

Executive Engineer
B & R Division HP.PWD.
Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work : Construction of Ambulance road -Jhamechar Muhaf in GP Dhar Km 0/00 to 0/350 Under MPLAD Cement (S.H.) Providing and laying Kharanja Stone Soling & Cement Concrete pavement at km 0/00 to 0/65)					Estimate Cost: 1,68,411.00 Earnest Money: 3,400.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate			AMOUNT Rs. P
				Figures	Words		
1	Preparation of sub grade by dressing to camber (Earth work for cutting involved for sub grade to paid for separately depending upon the classification of soil completed as per HPPWD specifications complete within all leads, lifts, carriage of material and other incidentals charges and to the entire satisfaction and direction of Engineer - in- Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	18.77	Per square metre				
2	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (one hundred millimeter) spread thickness (finished work including materials and labour) and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST.	18.77	Per Cubic metre				
3	Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints, over a prepared sub base. with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383. maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	18.77	Per Cubic metre				
Total							


 Executive Engineer
 B & R Division HP.PWD.
 Joginder Nagar

34

Schedule of Quantity

Estimated Cost:- 99060 00
 Earnest Money:- 2000 00
 Time:- Two months

Name of work:- Restoration of damages due to laying of OFC on Baijnath Lad Bharol Kandapattan road (Tullah section)

Sub Head:- Hiring of excavator cum loader for removal of slips dressing of berms cleaning of road side drains, debris and construction of road side katcha drains etc

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of hydraulic excavator cum loader of 1 00 (one) cubic metre loader capacity for removal of slips, dressing of berms, clearing of road side drains, debris and construction of road side katcha drains including cost of fuel oil lubricants and wages of operating staff, any repair/breakage during operation will be carried out by the contractor/owner at his own risk, shifting machinery from one place to other place will be absolute responsibility of the contractor. only actual working hour will be accounted for the payment Earth cutting in all kind of soils including loading in to tipper/truck with in all leads and lifts to the entire satisfaction of Engineer-In-Charge. The payment will be made on the submission of the copy of Log Book duly signed/checked by the concerned Engineer in Charge. The rate is inclusive of all taxes including GST levy by the Govt. time to time	78 00		--	Per working hour	
						Total:-


 Executive Engineer,
 B&R Division, HP PWD,
 Jalandhar Nagar

(35)

SCHEDULE OF QUANTITY

Name of Work : Restoration of Damages due to Laying of OFC on Ahju Bashai Road km 0/00 to 19/200 (SH: Construction of Retaining wall at km 5/625 to 5/632.80)					Estimate Cost: Earnest Money: Time Limit :			98,770.00 2,000.00 Two Months	
Sr. No.	Description of work	No. or Qty.	Unit		Rate		AMOUNT Rs. P		
					Figures	Words			
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D. technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	5.62	Per cubic metre						
2	Providing and laying cement concrete 1:5:10 (one cement: five sand: ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	18.25	Per cubic metre						

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	5.34	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry plain or reinforced concrete abutment. wing wall. return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1(v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614. 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time excluding GST.	9.00	Each			
	Total					


 Executive Engineer
 B & R Division HP.PWD.
 Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work : Restoration of Damages due to Laying of OFC on Ahju Bashai Road km 0/00 to 19/200 (SH: Construction of Retaining wall at km 5/670 to 5/677)					Estimate Cost: Earnest Money: Time Limit :			62,988.00 1,300.00 Two Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT			
				Figures	Words	Rs.	P		
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out. construction of shoring and bracing. removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost . The rate is inclusive all taxes levy by the government time to time excluding GST.	3.61	Per cubic metre						
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	11.76	Per cubic metre						

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	3.26	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time excluding GST.	4.00	Each			
Total						


 Executive Engineer
 B & R Division HP.PWD,
 Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work : Restoration of Machhyal Ropari Trembali road km 0/00 to 10/00 (S.M. : Providing and laying Cement Concrete pavement at km 5/405 to 5/455 & 5/525 to 5/575)				Estimate Cost: Earnest Money: Time Limit :		2,70,040.00 5,400.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	40.70	Per Cubic metre				
Total							


 Executive Engineer
 B & R Division HP.PWD.
 Joginder Nagar

16

SCHEDULE OF QUANTITY

Name of Work : Construction of road from Panjalag to Harizan Basti Katoun via Nichala Panjalag Km. 0/0 to 2/0 under SCSP (S.H. : Providing and laying Cement Concrete pavement at km 1/088 to 1/140)					Estimate Cost:	
					Earnest Money:	
					Time Limit :	
					Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT
				Figures	Words	
1	Construction of un-reinforced cement concrete pavement as per design and drawing with expansion and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	22.23	Per Cubic metre			
		Total				


 Executive Engineer
 B & R Division HP PWD,
 Jalandhar Nagar