




Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:- ee-baij-hp@nlc.in

CERTIFICATE

CERTIFIED THAT THE TENDERS OF WORKS, AS
CALLED VIDE THIS OFFICE LETTER NO.PWD/BD/TA/NIT/2023-24/-
15022-15071. DATED 04/01/2024, ARE URGENT NATURE
AND PUBLIC INTEREST.


Executive Engineer,
Baijnath Division,
HP.PWD, Baijnath.





Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:- ee-baij-hp@nfc.in

"NOTICE INVITING TENDER"

Scaled item rate of tender form No. 6 & 8 are hereby invited by the Executive Engineer, Baijnath Division H.P.PWD., Baijnath on behalf of the Governor of HP for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rule and also registered under the HP General Sales Tax act 1968 so as to reach in this office on or before 18.01.2024 up to 11.30 A.M and will be opened on the same day at 12.00 Noon in the presence of intending contractors or their authorized representatives. The tender forms can be had from his office against cash payment (Non refundable) on 17.01.2024 between 2.00 PM up to 4.30 P.M and the application for issue of tender forms shall be received on 16.01.2024 up to 12.00 Noon.

The earnest money in the shape of National Saving Certificate/Time Deposit accounts/Saving Accounts in any Post Office/Bank in H.P. duly pledged in favour of the XEN H.P.PWD., Baijnath must be accompanied with the each tender. Conditional/incomplete tenders and the tenders received without earnest money as mentioned above will be similarly rejected, the offer of the tender shall be kept open for 75 days. The XEN reserves the right to accept or reject any or all tenders or to drop the proposal of the tender without assigning any reasons.

Sr. No.	Name of work.	Amount put to tender/Estimated cost.	Earnest Money	Cost of tender form	Time limit
1	C/O Stage for Children in Govt. Primary School Mohal Sansal Under SDP. (SH: C/O Stage.) Deposit work	Rs.99,517/-	Rs.2,000/-	Rs.350/-	Two Months
2	Restoration of rain damages on Holta Chadhiar Sandhole road Km 56/00 to 74/00 (SH: P/L WBM G-I, G-II and 2cm Premix carper seal coat at Km 60/405 to 60/485 & C/O U-Shape Drain at Km 60/380 to 60/480)	Rs.3,81,174/-	Rs.7,700/-	Rs.350/-	Two Months
3	Construction of Pucca path from Prakash Chand House to Subhash Chand House Ghirtholi ward No.4 (SH: Providing and Laying Khamja stone soling and C.C. pavement at RD 0/00 to 0/250)	Rs.1,95,000/-	Rs.3,900/-	Rs.350/-	One Month
4	Pucca Path from House of Shri Ilam Chand to House of Shri Kamlesh Chand Mohal Kudail (SH: P/L C.C. Pavement) (Deposit Work)	Rs.95,012/-	Rs.1,900/-	Rs.350/-	One Month
5	Improvement of Black spot on Langhoo Jamrella Road (SH: P/F Crash Barrier at RD 3/120 to 3/190 for removal of Black Spot)	Rs.2,95,544/-	Rs.6,000/-	Rs.350/-	One Month
6	C/O Pucca Path from Shashi House to Narendra House G.P. Chobin (SH: Providing and laying Cement Concrete Pavement.) (Deposit Work)	Rs.74,620/-	Rs.1,500/-	Rs.350/-	Two Months
7	Balance work for C/O A.E. Office cum Residence at Bir (SH: Providing Cement Primer, Acrylic Emulsion, Water Proof Apex Exterior Emulsion & P/L Paver block etc.)	Rs.3,05,695/-	Rs.6,200/-	Rs.350/-	Two Months
8	Construction of Bridge over Binwa Khad on Utrala Surahi Pass Road at RD 15/150 (SH: Preparation of Hydraulic Data.)	Rs.60,000/-	Rs.1,200/-	Rs.350/-	Three Months
9	Construction of link road to Harizan Basti Village Bhirdi Ward No. 4 Km 0/00 to 1/200 (SH: Cause way from RD 0/835 to 0/865 and Edge wall at RD 0/845 to 0/855)	Rs.2,17,118/-	Rs.4,400/-	Rs.350/-	One Month
10	C/O Baijnath Chobin Balander road Km 0/00 to 14/200 (SH: C/O B/Wall for protection of Govt. Primary School Bandiyan at RD 6/410 to 6/417.50)	Rs.1,37,896/-	Rs.2,800/-	Rs.350/-	One Month
11	Additionalilty to complete under Constriction road at village order (under Deposit) (SH: P/L C.C. Pavement & Khamja Soling at Km 0/700 to 0/760)	Rs.1,92,375/-	Rs.3,900/-	Rs.350/-	One Month
12	C/O Community Bhawan Kachcha Khoo Mohal Matial (SH: Plastering, Flooring, and Distemping of community Bhawan)	Rs.1,18,437/-	Rs.2,400/-	Rs.350/-	Two Months

13	C/O Link road Sansal Dhandole to Jamthala Ladh Bharol Road Km 0/00 to 1/00 (SH: C/O 900 mm Dia Hume Pipe Culvert at RD 0/875)	Rs.93,731/-	Rs.1,000/-	Rs.350/-	One Month
14	C/O Ahju Bir Gunchar Road Km 0/00 to 6/00 (SH: Construction of Hume Pipe & Wing wall for 900mm Dia Hume Pipe Culvert at RD 5/740)	Rs.2,18,328/-	Rs.4,400/-	Rs.350/-	Two Months
15	C/O Link road to Village Banwar Kuran to Village Udhhar Km 0/00 to 1/800 (SH: Providing and Laying Kharanja Stone Soling in Km 0/00 to 0/400)	Rs.2,95,021/-	Rs.6,000/-	Rs.350/-	Two Months
16	C/O Rakkar Rajot Noun Road Km 0/00 to 4/00 (SH: C/O 0.60 Mtr. Span RCC Slab Culvert at RD 3/900)	Rs.1,04,284/-	Rs.2,100/-	Rs.350/-	Two Months
17	Restoration of Rain Damages on Ahju Bir Gunchar Road Km 0/00 to 6/00 (SH: C/O U-Shape drain at RD 5/450 to 5/550)	Rs.97,812/-	Rs.2,000/-	Rs.350/-	One Month
18	Construction of AHC Building at Sansal (SH: C/O U-Shape Drain and P/L Kharanja Stone soling and C.C. Pavement, wall Painting, steel Painting etc.)	Rs.1,73,854/-	Rs.3,500/-	Rs.350/-	Two Months

Terms and conditions:-

1. The contractor should be registered as dealer under H.P. GST Tax Act. 2018 and also produce the Tin number. H.P. sales Tax clearance certificate from the Excise and Taxation Department.
2. The Pan Number, latest Income Tax clearance certificate and EPF No (Where applicable) duly attached with the application.
3. The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained.
4. In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
5. Only two tenders form will be issued to the contractor/firm which may be noted.
6. The contractor will also have to attach the labour employer license from the labour office with the application.
7. Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
8. The contractor shall be responsible for rectifying defects noticed within One year from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
9. The contractor shall have all required machinery such as Truck/ Tipper, Mixture, water tanker Vibrator etc or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
10. The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an under taking viz he will get complete the works in hand before award of work with in schedule time.
11. All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
12. The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/ permit.

Executive Engineer,
Bajjnath Division.,
H.P.PWD., Bajjnath.

For & On behalf of the governor of H.P.

NO:-PWD/BD/TA/NIT/2023-24/- 15022 - 15071

Dated:- 04/11/24

1. Copy to the F.C. cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
2. The Engineer-in-chief, HPPWD, Shimla.
3. The Chief Engineer (MZ), HPPWD, Mandi.
4. The Superintending Engineer, JNR. Circle HPPWD, Joginder Nagar.
5. All the Assistant Engineer working under this Division.
6. Drawing Branch in this office.
7. Notice Board.
8. The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
Bajjnath Division.,
H.P.PWD., Bajjnath.

DNIT/DRAFT SCHEDULE OF QUANTITY

① 6



Name of Work: - C/O Stage For Children In Govt. Primary School Mohal Sansal Under SDP.
(SH:- C/O Stage.) Deposit work.

Estimate Cost:- 99517.00/-
Earnest Money:- 2000.00/-
Time Limit : Two Month

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, (fifty meter) dressing of sides and bottom and backfilling in trenches with excavated suitable material. as per the entire satisfaction and direction of Engineer-in-Charge. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	1.62	Per Cubic Meter			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete nominal mix 1:4:8 (one cement is to four sand is to eight crushed stone agg. 40mm(forty millimetre) nominal size) in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work and open in foundation as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	8.94	Per Cubic Meter			
3	Back filling behind abutments, wing walls and return walls complete as per drawing and M.O.R.D. technical specification clause 1203 and 1604 and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	15.56	Per Cubic Meter			
4	Stone filling dry hand packed behind retaining walls or under floor including curring and carriage of material within all leads and lifts complete in all respect as per direction of Engineer in Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	5.66	Per Cubic Meter			

① ②

5	Providing and laying mechanically mixed vibrated reinforced cement concrete in substructure using concrete grade M-20 (M twenty) design Mix with cement contents not less then 330 kg (three hundred and thitry kilogram) per cubic meter as per drawing and M.O.R.D. technical specification section 800, 900,1200. Including the cost of form work in bed block and dirt wall etc. excluding the cost of reinforcement for reinforced concrete work but icluding curing complete as per direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	4.24	Per Cubic Meter			
6	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M ten) per cubic metre nominal mix 1:3:6 (one cement is to three sand is to six crushed stone agg. 40mm(forty millimetre) nominal size) in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work and open in foundation as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	1.05	Per Cubic Meter			
Total						


 Executive Engineer
 Baijnath Division
 H.P.P.W.D. Baijnath


(2) (a)

DNIT/DRAFT SCHEDULE OF QUANTITY						Estimate Cost:	381,174.00
Name of work :- Restoration of rain damages on Holta Chadhiar Sandhole Road km 56/00 to 74/00 .						Earnest Money:	7,700.00
(Sh:- P/L WBM G-I ,G-II and 2 cm Premix carpet seal coat at km 60/405 to 60/485 & C/O U-shape Drain at km 60/380 to 60/480)						Time Limit :	Two Months
SCHEDULE OF WORKS						AMOUNT	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		Rs.	P
				Figures	Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5m (one point fifty meter) in width or 10 sqm), including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point fifty meter) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m(Fifty meter).All kinds of soil,with in all leads by any mode of transportation and other incidental ,as per direction and entire satisfaction of Engineer -in -charge.The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	Per Cubic Meter	38.50				
2	Providing and Laying, spreading and compacting stone aggregates size 90 mm to 45 mm (Ninety millimeter to forty five millimeter) grading-I(100 mm Consolidated thickness) to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming. Crushable type such as Moorum or Gravel for grading-I @ 0.30 cum per ten square meter and binding material at the rate of 0.08 cum (Zero point zero eight cubic meters) per ten Sqm (ten square meters) to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading I as per MORD technical specification clause no 405 The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	Per Cubic Meter	29.40				
3	Providing and Laying, spreading and compacting stone aggregates size 63mm to 45 mm (Sixty three millimeter to forty five millimeter) grading-II(75 mm Consolidated thickness) to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming. Crushable type such as Moorum or Gravel for grading II & III @ 0.22 cum (zero point two two cubic meter) per ten square meter and binding material at the rate of 0.06 cum (Zero point zero Six cubic meters) per ten Sqm (ten square meters) to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading II as per MORD technical specification clause no 405 and as per directions of Engineer in charge. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	Per Cubic Meter	27.11				
4	Providing and applying prime coat with Bitumen emulsion (SS-I) on prepared surface of granular base including cleaning of road surface with hydraulic broom and spraying prime at the rate of 0.70 to 1.00 Kg. per Square metres using mechanical means as per MORD technical specification clause 502, and as per directions of Engineer - in- Charge The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	Per Square metre	256.00				
5	Providing and applying tack coat with Bitumen emulsion (RS-I) using emulsion distributor at the Rate of 0.275 kg per sqm on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	Per Square metre	256.00				



(2) (b)

6	Providing and laying seal coat sealing the voids in a bituminous surface laid to the specified levels, grade and cross fall using Type A, Type B and Type C as per Technical Specification Clause 510. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	Per Square metre	256.00			
7	Providing, laying and rolling of open-graded premix carpet of 20 mm thickness composed of 13.2 mm to 5.6 mm aggregates either using penetration grade bitumen or emulsion to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 80-100 kN static roller capacity, finished to required level and grades to be followed by seal coat of either Type A or Type B or Type C as per Technical Specification Clause 508. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	Per Square metre	256.00			
8	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-10 (M-Ten) and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	cum	22.75			
Total						

Executive Engineer
 Building Division
 H.N. D., Baijnath

3

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work :Construction of Pucca path from Prakash Chand House to Subhash Chand House Gbirkhoff ward No.4 (SI:-Providing and Laying Kharanja stone soiling and C C pavement at RD 0/00 to 0/250).				Estimate Cost: 1,95,000.00/- Earnest Money: 3,900.00/- Time Limit :One Month		
SCHEDULE OF WORKS						
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing and laying hard stone Soiling properly hand packed intersects with kharanja stone and consolidating with power / hand roller to requested gradient and camber including spreading watering and rolling of binding mortar or earth etc complete as per HPPWD specification 100 mm spread thickness finished work including materials and labour as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	37.50	Per Cubic metre			
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	18.75	Per Cubic metre			
	Total					

Executive Engineer
Bajjnath Division
H.P.P.W.D., Bajjnath

4

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : Pucca Path from House of Shri Nam Chand to House of Shri Kamlesh Chand Mohal Kudall .
(SH:-P/L C. C Pavement) (DEPOSIT WORK)

Estimate Cost: 95,012.00/-
Earnest Money: 1,900.00/-
Time Limit : One Month

SCHEDULE OF WORKS							Time Limit : One month
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P	
				Figures	Words		
1	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	13.87	Per Cubic metre				
	Total						

Executive Engineer
Bajjnath Division
M.P.P.W.D., Bajjnath


DNIT/DRAFT SCHEDULE OF QUANTITY

5 (a)

Name of work : Improvement of Black spot on Langhoo Jamrella Road road (Sub Head :P/F Crash Barrier at RD 3/120 to 3/190 . for removal of Black Spot)				Estimate Cost: 2,95,544.00/- Earnest Money: 6,000.00/- Time Limit : One Month		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	8.02	Per Cubic metre			
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	8.02	Per Cubic metre			

(5) (6)

3	Providing and erecting a "W" metal beam crash barrier comprising of 3mm thick corrugated sheet metal beam rail, 70cm above road / ground level, fixed on ISMC series channel vertical post, 150 x 75 x 5mm spaced 2m centre to centre, 1.8m high, 1.1m below ground / road level, all steel parts and fittings to be galvanized by hot dip process, all fittings to conform to IS: 1367 and IS 1364, metal beam rail to be fixed on the vertical post with a spacer of channel section 150x75x5mm, 330 mm long complete as per clause 810 as per the direction of Engineer-in-charge including entire carriage of materials within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	70.00	Rmt			
Total						


Executive Engineer
Bajjnath Division
H.P.P.W.D., Bajjnath



6

D.N.I.T/ SCHEDULE OF QUANTITY						
Name of Work:- C/O Pucca Path From Shashi House to Narender House G.P Chobin. (SH:- Providing and Laying Cement Concrete Pavement.) (DEPOSIT WORK)				Estimated Cost	74620.00	
				Earnest Money	1500.00	
				Time limit	Two Months	
Sr No.	Description of work	No.or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (Eighty to One Hundred Kilo Newton) static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading-II as per Technical Specification Clause 405.(63mm to 45mm) (sixty three millimeter to forty five millimeter).The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government	11.70	Per Cubic Meter			
2	Providing concrete for plain / reinforced concrete PCC Grade M-20 Nominal Mix 1:2:4 (one cement two sand four graded stone aggregate 20mm nominal size) in pavements, laid to required slop and camber in panels required including consolidation finishing and temping complete as per the direction of Engineer-in-charge including entire carriage of materials within all leads and lifts and other incidentals.The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government	7.80	Per Cubic Meter			
				Total		

[Signature]
Executive Engineer
Bajnath Division
H.P.P.W.D., Bajnath


DNIT/DRAFT SCHEDULE OF QUANTITY

(7) (a)

Name of work :- Balance work For C/O A.E Office Cum Residence at Bir (SH:- Providing Cement Primer , Arcylic Emulsion , WaterProof Apex Exterior Emulsion & P/L Paver block etc .)				Estimate Cost: 3,05,695.00 Earnest Money:6,200.00 Time Limit : Two Month		
Sr. n	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				Fig	Words	
1	Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour Two coats The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	676.73	Sqm			
2	Finishing wall with weather proof exterior grade emulsion of approved design (Apexultima) or its equarried on undecorated wall surfaces (two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc including sand paper smooth complete.The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	203.62	Sqm			
3	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface Water thinnable cement primer The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	880.35	Sqm			
4	Providing and fixing Hydraulic Door Closer anodized colour and shade with bolts and nuts screws etc. complete and technical specifications Including carriage of materials within all leads and lifts and other incidental The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	1.00	Each			
5	Providing and fixing Door spring anodized colour and shade with bolts and nuts screws etc. complete and technical specifications Including carriage of materials within all leads and lifts and other incidental The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	1.00	Each			
6	Providing and fixing Water Mixer with bolts and nuts screws etc. complete in all respect and technical specifications Including carriage of materials within all leads and lifts and other incidental The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	2.00	Each			
7	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (one Cement : two coarse sand : four graded stone aggregate 40 mm nominal size) .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	5.63	Cum.			

(7)(6)

	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (one Cement : two coarse sand : four graded stone aggregate 40 mm nominal size) .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	3.00	Cum.			
9.	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in Charge 60mm (sixty millimeter) thick cement concrete paver block of M-35 grade with approved colour, design & pattern..The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	75.00	Sqm			


 Executive Engineer
 Baljnath Division
 H.P.P.W.D., Baljnath

8

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work :- Construction of Bridge Over Binwa Khad on Uthra Surahi Pass Road at RD 15/150.
(SI: Prepration of Hydraulic Data .)

Estimate Cost: 60,000.00
Earnest Money: 1,200.00
Time Limit : Three Months

SCHEDULE OF WORKS

Sl. No.	Description of work	No. or Qty.	Unit	Rate to be entered by the Bidder in		AMOUNT Rs. P
				Figures	Words	
1	Prepration of Hydraulic data of Binwa Khad Complete in all respect , (i.e contour site plan 300 meter up and down stream side , cross section center , 50 , 150 and 300 meter up and down stream side , L-section of Khad and road) During approval of Hydraulic data from competent authority ,If any Correction / amendment has desired by the head office the same may be corrected as desired and directed and directed by the Engineer -Incharge .after approval the same should be submitted in fair form etc complete	1.00	Per Job			

Executive Engineer
Bijnath Division
H.P.R.W.D., Bijnath

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work :- Construction of Link Road to Harizna Basti Village Bhirdi Ward No. 4 km 0/00 to 1/200 . (Silt:-C/O Cause way from RD 0/835 to 0/865 and Edge wall at RD 0/845 to 0/855)				Estimate Cost: 2,17,118.00/- Earnest Money: 4,400.00/- Time Limit :One Month		
SCHEDULE OF WORKS						
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P.
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In - Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	1.01	Per Cum			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M ten) per cubic metre nominal mix 1:3:6 (one cement is to three sand is to six crushed stone agg. 20mm(twenty millimetre) nominal size) in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work in drain and open foundation as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	3.38	Per Cubic metre			
3	Providing laying spreading and compacting stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven decimal point two millimetre) nominal size at the rate of 0.20 cubic metre (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 cubic metre (zero decimal zero six) cubic metre per ten square metre to fill up the intersitices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications clause No. 405 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	6.86	Per Cubic Metre			

96

4	Construction of un-reinforced, dowel jointed at expansion and construction joint only, plain cement concrete pavement of thickness as per design, over a prepared sub base with 43(forty three) grade cement M-30 (thirty) grade, design mix cement concrete, coarse and fine aggregates conforming to IS:383(three hundred eighty three), maximum size of coarse aggregate not exceeding 25mm(twenty five millimeter) mixed in a concrete mixer of not less than 0.2 (zero point two) cubic meter capacity and appropriate weight batcher using approved mix design, laid in approved fixed side form work (steel channel) laying and fixing of 125(one hundred twenty five) micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge/culvert and construction joints, admixtures as approved, curing of concrete slabs using curing compound (where specified) and water, finishing to line and grade as per drawing and as per M.O.R.D. technical specification clause 1501 and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	23.70	Per cubic metre			
Total						

Executive Engineer
Baijnath Division
H.P.P.W.D., Baijnath



DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work :- C/O Baijnath Chobin Balander road km 0/00 to 14/200 .

(SI:- C/O B/wall for protection of Govt Primary School Bandiyam at RD 6/410 to 6/417.50)

Estimate Cost:1,37,896.00/-

Earnest Money: 2,800.00/-

Time Limit : One Month

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In - Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	9.00	Per Cum			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	26.85	Per Cum			
3	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals. Including entire carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	5.40	Per Cum			
4	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including entire carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	6.00	Each			
Total						

Executive Engineer
Baijnath Division
H.P.P.W.D., Baijnath

11

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work :- Additionality to complete under construction road at village order (under Deposit)
(SH:-P/L C. C Pavement & Kharanja Soling at km 0/700 to 0/760)

Estimate Cost: 1,92,375.00/-
Earnest Money: 3,900.00/-
Time Limit :One Month

SCHEDULE OF WORKS						
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing and laying hard stone Soling properly hand packed intersects with kharanja stone and consolidating with power / hand roller to requested gradient and camber including spreading watering and rolling of binding morrum or earth etc complete as per HPPWD specification 100 mm spread thickness finished work including materials and labour as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	22.50	Per Cubic metre			
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	22.50	Per Cubic metre			
Total						

Executive Engineer
Bajjnath Division
H.P.P.W.D., Bajjnath

(12) (a)

D.N.I.T/ SCHEDULE OF QUANTITY

Name of work:- C/O Community Bhawan Kachcha Khoo Mohal Matial.
(SH:- Plastering, Flooring, and Distemping of Community Bhawan).


Estimated Cost
Earnest Money
Time limit

118437.00
2400.00
Two Month /5

Sr No.	Description of work	No.or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1	15mm Cement plaster in single coat on the rough side of brick/ concrete/stone walls for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth. Cement Mortar (one Cement:six Sand). The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	173.26	Per Square Meter			
2	Distemping (two coats) with synthetic washable distemper of Asian/ Nerolac brand and manufacture and of required shade on undecorated wall surfaces to give an even shade over and including and priming coat with distemper primer of approved brand and manufacture after thoroughly brushing the surface free from mortar droppings and other foreign matter and also including preparing the surface even and sand papered smooth as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.	173.26	Per Square Meter			
3	Boulder filling dry hand packed tightly as under floor The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction of Engineer-in-charge including entire carriage of materials within all leads and lifts and other incidentals The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	5.25	Per Cubic Meter			
4	Providing concrete for plain / reinforced concrete PCC Grade M-20 Nominal Mix 1:2:4 (one cement two sand four graded stone aggregate 20mm nominal size) in pavements, laid to required slop and camber in panels required including consolidation finishing and temping complete as per the direction of Engineer-in-charge including entire carriage of materials within all leads and lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government (Flooring)	35.03	Per Square Meter			
5	Providing and fixing Glazed shutters for Doors, Windows and Windows using 4mm (Four millimetre) float glass panes 35 mm (thirty five millimetre) thick The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	5.76	Per Square Meter			
6	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.75 ltr/10 sqm of approved brand and manufacture. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government	11.52	Per Square Meter			

12 6

7	Applying priming coat with ready mixed pink or grey primer of apprived brand and manufacture on wood work.The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government	11.52	Per Square Meter			
TOTAL						


Executive Engineer
Bailnath Division
H.P.P.W.O., Bailnath

DNIT/DRAFT SCHEDULE OF QUANTITY

13/7

C/O Link road Sansai Dhandole to Jamthala LadhBharol Road Km 0/00 to 1/00.
(Sk:- C/O 900 mm Dia Hume pipe Culvert at RD 0/875)

Estimate Cost: 93,731.00/-
Earnest Money: 1900,00/-
Time Limit : One Month

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earthwork in excavation for all type of road structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m. (Fifty meters) dressing of sides and bottom and backfilling in trenches with excavated suitable material. The rate inclusive royalty malkana, toll texes, GST and other taxes imposed by the Govt.	37.45	Per Cubic metre			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M ten) per cubic metre nominal mix 1:3:6 (one cement is to three sand is to six crushed stone agg. 40mm(forty millimetre) nominal size) in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work and open in foundation as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate inclusive royalty malkana, toll texes, GST and other taxes imposed by the Govt.	3.21	Per Cubic metre			
3	Providing and laying mechanically mixed and vibrated plain/ cement concrete in sub structure for all type of structure complete using plain cement concrete grade M-15 (M fifteen) design mix with cement contents not less than 275 kg (two hundred seventy five kilogram) per cubic metre in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work in abutments as per drawings and M.O.R.D. technical specification section 800,900 & 1200 and curing complete including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate inclusive royalty malkana, toll texes, GST and other taxes imposed by the Govt.	9.63	Per Cubic metre			

laying (to level or slope) 900mm dia (nine hundred millimeter) diameter reinforced cement concrete pipes IS Class NP-2 for culverts in single row including fixing collar with cement mortar 1 : 2 (One cement : two sand) but excluding the cost of excavation, protection works, back filling, bedding concrete and masonry work in head walls and parapets as per drawing and M.O.R.D. technical specifications clause 1101 and as per direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.(Labour Rate) The rate inclusive royalty malkana, toll taxes, GST and other taxes imposed by the Govt.	7.50	Per Running metre			
TOTAL					

Executive Engineer
Bajjnath Division
H.P.P.W.D. Bajjnath

[Signature]

D.N.I.T/ SCHEDULE OF QUANTITY

Name of Work: C/O Ahju Bir Gunthar Road Km 0/00 to 6/00.
(SH: Construction of Hume Pipe & Wing wall for 900mm Dia Hume Pipe Culvert at RD 5/740).

Estimated Cost 218328.00
Earnest Money 4400.00
Time limit Two Months

Sr No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT	
				Figure	Words	Rs.	P
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m. (fifty meter) dressing of sides and bottom and backfilling in trenches with excavated suitable material, as per the entire satisfaction and direction of Engineer-in-Charge. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	37.63	Cum				
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M ten) per cubic metre nominal mix 1:3:6 (one cement is to three sand is to six crushed stone agg. 40mm(forty millimetre) nominal size) in or under water and curing complete including pumping or hauling out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work and open in foundation as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and to the entire satisfaction and direction of Engineer - in- Charge including hauling carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	2.51	Cum				
3	Providing concrete for plain reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 804, 805, 806, 807, 1202 and 1204 M-15 (1:2.5:5) (one: cement two and half: sand five: stone aggregate) The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	9.44	Cum				
4	Providing and laying cement concrete for plain reinforcement concrete in open foundation complete as per drawing and technical specifications clouse 802 , 803 , 1202, 1203, (1:5:10 40 mm aggregate size) and curing complete including cost of form work in R/Wall or B/Wall including entire carriage of material within all leads and lifts and other incidental. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	21.46	Cum				

(14) (b)

5	Back filling behind abutments, wing walls and return walls complete as per drawing and M.O.R.D. technical specification clause 1203 and 1604 and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	4.59	Cum			
6	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1204.3.7 including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect and as per the direction of Engineer-In-Charge.The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	12.00	Each			
7	Constraction of embankment with approved material deposited at site from borowpits and excavation from drain and foundation of other structures graded and compacted to meet requirement to tables 300.1 and 300.2 as per tecgnical specification clause 301.5 as per the direction of Engineer-In-Charge.The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	0.69	Cum			
8	Providing and laying reinforced cement concrete pipe NP2 for culverts first class bedding of granular material (light duty)R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete 900 mm (Nine Hundred milimeter) dia. R.C.C. pipe as per the entire satisfaction and direction of Engineer-in-Charge.The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	5.00	Rmt			
TOTAL						

Executive Engineer
Bajjnath Division
H.P.R.W.D. Bajjnath

SCHEDULE OF QUANTITY

Name of Work:- C/O Link Road to Village Banwar Kuran to village Uihdhar Km 0/00 to 1/800.
(SH:- Providing and Laying Kharanja Stone Soling in Km 0/00 to 0/400.)

Estimated Cost 295021.00
Earnest Money 6000.00
Time limit Two Months

Sr No.	Description of work	No.or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1	Preparation of sub grade by dressing to comber (Earth work for the cutting involved for sub-grade to be paid for separately depending upon the classification of soil completed as per HP.PWD specifications. as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals satisfaction. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	879.38	Per Sqm			
2	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (Hundred millimeter) spread thickness (finished work including materials and labour) as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals satisfaction. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	131.91	Per Cubic Meter			

Executive Engineer
Baijnath Division
HPPWD Baijnath

16 (a)

D.N.I.T/ SCHEDULE OF QUANTITY

Name of Work:- C/O Rakkar Rajot Noun Road Km 0/00 to 4/00.
(SH:- C/O 0.60 Mtr. Span RCC Slab Culvert at RD 3/900.)

Estimated Cost: Rs. 104284.00

Earnest Money: Rs. 2,100.00

Time Limit : Two Months

SCHEDULE OF WORKS

Sr No.	Description of work	No.or Qty.	Unit	Estimated Rate		AMOUNT	
				Figure	Words	Rs.	P
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, (Fifty meters) dressing of sides and bottom and backfilling in trenches with excavated suitable material. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government	15.39	Cum				
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 M-10 (1:3:6) (one cement: three coarse sand: six graded stone aggregate 40mm (forty milimeter) nominal size) The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government	2.59	Cum				
3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 804, 805, 806, 807, 1202 and 1204 M-15 (1:2.5:5) (one cement: two point five coarse sand: five graded stone aggregate) The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government	9.93	Cum				
4	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 800, 1205.4 and 1205.5 RCC M-25 (1:1.5:3) (one cement: one point five coarse sand: three graded stone aggregate 20mm (twenty milimeter) nominal size) The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government	1.68	Cum				

(16) (b)

5	Steel Reinforcement for RCC work including straightening, Cutting, Bending, placing in position and binding all complete upto plinth level. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government	150	Kg			
	TOTAL					


Executive Engineer
Barghosh Division
H.P.W.D. Bijnath

D.N.I.T/ SCHEDULE OF QUANTITY

Name of work :- Restoration of Rain Damages on Ahju Bir Gunchar Road km 0/00 to 6/00 .
(SH:- C/O U- Shape Drain at RD 5/450 to 5/550.)

Estimated Cost 97812.00
Earnest Money 2000.00
Time limit Two Months

Sr No.	Description of work	No.or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5m (one point fifty meter) in width or 10 sqm), including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point fifty meter) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m(Fifty meter).All kinds of soil.with in all leads by any mode of transportation and other incidental ,as per direction and entire satisfaction of Engineer -in -charge. The rate inclusive royalty malkana, toll texes, GST and other taxes imposed by the Govt.	31.50	Per Cum			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M ten) per cubic metre nominal mix 1:3:6 (one cement is to three sand is to six crushed stone agg. 40mm(forty millimetre) nominal size) in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work and open in foundation as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and to the entire satisfaction and direction of Engineer - in- Charge. The rate inclusive royalty malkana, toll texes, GST and other taxes imposed by the Govt.	15.75	Per Cum			

Executive Engineer
Bajjnath Division
H.P.P.W.D. Bajjnath


DNIT/DRAFT SCHEDULE OF QUANTITY

(18) (9)

Name of work :Construction of AHC Building at Sansal . (SH: C/O U-Shape Drain and P/L Kharuja stone soling and C C pavement , wall Painting , steel painting etc .)				Estimate Cost: 1,73,854.00/- Earnest Money: 3,500.00/- Time Limit : Two Month		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	11.94	Cum			

2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M ten) per cubic metre nominal mix 1:3:6 (one cement is to three sand is to six crushed stone agg. 40mm(forty millimetre) nominal size) in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work and open in foundation as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	7.05	Cum		
3	Painting on undecorated wall surfaces with apex weather proof exterior emulsion of asian / nerolac two coats to give an even shade with enamel white or other than white including thoroughly brooming the surface to remove all dirt dust mortar dirt and other foreign matter. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	111.00	Per square metre		
4	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint. In gratings framed guard bars, ladders, railing, brackets and similar works. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	72.90	Kilogram		
5	Painting two or more coats (including priming costs) on new steel and other metal surfaces with Deluxe multi surface paint to give an even shade including cleaning the surfaces of all dirt, dust and other foreign matters complete as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	33.00	Per square metre		

6	Providing and laying hard stone soiling properly hand packed intersects with kharnja stone and consolidating with power / hand road roller to the requested gradient and camber including spreading watering and rolling of binding morrum or earth etc Complete as per HPPWD specification 100 mm spread thickness (finished work including materilas and labour as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and entire satisfaction The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	12.00	Cum				(12) (e)
7	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Milimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals satisfaction The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	12.00	Cum				
Total							


 Executive Engineer
 Division
 In

