




Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:- ee-baij-hp@nic.in

CERTIFICATE

CERTIFIED THAT THE TENDERS OF WORKS, AS
CALLED VIDE THIS OFFICE LETTER NO.PWD/BD/TA/NIT/2023-24/-
15825-75 DATED 10-01-2024 ARE URGENT NATURE
AND PUBLIC INTEREST.


Executive Engineer,
Baijnath Division,
HP.PWD, Baijnath.



Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:- ee-baij-hp@nic.in

"NOTICE INVITING TENDER"

Sealed item rate of tender form No. 6 & 8 are hereby invited by the Executive Engineer, Baijnath Division H.P.PWD., Baijnath on behalf of the Governor of HP for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rule and also registered under the HP General Sales Tax act 1968 so as to reach in this office on or before **24.01.2024** up to **11.30 A.M** and will be opened on the same day at **12.00 Noon** in the presence of intending contractors or their authorized representatives. The tender forms can be had from his office against cash payment (Non refundable) on **23.01.2024 between 2.00 PM up to 4.30 P.M** and the application for issue of tender forms shall be received on **22.01.2024 up to 12.00 Noon**.

The earnest money in the shape of National Saving Certificate/Time Deposit accounts/Saving Accounts in any Post Office/Bank in H.P. duly pledged in favour of the XEN H.P.PWD., Baijnath must be accompanied with the each tender. Conditional/incomplete tenders and the tenders received without earnest money as mentioned above will be similarly rejected. the offer of the tender shall be kept open for 75 days. The XEN reserves the right to accept or reject any or all tenders or to drop the proposal of the tender without assigning any reasons.

Sr. No.	Name of work.	Amount put to tender/Estimated cost.	Earnest Money	Cost of tender form	Time limit
1	C/O A.E. HPPWD office cum Residence Building at Bir (SH: C/O Boundary wall and Main gate)	Rs.4,98,090/-	Rs.10,000/-	Rs.350/-	Three Months

Terms and conditions:-

1. The contractor should be registered as dealer under H.P. GST Tax Act, 2018 and also produce the Tin number, H.P. sales Tax clearance certificate from the Excise and Taxation Department.
2. The Pan Number, latest Income Tax clearance certificate and EPF No (Where applicable) duly attached with the application.
3. The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained.
4. In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
5. Only two tenders form will be issued to the contractor/firm which may be noted.
6. The contractor will also have to attach the labour employer license from the labour office with the application.
7. Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
8. The contractor shall be responsible for rectifying defects noticed within One year from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
9. The contractor shall have all required machinery such as Truck/ Tipper, Mixture, water tanker Vibrator etc or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
10. The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an under taking viz he will get complete the works in hand before award of work with in schedule time.
11. All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
12. The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/ permit.

Executive Engineer,
Baijnath Division.,
H.P.PWD., Baijnath.

For & On behalf of the governor of H.P.

NO:-PWD/BD/TA/NIT/2023-24/-

15825-75

Dated:-10.01.2024

1. Copy to the F.C. cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
2. The Engineer-in-chief, HPPWD, Shimla.
3. The Chief Engineer (MZ), HPPWD, Mandi.
4. The Superintending Engineer, JNR. Circle HPPWD, Joginder Nagar.
5. All the Assistant Engineer working under this Division.
6. Drawing Branch in this office.
7. Notice Board.
8. The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
Baijnath Division.,
H.P.PWD., Baijnath.

(1) (a)

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work: - C/O A.E HPPWD Office cum Residence Building at Bir .
(SH:C/O Boundary wall and Main gate .)

Estimate Cost: 4,98,090.00
Earnest Money: 10,000 .00
Time Limit :Three Months


SCHEDULE OF WORKS

Sl. No.	Description of work	No.or Qty.	Unit	Rate to be entered by the Bidder		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (one point five metre) in width or 10 sqm (ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m,(one point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m (fifty metre).All kinds of soil.The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	34.46	cum			
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:6:12 (one cement : six coarse twelve sand): ten graded stone aggregate 40 mm (forty milimeter) nominal size The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	6.16	cum			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:2:4 (one cement : two coarse sand) : four graded stone aggregate 20 mm (twenty millimeter)nominal size The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	0.65	cum			
4	Providing and laying in position specified grade of reinforced cement concrete, including the cost of centering, shuttering, finishing and reinforcement - All work up to floor two level : 1:2:4 (one cement : Two coarse sand) :four graded stone aggregate 20 mm (Twenty millimeter) nominal size and Clause 5.9.6 for form work. Clause 5.1.3 The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	1.30	cum			

5	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (one cement : six coarse sand : twelve graded stone aggregate 20 mm (twenty millimeter) nominal size upto plinth level with :Cement mortar 1:6 (one cement : six coarse sand) The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	15.80	cum			
6	Coursed rubble masonry (second sort) with hard stone in foundation & plinth with :Cement mortar 1:6 (one cement : six coarse sand) The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	4.50	cum			
7	Providing and laying damp-proof course 50mm (fifty millimeter) thick with cement concrete 1:2:4 (one cement : two coarse sand) : four graded stone aggregate 20mm nominal size). Clause 4.11 The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	30.00	sqm			
8	Providing and fixing up to floor five level precast cement concrete hollow block, including hoisting and setting in position with cement mortar 1:3 (one cement : three coarse sand), cost of required centering, shuttering complete. 1:1½:3 (one Cement: one point five coarse sand): three graded stone aggregate 20 (Twenty) mm nominal size). Clause 4.8.1 The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	31.44	cum			
9	Providing and laying cement concrete in retaining walls, walls (any thickness) including columns, piers, abutments, pillars, string or lacing courses, parapets, coping, bed blocks, anchor blocks, etc. up to floor five level, excluding the cost of centering, shuttering and finishing: 1:2:4 (1 Cement: 2 coarse sand :4 graded stone aggregate 20 mm nominal size). Clause 4.2.3	1.79	cum			
10	12 mm (twelve) cement plaster of mix 1:4 (one cement: four coarse sand) on rough side of wall. Clause 13.4.1 The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	174.66	sqm			

(1) (2)

11	Finishing walls with Acrylic Smooth exterior paint of required shade New work (Two or more coat applied @ 1.67 ltr 10 sqm (one point six seven ltr per ten square meter) over and including priming coat of exterior primer applied @ 2.20 kg 10 sqm (two point two zero kilogram per ten square meter). Clause 13.46.1 The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	174.66	sqm			
12	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete with Mild steel and Medium Tensile steel bars. Clause 5.22 The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	310.00	kg			
13	Steel work welded in built up sections, trusses and frame work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint. In gratings framed guard bars, ladders, railing, brackets and similar works. Clause 10.1 The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	225.00	kg			


 Executive Engineer
 Belinath Division

Date: 22/01/2024 2