

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

Short terms tenders on form 6&8 are hereby invited by the Executive Engineer Bangana Division HP.PWD Bangana on behalf of the Governor of H.P. for the following works from the approved and eligible contractors/firms of appropriate class enlisted in HPPWD as per latest instructions so as to reach and open in his office as per time schedule given below The offer of the tender will be kept open for 45 days from the date of opening of the tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

1. Date of receipt of applications for the tender
Form a/w requisite documents: -
2. Date of issue /sale of tender forms against
Cash payment (Non-refundable):-
3. Date of receipt of tenders: -
4. Date of opening of tenders: -

19.01.2024 upto 2.00 PM.

20.01.2024 2:00 to 5.00 PM.

22.01.2024 upto 10.30 A.M.

22.01.2024 at 11.00 A.M.

Sr. No.	Name of Work	Estimated Cost	EMD	Time Limit	Cost of Tender	Eligible class of Contractor
1	A/R & M/O Majher to Madhan via Balh Kholi road km. 0/000 to 8/825(Maintenance of Berms and Drain)	385056.00	7800.00	Two Month	350	Class D
2	C/O Link road from Village Jasana to Asari Guffa KM. 0/000 0/750(SH:- C/O 900 mm dia Hume Pipe Culvert at RD. 0/260, 0/400,0/530)	494555.00	9900.00	Two Month	350	Class-D
3	Balance work of P.H.C. Building at Chalola (SH:- Balance work of building portion)	441458.00	8900.00	Two Month	350	Class-D
4	C/O Link road to Village Matoh km. 0/000 to 1/000(SH:- C/O Edge wall in km. 0/156 to 0/195, 0/210 to 0/240 & 0/338 to 0/360)	470811.00	9500.00	Two Month	350	Class-D
5	Special Repair of Junior Engineer office Mechanical work shop at Dumkhar Tehsil Bangana Distt. Una (SH:- C/O attached bathroom in J.E. office , Distempering & Painting etc.)	308239.00	9800.00	Two Month	350	Class-D
6	C/O Link road from Basal Baba Rudru Dhamandri road to Village Lower Nari km. 0/000 to 0/700(SH: P/L Interlocking paver block in km. 0/130 to 0/208)	498108.00	10000.00	Two Month	350	Class D
7	Improvement of Black Spot on Samoor Lamlehri road (C/O R/Wall and Crash Berrier in km. 0/315 to 0/355) Road Safety	399484.00	8000.00	Two Month	350	Class-D
8	C/O Link road Lambobal to Fatewal km. 0/000 to 1/750 (SH:-C/O C.C. Pavement in km. 0/000 to 0/139)under MMGSY	499421.00	10000.00	Two Month	350	Class-D
9	C/O Road from Upper Thana to Kut Chhaterar to Alshan Haizen Basti & Village Lower Thana km. 0/000 to 6/615(SH:- Formation utting in km. 3/375 to 3/495 & 6/450 to 6/495)	498356.00	10000.00	Two Month	350	Class-D
10	C/O Link rod Handola to Panjpeeri Gugga Zahir Mandir (SH:- C/O C.C. Pavement in km. 0/000 to 0/139)under MMGSY	499421.00	10000.00	Two Month	350	Class-D
11	C/O Rain Shelter in Village Tanoh on Una Aghar Mandi Road	485207.00	9800.00	Two Month	350	Class D
12	C/O Rain Shelter in Village Tihra on T.M.B.D. Road	485207.00	9800.00	Two Month	350	Class-D

13	A/R & M/O Link road to Mohalla Parohitan (Dhamandri) (Sh:- C/O R/Wall in km. 0/090 to 0/107)	321800.00	6500.00	Two Month	350	Class-D
14	R.R.D. on U.A.M. Road km. 19/000 to 39/700 (SH:- C/O U-Shape Drain in km. 25/ to 25/ & P/L 90mm me Pipe culvert in km. 25/872 to 25/897)	474700.00	9500.00	Two Month	350	Class-D
15	Repair and Maintenance of Link Road to Pirnigah Pir Gous Gyahrwin wala km. 0/000 to 0/600 (SH:- P/L Interlocking Paver Block in km. 0/166 to 0/209) Deposit Work	498477.00	10000.00	Two Month	350	Class-D


The Earnest money in the shape of National Saving certificate/Time deposit/Saving account of any post office or FDR of Nationalised Bank duly pledged in the name of undersigned must be accompanied with each tender. The conditional tender and tender not accompanying the earnest money in the proper mode of deposit will summarily be rejected.

The Tender documents to be sent should have invariably be waxed in sealed cover and in failure of that those will not be entertained.


The Copy of valid enlistment, GST Registration No., Income Tax PAN No & EPF No. must be attached with application.

SPECIAL CONDITION:-

1. The tender form will be issued to those contractors who have relevant machinery and equipment, the list of which may be attached with their applications. (The proof of ownership of machinery/legal tie up arrangement).
2. The tender form will not be issued to those contractors who have already two works in hand. The earnest money for the above work should be submitted with the application for the purchase of the tender forms. The application received without earnest money shall summarily be rejected.
3. The conditional/ambiguous/telegraphic tenders or tender by fax shall not entertained/considered in any case.


Executive Engineer
Bangana Division
HPPWD Bangana.

Dated 12-01-24


Executive Engineer,
Bangana Division,
HPPWD Bangana.

No.PW/BGN/CB/T-1/2023-24-

8415-44

Copy forwarded to the following for information and necessary action:-

1. The Engineer-in-Chief HPPWD. Nirman Bhawan Shimla.
2. All the Assistant Engineer, working under this Division.
3. Various Contractors working under this Division.
4. Notice Board.

Percentage BoQ.

Name of work:- A/R & M/O Majher to Madan via Balh Kholi road km. 0/000 to 8/825 (SH:- Maintenance of Berms and Drain n km. 0/000 to 8/825)

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter Bidder name and values only

PRICE SCHEDULE

Sr. No.	Description of work	Estimated Cost		Earnest Money	7800.00	Time Limit	Two Months
		Quantity	Unit				
1	Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	4320.00	Per Square meter	41.30	178416.00		Rupees For One - Paid Thirty On
2	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	9600.00	Per Square meter	16.00	153600.00		Rupees Six Only
3	Construction of unlined surface drain in all kinds and classification of soil average cross sectional area 0.40 (Zero point forty) square metre in soil to specified lines, grades, levels and dimension. Excavated materials to be used in embankment with any lift and lead as per M.O.R.D. technical specification Clause 307 including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1360.00	Per Running metre	39.00	53040.00		Rupees Thir Nine Only
Total in Figures						385056.00	Rupees Three Lak Eighty Five Thousand & Fifty Six Only
Quoted Rate in Figures				Excess(+)			
				Less(-)			


 Executive Engineer
 Bangana Division
 H.P.P.W.D. Bangana

Percentage BoQ.


Name of work:- C/O Link road from Village Jasana to Asari Guffa km. 0/000 to 0/750(SH:- C/O 900mm dia Hume pipe culver at Rd. 0/260,0/400, 0,530)

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bid are allowed to enter Bidder name and values only

Sr. No.	Description of work	Estimated Cost	Quantity	Earnest Money Unit	Estimated Rate in Words	Time Limit Total amount without Taxes	Two Month AMOUNT Rs. P
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	494555.00	51.29	Per Cubic metre.	364.00	18670.00	Rupees Three Hundred & Sixty Four Only
2	Providing and laying cement concrete 1:4:8 (One cement : four coarse sand : eight graded crushed stone aggregate 40mm (forty millimetre) nominal size)mechanically mixed and curing complete excluding cost of form work upto all work plinth level including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST , labour cess or other taxes imposed by the Government.	48.16	Per Cubic metre.	3880.00	186861.00	Rupees Three Thousand Eight Hundred & Eighty Only	
3	Providing and laying cement concrete work 1:3:6 (one cement: three sand:six graded stone aggregate) 40mm (forty millimetre) nominal size in open foundation mechanically mixed and vibrated including curing complete, including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge, including carriage of material within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the	43.25	Per Cubic metre.	4582.00	198172.00	Rupees Four Thousand Five Hundred & Eighty Two Only	

Sr. No.	Description of work	Quantity	Unit	Estimated Rate in Words	Total amount without Taxes	AMOUNT Rs. P
4	Providing and laying 900mm(nine hundred millimetre) dia reinforced cement concrete pipe NP-2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2(one cement:two sand) but excluding excavation protection work, back filling, concrete and masonry work in head walls and parapets as per technical specifications clause -1106 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana , toll tax,GST,labour cess or other taxes imposed by the Government.	18.75	Per Running meter	3728.00	69900.00	Rupees Three Thousand Seven Hundred & Twenty Eight Only
5	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre) dia PVC pipe make of (D-plast) / Finolex,) working pressure not less than 4.5 (four point five) kg/cm ² extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	24.000	Each	297.00	7128.00	Rupees Two Hundred & Ninty Seven Only
6	Back filling with granular material behind return wall, abutment, wing wall and retaining walls complete as per drawing and technical specifications clause 1204.3.8 and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkhana, toll tax, sale tax goods service tax, labour cess or other taxes imposed by the Government.	17.28	Per cubic metre	800.00	13824.00	Rupees Eight Hundred On
Total in Figures					494555.00	Rupees Four Lakh Nin Four Thousand Fiv Hundred & Fifty Five Only
Quoted Rate in Figures				Excess(+) Less(-)		


 Executive Engineer
 Bangana Division
 H.P.P.W.D. Bangana


Percentage BoQ.

Name of work:- Balance work for the C/O P.H.C. Building at Chalola (SH:- C/O Approach road to P.H.C. Building at Chalola)

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter Bidder name and values only

Sr. No.	Description of work	Estimated Cost		Quantity	Earnest Money Unit	Estimated Rate in Words	Time Limit Total amount without Taxes	Two Month AMOUNT Rs.
		441458.00	8900.00					
1	Providing and laying cement concrete 1:4:8 (One cement : four coarse sand : eight graded crushed stone aggregate 40mm (forty millimetre) nominal size)mechanically mixed and curing complete excluding cost of form work upto all work plinth level including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST , labour cess or other taxes imposed by the Government.	20.46	Per Cubic metre.	4296.00	87896.00	Rupees Four Thousand and Eight Hundred and Ninety Six (4296.00)		
2	Construction of pavement with 80mm (eighty millimetre) thick concrete blocks conforming to clause 1504.2.1 of MORD specifications, paved and compacted over a thin bedding of sand layers (material meeting the requirement of Table 1500.6 of these specifications) of specified grading to be spread over a properly constructed and profiled base course and bounded by properly edge restraints conforming to clause 1504.2.2 and 1504.2.3 of these specifications and complete the work to the satisfaction of Junior Engineer and Assistant Engineer of	272.81	Per Square Meter	1296.00	353562.00	Rupees One Thousand and Three Hundred and Fifty Six (1296.00)		
Total in Figures						441458.00		
Quoted Rate in Figures		Excess(+)		Less(-)				


 Executive Engineer
 Banganga Division
 H.P.P.W.D. Banganga

Percentage BoQ.


Name of work:- C/O Link road to Village Matoh km. 0/000 to 1/000(SH:- C/O Edge wall in km. 0/156 to 0/195, 0/210 to 0/240 & 0/338 to 0/360)

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bids are allowed to enter Bidder name and values only

Sr. No.	Description of work	Estimated Cost	470811.00	Quantity	Earnest Money	Unit	9500.00	Estimated Rate in Words	491.47	Total amount without Taxes	16774.00	Two Months
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	34.13	Per Cubic metre.	491.47	16774.00	Rupees Four Hundred Ninety Nine Paise Four Seven Or						
2	Providing and laying cement concrete 1:4:8 (One cement : four coarse sand : eight graded crushed stone aggregate 40mm (forty millimetre) nominal size)mechanically mixed and curing complete excluding cost of form work upto all work plinth level including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST , labour cess or other taxes imposed by the Government.	101.78	Per Cubic metre.	3840.00	390835.00	Rupees Three Thousand Eight Hundred Forty Or						
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe make of (D-plast) / Finolex,) working pressure not less than 4.5 (four point five) kg/cm² extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	90.000	Each	276.00	24840.00	Rupees Two Hundred & Seventy Six Only						

Sr. No.	Description of work	Quantity	Unit	Estimated Rate in Words	Total amount without Taxes	AMOU Rs.
	Back filling with granular material behind return wall, abutment, wing wall and retaining walls complete as per drawing and technical specifications clause 1204.3.8 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax goods service tax, labour cess or other taxes imposed by the Government.	32.76	Per cubic metre	1171.00	38362.00	Rupees Thousand Hundred Seventy Seven Only
Total in Figures					470811.00	Rupees Four L Seventy Thousand Eight Hundred Eleven Only
	Quoted Rate in Figures			Excess(+) Less(-)		


 Executive Engineer
 Banganga Division
 H.P.P.W.D. Banganga

Percentage BoQ.

Name of work:- Special Repair of Junior Engineer office Mechanical work shop at Dumkhar Tehsil Bangara Dist. Una (SH:- C/O attached bathroom in J.E. office, Distempereing & Paint etc.)

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter Bidder name and values only

Sr. No.		Description of work	Estimated Cost	Quantity	Earnest Money Unit	6200.00 Estimated Rate in Words	Time Limit	Two Mon
1		Earth work by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains in ordinary rock / all kind of soil (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, upto all leads and lifts, including getting out the excavated soil and disposal of surplus excavated soil as directed, within all lead and lifts and disposed earth to be levelled and neatly dressed as directed by Engineer-in-charge all leads and lifts including clearing of jungle, Pick Jumper work and then disposing of all surplus unserviceable excavated earth as directed by the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, Labour Cess or other taxes imposed by the Government.	308239.00	7.13	Per cubic metre	297.90	2124.00	Rupees T Hundred Ninety Seven Paise Nin Only
2		Providing form work with steel plates 3.15mm (three point fifteen millimeter) thick welded with angle iron in frame 30x30x5mm (thirty into thirty into five millimeter) so as to give a fair finish including centring, shuttering, strutting and propping etcetera with wooden battens and ballies upto any height of propping and centring below supporting floor to ceiling upto any height and removal of the same for in-situ reinforced cement concrete and plain concrete work as per HPPWD specifications in Suspended floors, roofs, landings, balconies and access platforms per the direction by the Engineer in charge upto any floor level including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	18.00	Per Square Meter	499.70	8995.00	Rupees F Hundred Ninety Nine Paise Seven Only	
3		Providing and laying in position cement concrete 1:2:4 (One cement : two coarse sand : four graded crushed stone aggregate 40mm (forty millimetre) nominal size)mechanically mixed and curing complete excluding cost of form work upto all work foundation and plinth level including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST , labour cess or other taxes imposed by the Government.	2.38	Per cubic metre	5237.60	12465.00	Rupees F Thousand T Hundred Thirty Seven Paise Seven Only	
4		Providing Fe-500D for steel reinforcement make of SAIL, TISCO, RINL, JINDAL, PANTHER of JSPL, SHAYAM STEEL as per structural design for reinforced cement concrete work including straightening, cutting, bending, binding and placing in position complete in all height including cost of binding wire upto floor all level including carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	286.00	Per Kilo Gramme	105.50	30173.00	Rupees O Hundred Fourty Five Paise Fifty Only	
5		Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to any floor level including scaffolding in all shapes and sizes in cement mortar 1:6 (one cement: six coarse sand) as per the direction by the Engineer in charge including carriage of materials with in all leads and lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	5.97	Per Cubic metre.	7035.00	41999.00	Rupees Sev Thousand & Thirty Five Only	

Sl. No.	Description of work	Quantity	Unit	Estimated Rate in Words	Total amount without Taxes	AMOUNT Rs.
6	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make Hindalco, Jindal, Indian Aluminium Company conforming to IS- 733 and IS- 1285, fixing with dash fasteners of required dia and size, including necessary fitting up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, milled and joined mechanically wherever required including cleat angle. Aluminium snap heading for glazing/ paneling, C.P. brass/ stainless steel screws, all complete for fixed portion Polyester powder coated aluminium (minimum thickness of polyester powder coating 50 micron) complete upto all floor level as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) including carriage of materials with in all leads and lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	60.54	Per Kilogram ^e	471.60	28551.00	Rupees Five Hundred Seventy One Paise Six Only
7	Providing and fixing 300x16mm aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete as per the direction by the Engineer-in-charge including entire carriage of materials with in all leads and lifts including other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	1.00	Each	365.00	365.00	Rupees Three Hundred Sixty Five Only
8	Providing and fixing 250x16mm aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete as per the direction by the Engineer-in-charge including entire carriage of materials with in all leads and lifts including other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	1.00	Each	303.70	304.00	Rupees Three Hundred Three - Paise Seventy One
9	Providing and fixing 125mm (one hundred twenty five millimeter) aluminium handles, ISI marked, anodized (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete upto all floor level as per the direction by the Engineer-in-charge including entire carriage of materials with in all leads and lifts including other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	2.00	Each	65.70	131.00	Rupees Sixty Five - Paise Seventy One
10	Providing and fixing 100mm (one hundred millimeter) aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete upto all floor level as per the direction by the Engineer-in-charge including entire carriage of materials with in all leads and lifts including other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	2.00	Each	62.80	126.00	Rupees Sixty Two - Paise Eighty One
11	Providing and fixing 200x10mm (two hundred into ten millimeter) aluminium tower bolts, ISI marked, anodized (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete as per the direction by the Engineer-in-charge including entire carriage of materials with in all leads and lifts including other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	2.00	Each	110.50	221.00	Rupees One Hundred & Twenty One Paise Only
12	Providing and fixing 150x10mm (one hundred fifty into ten millimeter) aluminium tower bolts, ISI marked, anodized (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete as per the direction by the Engineer-in-charge including entire carriage of materials with in all leads and lifts including other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	2.00	Each	105.20	210.00	Rupees One Hundred & Five - Paise Twenty One

Sr. No.	Description of work	Quantity	Unit	Estimated Rate in Words	Total amount without Taxes	AMOUNT Rs.
13	Providing and fixing 10mm thick anti skid water proof stain and impact resistant heavy duty vetrifed tiles Nitro or equivalent 450x450mm x10mm manufactured of approved shade and colour in flooring, treads of steps and landings laid over 12mm thick cement mortar 1:3 (1 cement: 3 sand) jointed with cement slurry mixed with pigment to match the shade of tiles as required complete, including entire carriage of materials with in all leads and lifts including other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	22.38	Per Square Meter	1650.51	36938.00	Rupees (Thousand) Hundred & Fifty - Paise Fifty One
14	Providing and laying Duro stone vetrifed tiles (300x300mmx10mm) in grey/coloured or of approved shade in flooring, treads of steps and landing laid on a bed of 12mm thick cement mortar 1:3 (1 cement: 3 sand) laid over and jointed with neat cement slurry finished with flush pointing in white cement mixed with pigment of required shade to match the shade of tiles complete.including entire carriage of materials with in all leads and lifts including other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	13.80	Per Square Meter	1796.50	24792.00	Rupees C Thousand Seven Hun & Ninety S Paise Fif
15	Providing and laying Duro stone vetrifed tiles (300x300mmx8mm) in grey/ coloured of required shade in skirting risers of steps and dados on 12mm thick cement mortar 1:3 (ement: 3 sand) laid over and jointed with neat cement slurry finished with flush pointing in white cement mixed with pigment of required shade to match the shade of tiles complete.including entire carriage of materials with in all leads and lifts including other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	1.32	Per Square Meter	1750.70	2311.00	Rupees O Thousand Seven Hun & Fifty - P Seventy O
16	Providing and fixing 110mm (one hundred ten millimeter) diameter on wall face unplasticised Rigid PVC rain water pipesof Diplast/ Finolex, Supreme, AKG, Prince, Kisan, SFMC make having working pressure 4.00 kg (four point zero zero kilogram) per Square centimeter conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm (ten millimeter) gap for thermal expansion.-Single socketed pipes complete upto all floor level as per the direction by the Engineer in charge including carriage of materials with in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	3.50	Per Running meter	121.00	424.00	Rupees O Hundred Twenty O Only
17	Providing and fixing 110mm (one hundred ten millimeter) diameter on wall face unplasticised Rigid PVC rain water pipes of Diplast/ Finolex, Supreme, AKG, Prince, Kisan, SFMC make having working pressure 4.00 kg (four point zero zero kilogram) per Square centimeter conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm (ten millimeter) gap for thermal expansion.-Single socketed pipes complete upto all floor level as per the direction by the Engineer in charge including carriage of materials with in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2.00	Each	236.00	472.00	Rupees Two Hundred & Thirty Six Only
18	Providing and fixing 100mm (one hundred millimeter) PVC plain bend Diplast/ Finolex, Supreme, AKG, Prince, Kisan, SFMC make on wall face unplasticised -PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm (ten millimeter) gap for thermal expansion complete upto all floor level as per the direction by the Engineer in charge including carriage of materials with in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2.00	Each	208.80	418.00	Rupees Two Hundred & Eight - Paise Eighty Onl
19	Providing 6mm cement plaster to ceiling in cement mortar 1:3 (one cement : three sand) including carriage of materials within all leads and lifts in all floor levels, as per the direction by Engineer in charge including carriage of material within all leads lifts and other incidentals the rate inclusive of octroi,royalty,malkana and all type of taxes imposed by the Govt.	18.30	Per Square metre.	197.80	3620.00	Rupees One Hundred & Ninety Seven
20	15mm (fifteen millimeter) Cement plaster on the rough side of single or half brick wall of mix cement mortar 1:6 (one cement: six fine sand) in any floor level/any height as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	29.59	Per Square metre.	255.00	7545.00	Rupees Two Hundred & Fifty Five Only

Sr. No.	Description of work	Quantity	Unit	Estimated Rate in Words	Total amount without Taxes	AMOUNT Rs.
21	Providing and applying white cement based putty JK wall Putty/Birla white Putty of average thickness 1 mm (one millimeter), of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete upto all floor level/height as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	11.00	Per Square metre.	61.00	671.00	Rupees S S One On
22	Distemping two coat with 1st quality acrylic distemper, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacturer, including applying additional coats wherever required, to achieve even shade and colour complete upto all floor level/any height including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge . The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	104.06	Per Square metre.	94.80	9865.00	Rupees Ni Four - Pa Eighty O
23	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.Sintex make triple layer (1000 liter or 2000 liter each capacity) complete upto all floor level including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	1000.00	Per Liter	12.30	12300.00	Rupees Tw - Paise Th Only
24	Providing and fixing 15mm (fifteen millimeter) nominal ball valve (brass) of approved quality make of Zoloto, Sant, L&K, Leader High or low pressure, with plastic floats complete as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	1.00	Each	458.00	458.00	Rupees Fo Hundred Fifty Eigh Only
25	Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required :W.C. pan with ISI marked white solid plastic seat and lid of Cera/Hindware/Jaguar, Parryware, Sanitaryware, Neycer in complete upto all floor level, including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge . The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	1.00	Each	6368.50	6369.00	Rupees S S Three Hund & Sixty Eigh Paise Fift Only
26	Providing and fixing Vitreous china: automatic flushing cistern with a pair of C.I. Or M.S brackets complete with fittings including C.I. Syphonic apparatus mosquitos proof lid, C.P. brass unions and coupling for connecting with inlet, outlet and over flow pipes including cutting holes and making good the same (Over- flow pipe to be measured and paid for separately) as per the direction by the Engineer-in-charge . The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	1.00	Each	1674.50	1675.00	Rupees Or Thousand S Hundred & Seventy Fou Paise Fift
27	Providing and fixing Plastic Seat (Solid/ hollow type) and cover for wash down water closet with C.P. brass hinges and rubber buffers, including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	1.00	Each	458.40	458.00	Rupees Fo Hundred & Fifty Eigh
28	Providing and fixing white vitreous china pedestal of preferred make of Cera/Hindware Parryware, Sanitaryware, Neycer for wash basin completely recessed at the back for the reception of pipes and fittings complete upto all floor level as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess, or other taxes imposed by the Government.	1.00	Each	4013.75	4014.00	Rupees Fo Thousand & Thirteen Paise Seven

Description of work		Quantity	Unit	Estimated Rate in Words	Total amount without Taxes	AMOU Rs.
29	Providing and fixing white vitreous china pedestal of preferred make of Cera/Hindware Parryware, Sanitaryware, Neycer for wash basin completely recessed at the back for the reception of pipes and fittings complete upto all floor level as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	1.00	Each	1903.00	1903.00	Rupees Thousand & Hundred
30	Providing and fixing 32 mm (forty millimetre) dia PVC waste pipes for sink or wash basin including waste fittings complete upto all floor level including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	1.00	Each	108.50	109.00	Rupees Three C
31	Providing and fixing 600x450 mm (six hundred into four hundred fifty millimeter) beveled edge mirror of superior glass of preferred make Atul Modi Guard Golden fish with 6 mm (six millimeter) thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete upto all floor level as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	1.00	Each	1187.90	1188.00	Rupees Thousand & Hundred Eight - P
32	Providing and fixing PTMT towel rail complete of Prayag make with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour 600 mm (six hundred millimeter) long towel rail with total length of 645 mm (six hundred forty five millimeter), width 78 mm (seventy eight millimeter) and effective height of 88 mm, weighing not less than 190 gms (one hundred ninety grams) complete upto all floor level as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	1.00	Each	876.70	877.00	Rupees E Hundred Seventy S Paise N
33	Providing and fixing chromium plated brass soap dish holder having length of 138mm birth 102mm, height 75mm with concealed fitting arrangements, weighing not less than 106 gms. of Kingston, Gem, Parko, Techno, Jal, ESS-ESS, Jaguar, Seiko complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.00	Each	159.40	159.00	Rupees O Hundred Fifty Nine Paise Four Only
34	Providing and fixing toilet paper holder CP brass of Kingston, Gem, Parko, Techno, Jal, ESS-ESS, Jaguar, Seiko make (ACN-1151N) or its equivalent Hindware/Parryware complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.00	Each	606.30	606.00	Rupees S Hundred & - Paise Th Only
35	Providing and fixing CP brass angle valve with quarter turn head 15mm (Fifteen millimetre) dia without nuts and pipe of Kingston, Gem, Parko, Techno, Jal, ESS-ESS, Jaguar, Seiko make complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.00	Each	680.00	1360.00	Rupees S Hundred & Eighty On
36	Providing and fixing PVC connections pipe with brass unions 45cm (Forty five centimetres) length 15 mm (Fifteen millimetre) nominal bore heavy duty Finolex/ Cera/ Jaguar or hindware make including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.00	Each	151.00	302.00	Rupees O Hundred & Fifty One O
37	Providing and fixing Swan neck pillar tap with left hand operating knob single control CON-CHR-123BKN of Jaguar make complete upto all floor level as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	1.00	Each	1614.44	1614.00	Rupees O Thousand S Hundred & Fourteen

Sr. No.	Description of work	Quantity	Unit	Estimated Rate in Words	Total amount without Taxes	AMOUNT Rs.
38	Fixing water metre and stop cock in G.I pipe line including cutting and threading the pipe and making long screws etc. complete (water meter and stop cock to be measured and paid for separately), including upto all floor level carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2.00	Each	927.70	1855.00	Rupees Two Hundred & Twenty Seven
39	Providing and fixing 15mm (fifteen millimeter) nominal bore C.P. brass long nose bib cock Zoloto, Sam, L&K, Leader make conforming to IS standards (cat no.CON-107KN) complete upto all floor level as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	2.00	Each	1426.80	2854.00	Rupees Six Thousand
40	Providing and fixing 15mm nominal bore G.I. pipe with G.I. fittings in external work/internal work BST, Jindal (Hissar) Tata Steel Tube Limited, Parkash, Surya make including trenching and refilling etc. including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	15.00	Per Running Meter	423.80	6357.00	Rupees Six Hundred Twenty Seven
41	Providing and fixing 75 mm (seventy five millimeter) PVC floor traps ISI marked make of FINOLEX of self cleaning design including fixing with approved adhesive, cost of cutting and making good the wall and floors etcetera complete upto all floor level, including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2.00	Each	538.00	1076.00	Rupees Five Hundred Twenty Eight
42	Providing and fixing 110mm (one hundred ten millimeter) PVC plain bend ISI marked i/c fixing with approved adhesive etc complete. Victoreus / finolex or D-Plast make (High Pressure) complete in all respect as per HPPWD specifications, approved Drawing, design as per the entire satisfaction and direction of Engineer in charge including carriage of material within all leads lifts and other incidentals the rate inclusive of octroi, royalty, malkana and all type of taxes imposed by the Govt	2.00	Each	167.00	334.00	Rupees One Hundred Sixty Seven Only
43	Providing and fixing 75mm (seventy five millimeter) PVC plain bend ISI marked i/c fixing with approved adhesive etc complete. Victoreus / finolex or D-Plast make (High Pressure) complete in all respect as per HPPWD specifications, approved Drawing, design as per the entire satisfaction and direction of Engineer in charge including carriage of material within all leads lifts and other incidentals the rate inclusive of octroi, royalty, malkana and all type of taxes imposed by the Govt	2.00	Each	180.00	360.00	Rupees One Hundred Eighty Only
44	Providing and fixing 100 mm (one hundred ten millimeter) PVC single equal branch with oval access door, ISI marked make of FINOLEX insertion rubber washer 3 mm (three millimeter) thick bolts and nuts complete including fixing with approved adhesive etcetera complete upto all floor level, including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2.00	Each	240.00	480.00	Rupees Two Hundred Forty Only
45	Providing and fixing 75 mm (seventy five millimeter) PVC single equal branch with oval access door, ISI marked make of FINOLEX insertion rubber washer 3 mm (three millimeter) thick bolts and nuts complete including fixing with approved adhesive etcetera complete upto all floor level, including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2.00	Each	255.00	510.00	Rupees Two Hundred Fifty Five Only
46	Providing and fixing 110 mm (one hundred ten millimeter) PVC collars in all floor level ISI marked make of FINOLEX make including fixing with approved adhesive etcetera complete, upto all floor level including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3.00	Each	235.40	706.00	Rupees Two Hundred & Thirty Five
47	Providing and fixing 75 mm (seventy five millimeter) PVC collars in all floor level ISI marked make of FINOLEX make including fixing with approved adhesive etcetera complete, upto all floor level including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2.00	Each	252.20	504.00	Rupees Two Hundred & Fifty Two

Sr. No.	Description of work	Quantity	Unit	Estimated Rate in Words	Total amount without Taxes	AMOUNT Rs.
48	Providing and fixing 110mm (one hundred ten millimeter) dia PVC clamps ISI marked make of FINOLEX a of approved design with steel screws and rawal plugs etcetera complete upto all floor level, including carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	5.00	Each	101.30	507.00	Rupees Six Hundred
49	Providing and fixing 75mm (seventy five millimeter) dia PVC clamps ISI marked make of FINOLEX a of approved design with steel screws and rawal plugs etcetera complete upto all floor level, including carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	4.00	Each	98.00	392.00	Rupees Ninety Eight
50	Providing and fixing 8 mm (eight millimeter) dia C.P. / S.S. Jet with flexible tube upto 1(one) metre long with S.S. triangular plate to European type W.C. of quality and make as approved complete upto all floor level as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	1.00	Each	321.00	321.00	Rupees Three Hundred Twenty One Only
51	Providing and fixing C.P. Brass extension nipple (size 15mmx50mm) of approved make and quality as per direction of Engineer-in-charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	4.00	Each	79.00	316.00	Rupees Seventy Nine On
52	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	2.00	Each	249.00	498.00	Rupees Two Hundred Forty Nine
53	Providing and laying integral cement based water proofing treatment including preparation of surface as required for treatment of roofs, balconies, terraces etc consisting of following operations, (a)Applying a slurry coat of neat cement using 2.75 kg/sqm of cement admixed with water proofing compound conforming to IS. 2645 and approved by Engineer-in-charge over the RCC slab including adjoining walls upto 300 mm height including cleaning the surface before treatment, including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	32.37	Per Square metre.	1086.65	35175.00	Rupees One Thousand & Eighty Six Paise Sixty Five Only
54	Grading roof for water proofing treatment with Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	1.62	Per Cubic Meter	6100.15	9882.00	Rupees Nine Thousand Eight Hundred & Thirty Nine Only
Total in Figures					308239.00	
Quoted Rate in Figures		Excess(+)				
		Less(-)				

Executive Engineer
Bangana Division
H.P.P.W.D. Bangana

Percentage BoQ.

Name of work:- C/O Link road from Basal Baba Rudru Dhamandri road to Village Lower Nari km. 0/000 to 0/700(SH:- P/L 60mm thick Interlocking Paver Block from RD 0/130 to 0/208)

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidder are allowed to enter Bidder name and values only

St. No.	Description of work	Estimated Cost	Quantity	Earnest Money	10000.00	Estimated Rate in Words	Time Limit	Two Month
1	Providing and laying cement concrete 1:4:8 (One cement : four coarse sand : eight graded crushed stone aggregate 40mm (forty millimetre) nominal size)mechanically mixed and curing complete excluding cost of form work upto all work plinth level including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST , labour cess or other taxes imposed by the Government.	498108.00	35.10	Per Cubic metre.	3800.00	133380.00		Rupees Three Thousand Eight Hundred On
2	Construction of pavement with 60mm (sixty millimetre) thick concrete blocks conforming to clause 1504.2.1 of MORC specifications, paved and compacted over a thin bedding of sand layers (material meeting the requirement of Table 1500.6 of these specifications) of specified grading to be spread over a properly constructed and profiled base course and bounded by property edge restrains conforming to clause 1504.2.2 and 1504.2.3 of these specifications and complete the work to the satisfaction of Junior Engineer and Assistant Engineer of the area. (Subject to further entire satisfaction of the Engineer-in-Charge), including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	312.00		Per Square Meter	1117.00	348504.00		Rupees One Thousand On Hundred & Seventeen On
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundations upto all heights for all type structure complete of plain with cement concrete design mix of grade M-20 (M-twenty) cement contents not less than 350kg.(three hundred fifty kilogram) per cubic metre in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	3.12		Per cubic metre	5200.00	16224.00		Rupees Five Thousand Two Hundred On
Total in Figures							498108.00	Rupees Four Lakh Ninety Thousand One Hundred Eight Only
	Quoted Rate in Figures		Excess(+)					
			Less(-)					


Executive Engineer
Bangane Division
H.P.P.W.D. Bangane

Percentage BoQ.


Name o work:-Improvement of Black Spot on Samoor Lamlehri road (C/O R/Wall and Crash Berrier in km. 0/315 to 0/355) Road Safety

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bids are allowed to enter Bidder name and values only

		Estimated Cost						
Sr. No.	Description of work	Quantity	Earnest Money Unit	8000.00	Estimated Rate in Words	Time Limit Total amount without Taxes	Two Month AMOUNT Rs.	
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes	26.03	Per Cubic metre.	364.00	9475.00	Rupees TH Hundred Sixty Four Only		
	Providing and laying cement concrete 1:4:8 (One cement : four coarse sand : eight graded crushed stone aggregate 40mm (forty milimetre) nominal size)mechanically mixed and curing complete excluding cost of form work upto all work plinth level including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST , labour cess or other taxes imposed by the Government.	54.26	Per Cubic metre.	3880.00	210529.00	Rupees T Thousand Hundred Eighty Nine Only		
	Providing and laying cement concrete work 1:3:6 (one cement: three sand:six graded stone aggregate) 40mm (forty milimetre) nominal size in open foundation mechanically mixed and vibrated including curing complete, including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge, including carriage of material within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2.67	Per Cubic metre.	4582.00	12234.00	Rupees E Thousand Hundred Eighty Three Only		
	Back filling with granular material behind return wall, abutment, wing wall and retaining walls complete as per drawing and technical specifications clause 1204.3.8 and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax goods service tax, labour cess or other taxes imposed by the	7.52	Per cubic metre	800.00	6016.00	Rupees E Hundred Only		

Sr. No.	Description of work	Quantity	Unit	Estimated Rate in Words	Total amount without Taxes	AMOUNT Rs.
2	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre) dia PVC pipe make of (D-plast) / Finolex,) working pressure not less than 4.5 (four point five) kg/cm ² extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	30.000	Each	297.00	8910.00	Rupees T Hundred Ninety Se Only
3	Providing and erecting a "W" metal beam crash barrier comprising of 3 mm thick corrugated sheet metal beam rail, 70 cm above road/ground level, fixed on ISMC series channel vertical post, 150 x 75 x 5 mm spaced 2 m centre to centre, 1.8 m high, 1.1 m below ground/road level, all steel parts and fitments to be galvanised by hot dip process, all fittings to conform to IS:1367 and IS:1364, metal beam rail to be fixed on the vertical post with a spacer of channel section 150 x 75 x 5 mm, 330 mm long complete as per MORTH specification clouse 811.including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the	40.00	Per Running meter	3808.00	152320.00	Rupees T Thousand Hundred Eight O
Total in Figures					399484.00	Rupees T Ninety N Thousand H Hundred & E
	Quoted Rate in Figures	Excess(+)				
		Less(-)				


 Executive Engineer
 Bangana Division
 H.P.P.W.D. Bangana

Percentage BoQ.

Name of work:- C/O Link road Lambobal to Fatewal km. 0/000 to 1/750 (SH:-C/O C.C. Pavement in km. 0/000 to 0/139) under MMGSY

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter Bidder name and values only

Sr. No.	Description of work	Estimated Cost	Quantity	Earnest Money Unit	100000.00	Estimated Rate in Words	Total amount without Taxes	Time Limit	Two Months
1	Loosening of the ground upto a level of 300mm below the subgrade level, watered graded and compacted in layers to meet requirement of Tables 300.1 and 300.2 for subgrade construction as MORD per technical Specification Clause 303.5.2 including carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax goods service tax, labour cess or other taxes imposed by the Government.	499421.00	83.57	Per cubic metre	92.20	7705.00			Rupees Ninety Two - Pa Twenty O
2	Providing and laying cement concrete 1:4:8 (One cement : four coarse sand : eight graded crushed stone aggregate 40mm (forty millimetre) nominal size/mechanically mixed and curing complete excluding cost of form work upto all work plinth level including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, labour cess or other taxes imposed by the Government.	41.79		Per cubic metre	3880.00	162145.00			Rupees THIRTY Thousand H Hundred Eighty O
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in Super structure complete of plain with cement concrete design mix of grade M-20 (M-twenty) cement contents not less than 320kg.(three hundredtwenty kilogram) per cubic metre in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803,1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals . The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	62.68		Per Cubic metre	5258.00	329571.00			Rupees FIFTY Thousand 7 Hundred Fifty Eig Only
Total in Figures							499421.00		Rupees Four La Ninety Nine Thousand Four Hundred & Two
Quoted Rate in Figures				Excess(+)					
				Less(-)					


Executive Engineer
 Bangana Division
 H.P.P.W.D.Bangana


Percentage BoQ.

Name of work:- C/O Road from Upper Thana to Kut Chaterar to Alshan Haizen Basti & Village Lower Thana km. 0/000 to 6/615(SH:- Formation cutting in km. 3/375 to 3/495 & 6/450 to 6/495)

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter Bidder name and values only

St. No.	Description of work	Estimated Cost	Quantity	Earnest Unit	Estimated Rate in Words	Time Limit Total amount without Taxes	Two Months AMOUNT Rs.
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/ mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chiselling , wedging out of rock (where blasting is prohibited) and their intermediate classification of soil , setting out true to the required lines, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by Engineer-in-charge at site according to the MORD technical specification clause 302. 1603.1 and 1603.2 and sorting out useful materials and stacking the same in all leads and lifts on acquired width of road and transportation for filling in road ways, camber ,embankments for grade improvements and disposal of all surplus material to required width of the road or to approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials ,tool and labour if required. Any loss to the public private property during the course to execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all the cases as per the direction of engineer-in-charge including carriage of material with in all leads and lifts. All useful material such as stone, shingle, sand and slates etcetra shall be sorted out. A recovery of 66.74 cum (sixty six point seven four) stone to be obtained from excavation cutting at the rate of Rs. 300/- (Rupees three hundred only) per cubic metre shall be effected on prorata bases in each running bill for this item. including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax, GST,labour cess or other taxes imposed by the Government	498356.00	1001.72	Per Cubic metre.	497.50	498356.00	Rupees Four L Ninety Eight Thousand Three Hundred & Fifty Only
Total in Figures						498356.00	
	Quoted Rate in Figures	Excess(+) Less(-)					


Executive Engineer
 Bangane Division
 H.P.R.W.D. Bangane

Percentage BoQ.

Name of work:- C/O Link road Handola to Panjpeeri Gugga Zahir Mandir (SH:- C/O C.C. Pavement in km. 0/000 to 0/139)under MMGSY

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter Bidder name and values only

Sr. No.	Description of work	Estimated Cost		Earnest Money	Quantity	Unit	Estimated Rate in Words	Time Limit	Total amount without Taxes	Two Months AMOUNT Rs.
		499421.00								
1	Loosening of the ground upto a level of 300mm below the subgrade level, watered graded and compacted in layers to meet requirement of Tables 300.1 and 300.2 for subgrade construction as MORD per technical Specification Clause 303.5.2 including carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax goods service tax, labour cess or other taxes imposed by the Government.	83.57	Per cubic metre	92.20	7705.00					Rupees Ninety Two - Paise Twenty C
2	Providing and laying cement concrete 1:4:8 (One cement : four coarse sand : eight graded crushed stone aggregate 40mm (forty millimetre) nominal size)mechanically mixed and curing complete excluding cost of form work upto all work plinth level including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, labour cess or other taxes imposed by the Government.	41.79	Per cubic metre	3880.00	162145.00					Rupees Thousand Hundred Eighty C
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in Super structure complete of plain with cement concrete design mix of grade M-20 (M-twenty) cement contents not less than 320kg.(three hundredtwenty kilogram) per cubic metre in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803,1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	62.68	Per Cubic metre	5258.00	329571.00					Rupees F Thousand Hundred Fifty Eight Only
Total in Figures		499421.00								Rupees Four L Ninety Nine Thousand Four Hundred & Two One Only
Quoted Rate in Figures		Excess(+)								
		Less(-)								

Executive Engineer
Bangane Division
H.P.R.W.D. Bangane

Percentage BoQ.

Name of work:- C/O Rain Shelter in Village Tanoh on Una Aghar Mandi Road

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bids are allowed to enter Bidder name and values only

	Estimated Cost	485207.00	Earnest Money	9800.00	Time Limit	Two Mon
St. No.	Description of work	Quantity	Unit	Estimated Rate in Words	Total amount without Taxes	AMOUNT Rs.
1	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqmt. on plan) etcetera in all kinds of earth work including spade work, pick work, jumper work, blasting work and chiselling/wedging out of rock etcetera including dressing of sides and bed and disposing of excavated earth upto all leads and lifts and disposed earth to be levelled and neatly dressed as directed by Engineer-in-charge within all leads and lifts depth, including clearing of jungle, Pick Jumper work and than disposing of all surplus unserviceable excavated earth as directed by the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed	11.43	Per cubic metre	250.00	2858.00	Rupees T Hundred Fifty On
2	Providing and laying cement concrete 1:5:10 (one cement : five coarse sand : ten graded crushed stone aggregate 40mm (forty millimeter nominal size) mechanically mixed and curing complete excluding cost of form work and finishing in Retaining wall/ Breast wall in ant thickness including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc upto all floor level as per the direction of Engineer- In-Charge including entire carriage of material within all leads lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana toll tax, sale tax, GST, labour cess and other taxes imposed by the Government.	22.91	Per cubic metre	3545.00	81216.00	Rupees T Thousand Hundred Forty Five Only
3	Providing and laying in position cement concrete 1:2:4 (One cement : two coarse sand : four graded crushed stone aggregate 20mm (twenty millimetre) nominal size) mechanically mixed and curing complete excluding cost of form work upto all work foundation and plinth level including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, labour cess or other taxes imposed by the Government.	3.60	Per Cubic metre	5237.60	18855.00	Rupees F Thousand Seven Hundred Thirty Six Paise Six
4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in cement mortar 1:6 (One cement: six coarse sand) in all heights and depth as per the direction by the Engineer-in-charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	7.86	Per Cubic metre	6828.00	53668.00	Rupees S Thousand Eight Hundred Twenty Eight Only

Sr. No.	Description of work	Quantity	Unit	Estimated Rate in Words	Total amount without Taxes	AMOU Rs.
5	Providing and fixing 0.60mm thick prepainted steel sheet of Tata/Reliance / Jindal Sheets in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 microns over 5 microns primer coating to back coat of polyester of 5 microns over 5 microns primer coating i/c fixing with prepainted iron J or L hooks, bolts and nuts 6mm dia metre with prepainted limpet and rubber washers complete with all accessories as required as per the direction of Engineer-in-charge. including entire carriage of materials with in all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	48.77	Per Square metre.	1300.20	63411.00	Rupees Three Hundred and Thirty Two - Paise Twenty Only
6	Providing and fixing ridges or hips 60 cm overall with 0.60mm thick prepainted steel sheets of Tata/Reliance / Jindal in roofing with hot dipped metallic zinc coated sheets with top coat of regular modified polyester organic coating of 20 microns over 5 microns primer coating + back coat of polyester of 5 microns over 5 microns primer coating i/c fixing with prepainted iron J or L hooks, bolts & nuts 6mm dia & prepainted G.I. limpet and bitumen washers complete with all accessories as required as per the direction of Engineer in Charges. including entire carriage of materials with in all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	37.60	Per Running metre.	845.80	31802.00	Rupees Eight Hundred and Forty Five Paise Eight Only
7	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint. In beams joists channels, angles, tee flats with connecting plates or angle cleats as in main and cross beams, hip and jack rafters, purlins connected to common rafters and the like as per the direction of Engineer in Charges. including entire carriage of materials with in all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	1176.28	Per Kilogramme	103.00	121157.00	Rupees One Hundred and Three Only
8	Steel work welded in built up sections Anarkali type cast iron jali work including cutting hoisting and fixing in position and applying a primer coat of red lead paint in grating framed guard bars ladders railing and similar work etc. including carriage of materials within all leads and lifts, as per the direction of Engineer in Charges. including entire carriage of materials with in all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	169.31	Per Kilogramme	126.00	21333.00	Rupees One Hundred and Twenty Only
9	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete as per the direction by the Engineer in charge and including entire carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	5.18	Per cubic metre	599.00	3103.00	Rupees Five Hundred and Ninety Only
10	Providing and laying cement concrete 1:4:8 (One cement : four coarse sand : eight graded crushed stone aggregate 40mm (forty millimetre) nominal size) mechanically mixed and curing complete excluding cost of form work upto all work plinth level including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST , labour cess or other taxes imposed by the Government.	3.17	Per cubic metre	3837.00	12163.00	Rupees Three Thousand and One Hundred and Thirty Only

Sr. No.	Description of work	Quantity	Unit	Estimated Rate in Words	Total amount without Taxes	AMOUNT Rs.
11	Kota stone slab flooring over 20 mm (twenty millimeter) (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1:4 (one cement :four coarse sand) 25mm (twenty five millimeter) thick (yellow marble band to be paid separately) upto any floor level/ height as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentials . The rates are inclusive octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	21.80	Per Square metre.	1508.00	32874.00	Rupees (Three Thousand Hundred Eighty Four)
12	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Make of ICI (Dulux Gloss) Nerolac, Berger (Luxol High Gloss) Asian Paints (Premium Apeolite Gloss) Shalimar Two or more coat applied @ 0.90 ltr/ 10 sqm (zero point ninety liter per ten square meter) over an under coat of primer applied @ 0.80 ltr/ 10 sqm (zero point eighty liter per ten square meter) of approved brand and manufacture upto all heights in all floor level as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentials . The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	40.64	Per Square metre.	117.30	4767.00	Rupees (Four Hundred Seventy Seven) Paise Th Only
13	Providing and fixing garden bench (Deluxe Model) 1.60 metre long having capacity of four person with ornamental legs and arms of cast iron and back and feet rectangular hollow section 65mmx25mm 8 numbers strips and 50mmx25mm 5 nos strips including welding and painting and complete in all respect as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentials . The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	4.00	Each	9500.00	38000.00	Rupees (Three Thousand Eight Hundred) Only
					485207.00	Rupees (Four Lakh Eighty Five Thousand Two Hundred & Only
	Quoted Rate in Figures	Excess(+)				
		Less(-)				


 Executive Engineer
 Bangana Division
 H.P.P.W.D. Bangana

Percentage BoQ.

Name of work:- C/O Rain Shelter in Village Tihra on Una Aghar Mandi Road


PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter Bidder name and values only

St. No.	Description of work	Estimated Cost	Quantity	Earnest Money Unit	9800.00 Estimated Rate in Words	Time Limit Total amount without Taxes	Two Months AMOUNT Rs.
1	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqmt. on plan) etcetera in all kinds of earth work including spade work, pick work, jumper work, blasting work and chiselling/wedging out of rock etcetera including dressing of sides and bed and disposing of excavated earth upto all leads and lifts and disposed earth to be levelled and neatly dressed as directed by Engineer-in-charge within all leads and lifts depth, including clearing of jungle.Pick Jumper work and than disposing of all surplus unserviceable excavated earth as directed by the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed	485207.00	11.43	Per cubic metre	250.00	2858.00	Rupees THIRTY HUNDRED FIFTY ONLY
2	Providing and laying cement concrete 1:5:10(One cement : five coarse sand : ten graded crushed stone aggregate 40mm (forty millimeter nominal size) mechanically mixed and curing complete excluding cost of form work and finishing in Retaining wall/ Breast wall in ant thickness including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc upto all floor level as per the direction of Engineer- In-Charge including entire carriage of material within all leads lifts and other incidentials . The rates are inclusive octroi,royalty,malkana toll tax, sale tax,GST,labour cess and other taxes imposed by the Government.		22.91	Per cubic metre	3545.00	81216.00	Rupees THIRTY HUNDRED FORTY FIVE ONLY
3	Providing and laying in position cement concrete 1:2:4 (One cement : two coarse sand : four graded crushed stone aggregate 20mm (twenty millimetre) nominal size)mechanically mixed and curing complete excluding cost of form work upto all work foundation and plinth level including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST , labour cess or other taxes imposed by the Government.		3.60	Per Cubic metre	5237.60	18855.00	Rupees FORTY THOUSAND THREE HUNDRED THIRTY SEVEN PAISE SIX ONLY
4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in cement mortar 1:6 (One cement: six coarse sand) in all heights and depth as per the direction by the Engineer-in-charge including entire carriage of materials with in all leads and lifts and other incidentials . The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.		7.86	Per Cubic metre	6828.00	53668.00	Rupees SEVENTY THOUSAND EIGHT HUNDRED TWENTY EIGHT ONLY

Sr. No.	Description of work	Quantity	Unit	Estimated Rate in Words	Total amount without Taxes	AMOUNT Rs.
5	Providing and fixing 0.60mm thick preprinted steel sheet of Tata/Reliance / Jindal Sheets in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 microns over 5 microns primer coating to back coat of polyester of 5 microns over 5 microns primer coating i/c fixing with preprinted iron J or L hooks, bolts and nuts 6mm dia metre with preprinted limpet and rubber washers complete with all accessories as required as per the direction of Engineer-in-charge, including entire carriage of materials with in all leads and lifts and other incidentals . The rates are inclusive octoroi, royalty, Malkana, toll tax, sale tax, GST , labour cess or other taxes imposed by the Government.	48.77	Per Square metre.	1300.20	63411.00	Rupees 6 Thousand Three Hundred - Paise Twenty Only
6	Providing and fixing ridges or hips 60 cm overall with 0.60mm thick preprinted steel sheets of Tata/Reliance / Jindal in roofing with hot dipped metallic zinc coated sheets with top coat of regular modified polyester organic coating of 20 microns over 5 microns primer coating + back coat of polyester of 5 microns over 5 microns primer coating i/c fixing with preprinted iron J or L hooks, bolts & nuts 6mm dia & preprinted G.I. limpet and bitumen washers complete with all accessories as required as per the direction of Engineer in Charge, including entire carriage of materials with in all leads and lifts and other incidentals . The rates are inclusive octoroi, royalty, Malkana, toll tax, sale tax, GST , labour cess or other taxes imposed by the Government.	37.60	Per Running metre.	845.80	31802.00	Rupees 31 Thousand Eight Hundred Forty Five Paise Eight Only
7	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint. In beams joists channels, angles, tee flats with connecting plates or angle cleats as in main and cross beams, hip and jack rafters, purlins connected to common rafters and the like as per the direction of Engineer in Charge, including entire carriage of materials with in all leads and lifts and other incidentals . The rates are inclusive octoroi, royalty, Malkana, toll tax, sale tax, GST , labour cess or other taxes imposed by the Government.	1176.28	Per Kilogramme	103.00	121157.00	Rupees 121 Thousand Three Hundred Only
8	Steel work welded in built up sections Anarkali type cast iron jali work including cutting hoisting and fixing in position and applying a primer coat of red lead paint in grating framed guard bars ladders railing and similar work etc. including carriage of materials within all leads and lifts as per the direction of Engineer in Charge, including entire carriage of materials with in all leads and lifts and other incidentals . The rates are inclusive octoroi, royalty, Malkana, toll tax, sale tax, GST , labour cess or other taxes imposed by the Government.	169.31	Per Kilogramme	126.00	21333.00	Rupees 21 Thousand Three Hundred Only
9	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete as per the direction by the Engineer in charge and including entire carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octoroi, royalty, Malkana, toll tax, sale tax, GST , labour cess or other taxes imposed by the Government.	5.18	Per cubic metre	599.00	3103.00	Rupees 3103 Only
10	Providing and laying cement concrete 1:4:8 (One cement : four coarse sand : eight graded crushed stone aggregate 40mm (forty millimetre) nominal size) mechanically mixed and curing complete excluding cost of form work upto all work plinth level including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge and other incidental. The rates are inclusive of octoroi, royalty, Malkana, toll tax, GST , labour cess or other taxes imposed by the Government.	3.17	Per cubic metre	3837.00	12163.00	Rupees 12163 Only

Sr. No.	Description of work	Quantity	Unit	Estimated Rate in Words	Total amount without Taxes	AMOI Rs.
11	Kota stone slab flooring over 20 mm (twenty millimeter) (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1:4 (one cement :four coarse sand) 25mm (twenty five millimeter) thick (yellow marble band to be paid separately) upto any floor level/ height as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	21.80	Per Square metre.	1508.00	32874.00	Rupees Thousand Hundred Eight
12	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Make of ICI (Dulux Gloss) Nerolac, Berger (Luxol High Gloss) Asian Paints (Premium Apcolite Gloss) Shalimar Two or more coat applied @ 0.90 ltr/ 10 sqm (zero point ninety liter per ten square meter) over an under coat of primer applied @ 0.80 ltr/ 10 sqm (zero point eighty liter per ten square meter) of approved brand and manufacture upto all heights in all floor level as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	40.64	Per Square metre.	117.30	4767.00	Rupees Hundred Seventeen Paise Th Only
13	Providing and fixing garden bench (Deluxe Model) 1.60 metre long having capacity of four person with ornamental legs and arms of cast iron and back and feet rectangular hollow section 65mmx25mm 8 numbers strips and 50mmx25mm 5 nos strips including welding and painting and complete in all respect as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	4.00	Each	9500.00	38000.00	Rupees N Thousand Hundre Only
Quoted Rate in Figures		Excess(+)			485207.00	Rupees Four Lak Eighty Five Thout Two Hundred & Only
		Less(-)				


Executive Engineer
 Baramulla Division
 Baramulla, Jammu & Kashmir


Percentage BoQ.

Name of work:- A/R & M/O Link road to Mohalla Parohitan (Dhamandri) (Sh:- C/O R/Wall in km. 0/090 to 0/107)

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bid are allowed to enter Bidder name and values only

Sr. No.	Description of work	Estimated Cost	Quantity	Earnest Unit	Estimated Rate	Time Limit	Two Month
		321800.00			in Words	Total amount without Taxes	AMOUNT Rs.
1	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqmt. on plan) etcetera in all kinds of earth work including spade work, pick work, jumper work, blasting work and chiselling/wedging out of rock etcetera including dressing of sides and bed and disposing of excavated earth upto all leads and lifts and disposed earth to be levelled and neatly dressed as directed by Engineer-in-charge within all leads and lifts depth, including clearing of jungle, Pick Jumper work and than disposing of all surplus unserviceable excavated earth as directed by the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed		23.46	Per cubic metre	200.00	4692.00	Rupees T Hundred Only
2	Providing and laying cement concrete 1:5:10(one cement : five coarse sand : ten graded crushed stone aggregate 40mm (forty millimeter nominal size) mechanically mixed and curing complete excluding cost of form work and finishing in Retaining wall/ Breast wall in ant thickness including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc upto all floor level as per the direction of Engineer-In-Charge including entire carriage of material within all leads lifts and other incidentals .The rates are inclusive octroi,royalty,malkana toll tax, sale tax,GST,labour cess and other taxes imposed by the Government.		89.93	Per cubic metre	3455.00	310708.00	Rupees T Thousand Hundred Fifty Five Only
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe make of (D-plast) / Finolex,) working pressure not less than 4.5 (four point five) kg/cm ² extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material with in all leads and lifts and other		32.000	Each	200.00	6400.00	Rupees T Hundred Only
Total in Figures						321800.00	Rupees Three L Twenty One Th Eight Hundred
	Quoted Rate in Figures			Excess(+)			
				Less(-)			


Executive Engineer
 Bangana Division
 H.P.W.D. Bangana

Percentage BoQ.

Name of work:- R.R.D. on U.A.M. Road km. 19/000 to 39/700 (SH:- C/O U-Shape Drain in km. 25/ to 25/ & P/L 90mm me Pipe culvert in km. 25/872 25/897)

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bids are allowed to enter Bidder name and values only

Sr. No.	Description of work	Estimated Cost	Quantity	Earrest Unit	9500.00 Estimated Rate in Words	Time Limit Total amount without Taxes	Two Mon AMOU Rs.
1	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqmt. on plan) etcetera in all kinds of earth work including spade work, pick work, jumper work, blasting work and chiselling/wedging out of rock etcetera including dressing of sides and bed and disposing of excavated earth upto all leads and lifts and disposed earth to be levelled and neatly dressed as directed by Engineer-in-charge within all leads and lifts depth, including clearing of jungle.Pick Jumper work and than disposing of all surplus unserviceable excavated earth as directed by the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed		115.00	Per cubic metre	250.00	28750.00	Rupees 7 Hundred Fifty O
2	Providing and laying cement concrete work 1:3:6 (one cement: three sand:six graded stone aggregate) 40mm (forty millimetre) nominal size in open foundation mechanically mixed and vibrated including curing complete, including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge, including carriage of material within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.		67.03	Per Cubic metre.	4680.00	313700.00	Rupees 7 Thousand Hundred Eighty O
3	Providing and laying 900mm(nine hundred millimetre) dia reinforced cement concrete pipe NP-2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2(one cement:two sand) but excluding excavation protection work,back filling,concrete and masonry work in head walls and parapets as per technical specifications clause -1106 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.		15.00	Per Running meter	3981.00	59715.00	Rupees 7 Thousand Hundred Eighty O Only
4	Providing and laying in position cement concrete 1:2:4 (One cement : two coarse sand : four graded crushed stone aggregate 20mm (twenty millimetre) nominal size)mechanically mixed and curing complete excluding cost of form work upto all work foundation and plinth level including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST , labour cess or other taxes imposed by the Government.		7.31	Per Cubic metre	5247.00	38356.00	Rupees 7 Thousand Hundred Forty Seven Only

Sr. No.	Description of work	Quantity	Unit	Estimated Rate in Words	Total amount without Taxes	AMOU Rs.
5	Supplying, fitting and placing HYSD bar reinforcement of Sail, Tisco, Rinal, Jindal Panther of (JSPL) or Shyam Steel in all type of Sub-structure complete as per drawing and MORD 2014 technical specification clause 1600.2200 including cutting, bending, binding and placing in position complete in all respect including cost of binding wire upto all heights as per the entire satisfaction and directions of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rates are inclusive octroi, royalty, malkana, toll tax, Goods Service tax, Labour cess, or other taxes imposed by the Government.	91.000	Per Tonne	105.00	9555.00	Rupees Hundred Five O
6	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint. In beams joists channels, angles, tee, flats with connecting plates or angle cleats as in main and cross beams, hip and jack rafters, purlins connected to common rafters and the like, as per the direction of Engineer in Charge, including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	160.00	Per Kilogramme	153.90	24624.00	Rupees 6 Hundred Fifty Three Paise Nin Only
Total in Figures					474700.00	Rupees Four Lakh Seventy Four Thousand Seven Hundred
	Quoted Rate in Figures	Excess(+)				
		Less(-)				


Executive Engineer
 Banganga Division
 H.P.P.W.D. Banganga

Percentage BoQ.

Name of work:- Repair and Maintenance of Link Road ~~to~~ Pirnigah Pir Gous Gyahtwin wala km. 0/000 to 0/600 (SH:- P/L Interlocking Paver Block i km. 0/166 to 0/209) Deposit Work

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter Bidder name and values only

Sl. No.	Description of work	Estimated Cost	498477.00	Quantity	Unit	Earliest	10000.00	Estimated Rate in Words	Time Limit	Two Mon
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer- in-charge.Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix) as directed by the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes		51.60	Per cubic metre		1003.00	51755.00	Rupees C Thousand &Three C		
2	Loosening of the ground upto a level of 300mm below the subgrade level, watered graded and compacted in layers to meet requirement of Tables 300.1 and 300.2 for subgrade construction as MORD per technical Specification Clause 303.5.2 including carriage of materials with in all leads and lifts and other incidentals. The rates are ,inclusive of octroi, royalty, Malkana, toll tax, sale tax goods service tax, labour cess or other taxes imposed by the Government.		38.70	Per cubic metre		92.00	3560.00	Rupees Nin Two On		
3	Providing and laying cement concrete 1:4:8 (One cement : four coarse sand : eight graded crushed stone aggregate 40mm (forty millimetre) nominal size)mechanically mixed and curing complete excluding cost of form work upto all work plinth level including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST , labour cess or other taxes imposed by the Government.		23.65	Per cubic metre		4203.00	99401.00	Rupees Fo Thousand T Hundred d Three On		
4	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in Super structure complete of plain with cement concrete design mix of grade M-20 (M-twenty) cement contents not less than 320kg.(three hundredtwenty kilogram) per cubic metre in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803,1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana,toll tax,GST,labour cess or other taxes imposed by the Government..		5.70	Per Cubic metre		5250.00	29925.00	Rupees Fiv Thousand T Hundred & Fifty Only		

