

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

Short terms tenders on form 6&8 are hereby invited by the Executive Engineer Bangana Division HP.PWD Bangana on behalf of the Governor of H.P. for the following works from the approved and eligible contractors/firms of appropriate class enlisted in HPPWD as per latest instructions so as to reach and open in his office as per time schedule given below The offer of the tender will be kept open for 45 days from the date of opening of the tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

1. Date of receipt of applications for the tender

Form a/w requisite documents: -

22.01.2024 upto 2.00-PM.

2. Date of issue /sale of tender forms against

Cash payment (Non-refundable):-

23.01.2024 2:00 to 5.00 PM.

3. Date of receipt of tenders: -

24.01.2024 upto 10.30 A.M.

4. Date of opening of tenders: -

24.01.2024 at 11.00 A.M.

Sr. No.	Name of Work	Estimated Cost	EMD	Time Limit	Cost of Tender	Eligible class of Contractor
1	C/O Link road Badoli to I.P.H. Rig to Village Batuhi km. 0/000 to 2/000(SH:- C/O 900mm dia Hume pipe cuvert a/w wing wall in km. 0/070 & 0/200)under MMGSY	492257.00	9900.00	Two Month	350	Class D
2	C/O Link road to Village Panjain from T.M.B.D. Road (Bed Cutting & C.C. Pavement in km. 0/095 to 0/195)under MMGSY	498530.00	10000.00	Two Month	350	Class-D
3	C/O Link road to Village Taroi km. 0/000 to 1/000(SH:- Formation Cutting in km. 0/165 to 0/585)	465170.00	9400.00	Two Month	350	Class-D
4	R.R.D. On U.A.M. Road km. 19/000 to 39/700(SH:- C/O Edge wall from RD. 31/200 to 31/210,31/845 to 31/850,32/200 to 32/208 & Protection wall at RD. 31/852 to 31/864)	255665.00	5200.00	Two Month	350	Class-D
5	C/O Link road from Khurvain ambhehra Dhhraj road towards village Sakohn via Laliya da bada kuwari (C/O Both side wing wall to 6.00 meter span at RD. 0/070)	471418.00	9700.00	Two Month	350	Class-D
6	C/O Road from Upper Thana to Kut Chhaterar to Alshan Haizen Basti & Village Lower Thana km. 0/000 to 6/615(SH:- Formation cutting in km. 6/510 to 6/630)	499231.00	10000.00	Two Month	350	Class D
7	C/O Link road to S.S. Model School Piploo Ghaloon (SH:- C/O C.C. Pavement in km. 0/000 to 0/130) D.C. Deposit	472875.00	9500.00	Two Month	350	Class-D
8	C/O Play Ground in Govt. Sen. Sec. School at Charara (SH:- C/O R/Wall in km. 0/000 to 0/023)D.C.Deposit	456833.00	9200.00	Two Month	350	Class-D
9	C/O Link road to House of Sh. Subhash Chand Village Nalwari Tehsil Bangana Distt. Una (H.P.) (SH:- C/O C.C.Pavement in km. 0/300 to 0/440) D.C.Deposit	467031.00	9400.00	Two Month	350	Class-D
10	R.R.D. on Barubi Dumkhar road km. 16/000 to 27/270(SH:- Repair of Damaged Hume pipe Culvert a/w Wing wall in km. 16/150)	285999.00	5800.00	Two Month	350	Class-D
11	C/O Rain Shelter in Village Thanakalan on Una Aghar Mandi Road	485207.00	9800.00	Two Month	350	Class D
12	A/R & M/O various roads under Bangana Sub - Division(SH:- Painting of Sign boards and Kilometer Stone etc. Section Bangana -I)	383873.00	7700.00	Two Month	350	Class-D
13	C/O Link road Una Amb Mubarikpur via Ghandawal to Village Batuhi Harizen Basti (SH:-P/L Interlocking Pave Block flooring in km. 1/610 to 1/645 & R/Wall in km. 2/605 to 2/612)	333594.00	6700.00	Two Month	350	Class-D
14	C/O Link road to Village Match km. 0/000 to 1/000(SH:-P/L G.S.B. in km. 0/090 to 0/310, W.M.M. & M/T in km. 0/090 to 0/180 & C/O U-Shape Drain in km. 0/220 to 0/350)	486104.00	9800.00	Two Month	350	Class-D

The Earnest money in the shape of National Saving certificate/Time deposit/Saving account of any post office or FDR of Nationalised Bank duly pledged in the name of undersigned must be accompanied with each tender. The conditional tender and tender not accompanying the earnest money in the proper mode of deposit will summarily be rejected.

The Tender documents to be sent should have invariably be waxed in sealed cover and in failure of that those will not be entertained.

The Copy of valid enlistment, GST Registration No., Income Tax PAN No & EPF No. must be attached with application.

SPECIAL CONDITION:-


1. The tender form will be issued to those contractors who have relevant machinery and equipment, the list of which may be attached with their applications.(The proof of ownership of machinery/legal tie up arrangement).
2. The tender form will not be issued to those contractors who have already two works in hand.The earnest money for the above work should be submitted with the application for the purchase of the tender forms. The application received without earnest money shall summarily be rejected.
3. The conditional/ambiguous/telegraphic tenders or tender by fax shall not entertained/considered in any case.

No.PW/BGN/CB/T-1/2023-24-

8445-74

Copy forwarded to the following for information and necessary action:-

1. The Engineer-in-Chief HPPWD, Nirman Bhawan Shimla.
2. All the Assistant Engineer, working under this Division.
3. Various Contractors working under this Division.
4. Notice Board.


Executive Engineer
Bangana Division
HPPWD Bangana.

Dated 12-01-24


Executive Engineer,
Bangana Division,
HPPWD Bangana.

Percentage BoQ.


Name of work:- C/O Link road Badoli to IPH. Right to Village Batuhi km. 0/000 to 2/000(SH:- C/O 900mm Dia Hume pipe Culvert a/w Wing wall at RD. 0/070 & 0/200)

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be filled after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter Bidder name and values only

Sr. No.	Description of work	Estimated Cost	492257.00	Earnest Money	9900.00	Time Limit	Two Month
			Quantity	Unit	Estimated Rate in Words	Total amount without Taxes	AMOUNT Rs. P
1	Loosening of the ground upto a level of 300mm below the subgrade level, watered graded and compacted in layers to meet requirement of Tables 300.1 and 300.2 for subgrade construction as MORD per technical Specification Clause 303.5.2 including carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.		187.50	Per cubic metre	92.20	17288.00	Rupees Ninety Two - Paise Twenty Only
2	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.		64.60	Per Cubic metre.	364.00	23514.00	Rupees Three Hundred & Sixty Four Only
3	Providing and laying cement concrete 1:4:8 (One cement : four coarse sand : eight graded crushed stone aggregate 40mm (forty millimetre) nominal size)mechanically mixed and curing complete excluding cost of form work upto all work plinth level including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST , labour cess or other taxes imposed by the Government.		72.92	Per Cubic metre.	3820.00	278554.00	Rupees Three Thousand Eight Hundred & Twenty Only
4	Providing and laying cement concrete work 1:3:6 (one cement: three sand:six graded stone aggregate) 40mm (forty millimetre) nominal size in open foundation mechanically mixed and vibrated including curing complete, including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802.803,1202 and 1203 as per the direction of the Engineer-in-Charge, including carriage of material within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.		23.92	Per Cubic metre.	4518.00	108071.00	Rupees Four Thousand Five Hundred & Eighteen Only
5	Providing and laying 900mm(nine hundred millimetre) dia reinforced cement concrete pipe NP-2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2(one cement:two sand) but excluding excavation protection work,back filling,concrete and masonry work in head walls and parapets as per technical specifications clause -1106 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.		15.00	Per Running meter	3728.00	55920.00	Rupees Three Thousand Seven Hundred & Twenty Eight Only

Sr. No.	Description of work	Quantity	Unit	Estimated Rate in Words	Total amount without Taxes	AMOUNT Rs. p
6	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe make of (D-plast) / Finolex,) working pressure not less than 4.5 (four point five) kg/cm ² extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	30.000	Each	297.00	8910.00	Rupees Two Hundred & Ninety Seven Only
Total in Figures					492257.00	Rupees Four Lakh Ninety Two Thousand Two Hundred & Fifty
	Quoted Rate in Figures	Excess(+)				
		Less(-)				


 Executive Engineer
 Bangana Division
 H.P.P.W.D.Bangana

Percentage BoQ.

Name of work:- C/O Link road to Village Panjain from T.M.B.D. Road (SH:- Bed cutting and C.C. Pavement in km. 0/095 to 0/195) Under M.M.G.S.Y.

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter Bidder name and values only

Sr. No.	Description of work	Estimated Cost	498530.00	Earnest Money	10000.00	Time Limit	Two Month
			Quantity	Unit	Estimated Rate in Words	Total amount without Taxes	AMOUNT Rs. P
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/ mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chiecelling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by Engineer-in-charge at site according to the MORD technical specification clause 302, 1603.1 and 1603.2 and sorting out useful materials and stacking the same in all leads and lifts on acquired width of road and transportation for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to required width of the road or to approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials, tool and labour if required. Any loss to the public private property during the course to execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all the cases as per the direction of engineer-in-charge including carriage of material with in all leads and lifts. All useful material such as stone, shingle, sand and slates etcetra shall be sorted out. A recovery of 39.83 cum (thirty nine point eight three) stone to be obtained from excavation cutting at the rate of Rs. 300/- (Rupees three hundred only) per cubic metre shall be effected on prorata bases in each running bill for this item. including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty, malikhana ,toll tax, GST,labour cess or other taxes imposed by the Government..		239.70	Per Cubic metre.	558.00	133753.00	Rupees Five Hundred & Fifty Eight Only
2	Providing and laying cement concrete 1:4:8 (One cement : four coarse sand : eight graded crushed stone aggregate 40mm (forty millimetre) nominal size)mechanically mixed and curing complete excluding cost of form work upto all work plinth level including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST , labour cess or other taxes imposed by the Government.		31.00	Per Cubic metre.	3880.00	120280.00	Rupees Three Thousand Eight Hundred & Eighty Only

Sr. No.	Description of work	Quantity	Unit	Estimated Rate in Words	Total amount without Taxes	AMOUNT Rs. P
3	Providing and laying in position cement concrete 1:2:4 (One cement : two coarse sand : four graded crushed stone aggregate 40mm (forty millimetre) nominal size)mechanically mixed and curing complete excluding cost of form work upto all work foundation and plinth level including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST , labour cess or other taxes imposed by the Government.	46.50	Per cubic metre	5258.00	244497.00	Rupees Five Thousand Two Hundred & Fifty Eight Only
Total in Figures					498530.00	Rupees Four Lakh Ninety Eight Thousand Five Hundred & Thirty Only
	Quoted Rate in Figures	Excess(+)				
		Less(-)				


Executive Engineer
Banganga Division
H.P.W.D.Banganga

Percentage BoQ.

Name of work:- C/O Link road to Village Taroi km. 0/000 to 1/000(SH:-Formation Cutting in km. 0/165 to 0/585)

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be filled after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter Bidder name and values only

Sr. No.	Description of work	Estimated Cost	465170.00	Earnest Money	9400.00	Time Limit	Two Month
			Quantity	Unit	Estimated Rate in Words	Total amount without Taxes	AMOUNT Rs. P
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/ mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chieselling , wedging out of rock(where blasting is prohibited) and their intermediate classification of soil , setting out true to the required lines, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by Engineer-in-charge at site according to the MORD technical specification clause 302, 1603.1 and 1603.2 and sorting out useful materials and stacking the same in all leads and lifts on acquired width of road and transportation for filling in road ways, camber ,embankments for grade improvements and disposal of all surplus material to required width of the road or to approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials ,tool and labour if required. Any loss to the public private property during the course to execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all the cases as per the direction of engineer-in-charge including carriage of material with in all leads and lifts. All useful material such as stone, shingle, sand and slates etcetra shall be sorted out. A recovery of 61.12 cum (Sixty two point one two) stone to be obtained from excavation cutting at the rate of Rs. 300/- (Rupees three hundred only) per cubic metre shall be effected on prorata bases in each running bill for this item. including carriage of material with in all leads and lifts and other incidentals .The rate includes octori, royalty,malkhana ,toll tax, GST,labour cess or other taxes imposed by the Government..	1863.66	Per Cubic metre.	249.60	465170.00	Rupees Two Hundred & Forty Nine - Paise Sixty Only	
Total in Figures						465170.00	Rupees Four Lakh Sixty Five Thousand One Hundred & Seventy Only
Quoted Rate in Figures			Excess(+)				
			Less(-)				



Executive Engineer
Bangana Division
H.P.P.W.D.Bangana

Percentage BoQ.

Name of work:- R.R.D. On U.A.M. Road km. 19/000 to 39/700(SH:- C/O Edge wall from RD. 31/200 to 31/210,31/845 to 31/850,32/200 to 32/208 & Porction wall at RD. 31/852 to 31/864)

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter Bidder name and values only

Sr. No.	Description of work	Estimated Cost		Earnest Money Unit	5200.00 Estimated Rate in Words	Time Limit	Two Month
		Quantity	255665.00			Total amount without Taxes	AMOUNT Rs. p
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	7.76		Per Cubic metre.	364.00	2825.00	Rupees Three Hundred & Sixty Four Only
2	Providing and laying cement concrete 1:4:8 (One cement : four coarse sand : eight graded crushed stone aggregate 40mm (forty millimetre) nominal size)mechanically mixed and curing complete excluding cost of form work upto all work plinth level including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST , labour cess or other taxes imposed by the Government.	38.61		Per Cubic metre.	4172.00	161081.00	Rupees Four Thousand One Hundred & Seventy Two Only
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe make of (D-plast) / Finolex,) working pressure not less than 4.5 (four point five) kg/cm ² extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709.1204.3.7 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	18.000		Each	246.00	4428.00	Rupees Two Hundred & Forty Six Only

Sr. No.	Description of work	Quantity	Unit	Estimated Rate in Words	Total amount without Taxes	AMOUNT Rs. p
4	Providing and laying cement concrete work 1:2.5:5 (one cement: two decimal five sand: five graded stone aggregate) 40mm (forty millimetre) nominal size in substructure mechanically mixed and vibrated including curing complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204 and as per the direction of the Engineer-in-Charge, including carriage of material within all leads, lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	11.76	Per Cubic metre	4754.00	55907.00	Rupees Four Thousand Seven Hundred & Fifty Four Only
5	Supplying, fitting and placing HYSD bar reinforcement of Sail ,Tisco, Rinal , Jindal Panther of (JSPL) or Shyam Steel in all type of Sub-structure complete as per drawing and MORD 2014 technical specification clause 1600,2200 including cutting ,bending, binding and placing in position complete in all respect including cost of binding wire upto all heights as per the entire satisfaction and directions of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rates are inclusive of octroi ,royalty, malkana, toll tax, Goods Service tax ,Labour cess, or other taxes imposed by the Government.	131.050	Per Kilogramme	105.00	13760.00	Rupees One Hundred & Five Only
6	Back filling with granular material behind return wall, abutment, wing wall and retaining walls complete as per drawing and technical specifications clause 1204.3.8 and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax goods service tax, labour cess or other taxes imposed by the Government.	22.08	Per cubic metre	800.00	17664.00	Rupees Eight Hundred Only
Total in Figures					255665.00	Rupees Two Lakh Fifty Five Thousand Six Hundred & Sixty Five Only
Quoted Rate in Figures					Excess(+)	
					Less(-)	


 Executive Engineer
 Bangana Division
 H.P.P.W.D. Bangana

Percentage BoQ.

Name of work:- C/O Link road from Khurwain ambelra Dhhraj road towards village Sakolm via Laliya da bada kuwari (C/O Both side wing wall to 6.00 meter span at RD. 0/070)

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter Bidder name and values only

Sr. No.	Description of work	Estimated Cost	471418.00	Earnest Money	9500.00	Time Limit	Two Month
Sr. No.	Description of work	Estimated Cost	Quantity	Unit	Estimated Rate in Words	Total amount without Taxes	AMOUNT Rs. P
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks/ where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.		36.12	Per Cubic metre.	364.00	13148.00	Rupees Three Hundred & Sixty Four Only
2	Providing and laying cement concrete 1:4:8 (One cement : four coarse sand : eight graded crushed stone aggregate 40mm (forty millimetre) nominal size/mechanically mixed and curing complete excluding cost of form work upto all work plinth level including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST , labour cess or other taxes imposed by the Government.		117.39	Per Cubic metre.	3820.00	448430.00	Rupees Three Thousand Eight Hundred & Twenty Only
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe make of (D-plast) / Finolex,) working pressure not less than 4.5 (four point five) kg/cm ² extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST ,labour cess or other taxes imposed by the Government..		40.000	Each	246.00	9840.00	Rupees Two Hundred & Forty Six Only
Total in Figures						471418.00	Rupees Four Lakh Seventy One Thousand Four Hundred & Eighteen Only
Quoted Rate in Figures			Excess(+)				
			Less(-)				



Executive Engineer
Bangana Division
H.P.P.W.D.Bangana

Name of work:- C/O Road from Upper Thana to Kut Chhatarar to Alshan Haizen Basti & Village Lower Thana km. 0/000 to 6/615(
SH:- Frmation cutting in km. 6/510 to 6/630)

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter Bidder name and values only

	Estimated Cost	499231.00	Earnest Money	10000.00	Time Limit	Two Month
Sr. No.	Description of work	Quantity	Unit	Estimated Rate in Words	Total amount without Taxes	AMOUNT Rs. P
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/ mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chiecelling , wedging out of rock(wher blasting is prohibited) and their intermediate classification of soil , setting out true to the required lines, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by Engineer-in-charge at site according to the MORD technical specification clause 302, 1603.1 and 1603.2 and sorting out useful materials and stacking the same in all leads and lifts on acquired width of road and transportation for filling in road ways, camber ,embankments for grade improvements and disposal of all surplus material to required width of the road or to approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials ,tool and labour if required. Any loss to the public private property during the course to execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all the cases as per the direction of engineer-in-charge including carriage of material with in all leads and lifts. All useful material such as stone, shingle, sand and slates etcetra shall be sorted out. A recovery of 66.85 cum (Sixty six point eight five) stone to be obtained from excavation cutting at the rate of Rs. 300/- (Rupees three hundred only) per cubic metre shall be effected on prorata bases in each running bill for this item. including carriage of material with in all leads and lifts and other incidentals .The rate includes octori, royalty,malkhana ,toll tax, GST,labour cess or other taxes imposed by the Government..	1005.50	Per Cubic metre.	496.50	499231.00	Rupees Four Hundred & Ninety Six - Paise Fifty Only
Total in Figures					499231.00	Rupees Four Lakh Ninety Nine Thousand Two Hundred & Thirty One Only
Quoted Rate in Figures		Excess(+)				
		Less(-)				

Cherry

Executive Engineer
Bangana Division
H.P.P.W.D. Bangalore

Percentage BoQ.

Name of work:- C/O Link road to S.S. Model School Piploo Ghaloan (SH:- C/O C.C. Pavement in km. 0/000 to 0/130)

D.C.Deposit

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender.
Bidders are allowed to enter Bidder name and values only

Sr. No.	Description of work	Estimated Cost	472875.00	Earnest Money Unit	9500.00 Estimated Rate in Words	Time Limit Total amount without Taxes	Two Month AMOUNT Rs. P
1	Providing and laying cement concrete 1:4:8 (One cement : four coarse sand : eight graded crushed stone aggregate 40mm (forty millimetre) nominal size)mechanically mixed and curing complete excluding cost of form work upto all work plinth level including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST ,labour cess or other taxes imposed by the Government.		39.00	Per cubic metre	4250.00	165750.00	Rupees Four Thousand Two Hundred & Fifty Only
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in Super structure complete of plain with cement concrete design mix of grade M-20 (M-twenty) cement contents not less than 320kg.(three hundredtwenty kilogram) per cubic metre in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803,1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..		58.50	Per Cubic metre	5250.00	307125.00	Rupees Five Thousand Two Hundred & Fifty Only
Total in Figures						472875.00	Rupees Four Lakh Seventy Two Thousand Eight Hundred & Seventy Five Only
Quoted Rate in Figures			Excess(+)				
			Less(-)				

(Signature)

Executive Engineer
Bangana Division
H.P.P.W.D.Bangana

Percentage BoQ.

Name of work:- C/O Palyground in Govt. Sen. Sec. School at Charara (SH:- C/O R/Wall in km. 0/000 to 0/023)

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter Bidder name and values only

Sr. No.	Description of work	Estimated Cost	456833.00	Earnest Money Unit	9200.00 Estimated Rate in Words	Time Limit Total amount without Taxes	Two Month AMOUNT Rs. P
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government		53.13	Per Cubic metre.	364.00	19339.00	Rupees Three Hundred & Sixty Four Only
2	Providing and laying cement concrete 1:4:8 (One cement : four coarse sand : eight graded crushed stone aggregate 40mm (forty millimetre) nominal size)mechanically mixed and curing complete excluding cost of form work upto all work plinth level including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, labour cess or other taxes imposed by the Government.		95.91	Per Cubic metre.	4289.00	411358.00	Rupees Four Thousand Two Hundred & Eighty Nine Only
3	Back filling with granular material behind return wall, abutment, wing wall and retaining walls complete as per drawing and technical specifications clause 1204.3.8 and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax goods service tax, labour cess or other taxes imposed by the Government.		88.00	Per cubic metre	297.00	26136.00	Rupees Two Hundred & Ninety Seven Only

Sr. No.	Description of work	Quantity	Unit	Estimated Rate in Words	Total amount without Taxes	AMOUNT Rs. p
4	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre) dia PVC pipe make of (D-plast) / Finolex,) working pressure not less than 4.5 (four point five) kg/cm ² extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	21.620	Each	800.00	17296.00	Rupees Eight Hundred Only
Total in Figures					456833.00	Rupees Four Lakh Fifty Six Thousand Eight Hundred & Thirty Three Only
		Excess(+)				
		Less(-)				



Executive Engineer
Bangana Division
H.P.P.W.D. Bangana

Percentage BoQ.

Name of work:- C/O Link road to House of Sh. Subhash Chand Village Nalwari Tehsil Bangana Distt. Una (H.P.) (SH:- C/O C.C.Pavement in km. 0/300 to 0/440) D.C. Deposit

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter Bidder name and values only

Sr. No.	Description of work	Estimated Cost	Quantity	Earnest Unit	9400.00 Estimated Rate in Words	Time Limit Total amount without Taxes	Two Month AMOUNT Rs. P
1	Providing and laying cement concrete 1:4:8 (One cement : four coarse sand : eight graded crushed stone aggregate 40mm (forty millimetre) nominal size)mechanically mixed and curing complete excluding cost of form work upto all work plinth level including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST , labour cess or other taxes imposed by the Government.		47.40	Per cubic metre	4099.00	194293.00	Rupees Four Thousand & Ninety Nine Only
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in Super structure complete of plain with cement concrete design mix of grade M-20 (M-twenty) cement contents not less than 320kg (three hundredtwenty kilogram) per cubic metre in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803, 1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..		52.50	Per Cubic metre	5195.00	272738.00	Rupees Five Thousand One Hundred & Ninety Five Only
Total in Figures						467031.00	Rupees Four Lakh Sixty Seven Thousand & Thirty One Only
Quoted Rate in Figures			Excess(+)				
			Less(-)				



Executive Engineer
Bangana Division
H.P.W.D.Bangana

Percentage BoQ.

Name of work:- R.R.D.on Baruhi Dumkhar road km. 16/000 to 27/270(SH:- Repair of Damaged Hume pipe Culvert a/w Wing wall in km. 16/150)

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter Bidder name and values only

	Estimated Cost	285999.00	Earnest Money	5800.00	Time Limit	Two Month
Sr. No.	Description of work	Quantity	Unit	Estimated Rate in Words	Total amount without Taxes	AMOUNT Rs. P
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	17.24	Per Cubic metre.	364.00	6275.00	Rupees Three Hundred & Sixty Four Only
2	Providing and laying cement concrete 1:4:8 (One cement : four coarse sand : eight graded crushed stone aggregate 40mm (forty millimetre) nominal size)mechanically mixed and curing complete excluding cost of form work upto all work plinth level including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST , labour cess or other taxes imposed by the Government.	39.84	Per Cubic metre.	4099.00	163304.00	Rupees Four Thousand & Ninety Nine Only
3	Providing and laying cement concrete work 1:3:6 (one cement: three sand:six graded stone aggregate) 40mm (forty millimetre) nominal size in open foundation mechanically mixed and vibrated including curing complete, including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of	20.25	Per Cubic metre.	4518.00	91490.00	Rupees Four Thousand Five Hundred & Eighteen Only
4	Providing and laying 900mm(nine hundred millimetre) dia reinforced cement concrete pipe NP-2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2(one cement:two sand) but excluding excavation protection work,back filling,concrete and masonry work in head walls and parapets as per technical specifications clause -1106 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	5.00	Per Running meter	4095.00	20475.00	Rupees Four Thousand & Ninety Five Only

Sr. No.	Description of work	Quantity	Unit	Estimated Rate in Words	Total amount without Taxes	AMOUNT Rs. p
5	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre) dia PVC pipe make of (D-plast) / Finolex,) working pressure not less than 4.5 (four point five) kg/cm ² extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	15.000	Each	297.00	4455.00	Rupees Two Hundred & Ninety Seven Only
Total in Figures					285999.00	Rupees Two Lakh Eighty Five Thousand Nine Hundred & Ninety Nine Only
		Excess(+)				
		Less(-)				



Executive Engineer
Bangana Division
H.P.P.W.D.Bangana

Percentage BoQ.

Name of work:- C/O Rain Shelter in Village Thanaklan on Una Aghar Mandi Road

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter Bidder name and values only

Sr. No.	Description of work	Estimated Cost	485207.00	Earnest Money Unit	9800.00 Estimated Rate in Words	Time Limit Total amount without Taxes	Two Month AMOUNT Rs. P
1	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqmt. on plan) etcetera in all kinds of earth work including spade work, pick work, jumper work, blasting work and chiselling/wedging out of rock etcetera including dressing of sides and bed and disposing of excavated earth upto all leads and lifts and disposed earth to be levelled and neatly dressed as directed by Engineer-in-charge within all leads and lifts depth, including clearing of jungle.Pick Jumper work and then disposing of all surplus unserviceable excavated earth as directed by the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed		11.43	Per cubic metre	250.00	2858.00	Rupees Two Hundred & Fifty Only
2	Providing and laying cement concrete 1:5:10(one cement : five coarse sand : ten graded crushed stone aggregate 40mm (forty millimeter nominal size) mechanically mixed and curing complete excluding cost of form work and finishing in Retaining wall/ Breast wall in ant thickness including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc upto all floor level as per the direction of Engineer- In-Charge including entire carriage of material within all leads lifts and other incidentals .The rates are inclusive of octroi,royalty,malkana toll tax, sale tax,GST,labour cess and other taxes imposed by the Government.		22.91	Per cubic metre	3545.00	81216.00	Rupees Three Thousand Five Hundred & Forty Five Only
3	Providing and laying in position cement concrete 1:2:4 (One cement : two coarse sand : four graded crushed stone aggregate 20mm (twenty millimetre) nominal size)mechanically mixed and curing complete excluding cost of form work upto all work foundation and plinth level including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST , labour cess or other taxes imposed by the Government.		3.60	Per Cubic metre	5237.60	18855.00	Rupees Five Thousand Two Hundred & Thirty Seven - Paise Sixty
4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in cement mortar 1:6 (One cement: six coarse sand) in all heights and depth as per the direction by the Engineer-in-charge including entire carriage of materials with in all leads and lifts and other incidentals . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.		7.86	Per Cubic metre	6828.00	53668.00	Rupees Six Thousand Eight Hundred & Twenty Eight Only

Sr. No.	Description of work	Quantity	Unit	Estimated Rate in Words	Total amount without Taxes	AMOUNT Rs. P
5	Providing and fixing 0.60mm thick prepainted steel sheet of Tata/Reliance / Jindal Sheets in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 microns over 5 microns primer coating to back coat of polyester of 5 microns over 5 microns primer coating i/c fixing with prepainted iron J or L hooks, bolts and nuts 6mm dia metre with prepainted limpet and rubber washers complete with all accessories as required as per the direction of Engineer-in-charge, including entire carriage of materials with in all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	48.77	Per Square metre.	1300.20	63411.00	Rupees One Thousand Three Hundred - Paise Twenty Only
6	Providing and fixing ridges or hips 60 cm overall with 0.60mm thick prepainted steel sheets of Tata/Reliance / Jindal in roofing with hot dipped metallic zinc coated sheets with top coat of regular modified polyester organic coating of 20 microns over 5 microns primer coating + back coat of polyester of 5 microns over 5 microns primer coating i/c fixing with prepainted iron J or L hooks, bolts & nuts 6mm dia & prepainted G.I. Limpet and bitumen washers complete with all accessories as required as per the direction of Engineer in Charge. including entire carriage of materials with in all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government	37.60	Per Running metre.	845.80	31802.00	Rupees Eight Hundred & Fourty Five - Paise Eighty Only
7	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint. In beams joists channels, angles, tee, flats with connecting plates or angle cleats as in main and cross beams, hip and jack rafters, purlins connected to common rafters and the like as per the direction of Engineer in Charge. including entire carriage of materials with in all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	1176.28	Per Kilogramme	103.00	121157.00	Rupees One Hundred & Three Only
8	Steel work welded in built up sections Anarkali type cast iron jali work including cutting hoisting and fixing in position and applying a primer coat of red lead paint in grating framed guard bars ladders railing and similar work etc. including carriage of materials within all leads and lifts as per the direction of Engineer in Charge. including entire carriage of materials with in all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	169.31	Per Kilogramme	126.00	21333.00	Rupees One Hundred & Twenty Six Only
9	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete as per the direction by the Engineer in charge and including entire carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	5.18	Per cubic metre	599.00	3103.00	Rupees Five Hundred & Ninety Nine Only
10	Providing and laying cement concrete 1:4:8 (One cement : four coarse sand : eight graded crushed stone aggregate 40mm (forty millimetre) nominal size) mechanically mixed and curing complete excluding cost of form work upto all work plinth level including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, labour cess or other taxes imposed by the Government.	3.17	Per cubic metre	3837.00	12163.00	Rupees Three Thousand Eight Hundred & Thirty Seven Only

Sr. No.	Description of work	Quantity	Unit	Estimated Rate in Words	Total amount without Taxes	AMOUNT Rs. P
11	Kota stone slab flooring over 20 mm (twenty millimeter) (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1:4 (one cement :four coarse sand) 25mm (twenty five millimeter) thick (yellow marble band to be paid separately) upto any floor level/ height as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	21.80	Per Square metre.	1508.00	32874.00	Rupees One Thousand Five Hundred & Eight Only
12	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Make of ICI (Dulux Gloss) Nerolac, Berger (Luxol High Gloss) Asian Paints (Premium Apcolite Gloss) Shalimar Two or more coat applied @ 0.90 ltr/ 10 sqm (zero point ninety liter per ten square meter) over an under coat of primer applied @ 0.80 ltr/ 10 sqm (zero point eighty liter per ten square meter) of approved brand and manufacture upto all heights in all floor level as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	40.64	Per Square metre.	117.30	4767.00	Rupees One Hundred & Seventeen - Paise Thirty Only
13	Providing and fixing garden bench (Deluxe Model) 1.60 metre long having capacity of four person with ornamental legs and arms of cast iron and back and feet rectangular hollow section 65mmx25mm 8 numbers strips and 50mmx25mm 5 nos strips including welding and painting and complete in all respect.as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	4.00	Each	9500.00	38000.00	Rupees Nine Thousand Five Hundred Only
					485207.00	Rupees Four Lakh Eighty Five Thousand Two Hundred & Seven Only
	Quoted Rate in Figures	Excess(+)				
		Less(-)				



Executive Engineer
Bangana Division
H.P.P.W.D.Bangand

Percentage BoQ.

Name of work:- A/R & M/O various roads under Bangana Sub -Division(SH:- Painting of Sign boards and Kilometer Stone etc. Section Bangana -1)

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter Bidder name and values only

Sr. No.	Description of work	Estimated Cost	Quantity	Earnest Money Unit	7700.00 Estimated Rate in Words	Time Limit Total amount without Taxes	Two Month AMOUNT Rs. p
1	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete as directed by the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.		725.39	Per Square metre.	10.00	7254.00	Rupees Ten Only
2	Finishing walls with 100% Premium acrylic emulsion paint Nerolac, Berger(Bison Acrylic) Asian Paint (Tractor, Acrylic) Shalimar having VOC less than 50 gm/litre and UV resistance as per IS 15489:2004, Alkali & fungal resistance, dirt resistance exterior paint of required shade (Company Depot Tinted) with silicon additives. New work (Two or more coats applied @1.43 litre/ 10 sqm. Over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm. complete upto all floor level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.		2679.82	Per Square metre.	118.30	317023.00	Rupees One Hundred & Eighteen - Paise Thirty Only
3	Removing old paint or polish from wood and wood based surfaces with paint remover of approved brands and manufacture and making the surface even with: Paint remover of approved brand and manufacture as per the entire satisfaction and direction of Engineer-in-charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, labour cess or other taxes imposed by the Government.		567.58	Per Square metre.	50.00	28379.00	Rupees Fifty Only
4	Painting wood work with Deluxe Multi Surface Paint of required shade of Nerolac/ Asian/Berger ICI (Dulux Gloss) (Luxol high Gloss) (Premium Apcolite Gloss) Shalimar make two or more coats applied @ 0.90 ltr/10 sqm (zero point ninety liter per ten square meter) over an under coat of primer applied @0.75 ltr/10 sqm (zero point seven five liter per ten square meter) of approved brand and manufacture in all height all floor level as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.		567.58	Per Square metre.	55.00	31217.00	Rupees Fifty Five Only
						383873.00	Rupees Three Lakh Eighty Three Thousand Eight Hundred & Seventy Three Only
			Excess(+)				
			Less(-)				



Executive Engineer
Bangana Division
H.P.P.W.D. Bangana

Percentage BoQ.

Name of work:- C/O Link road Una Amb Mubarikpur via Ghandawal to Village Batuhi Harizen Basti (SH:-P/L Interlocking Pave Block flooring in km. 1/610 to 1/645 & R/Wall in km. 2/605 to 2/612)

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter Bidder name and values only

Sr. No.	Description of work	Estimated Cost	Quantity	Earnest Unit	6700.00 Estimated Rate in Words	Time Limit Total amount without Taxes	Two Month AMOUNT Rs. P
1	Excavating, supplying and filling of local earth (including royalty) by mechanical transport upto a lead of 5km also including ramming and watering of the earth in layers not exceeding 20 cm in trenches, plinth, sides of foundation etc. complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, labour cess or other taxes imposed by the Government.		42.00	Per Square metre.	200.00	8400.00	Rupees Two Hundred Only
2	Construction of gravel/soil aggregate sub base/base by providing well graded material of nominal maximum size grading 80mm as per table 2.3 of IRC SP 77-2008, Spreading in uniform layers with tractor mount appropriate grading arrangements on prepared surface, mixing by mix in place method at OMC with tractor mount appropriate rotavator attachment and compaction with three wheel 80-100 KN Static roller capacity to achieve the desired density complete as per specifications contained in Para 2.2,3,6 and 3.7 of IRC SP 77-2008 including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.		17.50	Per Cubic metre.	1308.00	22890.00	Rupees One Thousand Three Hundred & Eight Only
3	Providing and laying cement concrete 1:4:8 (One cement : four coarse sand : eight graded crushed stone aggregate 40mm (forty millimetre) nominal size) mechanically mixed and curing complete excluding cost of form work upto all work plinth level including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, labour cess or other taxes imposed by the Government.		39.11	Per Cubic metre.	3947.00	154367.00	Rupees Three Thousand Nine Hundred & Fourty Seven Only
4	Providing and laying in position cement concrete 1:2:4 (One cement : two coarse sand : four graded crushed stone aggregate 40mm (forty millimetre) nominal size) mechanically mixed and curing complete excluding cost of form work upto all work foundation and plinth level including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, labour cess or other taxes imposed by the Government.		1.40	Per cubic metre	5044.00	7062.00	Rupees Five Thousand & Fourty Four Only

Sr. No.	Description of work	Quantity	Unit	Estimated Rate in Words	Total amount without Taxes	AMOUNT Rs. P
5	Construction of pavement with 60mm (sixty millimetre) thick concrete blocks conforming to clause 1504.2.1 of MORD specifications, paved and compacted over a thin bedding of sand layers (material meeting the requirement of Table 1500.6 of these specifications) of specified grading to be spread over a properly constructed and profiled base course and bounded by properly edge restraints conforming to clause 1504.2.2 and 1504.2.3 of these specifications and complete the work to the satisfaction of Junior Engineer and Assistant Engineer of the area. (Subject to further entire satisfaction of the Engineer-in-Charge), including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	122.50	Per Square Meter	1150.00	140875.00	Rupees One Thousand One Hundred & Fifty Only
Total in Figures					333594.00	Rupees Three Lakh Thirty Three Thousand Five Hundred & Ninety Four Only
	Quoted Rate in Figures	Excess(+)				
		Less(-)				



Executive Engineer
Bangana Division
H.P.P.W.D. Bangana

Percentage BoQ.

Name of work:- C/O Link road to Village Matoh km. 0/000 to 1/000(SH:-P/L G.S.B. in km. 0/090 to 0/310, W.M.M. & M/T in km. 0/090 to 0/180& C/O U-Shape Drain in km. 0/220 to 0/350)

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter Bidder name and values only

Sr. No.	Description of work	Estimated Cost	486104.00	Earnest Unit	9800.00 Estimated Rate in Words	Time Limit Total amount without Taxes	Two Month AMOUNT Rs. P
1	Preparation of sub grade by dressing to camber (Earth work for the cutting involved for sub grade to be paid for separately) depending upon the classification of soil complete as per HP.PWD., specifications and as per direction of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, Goods Service tax, Labour cess, or other taxes imposed by the Government.		316.58	Per Square metre	1.50	475.00	Rupees One - Paise Fifty Only
2	Consolidation of sub grade with power 8-10 (eight to ten) tonne capacity road roller including making good the undulation etcetra with earth or quarry soil etcetra and re-rolling the sub grade complete as per the HP.PWD specifications and as per the entire satisfaction and direction of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals The rates are inclusive of octroi, royalty, Malkana, toll tax, Goods Service tax, Labour cess, or other taxes imposed by the Government.		316.58	Per Square metre	1.05	332.00	Rupees One - Paise Five Only
3	Construction of gravel/soil aggregate sub base/base by providing well graded material of nominal maximum size grading 80mm as per table 2.3 of IRC SP 77-2008, Spreading in uniform layers with tractor mount appropriate grading arrangements on prepared surface, mixing by mix in place method at OMC with tractor mount appropriate rotavator attachment and compaction with three wheel 80-100 KN Static roller capacity to achieve the desired density complete as per specifications contained in Para 2.2,3,6 and 3.7 of IRC SP 77-2008 including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.		66.15	Per cubic metre	1677.00	110934.00	Rupees One Thousand Six Hundred & Seventy Seven Only
4	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mixer (Pug Mill), carriage of mixed material by tipper to site, laying in uniform layers in sub-base/base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100KN weight to achieve the desired density including lighting, barricading and maintenance of diversion, etc as per Tables 400.11 & 400.12 and Technical Specification Clause 406, including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government		21.62	Per Cubic metre	2125.00	45943.00	Rupees Two Thousand One Hundred & Twenty Five Only

Sr. No.	Description of work	Quantity	Unit	Estimated Rate in Words	Total amount without Taxes	AMOUNT Rs. P
5	Providing and applying primer coat with BITUMEN emulsion SS-1 on the prepared surface of granular base including cleaning of road surface with hydraulic brooms and spraying primer @ 0.70kg-1.00 kg (zero decimal seven zero kilogram to one decimal zero kilogram) per square metre using mechanical means as per M.O.R.D. technical specifications clause 502 including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	288.23	Per Square metre	69.30	19974.00	Rupees Sixty Nine - Paise Thirty Only
6	Providing and applying tack coat with bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kg per sqm (Zero point two hundred seventy five kilogram) per square metre on the prepared granular surfaces treated with primer and cleaned with Hydraulic broom as per technical specification clause 503 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	288.23	Per Square metre	24.00	6918.00	Rupees Twenty Four Only
7	Providing laying and rolling of open graded premix carpet of 20mm (twenty millimetre) thickness composed of 13.2mm (thirteen decimal two millimetre) to 5.6mm (five decimal six millimetre size aggregate at the rate of 0.27 cum(zero point two seven cubic metre)mixed with penetration grade bitumen binder VG-30 at the rate of 14.6 kg. per ten square metre and laying with paver finisher to required line grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant laying and rolling with a three wheel 80-100 (eighty to one hundred)KN static road roller. ,capacity finished to required level and grade to be followed by seal coat of either type A or type B or type C mechanically as per technical specifications clause No. 508 (Bitumen VG-30) as per the entire satisfaction and direction of Engineer – in- Charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	288.23	Per Square metre	207.00	59664.00	Rupees Two Hundred & Seven Only
8	Providing and laying seal coat for sealing the voids in a bituminous surface laid to specified level grade and cross fall using type-B as per technical specification clause 510 using BITUMEN V G - 30 at the rate of 0.68 kg (zero point six eight kilogram) premixed with 0.006 (zero point zero-zero six) cubic metre of fine aggregate per Sqm. (square metre) heated in mini hot mix plant and laying mechanically of mixed material and rolling with power road roller 8-10 (eight to ten) tonne capacity including carriage of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	288.23	Per Square metre	98.70	28448.00	Rupees Ninety Eight - Paise Seventy Only

Sr. No.	Description of work	Quantity	Unit	Estimated Rate in Words	Total amount without Taxes	AMOUNT Rs. P
9	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	104.00	Per Cubic metre.	250.00	26000.00	Rupees Two Hundred & Fifty Only
10	Providing and laying cement concrete work 1:3:6 (one cement: three sand:six graded stone aggregate) 40mm (forty millimetre) nominal size in open foundation mechanically mixed and vibrated including curing complete, including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge, including carriage of material within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	38.70	Per Cubic metre.	4680.00	181116.00	Rupees Four Thousand Six Hundred & Eighty Only
11	Providing and laying in position cement concrete 1:2:4 (One cement : two coarse sand : four graded crushed stone aggregate 20mm (twenty millimetre) nominal size)mechanically mixed and curing complete excluding cost of form work upto all work foundation and plinth level including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST , labour cess or other taxes imposed by the Government.	0.40	Per Cubic metre.	5250.00	2100.00	Rupees Five Thousand Two Hundred & Fifty Only
12	Supplying, fitting and placing HYSD bar reinforcement of Sail ,Tisco, Rinal , Jindal Panther of (JSPL) or Shyam Steel in all type of Sub-structure complete as per drawing and MORD 2014 technical specification clause 1600,2200 including cutting ,bending, binding and placing in position complete in all respect including cost of binding wire upto all heights as per the entire satisfaction and directions of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rates are inclusive octroi ,royalty, malkana, toll tax, Goods Service tax ,Labour cess, or other taxes imposed by the Government.	40.000	Per Tonne kg	105.00	4200.00	Rupees One Hundred & Five Only
Total in Figures					486104.00	Rupees Four Lakh Eighty Six Thousand One Hundred & Four Only
	Quoted Rate in Figures	Excess(+)				
		Less(-)				

Carhu
 Executive Engineer
 Bangana Division
 H.P.P.W.D.Bangana