



E- Mail id – ee-bil2-hp@nic.in
Phone No. 01978-222551

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

“NOTICE INVITING TENDERS”

Sealed items rates tender for the following works are hereby invited by the Executive Engineer Bilaspur Division No. II HPPWD Bilaspur (H.P.) from the eligible contractors of the appropriate class registered in HPPWD, as per revised enlistment rules so as to reach in the office undersigned on 24/01/2024 up to 10:30 AM and will be opened on the same day at 11:00 AM in the presence of intending contractors. The tender application will be received in this office against cash payment on 23/01/2024 up to 10:00 AM to 02:00 PM and tender form can be had from this office on same day from 03:00 PM to 05:00 PM. The earnest money as shown against each in the shape of FDR of any bank in Himachal Pradesh duly pledged in the name of undersigned must accompany with each tender. The tender form will be issued on contractor giving proof of enlistment, GST, PAN No. etc. Conditional tender and tender received without earnest money will be outrightly rejected. The offer of the tender shall be kept open for 90 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors on the office of the undersigned on any working day during the office hours.

Sr. No.	Name of work	Estimated cost	Earnest Money	Cost form	Time limit
1	Construction of PHC Building at Bhakra Tehsil Sh. Naina Devi Ji Distt. Bilaspur (SH:- C/o R/wall at RD 0/030 to 0/042).	Rs. 2,97,272/-	Rs. 6,000/-	Rs. 350/-	Three Month
2	Construction of link road from NH-205 to village Kaital Bagheri Km. 0/0 to 2/0 (SH:- C/o Subgrade, P/L Gr-I in Km. 0/0 to 0/600)	Rs. 4,72,963/-	Rs. 9,500/-	Rs. 350/-	Three Month
3	Restoration of Rain damages on link road to Harizen Basti Tiun Khas Km. 0/0 to 3/135 (SH:- C/o wire crate as a R/wall at RD 0/400 to 0/410).	Rs. 3,67,328/-	Rs. 7,400/-	Rs. 350/-	Three Month
4	Improvement of Blind curve on SNB road Km. 13/0 to 37/300 (SH:- Cutting of Blind curve in Km. 22/225 to 22/250).	Rs. 4,94,431/-	Rs. 10,000/-	Rs. 350/-	Three Month
5	Restoration of Rain damages on Sh. Naina Devi Ji Bhakra road Km. 0/0 to 37/300 (SH:- C/o R/wall at RD 32/198 to 32/205)	Rs. 4,01,382/-	Rs. 8,100/-	Rs. 350/-	Three Month
6	Restoration of Rain damages on link road to Harizen Basti Tiun Khas Km. 0/0 to 3/135 (SH:- C/o wire crate as a R/wall at RD 0/380 to 0/390).	Rs. 3,74,164/-	Rs. 7,500/-	Rs. 350/-	Three Month
7	Construction of link road from NH-205 to village Kaital Bagheri Km. 0/0 to 2/0 (SH:- C/o Subgrade, P/L gr-I in Km. 0/600 to 1/200)	Rs. 4,72,963/-	Rs. 9,500/-	Rs. 350/-	Three Month

Certified that tender of above works are being called of emergent nature in exigency of Public interest.

Terms and Conditions:-

1. The contractor should produce a copy of enlistment/renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/firm shall have his registration and GST No., the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Bilaspur Division No. II HPPWD Bilaspur and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall be similarly rejected.
5. The contractor/firms are requested to insert the rate of each item in words as in figures failing which XEN reserves the rights to accept/reject any tender without assigning any reason at any stage.
6. The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
Bilaspur Divn.No.II,
HP.PWD., Bilaspur.

Dated:- 18.1.2024

No.PW/NBT/CB/Tender-State/EA-1/2023- 12711-16

Copy forwarded to the following for information and necessary action to:-

1. The Engineer-In-Chief HPPWD Nirman Bhawan Nigam Vihar Shimla-2,
2. The Chief Engineer (HZ) HPPWD Hamirpur
3. The Superintending Engineers, 10th Circle, HPPWD Bilaspur.
4. The Executive Engineer (IT) O/o Engineer-in-Chief HPPWD Shimla through email- eeict-pwd-shi@hp.gov.in & ee-pwd-hp@nic.in for uploading the same on HPPWD web portal.
5. All the Assistant Engineers working under this Division.
6. Drawing Branch in this office/Notice Board.

Executive Engineer,
Bilaspur Divn.No.II,
HP.PWD., Bilaspur.

SCHEDULE OF QUANTITY.							
Estimated cost:- Rs.2,97,272/-Only.							
Earnest Money :- Rs.6,000/-							
Time:- Three Months.							
NAME OF WORK:- Construction of P.H.C Building at Bhakhra Tehsil Sh. Naina Devi Ji Distt. Bilaspur (SH:- C/o R/wall at RD 0/030 to 0/042)							
Sr No.	Description of items.	Quantity		Rates in		Unit	Amount
		Figure.	Words.				
1	2	3	4	5	6	7	
1	Earth work in excavation by mechanical means (Hydraulic excavator/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	24.42	cubic metre				
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, Malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	63.43	Cubic metre				
3	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	30.00	Nos.				
Total:-							

Executive Engineer:
Bilaspur Division No. 11
P.W.D., Bilaspur

SCHEDULE OF QUANTITY.							Estimated cost:- Rs.4,72,963/-Only.		
							Earnest Money :- Rs.9,500/-		
							Time:-Three Months.		
NAME OF WORK:- Construction of link road from NH-205 to Village Kattal Bagheri km 0/00 to 2/00 (SH:- C/O Subgrade, P/L Gr- I, in KM 0/00 to 0/600)									
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount			
			Figure.	Words.					
1	2	3	4	5	6	7			
1	Preparation of sub-grade by dressing to camber (Earth work) for the cutting involved for sub-grade to be measured and paid for separately depending upon the classification of soil completed as per HP PWD, Specification as per direction of Engineer-in-Charge including carriage of material with in all leads and lifts and other incidentals. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2110.50	Square metre.		Per Square metre.				
2	Consolidation of sub-grade with road roller including making good the undulation etcetra with earth or quarry soil etcetera and re-rolling the sub-grade completed as per HP PWD, specification including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2110.50	Square metre.		Per Square metre.				
3	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 1 as per Technical Specification Clause 404. By Manual Means including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax, goods and service tax, building and other construction workers, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	211.05	Cubic metres		Per Cubic metre				
Total:-									

Executive Engineer,
Bilaspur Division No. 4
HP PWD, Bilaspur

DRAFT SCHEDULE OF QUANTITY.				Estimated cost:- Rs.3,67,328/-Only.		
				Earnest Money :- Rs.7,400/-		
				Time:- Three Months.		
NAME OF WORK:-Restoration of Rain Damages on link road to Harizan Basti Tiun Khas km 0/00 to 3/135 (SH:- C/o wire crate as a R/wall at RD 0/400 to 0/410)						
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2	3	4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. All kind of soil including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	27.90	cubic metre		Per cubic metre	7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:3:6 (one Cement : Three coarse sand : six graded stone aggregate 20 mm (Twenty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.00	Cubic metre.		Per Cubic Metre	
3	Providing and laying of boulder apron laid in wire crates with 4mm (Four Millimeter) dia GI wire confirming to IS:280 and IS:4826 in 100 mmx100 mm (One Hundred Millimeter into One Hundred Millimeter) mesh(Woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighing not less than 25kg as per drawing and technical specification clause 301. including cost of form work and curing complete. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	89.85	Cubic metre		Per Cubic metre	
4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	20.20	Cubic metre.		Per Cubic Metre	
					Total:-	

SCHEDULE OF QUANTITY.						
Estimated cost:- Rs.4,94,431/-Only.						
Earnest Money :- Rs.10,000/-						
Time:- Three Months.						
NAME OF WORK:- Improvement of Blind Curve on SNB road km 13/00 to 37/300 (SH:- Cutting of blind curve in km 22/225 to 22/250)						
Sr No.	Description of Items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grade width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification Clause 300.1603.1, 1603.2, & sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un-useful material for filling in road way, camber, embankments for grade improvements and disposal of all surplus un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals, transport or mechanical means, alongwith its levelling fine dressing and carriage of machineries, materials, tools equipments and safety measures and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work hard rock 1/6th (One sixth) of jumper work in all cases failing which recovery shall be effected on the prevailing market rates. Any loss to the public/private property during the course of execution shall be the absolute responsibility of all the Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate includes octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government. A recovery of useful stones for 376.22 (Three Hundred Seventy Six point Twenty Two) cubic metre @ Rs.300/- (three hundred) Per cubic metre shall be done on pro-rata basis in each running bill for this item	1213.63			Per Cubic metre	7
Total						

Executive Engineer
Bilaspur Division No. 11
P.W.D., Bilaspur

SCHEDULE OF QUANTITY.							Estimated cost:- Rs.4,01,382/-Only.	
							Earnest Money :- Rs.8,100/-	
							Time:- Three Months.	
NAME OF WORK:- Restoration of Rain Damages on Sh. Naina Devi ji Bakhra road km 0/00 to 37/300 (SH:- C/O R/wall at RD 32/198 to 32/205)								
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount		
			Figure.	Words.				
1	2	3	4	5	6	7		
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge, ordinary rock, including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty ,Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.78	cubic metre		Per cubic metre			
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	76.48	Cubic metre		Per Cubic metre			
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	28.28	Cubic metre		Per Cubic Metre			
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7.including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess ,royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	30.00	Nos		Each			
Total:-								

Executive Engineer,
 P.W.D. Division No. 2,
 P.W.D., Bikaner (R.P.)

SCHEDULE OF QUANTITY.						Estimated cost:- Rs.3,74,164/-Only.	
						Earnest Money :- Rs.7,500/-	
						Time:- Three Months.	
NAME OF WORK:-Restoration of Rain Damages on link road to Harizan Basti Tiun Khas km 0/00 to 3/135 (SH:- C/o wire crate as a R/wall at RD 0/380 to 0/390)							
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount	
			Figure.	Words.			
1	2	3	4	5	6	7	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. All kind of soil including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	25.10			cubic metre	Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:3:6 (one Cement : Three coarse sand : six graded stone aggregate 20 mm (Twenty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.00			Cubic metre.	Per Cubic Metre	
3	Providing and laying of boulder apron laid in wire crates with 4mm (Four Millimeter) dia GI wire confirming to IS:280 and IS:4826 in 100 mmx100 mm (One Hundred Millimeter into One Hundred Millimeter) mesh(Woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighing not less than 25kg as per drawing and technical specification clause 301 including cost of form work and curing complete including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	89.85			Cubic metre	Per Cubic metre	
4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	26.40			Cubic metre.	Per Cubic Metre	
						Total:-	

Executive Engineer,
 Disaster Division No. II
 PWD, Bileasap

SCHEDULE OF QUANTITY.						
Estimated cost:- Rs.4,72,963/-Only.						
Earnest Money :- Rs.9,500/-						
Time:- Three Months.						
NAME OF WORK:- Construction of link road from NH-205 to Village Kattal Bagheri km 0/00 to 2/00 (SH:- C/O Subgrade, P/L Gr-I in KM 0/600 to 1/200)						
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2	3	4	5	6	7
1	Preparation of sub-grade by dressing to camber (Earth work) for the cutting involved for sub-grade to be measured and paid for separately depending upon the classification of soil completed as per HP PWD, Specification as per direction of Engineer-in-Charge including carriage of material with in all leads and lifts and other incidentals. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2110.50	Square metre.		Per Square metre.	
2	Consolidation of sub-grade with road roller including making good the undulation etcetra with earth or quarry soil etcetera and re-rolling the sub-grade completed as per HP.PWD, specification including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction workers, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2110.50	Square metre.		Per Square metre.	
3	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 1 as per Technical Specification Clause 404. By Manual Means including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax, goods and service tax, building and other construction workers, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	211.05	Cubic metres		Per Cubic metre	
Total:-						

Executive Engineer
Bilaspur Division No. II
HP PWD, Bilaspur