



E- Mail id – ee-bil2-hp@nic.in
Phone No. 01978-222551

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

"NOTICE INVITING TENDERS"

Sealed items rates tender for the following works are hereby invited by the Executive Engineer Bilaspur Division No. II HPPWD Bilaspur (H.P.) from the eligible contractors of the appropriate class registered in HPPWD, as per revised enlistment rules so as to reach in the office undersigned on 08/01/2024 up to 10:30 AM and will be opened on the same day at 11:00 AM in the presence of intending contractors. The tender application will be received in this office against cash payment on 06/01/2024 up to 10:00 AM to 02:00 PM and tender form can be had from this office on same day from 03:00 PM to 05:00 PM. The earnest money as shown against each in the shape of FDR of any bank in Himachal Pradesh duly pledged in the name of undersigned must accompany with each tender. The tender form will be issued on contractor giving proof of enlistment, GST, PAN No. etc. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 90 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors on the office of the undersigned on any working day during the office hours.

Sr. No.	Name of work	Estimated of cost	Earnest Money	Cost of form	Time limit
1	Construction of link road from Makri to village Bariwala Km. 0/0 to 4/500 (SH:- c/o 900mm dia RCC hume pipe culvert at RD 2/150)	Rs. 2,27,252/-	Rs. 4,600/-	Rs. 350/-	Three Month
2	Widening of Patwarkhana Plog Dungloo road Km. 0/0 to 7/0 (SH:- Improvement of curve in Km. 4/300 to 4/360)	Rs. 1,91,390/-	Rs. 3,900/-	Rs. 350/-	Three Month
3	C/o link road village Namhol Km. 0/0 to 0/500 (SH:- Providing and laying M.T. work in Km. 0/300 to 0/500) Deposit work	Rs. 1,46,231/-	Rs. 3,000/-	Rs. 350/-	Three Month
4	Improvement of Blind curve on Ghawandal to Ajnol road Km. 0/0 to 4/765 (SH:- Improvement of curve in Km. 3/770 to 3/800)	Rs. 2,21,303/-	Rs. 4,500/-	Rs. 350/-	Three Month
5	Improvement of Blind curve on SNB road Km. 13/0 to 37/300 (SH:- Cutting of Blind curve in Km. 22/360 to 22/420).	Rs. 4,89,978/-	Rs. 10,000/-	Rs. 350/-	Three Month
6	Construction of link road from Makri to village Bariwala Km. 0/0 to 4/500 (SH:- c/o 900mm dia RCC hume pipe culvert at RD 1/705)	Rs. 2,64,181/-	Rs. 5,300/-	Rs. 350/-	Three Month

Certified that tender of above works are being called of emergent nature in exigency of Public interest.

Terms and Conditions:-

1. The contractor should produce a copy of enlistment/renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/firm shall have his registration and GST No., the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Bilaspur Division No. II HPPWD Bilaspur and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall be similarly rejected.
5. The contractor/firms are requested to insert the rate of each item in words as in figures failing which XEN reserves the rights to accept/reject any tender without assigning any reason at any stage.
6. The tender shall be issued to those contractors who have not more than two works in hand.

sd/
Executive Engineer,
Bilaspur Divn.No.II,
HP.PWD., Bilaspur.

No.PW/NBT/CB/Tender-State/EA-1/2023-

12013-22

Dated:- 02-01-2024

Copy forwarded to the following for information and necessary action to:-

1. The Engineer-In-Chief HPPWD Nirman Bhawan Nigam Vihar Shimla-2.
2. The Chief Engineer (HZ) HPPWD Hamirpur
3. The Superintending Engineers, 10th Circle, HPPWD Bilaspur.
4. The Executive Engineer (IT) O/o Engineer-in-Chief HPPWD Shimla through email eeict-pwd-shi@hp.gov.in & ee-bil2-hp@nic.in for uploading the same on HPPWD web portal.
5. All the Assistant Engineers working under this Division.
6. Drawing Branch in this office/Notice Board.

sd/
Executive Engineer,
Bilaspur Divn.No.II,
HP.PWD., Bilaspur.

SCHEDULE OF QUANTITY.						
Estimated cost:- Rs.2,27,252/-Only.						
Earnest Money :- Rs.4,600/-						
Time:- Three Months.						
NAME OF WORK:- Construction of link road from Makri to village Bariwala km 0/00 to 4/500 (SH:- C/o 900 mm dia RCC Hume Pipe culvert at Rd 2/150)						
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2	3	4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge, ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	39.43	cubic metre		Per cubic metre	7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.93	Cubic metre		Per Cubic metre	
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (one Cement : Four coarse sand) : Eight graded stone aggregate 40 mm (forty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.88	Cubic Metre		Per Cubic Metre	
4	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:3:6 (one Cement : Three coarse sand : six graded stone aggregate 20 mm (Twenty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.99	Cubic metre		Per Cubic Metre	
5	Providing reinforced concrete in sub-structure complete as per drawings and technical specifications clause 802.804,805,806,807,1202 & 1204, P.C.C. grade M-15 (i) Nominal mix 1:2:5.5) (One Cement two and half sand five graded stone aggregate 40 mm nominal size. The minimum cement contents should not be less than 225 kg per cubic meter including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.96	Cubic Metre		Per Cubic Metre	

6	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (One cement : Two fine sand) including testing of joints etc. complete 900 mm (Nine Hundred Millimeter) dia. R.C.C. pipe including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.50	Running Meter		Per Running Meterr
7	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:2:4 (one Cement : Two coarse sand : Four graded stone aggregate) 20 mm (Twenty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.110	Cubic metre.		Per Cubic Metre
8	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204, 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.56	Cubic metre.		Per Cubic Metre
9	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.00	Nos.		Each
Total:-					

Executive Engineer,
Bilaspur Division No. 2,
HP. PWD., Bilaspur (HP).

SCHEDULE OF QUANTITY.				Estimated cost:- Rs.1,91,390/-Only.			
				Earnest Money :- Rs. 3,900/- only			
				Time:- Three Months.			
NAME OF WORK:- Widening of Patwarkhana Plog Dungloo road km 0/00 to 7/00 (SH:- Improvement of curve in km 4/300 to 4/360)							
Sr No.	Description of items.	Quantity		Rates in		Unit	Amount
				Figure.	Words.		
1	2	3		4	5	6	7
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual /mechanical means including saturated soil comprising of ordinary soil , soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grade width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification 2014 Clause 300, 1603 & sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un -useful material for filling in road way, camber , embankments for grade improvements and disposal of all surplus un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, alongwith its levelling fine dressing ,and carriage of machineries, materials tools equipments and safety measures and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work hard rock 1/6th(One sixth) of jumper work in all cases failing which recovery shall be effected on the prevailing market rates,Any loss to the public/private property during the course of execution shall be the absolute responsibility of all the Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts The rate includes octroi, royalty, Malkana,toll tax, Goods & service Tax or other taxes imposed by the Government. A recovery of useful stones for 85.00 (Eighty Five) cubic metre @ Rs. 300/- (Three Hundred) Per cubic metre shall be done on pro-rata basis in each running bill for this item	637.50	Cubic Metre			Per Cubic Metre	
Total:-							

Executive Engineer:
Bilaspur Division No. 1,
H.P. & W.D., Bilaspur/H.P.,
(21)

SCHEDULE OF QUANTITY.							Estimated cost:- Rs.1,46,231/-Only.	
							Earnest Money :- Rs.3,000/-	
							Time:- Three Months.	
NAME OF WORK:- Construction of link road Village Namhol km 0/00 to 0/500 (SH:- Providing and Laying M.T work in km . 0/300 to 0/500) Deposit work								
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount		
			Figure.	Words.				
1	Providing laying spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness hand packing rolling with three wheel 80-100 KN static roller in stages to proper grade and camber applying and brooming stone screening/binding materials to fill-up the interstices of coarse aggregate watering and compacting to the required density Grading 3 as per Technical Specification Clause 405. (By Manual means) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction workers, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.99	Cubic metres		Per Cubic metre			
2	Providing and applying primer coat with bitumen emulsion (SS-I) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70 -1.00 (Zero point seven zero to one point zero)Kilogramme per Square metre using mechanical means as per Technical Specifications Clause 502. including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge..The rates includes octroi,royalty ,Malkana toll tax ,goods and service tax ,building and other construction workers, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	630.00	Square metre.		Per Square metre.			
3	Providing and applying tack coat with bitumen emulsion (RS-I) using emulsion distributor at the rate of 0.20 to 0.25 Kg. (Zero point two zero to Zero point two five)Kilogram per square metre on the prepared granular surface treated with primer and cleaned with Hydraulic broom as per Technical Specification Clause-503 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge..The rates includes octroi,royalty ,Malkana toll tax ,goods and service ,building and other construction workers, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	630.00	Square metre.		Per Square metre.			

4	Providing, laying and rolling of open-graded premix carpet of 20mm (Twenty millimetre) compacted thickness composed of crushed stone aggregate 13.2 mm to 5.6 mm (Thirteen point two millimetre to five point six millimetre) @ 0.27 cubic metres (Zero point two seven) per 10 square metre (Ten Square metre) mixed with penetration grade paving bitumen V.G-30 (Viscosity grade-Thirty) at the rate of 14.6 kg.(Fourteen point six kilogramme) per ten square metre of road surface to required line, grade and level to serve as wearing course on a previously prepared base including mixing and heating binder and aggregate in suitable plant, laying with paver finisher and rolling with a three wheel 80-100 KN (Eighty - hundred) capacity static road roller finished to required level and grade to be followed by seal coat of type-B by mechanical means as per MORD technical specification 2014. clause 508 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax, goods and service tax, building and other construction workers, welfare cess royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	630.00	Square metre.		Per Square metre.
5	Providing and laying seal coat for sealing the voids in bituminous surface laid to the specified levels, grade and cross fall using Type-B and as per Technical Specifications, 2014 Clause 510 using Bitumen (S-90) by Mechanical means including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax, goods and service tax, building and other construction workers, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	630.00	Square metre		Per Square metre
	Total				


Executive Engineer,
Bilaspur Division No. 2,
HP. PWD., Bilaspur (HP)

SCHEDULE OF QUANTITY.						Estimated cost:- Rs.2,21,303/-Only.		
						Earnest Money :- Rs. 4,500/- only		
						Time:- Three Months.		
NAME OF WORK:- Improvement of Blind Curve on Ghawandal to Ajnol road km 0/00 to 4/765 (SH):- Improvement of curve in km 3/770 to 3/800)								
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount		
			Figure.	Words.				
1	2 Excavation in hilly area in all heights and depths in all kinds of soil by manual /mechanical means including saturated soil comprising of ordinary soil , soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grade, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. Technical Specification 2014 Clause 300.302.3.5 & sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of material for filling in road way, camber ,embankments for grade improvements and disposal of all surplus un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, alongwith its levelling fine dressing and carriage of machineries, materials tools equipments and execution shall be the absolute responsibility of all the Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate includes octroi, royalty, Malkana,toll tax, Goods & service Tax or other taxes imposed by the Government. A recovery of useful stones for 85.68 (Eighty Five point Sixty Eight) cubic metre @ Rs. 300/- (Three Hundred) Per cubic metre shall be done on pro-rata basis in each running bill for this item.	3 257.03	4 Cubic Metre	5	6 Per Cubic Metre	7		
Total:-								

Executive Engineer,
Bilaspur Division No. 2,
HP. PWD., Bilaspur (HP).

SCHEDULE OF QUANTITY.

SCHEDULE OF QUANTITY.		Estimated cost:- Rs.4,89,978/-Only.				
		Earnest Money :- Rs.10,000/-				
		Time:- Three Months.				
N/ME OF WORK:- Improvement of Blind Curve on SNB road km 13/00 to 37/300 (SH:- Cutting of blind curve in km 22/360 to 22/420)						
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual /mechanical means including saturated soil comprising of ordinary soil , soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grade width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification Clause 300,1603.1,1603.2, & sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un -useful material for filling in road way, camber ,embankments for grade improvements and disposal of all surplus un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, alongwith its levelling fine dressing and carriage of machineries, materials tools equipments and safety measures and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work hard rock 1/6th(One sixth) of jumper work in all cases failing which recovery shall be effected on the prevailing market rates.Any loss to the public/private property during the course of execution shall be the absolute responsibility of all the Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate includes octroi, royalty, Malkana toll tax sale tax or other taxes imposed by the Government. A recovery of useful stones for 382.90 (Three Hundred Eighty Two point Ninety) cubic metre @ Rs.300/- (three hundred) Per cubic metre shall be done on pro-rata basis in each running bill for this item	3	4	5	6	7
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual /mechanical means including saturated soil comprising of ordinary soil , soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grade width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification Clause 300,1603.1,1603.2, & sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un -useful material for filling in road way, camber ,embankments for grade improvements and disposal of all surplus un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, alongwith its levelling fine dressing and carriage of machineries, materials tools equipments and safety measures and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work hard rock 1/6th(One sixth) of jumper work in all cases failing which recovery shall be effected on the prevailing market rates.Any loss to the public/private property during the course of execution shall be the absolute responsibility of all the Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate includes octroi, royalty, Malkana toll tax sale tax or other taxes imposed by the Government. A recovery of useful stones for 382.90 (Three Hundred Eighty Two point Ninety) cubic metre @ Rs.300/- (three hundred) Per cubic metre shall be done on pro-rata basis in each running bill for this item	1148.70			Per Cubic metre	
Total						


 Executive Engineer,
 Bilaspur Division No. 2,
 HP. PWD., Bilaspur (HP).

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.2,64,181/-Only.
 Earnest Money :- Rs.5,300/-
 Time:- Three Months.

NAME OF WORK:- Construction of link road from Makri to village Bariwala km 0/00 to 4/500 (SH:- C/o 900 mm dia RCC Hume Pipe culvert at Rd 1705)

Sr No.	Description of items.	Quantity		Rates in		Unit	Amount
		Figure.	Words.	Figure.	Words.		
1	2 Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge, ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3 41.37	cubic metre	4	5	6 Per cubic metre	7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	24.98	Cubic metre			Per Cubic metre	
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (one Cement : Four coarse sand) : Eight graded stone aggregate 40 mm (forty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.93	Cubic Metre			Per Cubic Metre	
4	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:3:6 (one Cement : Three coarse sand : six graded stone aggregate 20 mm (Twenty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	11.65	Cubic metre			Per Cubic Metre	
5	Providing reinforced concrete in sub-structure complete as per drawings and technical specifications clause 802.804.805.806.807, 1202 & 1204 P.C.C. grade M-15 (i) Nominal mix 1:2:5:5)(One Cement two and half sand five graded stone aggregate 40 mm nominal size. The minimum cement contents should not be less than 225 kg per cubic meter including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.96	Cubic Metre			Per Cubic Metre	

6	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (One cement : Two fine sand) including testing of joints etc. complete 900 mm (Nine Hundred Millimeter) dia R.C.C. pipe including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.50	Running Meter		Per Running Meterr
7	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:2:4 (one Cement : Two coarse sand : Four graded stone aggregate) 20 mm (Twenty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.110	Cubic metre.		Per Cubic Metre
8	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	9.54	Cubic metre.		Per Cubic Metre
9	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.00	Nos.		Each
Total:-					

Executive Engineer,
Bilaspur Division No. 2,
HP. PWD., Bilaspur (HP).