

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.PWI/CB/2nd C/Tender/2023-24- 6210-40
To

Dated: 09/01/2024


✓ The Executive Engineer,
HP.PWD. Nirman Bhawan, Nigam Vihar,
Shimla.

Subject:- Publication of tender Notice on departmental site.

Sir,

In this context, it is submitted that the tender notice is being enclosed herewith for up loading on Department web-site as per Notification of the Principal Secretary (PW) to the Govt. of Himachal Pradesh letter No. PBW-(B)A-9 (3)1/2020 dated Shimla-2 the 16th July 2021 as the work mentioned in the tender notice are urgent in nature and in public intrest.


DA/As above.


Executive Engineer,
Indora Division, HPPWD,
Indora.

Copy forwarded for information to following for information please:-

- The Superintending Engineers 9th Circle, HPPWD, Nurpur.
- All the Assistant Engineers working under this Division.
- All the Contractors.
- Notice Board.

DA/As above.


Executive Engineer,
Indora Division, HPPWD, Indora
Telephone No. 01893-242336
e-mail- eepwd-indora-hp@gov.in

Indora Division, HPPWD, Indora,
Telephone No. 01893-2241233
e-mail- eePWD-indora-hp@gov.in
On behalf of Governor of HP.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**


Sealed item rate tenders on the form 6 & 8 are hereby invited by the the Executive Engineer, Indora Division HPPWD., Indora on behalf of the worthy Governor of Himachal Pradesh for the following works from the approved and eligible contractors enlisted in HP.PWD. The application for purchase of tender form should be reached in this office on dated 23.01.2024 up to 1.00 PM and tender form will be issued from this office against cash payment (Nonrefundable) up to 4.00 PM on same day. The tender will be opened on 24.01.2024 at 11.30 PM in presence of the contractor or their authorized representatives who may like to be present.

The Earnest Money in shape of National Saving Certificate/ time deposit account/saving account in any nationalized bank in HP duly pledged in favour of the Executive Engineer, Indora division, HPPWD., Indora will be received along with application for obtaining tenders form. The conditional tenders will summarily be rejected. The offer of the tenders will be kept open for 90 days from the date of opening of tender. The Executive Engineer, Indora Division, HP.PWD. Indora reserves the right to reject any or all tenders without assigning any reason. The contractor should append their Enlistment/ Renewed Certificate/ Sale Registration Number with the application for issue of tender form. If any of the mentioned above date happens to be holiday the same should be processed on next working day.

| Sr. No | Name of work. | Estimated cost (Rs.) | Earnest money (Rs) | Time limit | Cost of form | Eligible class of Contractor. |
|--------|--|----------------------|--------------------|------------|--------------|-------------------------------|
| 1. | A/R & M/O to Damtal Kandwal road Km. 0/0 to 9/500 (Repair of Pot holes in Km. 3/520 to 4/00). | 493140 | 10000 | One Month. | 350/- | Class D & C |
| 2. | A/R & M/O to Damtal Kandwal road Km. 0/0 to 9/500 (Repair of Pot holes in Km. 4/030 to 4/510). | 493591 | 10000 | One Month. | 350/- | Class D & C |
| 3. | A/R & M/O to Damtal Kandwal road Km. 0/0 to 9/500 (Repair of Pot holes in Km. 4/550 to 5/100). | 493182 | 10000 | One Month. | 350/- | Class D & C |

TERMS AND CONDITIONS:-


1. The contractor/Firm shall have his GST No. & copy of the same be attached with the application.
2. The intending Contractors/firm should have attached copy of registration/renewal.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender for The application received without earnest money & cost of tender form shall summarily be rejected.
4. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender form. In this regard, the contractor has submitted an affidavit that he is not having more than two works.
5. The intending contractors are required to see the site of the work before submitting the tender.
6. The offer of the tender shall remain valid upto 75 days after the opening of tender.
7. The Executive Engineer reserves the right to reject/accept any or all tenders without assigning any reasons.


Executive Engineer,
Indora Division, HPPWD, Indora,
Telephone No. 01893-2241233
e-mail- eePWD-indora-hp@gov.in
On behalf of Governor of HP.

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

CERTIFICATE

It is certified that the tenders called vide this office letter No.PWL/ CB/ 2ndC /Tender/ 2023-24- 6040-70 dated 06.01.2023 is emergent nature and also in the public interest.


Executive Engineer,
Indora Division, HPPWD,
Indora.

BILL OF QUANTITY


Name of Work:- A/R & M/O to Damtal Kandwal road km 0/00 to 9/500 (Sh:- Repair of Pot holes in km 3/520 to 4/00)

Estimated Cost :-Rs. 493140/-

Earnest Money:- Rs 10000/-

Time Limit :- Two Months

| Sr.N | Description of Items | Quantity | Units | Rate in fig. | words | Amount |
|---------|--|----------|------------------|--------------|-------|--------|
| 1 | Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.40 mm (fifty three millimetres to twenty two point four zero millimetres) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. | 10.77 | Per Cubic Meter | | | |
| 2 | Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing, laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27 cum, per 10 sqm (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10 (viscosity grade- ten) at the rate 14.6 Kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06 (zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10 (viscosity grade -ten) 6.8 Kg. (Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. | 1381.73 | Per Square Meter | | | |
| Total:- | | | | | | |


 Executive Engineer
 H.P.W.D Division
 Indora (Kangra) H.P.

BILL OF QUANTITY

Name of Work:- A/R & M/O to Damtal kandwal road km 0/00 to 9/500 (SH:- Repair of Pot holes in km 3/520 to 4/00)

194

| Name of Work:- A/R & M/O to Damtal kandwal road km 0/00 to 9/500 (SH:- Repair of Pot holes in km 3/520 to 4/00) | | | | | | Estimated Cost :-Rs. 493140/- | |
|--|--|----------|------------------|--------------|--|-------------------------------|--|
| | | | | | | Earnest Money:- Rs 10000/- | |
| | | | | | | Time Limit :- Two Months | |
| Sr.N | Description of Items | Quantity | Units | Rate in fig. | words | Amount | |
| 1 | Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -111, 53mm to 22.40 mm (fifty three millimetres to twenty two point four zero millimetres) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. | 10.77 | Per Cubic Meter | 1411.30 | Rupees One thousand Four Hundred Eleven and paise Thirty Only. | 15200.00 ✓ | |
| 2 | Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing, laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal two millimeter) aggregate at the rate of 0.12 cum per 10 sqm (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10 (viscosity grade- ten) at the rate 14.6 Kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06 (zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10 (viscosity grade -ten) 6.8 Kg. (Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials within all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. | 1381.73 | Per Square Meter | 345.90 | Rupees Three hundred forty five and paise Ninety Only. | 477940.00 ✓ | |
| Total:- | | | | | | 493140.00 ✓ | |

Drafts are approved for Rs. 493140/- only (Four Lacs Ninety three thousand one hundred forty)

Executive Engineer
H.P.W.D Division
Indora (Kangra) H.P.

BILL OF QUANTITY


Name of Work:- A/R & M/O to Danttal kandawal road km 0/00 to 9/500 (SH:- Repair of Pot holes in km 4/030 to 4/510)

Estimated Cost :-Rs. 493591/-

Earnest Money:- Rs 10000/-

Time limit :- Two Months

| Sr.N | Description of Items | Quantity | Units | Rate in fig. | words | Amount |
|------|--|----------|------------------|--------------|-------|--------|
| 1 | Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -II, 53mm to 22.40 mm (fifty three millimetres to twenty two point four zero millimetres) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. | 11.09 | Per Cubic Meter | | | |
| 2 | Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing, laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27 cum, per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10 (viscosity grade- ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06 (zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10 (viscosity grade -ten) 6.8 Kg. (Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. | 1381.73 | Per Square Meter | | | |
| | Total:- | | | | | |


 Executive Engineer
 H.P.W.D Division
 Indora (Kangra) H.P.

195

BILL OF QUANTITY

Name of Work:- A/R & M/O to Danttal kandwal road km 0/00 to 9/500 (SH:- Repair of Pot holes in km 4/030 to 4/510)

Estimated Cost:-Rs. 493591/-

Earnest Money:- Rs 10000/-

Time Limit:- Two Months

| Sr.N | Description of Items | Quantity | Units | Rate in fig. | words | Amount |
|---------|---|----------|------------------|--------------|--|-----------|
| 1 | Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -11, 53mm to 22.40 mm (fifty three millimetres to twenty two point four zero millimetres) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. | 11.09 | Per Cubic Meter | 1411.30 | Rupess One thousand Four Hundred Eleven and paise Thirty Only. | 15651.00 |
| 2 | Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS- Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum, per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg (Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. | 1381.73 | Per Square Meter | 345.90 | Rupess Three hundred forty five and paise Ninety Only. | 477940.00 |
| Total:- | | | | | | 493591.00 |

Draft S.O. approved for Rs. 493591/- only
(2 Four Lacs Ninety three thousand five hundred Ninety one) only.

Executive Engineer
H.P.W.D Division
Indora (Kangra) H.P.

195

BILL OF QUANTITY


Name of Work:- A/R & M/O to Dambal Kandwal road km 0/00 to 9/500 (SH:- Repair of Pot holes in km 4/550 to 5/100)

Estimated Cost :-Rs. 493182/-

Earnest Money:- Rs 10000/-

Time Limit :- Two Months

| Sr.N | Description of Items | Quantity | Units | Rate in fig. | words | Amount |
|----------------|--|----------|------------------|--------------|-------|--------|
| 1 | Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -II, 53mm to 22.40 mm (fifty three millimetres to twenty two point four zero millimetres) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. | 10.80 | Per Cubic Meter | | | |
| 2 | Repair to pot holes and removal of loose materials, trimming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing, laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum. per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10 (viscosity grade- ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06 (zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10 (viscosity grade- ten) 6.8 Kg. (Six decimal eight kilogramme) as per MORD technical specification clause-1804.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads, and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. | 1381.73 | Per Square Meter | | | |
| Total:- | | | | | | |


Executive Engineer
 H.P.W.D Division
 Indora (Kangra) H.F.

BILL OF QUANTITY

Name of Work:- A/R & M/O to Darnatal Kandawal road km 0/00 to 9/500 (SH:- Repair of Pot holes in km 4/550 to 5/100)

Estimated Cost :- Rs. 493182/-

Earnest Money:- Rs 10000/-

Time Limit :- Two Months

| Sl. N o. | Description of Items | Quantity | Units | Rate in fig. | words | Amount |
|-------------|---|----------|------------------|--------------|--|------------------|
| 1 | Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -111, 53mm to 22.40 mm (fifty three millimetres to twenty two point four zero millimetres) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. | 10.80 | Per Cubic Meter | 1411.30 | Rupees One thousand Four Hundred Eleven and paise Thirty Only. | 15242.00 |
| 2 | Repair to pot holes and removal of loose materials, turning of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelled or towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum, per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade- ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat (type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg (Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government | 1381.73 | Per Square Meter | 345.90 | Rupees Three hundred forty five and paise Ninety Only. | 477940.00 |
| | Total:- | | | | | 493182.00 |

*Rate so & approved for Rs. 493182/- only
(3 four lakhs Ninety three thousand one hundred
Eighty two) only.*

*Executive Engineer
H.P.W.D Division
Indora (Kangra) H.P.*

196