



Office of
Executive Engineer B&R Division HP.PWD. Joginder Nagar
Himachal Pradesh Public Works Department, Mandi-175015
Phone & Fax No. 01908-222033 E-Mail:- ee-jog-hp@nic.in

"NOTICE INVITING TENDER"

Sealed item rate tender for the following works are hereby invited by the Executive Engineer, B&R Division HP.PWD., Joginder Nagar District Mandi (H.P.) from the eligible contractors of the appropriate class registered in HP.PWD. as per revised enlistment rules so as to reach in the office of under signed on 04-03-2024 up to 11:30 A.M. and will be opened on the same day at (12:00 noon) in the presence of intending contractors. The tender application will be received in this office on 01-03-2024 up to 10.00 A.M. to 12:30 P.M. and tender form can be had from this office on 02-03-2024 from 2.00 P.M. to 5.00 Pm. The earnest money as shown against each in the shape of F.D.R of any bank in Himachal Pradesh duly pledged in the name of the under signed must accompany with each tender. The tender form will be issued to contractor giving proof of enlistment, GST. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors in the office of the under signed on any working day during the office hours.

Sr. No.	Name of work	Amount put to tender/ Estimated cost	Earnest Money	Cost tender form	Eligible Class of Contractor	Time
1	Construction of Multipurpose Sports Stadium at Chauntra distt. Mandi (H.P.) (SH:- C/O R/Wall Chauntra side at RD. 0/0 to 0/015).	Rs.4,33,670/-	Rs.8,700/-	Rs. 350/-	Class "D"	Three Months
2	Construction of link road Shiv Mandir Panch Mukhi Mahadev to GSSS Langna km. 0/00 to 1/450 (SH:- Providing and laying Kharanja Soling and CC pavement at km. 0/170 to 0/270).	Rs. 3,52,845/-	Rs. 7,100/-	Rs. 350/-	Class "D"	Three Months
3	Construction of Bhajera Tila Jarla Road km. 0/00 to 2/0 under MGNREGA (SH:- Supply and stacking of Crushed stone aggregate 20mm, Course sand and Boulder)	Rs.2,53,708/-	Rs.5,000/-	Rs. 350/-	Class "D"	Three Months
4	Construction & M/T on Nagan Jaral Bhajera road km. 0/0 to 3/0 under MGNREGA (SH:- Supply and stacking of Crushed stone aggregate 20mm, Course sand and Boulder)	Rs.2,53,708/-	Rs.5,000/-	Rs. 350/-	Class "D"	Three Months
5	Construction of Cement Concrete Road Danehad km. 0/0 to 0/500 under MGNREGA (SH:- Supply and stacking of Crushed stone aggregate 20mm, Course sand and Boulder).	Rs.2,53,708/-	Rs.5,000/-	Rs. 350/-	Class "D"	Three Months
6	Concrete and soling link road Matkehar km. 0/0 to 2/500 under MGNREGA (SH:- Supply and stacking of Crushed stone aggregate 20mm, Course sand and Boulder).	Rs.2,53,708/-	Rs.5,000/-	Rs. 350/-	Class "D"	Three Months
7	Concrete and soling link road Nafu Gaon km. 0/0 to 1/700 under MGNREGA (SH:- Supply and stacking of Crushed stone aggregate 20mm, Course sand and Boulder).	Rs.2,53,708/-	Rs.5,000/-	Rs. 350/-	Class "D"	Three Months
8	Construction of Cement Concrete Jagmohan road km. 0/0 to 1/500 under MGNREGA (SH:- Supply and stacking of Crushed stone aggregate 20mm, Course sand and Boulder).	Rs.2,53,708/-	Rs.5,000/-	Rs. 350/-	Class "D"	Three Months
9	Construction of Concrete link road Bella km. 0/0 to 1/000 under MGNREGA (SH:- Supply and stacking of Crushed stone aggregate 20mm, Course sand and Boulder).	Rs.2,53,708/-	Rs.5,000/-	Rs. 350/-	Class "D"	Three Months
10	Construction of Concrete link road Langha km. 0/0 to 1/000 under MGNREGA (SH:- Supply and stacking of Crushed stone aggregate 20mm, Course sand and Boulder).	Rs.2,53,708/-	Rs.5,000/-	Rs. 350/-	Class "D"	Three Months
11	Construction of Concrete road Majhogla to Shanan upto Mala Langha km. 0/00 to 1/000 under MGNREGA (SH:- Supply and stacking of Crushed stone aggregate 20mm, Course sand and Boulder).	Rs.2,53,708/-	Rs.5,000/-	Rs. 350/-	Class "D"	Three Months
12	Construction of Concrete road to Jhamehar village km. 0/00 to 1/000 under MGNREGA (SH:- Supply and stacking of Crushed stone aggregate 20mm, Course sand and Boulder).	Rs.2,53,708/-	Rs.5,000/-	Rs. 350/-	Class "D"	Three Months
13	Construction of Concrete Road to Mata Chaturbhujia km. 0/0 to 1/500 under MGNREGA (SH:- Supply and stacking of Crushed stone aggregate 20mm, Course sand and Boulder).	Rs.2,53,708/-	Rs.5,000/-	Rs. 350/-	Class "D"	Three Months
14	M/O link rod to Mata Bhabhori km. 0/0 to 4/000 under MGNREGA (SH:- Supply and stacking of Crushed stone aggregate 20mm, Course sand and Boulder).	Rs.2,53,708/-	Rs.5,000/-	Rs. 350/-	Class "D"	Three Months
15	Construction of Cement Concrete road Panjaiter to Sasnu Bharola km. 0/0 to 1/000 under MGNREGA (SH:- Supply and stacking of Crushed stone aggregate 20mm, Course sand and Boulder).	Rs.2,53,708/-	Rs.5,000/-	Rs. 350/-	Class "D"	Three Months
16	Construction of Cement concrete Road Bharola Sasnu to Kuthera km. 0/0 to 1/000 under MGNREGA (SH:- Supply and stacking of Crushed stone aggregate 20mm, Course sand and Boulder).	Rs.2,53,708/-	Rs.5,000/-	Rs. 350/-	Class "D"	Three Months
17	Construction of link road Drubbal to Sarmana km. 0/0 to 2/500 under MGNREGA (SH:- Supply and stacking of Crushed stone aggregate 20mm, Course sand and Boulder).	Rs.2,53,708/-	Rs.5,000/-	Rs. 350/-	Class "D"	Three Months

18	Construction of concrete link road Pipil Badhu Bharmara km. 0/0 to 4/500 under MGNREGA (SH:- Supply and stacking of Crushed stone aggregate 20mm, Course sand and Boulder).	Rs.2,53,708/-	Rs.5,000/-	Rs. 350/-	Class "D"	Three Months
19	Construction of Concrete road to Jhamehar Syohi Banon km. 0/0 to 1/000 under MGNREGA (SH:- Supply and stacking of Crushed stone aggregate 20mm, Course sand and Boulder).	Rs.2,53,708/-	Rs.5,000/-	Rs. 350/-	Class "D"	Three Months
20	Construction of concrete road Ahju to Kholi km. 0/00 to 2/500 under MGNREGA (SH:- Supply and stacking of Crushed stone aggregate 20mm, Course sand and Boulder).	Rs.2,40,640/-	Rs.4,800/-	Rs. 350/-	Class "D"	Three Months
21	Construction of Concrete road Khopu to Nainidhar km. 0/00 to 3/000 under MGNREGA (SH:- Supply and Stacking of crushed stone aggregate 20mm, Course sand and Boulder).	Rs.2,27,225/-	Rs.4,500/-	Rs. 350/-	Class "D"	Three Months
22	Construction of concrete road Ahju Basahi to Kholi km. 0/0 to 1/000 under MGNREGA (SH:- Supply and Stacking of crushed stone aggregate 20mm, Course sand and Boulder).	Rs.2,40,640/-	Rs.4,800/-	Rs. 350/-	Class "D"	Three Months
23	Construction of concrete link road to Baggi km. 0/00 to 1/00 under MGNREGA (SH:- Supply and Stacking of crushed stone aggregate 20mm, Course sand and Boulder).	Rs.2,40,640/-	Rs.4,800/-	Rs. 350/-	Class "D"	Three Months
24	Construction of concrete road Thalehad road km. 0/0 to 1/000 under MGNREGA (SH:- Supply and Stacking of crushed stone aggregate 20mm, Course sand and Boulder).	Rs.2,27,225/-	Rs.4,500/-	Rs. 350/-	Class "D"	Three Months
25	Construction of Chanjra Tharu link rd Thaaru km. 0/00 to 4/000 under MGNREGA (SH:- Supply and Stacking of crushed stone aggregate 20mm, Course sand and Boulder).	Rs.2,27,225/-	Rs.4,500/-	Rs. 350/-	Class "D"	Three Months
26	M/O road Bhagehar to Lahad km. 0/00 to 3/000 under MGNREGA (SH:- Supply and Stacking of crushed stone aggregate 20mm, Course sand and Boulder).	Rs.2,27,225/-	Rs.4,500/-	Rs. 350/-	Class "D"	Three Months
27.	Construction of concrete road with drain Suja to Sandrahal km. 0/0 to 1/500 under MGNREGA (SH:- Supply and Stacking of crushed stone aggregate 20mm, Course sand and Boulder).	Rs.2,27,225/-	Rs.4,500/-	Rs. 350/-	Class "D"	Three Months
28.	Construction of concrete road Khalehi to Chount road km. 0/0 to 1/000 under MGNREGA (SH:- Supply and Stacking of crushed stone aggregate 20mm, Course sand and Boulder).	Rs.2,27,225/-	Rs.4,500/-	Rs. 350/-	Class "D"	Three Months
29.	Construction of residential accommodation for Junior Engineer/ Work Inspector for Chauntra Section at Bajgar store (SH:- Supplying and stacking of crushed/ broken stone agg. 20mm and sand)	Rs.98,750/-	Rs.2,000/-	Rs. 350/-	Class "D"	Two Months
30	Restoration of rain damages on Langha School to Nichla Mandhota road km. 0/00 to 1/500 (SH:- Construction of Retaining Wall at km. 0/680 to 0/695).	Rs. 2,67,136/-	Rs.5,300/-	Rs. 350/-	Class "D"	Three Months
31	A/R & M/O Badoun Pipil road km. 0/00 to 12/600 (SH:- Construction of Breast wall at km. 3/285).	Rs. 1,93,108/-	Rs.3,900/-	Rs. 350/-	Class "D"	Three Months
32	Restoration of rain damages on Bella to Samshan Ghat Kurahal km. 0/0 to 2/00 (Construction of 900mm dia Hume Pipe at km. 0/560)	Rs. 2,44,210/-	Rs. 4,900/-	Rs. 350/-	Class "D"	Three Months
33	Construction of Multipurpose Sports Stadium at Chauntra Distt. Mandi (H.P.0 (SH:- C/O R/Wall Chauntra side at RD. 0/015 to 0/030).	Rs.4,33,670/-	Rs.8,700/-	Rs. 350/-	Class "D"	Three Months
34	Construction & M/T of link road village Patku to Changrehar upto Galu School km. 0/00 to 2/500 (SH:- Formation cutting in km. 0/540 to 1/030).	Rs. 4,02,411/-	Rs. 8,000/-	Rs. 350/-	Class "D"	Three Months
35	Restoration of rain damages on Tikkar Harizan Bati via Nichla Andralu Basher (SH:- Construction of Breast Wall at km. 1/345 to 1/360).	Rs. 2,54,665/-	Rs. 5,100/-	Rs. 350/-	Class "D"	Three Months
36	Construction o link road to Village Lakhnot km. 0/0 to 1/300 (SH:- Construction of retaining wall at km. 1/110 to 1/125).	Rs. 2,66,487/-	Rs. 5,300/-	Rs. 350/-	Class "D"	Three Months
37	Construction of Veterinary Dispensary at Balh Chalharg in Tehsil Joginder Nagar District Mandi (H.P.) (SH:- C/O Retaining wall for site development at RD. 0/00 to 0/015).	Rs. 2,57,523/-	Rs. 5,200/-	Rs. 350/-	Class "D"	Three Months
38	Restoration of rain damages on Badoun Pipil road km. 0/00 to 12/500 (SH:- Construction of Retaining wall at km. 4/410 to 4/422).	Rs. 3,62,241/-	Rs. 7,200/-	Rs. 350/-	Class "D"	Three Months
39	Restoration of rain damages on Drobari Salang road km. 0/00 to 9/00 (SH:- Construction o Retaining wall at km. 1/755 to 1/765).	Rs. 1,21,218/-	Rs. 2,400/-	Rs. 350/-	Class "D"	Three Months
40	Restoration of damages due to laying o OFC on Baijnath Lad Bharol Kandapattan road km. 0/00 to 46/00 (SH:- Construction of U-Shape drain In km. 30/665 to 30/802).	Rs. 1,66,508/-	Rs. 3,300/-	Rs. 350/-	Class "D"	Three Months
41	Restoration of Rain Damages on Machhyal Bhararu Bihun road km. 0/00 to 12/00 (SH:- Construction of Retaining wall at km. 6/813 to 6/820).	Rs. 2,68,365/-	Rs. 5,400/-	Rs. 350/-	Class "D"	Three Months
42	Restoration of rain damages on link road to Village Banogi km. 0/00 to 1/500 (SH:- Construction of Breast wall for protection of Existing house at km. 0/915 to 0/930).	Rs. 1,90,416/-	Rs. 3,800/-	Rs. 350/-	Class "D"	Three Months

43	Restoration of Rain Damages on Kamal Galu to Pantehar road km. 0/00 to 2/00 (SH:- Construction of Missing /Damages 900mm CD double land hume pipe Culvert with wing wall at km. 0/300).	Rs. 3,76,775/-	Rs. 7,500/-	Rs. 350/-	Class "D"	Three Months
44	Restoration of damages Joginder Nagar Sarkaghat Ghumanwin road km. 0/00 to 34/300 (OFC) (SH:- Construction of Damages wing wall of 3.00 mtr. Existing Culvert at km. 9/590).	Rs. 4,57,547/-	Rs. 9,200/-	Rs. 350/-	Class "D"	Three Months
45	Restoration of rain damages on Bhala Ka Rihra Tikru road km. 0/00 to 2/600 (SH:- Construction of Breast wall at km. 0/710 to 0/725).	Rs. 1,86,138/-	Rs. 3,700/-	Rs. 350/-	Class "D"	Three Months
46	Improvement of Black Spot on Ahju Bashal road km. 0/00 to 33/00 (SH:- Improvement of Sharp Curve at km. 4/005 to 4/018).	Rs. 99,447/-	Rs. 2,000/-	Rs. 350/-	Class "D"	Two months
47	Construction of Ambulance road from Main road to link road Langha deposit under head SID VKV/2019/162 RS 0.50 lacs.(SH:- Hiring of excavator cum loader for removal of slips, dressing of berms, clearing of road side drains, debris and C/O road side katcha drains etc.).	Rs. 49,530/-	Rs. 1,000/-	Rs. 350/-	Class "D"	One month
48	Providing way side facility on link road from Khuddi Gharlan to Nagaun Bhamori Mata Temple km. 0/00 to 5/00 (SH:- Construction of Rain Shelter at Bhamori Mata km. 5/00).	Rs. 2,52,922/-	Rs. 5,100/-	Rs. 350/-	Class "D"	Three Months
49	Construction of link rod from Khuddi Gharlan to Nagaun Bhamori Mata Temple km. 0/00 to 5/00 (SH:- Widening of Narrow curves and construction of Unlined drain between km. 2/00 to 5/00).	Rs. 4,84,590/-	Rs. 9,700/-	Rs. 350/-	Class "D"	Three Months
50	Restoration of rain damages on Slun Bhararpatt road km., 0/00 to 2/00 (SH:- Construction of Breast wall at km. 0/230 to 0/250).	Rs. 3,77,426/-	Rs. 7,500/-	Rs. 350/-	Class "D"	Three Months
51	Restoration of rain damages on Baijnath Nahali Padhar road (MDR-56) km. 0/00 to 85/00 (SH:- Construction of Breast wall for protection of Existing house at km. 61/210 to 61/225).	Rs. 1,87,685/-	Rs. 3,800/-	Rs. 350/-	Class "D"	Three Months
52	Stock and storage on various roads under HP PWD Division Joginder Nagar (SH:- Supplying and stacking of warner Edge marker with 3M Reflective tape).	Rs. 4,98,000/-	Rs. 10,000/-	Rs. 350/-	Class "D"	Three Months
53	Restoration of rain damages on Maachhyal Bhal Jol Ropari road km. 0/00 to 9/00 under NDRF Deposit (SH:- Providing and Cement Concrete Pavement at km. 5/560 to 5/700).	Rs. 3,53,574/-	Rs. 7,100/-	Rs. 350/-	Class "D"	Three Months
54	Construction of link road from Ladruhin to Join Dhelu Chowki Chauntra road km. 0/00 to 2/300 (SH:- Providing and laying of Wearing G-II and Cement Concrete pavement in berms at km. 0/0 to 0/425).	Rs. 4,96,214/-	Rs. 9,900/-	Rs. 350/-	Class "D"	Three Months
55	Construction of link road to Village Sainthal Bhala Ka Rihra Tikru km. 0/00 to 9/00 (Drobari Salang road (SH:- Providing and laying of Wearing G-II & Cement Concrete pavement at km. 3/850 to 3/950).	Rs. 2,96,510/-	Rs. 5,900/-	Rs. 350/-	Class "D"	Three Months
56	Stock and storage on various roads under HP PWD Division Joginder Ngar (SH:- Supply and stacking of warner Edge marker with 3M Reflective tape).	Rs. 4,98,000/-	Rs. 10,000/-	Rs. 350/-	Class "D"	Three Months
57	A/R & M/O various road under Joginder Nagar Sub Division HP PWD, Joginder Nagar (Local Section (SH:- Supplying and stacking of hard fuel wood for patch work).	Rs. 99,750/-	Rs. 2,000/-	Rs. 350/-	Class "D"	Two Months

1. Certified that tender of above works are being called of emergent nature in exigency of public interest

Terms and conditions:-

- The contractor should produce a copy of enlistment / renewal letter at time of application.
- Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
- The contractor/Firm shall have his registration and GST No. the copy of same be attached with the application.
- The earnest money shall be deposited duly pledged in favour of Executive Engineer B&R Division HPPWD., Joginder Nagar & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
- No tender form will be issued to the contractor without producing the work done certificate from the Executive Engineer concerned.
- The contractor/firms are requested to insert the rate of each item in words as well as in figures failing which XEN reserves the right to accept/reject any tender without assigning any reason at any stage.
- The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar.
District Mandi (HP) for on behalf of
Governor of Himachal Pradesh
Ph. 01908-222033

No. PW-JND-B&R-EA-I/NIT/Press/2023-24-

Dated:-

33250-33340

29-01-2024

- Copy to the F.C. Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
- The Engineer-in-Chief, HPPWD, Shimla.
- The Chief Engineer (MZ), HPPWD, Mandi.
- The Superintending Engineer, Joginder Nagar Circle HPPWD, Joginder Nagar.
- All the Assistant Engineer working under this Division.
- All the Contractor working under this Division.
- Drawing Branch in this office.
- Notice Board.
- The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
B&R Division HP PWD.,
Joginder

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : Construction of Multipurpose Sports Stadium at Chauntra Distt Mandi (H.P.) (SH: Construction of Retaining wall Chauntra Side at RD 0/00 to 0/015)						Estimate Cost: 4,33,670.00 Earnest Money: 8,700.00 Time Limit : Three Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D. technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	20.40	Per cubic metre	452.95	Rupees Four Hundred Fifty Two And Paise Ninety Five Only	9,240.00
2	Providing and laying cement concrete 1:5:10 (one cement: five sand: ten graded crushed broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other preliminaries. The rate is inclusive all taxes levy by the government time to time excluding GST.	79.35	Per cubic metre	4,884.50	Rupees Four Thousand Eight Hundred Eighty Four And Paise Fifty Only	3,87,585.00

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	32.85	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time excluding GST.	31.00	Each			
	Total					


 Executive Engineer
 B & R Division HP.PWD.
 Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work : Construction of link road Shiv Mandir Panch Mukhi Mahadev to GSSS Langna km 0/00 to 1/450 (SH: Providing and Laying Kharanja Soling and CC Pavement at km 0/170 to 0/270)				Estimate Cost: 3,52,845.00 Earnest Money: 7,100.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and combor including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (one hundred millimeter) spread thickness (finished work including hauling /carriage of materials to satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads. lifts and other incidental complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST.	45.00	Per Cubic metre			
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints. over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	37.50	Per Cubic metre			
Total						


 Executive Engineer
 B & R Division HP, PWD,
 Joginder Nagar

Schedule of Quantity

Estimated Cost:- 253708 00
Earnest Money:- 5000 00
Time:- Three months

Name of work:- Construction of Bhajera Tila Jaral road Km. 0/0 to 2/0 Under MGNREGA
(SH: Supply and Stacking of Crushed stone aggregate 20 mm, Course Sand and Boulder)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Supplying and stacking of Crushed/broken stone aggregate 20mm (twenty millimeter) nominal size free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST including GST.	46.24			Per cubic metre	
2	Supply and stacking of course sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST including GST.	24.15			Per cubic metre	
3	Supply and stacking of boulder of specified size at the site of work of hard stone of approved quality as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST including GST.	62.68			Per cubic metre	
				Total:-		


Executive Engineer
 B&R Division, HPPWD,
 Joginder Nagar


Executive Engineer
 B&R Division, HPPWD
 Joginder Nagar (H.P.)

Schedule of Quantity

Estimated Cost:- 253708.00
 Earnest Money:- 5000.00
 Time:- Three months

Name of work:-Construction & MT on Nagan Jarai Bhajera road Km. 0/0 to 3/0 Under MGNREGA
 (SH: Supply and Stacking of Crushed stone aggregate 20 mm, Course Sand and Boulder)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Supplying and stacking of Crushed/broken stone aggregate 20mm (twenty millimeter) nominal size free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding including GST.	46.24			Per cubic metre	
2	Supply and stacking of course sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding including GST.	24.15			Per cubic metre	
3	Supply and stacking of boulder of specified size at the site of work of hard stone of approved quality as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding including GST.	62.68			Per cubic metre	
				Total:-		

Executive Engineer
 B&R Division, HPPWD,
 Joginder Nagar

Executive Engineer
 B&R Division, HPPWD
 Joginder Nagar (H.P.)

5

Schedule of Quantity

Estimated Cost:- 253708.00
Earnest Money:- 5000.00
Time:- Three months

Name of work:- Construction of Cement Concrete road Danehad Km. 0/0 to 0/500 Under MGNREGA
(SH) Supply and Stacking of Crushed stone aggregate 20 mm, Course Sand and Boulder

Sr. No.1	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Supplying and stacking of Crushed/broken stone aggregate 20mm (twenty millimeter) nominal size free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect The rate is inclusive all taxes levy by the government time to time including GST including	46.24			Per cubic metre	
2	Supply and stacking of course sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect The rate is inclusive all taxes levy by the government time to time including GST including	24.15			Per cubic metre	
3	Supply and stacking of boulder of specified size at the site of work of hard stone of approved quality as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect The rate is inclusive all taxes levy by the government time to time including GST including	62.68			Per cubic metre	
			Total:-			

Executive Engineer
B&R Division H.P PWD,
Joginder Nagar

Executive Engineer
B&R Division, HPPWD
Joginder Nagar (H.P.)

6

Schedule of Quantity

Estimated Cost:- 253708.00
Earnest Money:- 5000.00
Time:- Three months

Name of work:- Concrete and soling link road Maikhar Km 0/0 to 2/500 Under MGNREGA
(SH. Supply and Stacking of Crushed stone aggregate 20 mm, Course Sand and Boulder)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Supplying and stacking of Crushed/broken stone aggregate 20mm (twenty millimeter) nominal size free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect The rate is inclusive all taxes levy by the government time to time including GST	46.24			Per cubic metre	
2	Supply and stacking of course sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect The rate is inclusive all taxes levy by the government time to time including GST	24.15			Per cubic metre	
3	Supply and stacking of boulder of specified size at the site of work of hard stone of approved quality as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect The rate is inclusive all taxes levy by the government time to time including GST.	62.68			Per cubic metre	
			Total:-			

Executive Engineer
B&R Division, HP PWD,
Joginder Nagar

Executive Engineer
B&R Division, HP PWD
Joginder Nagar (H.P.)

7

Schedule of Quantity

Estimated Cost:- 253708 00
Earnest Money:- 5000 00
Time:- Three months

Name of work:- Concrete and soling link road Nalu Gaon Km. 0/0 to 1/700 Under MGNREGA
(SH: Supply and Stacking of Crushed stone aggregate 20 mm, Course Sand and Boulder)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Supplying and stacking of Crushed/broken stone aggregate 20mm (twenty millimeter) nominal size free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	46.24			Per cubic metre	
2	Supply and stacking of course sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	24.15			Per cubic metre	
3	Supply and stacking of boulder of specified size at the site of work of hard stone of approved quality as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	62.68			Per cubic metre	
			Total:-			

Executive Engineer
B&R Division, HPPWD,
Joginder Nagar.

Executive Engineer
B&R Division, HPPWD
Joginder Nagar (H.P.)

8

Schedule of Quantity

Estimated Cost:- 253708.00
Earnest Money:- 5000.00
Time:- Three months

Name of work:- Construction of Cement Concrete Jagmohan road Km. 0/0 to 1/500 Under MGNREGA
(SH- Supply and Stacking of Crushed stone aggregate 20 mm, Course Sand and Boulder)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Supplying and stacking of Crushed/broken stone aggregate 20mm (twenty millimeter) nominal size free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect The rate is inclusive all taxes levy by the government time to time including GST.	46.24			Per cubic metre	
2	Supply and stacking of course sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect The rate is inclusive all taxes levy by the government time to time including GST.	24.15			Per cubic metre	
3	Supply and stacking of boulder of specified size at the site of work of hard stone of approved quality as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect The rate is inclusive all taxes levy by the government time to time including GST.	62.68			Per cubic metre	
				Total:-		

Executive Engineer
B&R Division, HPPWD
Joginder Nagar

Executive Engineer
B&R Division, HPPWD
Joginder Nagar (H.P.)

9

Schedule of Quantity

Name of work:- Construction of Concrete link road Bellakm. 0'0 to 1'000 Under MGNREGA
(SH: Supply and Stacking of Crushed stone aggregate 20 mm, Course Sand and Boulder)

Estimated Cost:- 253708.00
Earnest Money:- 5000.00
Time:- Three months

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Supplying and stacking of Crushed broken stone aggregate 20mm (twenty millimeter) nominal size free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect The rate is inclusive all taxes levy by the government time to time including GST.	46.24			Per cubic metre	
2	Supply and stacking of course sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect The rate is inclusive all taxes levy by the government time to time including GST.	24.15			Per cubic metre	
3	Supply and stacking of boulder of specified size at the site of work of hard stone of approved quality as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect The rate is inclusive all taxes levy by the government time to time including GST.	62.68			Per cubic metre	
			Total:-			

Executive Engineer
B&R Division, HP PWD,
Joginder Nagar

21

Schedule of Quantity

Name of work:- Construction of Concrete link road Langha Km. 0/0 to 1/000 Under MGNREGA
(SH: Supply and Stacking of Crushed stone aggregate 20 mm, Course Sand and Boulder)

Estimated Cost:- 253708.00
Earnest Money:- 5000.00
Time:- Three months

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Supplying and stacking of Crushed/broken stone aggregate 20mm (twenty millimeter) nominal size free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	46.24			Per cubic metre	
2	Supply and stacking of course sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	24.15			Per cubic metre	
3	Supply and stacking of boulder of specified size at the site of work of hard stone of approved quality as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	62.68			Per cubic metre	
			Total:-			

Executive Engineer
B&R Division HP-PWD,
Joginder Nagar

11

Schedule of Quantity

Estimated Cost:- 253708.00
Earnest Money:- 5000.00
Time:- Three months

Name of work:- Construction of Concrete road Majhogla to Shanan upto Mala Langha Km. 0/0 to 1/000 Under MGNREGA
(SH, Supply and Stacking of Crushed stone aggregate 20 mm, Course Sand and Boulder)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Supplying and stacking of Crushed/broken stone aggregate 20mm (twenty millimeter) nominal size free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including cartage of material with in all leads and lifts complete in all respect The rate is inclusive all taxes levy by the government time to time including GST	46.24			Per cubic metre	
2	Supply and stacking of course sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including cartage of material with in all leads and lifts complete in all respect The rate is inclusive all taxes levy by the government time to time including GST.	24.15			Per cubic metre	
3	Supply and stacking of boulder of specified size at the site of work of hard stone of approved quality as per PWD specification and as desired by the Engineer-In-Charge including cartage of material with in all leads and lifts complete in all respect The rate is inclusive all taxes levy by the government time to time including GST.	62.68			Per cubic metre	
			Total:-			

Executive Engineer
B&R Division, HP PWD,
Joginder Nagar

12

Schedule of Quantity

Estimated Cost:- 253708.00
Earnest Money:- 5000.00
Time:- Three months

Name of work:- Construction of Concrete road to Jhamehar village Km. 0/0 to 1/000 Under MGNREGA
(SH: Supply and Stacking of Crushed stone aggregate 20 mm, Course Sand and Boulder)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Supplying and stacking of Crushed/broken stone aggregate 20mm (twenty millimeter) nominal size free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect The rate is inclusive all taxes levy by the government time to time including GST.	46.24			Per cubic metre	
2	Supply and stacking of course sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect The rate is inclusive all taxes levy by the government time to time including GST.	24.15			Per cubic metre	
3	Supply and stacking of boulder of specified size at the site of work of hard stone of approved quality as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect The rate is inclusive all taxes levy by the government time to time including GST.	62.68			Per cubic metre	
			Total:-			

Executive Engineer
B&R Division, HP PWD,
Joginder Nagar

13

Schedule of Quantity

Estimated Cost:- 253708.00
Earnest Money:- 5000.00
Time:- Three months

Name of work:- Construction of Concrete road to Mata Chaterbhuja Km. 0/0 to 1/500 Under MGNREGA
(SH- Supply and Stacking of Crushed stone aggregate 20 mm, Course Sand and Boulder)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Supplying and stacking of Crushed/broken stone aggregate 20mm (twenty millimeter) nominal size free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	46.24			Per cubic metre	
2	Supply and stacking of course sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	24.15			Per cubic metre	
3	Supply and stacking of boulder of specified size at the site of work of hard stone of approved quality as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	62.68			Per cubic metre	
				Total:-		

Executive Engineer
B&R Division, HP PWD
Joginder Nagar

Schedule of Quantity

Estimated Cost:- 253708.00
 Earnest Money:- 5000.00
 Time:- Three months

Name of work:- M/O link road to Mata Bhabhori Km. 0/0 to 4/000 Under MGNREGA
 (SH: Supply and Stacking of Crushed stone aggregate 20 mm, Course Sand and Boulder)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Supplying and stacking of Crushed/broken stone aggregate 20mm (twenty millimeter) nominal size free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including cartage of material with in all leads and lifts complete in all respect The rate is inclusive all taxes levy by the government time to time including GST.	46.24			Per cubic metre	
2	Supply and stacking of course sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including cartage of material with in all leads and lifts complete in all respect The rate is inclusive all taxes levy by the government time to time including GST.	24.15			Per cubic metre	
3	Supply and stacking of boulder of specified size at the site of work of hard stone of approved quality as per PWD specification and as desired by the Engineer-In-Charge including cartage of material with in all leads and lifts complete in all respect The rate is inclusive all taxes levy by the government time to time including GST.	62.68			Per cubic metre	
				Total:-		


 Executive Engineer
 B&R Division, HP, PWD,
 Joginder Nagar

15

Schedule of Quantity

Estimated Cost:- 253708.00
 Earnest Money:- 5000.00
 Time:- Three months

Name of work:- Construction of Cement Concrete road Panjialler to Sasnu Bharola Km 0/0 to 1/000 Under Undor MGNREGA
 (SH- Supply and Stacking of Crushed stone aggregate 20 mm, Course Sand and Boulder)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Supplying and stacking of Crushed/broken stone aggregate 20mm (twenty millimeter) nominal size free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	46.24			Per cubic metre	
2	Supply and stacking of course sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	24.15			Per cubic metre	
3	Supply and stacking of boulder of specified size at the site of work of hard stone of approved quality as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	62.68			Per cubic metre	
				Total:-		

Executive Engineer
 B&R Division, HP PWD,
 Joginder Nagar

16

Schedule of Quantity

Estimated Cost:- 253708.00
Earnest Money:- 5000.00
Time:- Three months

Name of work:- Construction of Cement Concrete road Bharola Sasnu to KuheraKm. 0/0 to 1/000 Under Order MGNREGA
(SH: Supply and Stacking of Crushed stone aggregate 20 mm, Course Sand and Boulder)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Supplying and stacking of Crushed/broken stone aggregate 20mm (twenty millimeter) nominal size free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect The rate is inclusive all taxes levy by the government time to time including GST.	46.24			Per cubic metre	
2	Supply and stacking of course sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect The rate is inclusive all taxes levy by the government time to time including GST.	24.15			Per cubic metre	
3	Supply and stacking of boulder of specified size at the site of work of hard stone of approved quality as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect The rate is inclusive all taxes levy by the government time to time including GST.	62.68			Per cubic metre	
				Total:-		

Executive Engineer
B&R Division, HP PWD,
Joginder Nagar

Schedule of Quantity

Name of work:- Construction of link road Drubbal to Sarmana Km. 0/0 to 2/500 under MGNREGA (SH: Supply and Stacking of Crushed stone aggregate 20 mm, Course Sand and Boulder)

Estimated Cost:- 253708.00
Earnest Money:- 5000.00
Time:- Three months

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Supplying and stacking of Crushed/broken stone aggregate 20mm (twenty millimeter) nominal size free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	46.24			Per cubic metre	
2	Supply and stacking of course sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	24.15			Per cubic metre	
3	Supply and stacking of boulder of specified size at the site of work of hard stone of approved quality as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	62.68			Per cubic metre	
				Total:-		


 Executive Engineer
 B&R Division, HP PWD,
 Joginder Nagar

16

Schedule of Quantity

Estimated Cost:- 253708.00
Earnest Money:- 5000.00
Time:- Three months
Name of work:- Construction of concrete link road Pipji Badhu Bharmara Km. 0/0 to 4/000 under MGNREGA (SH: Supply and Stacking of Crushed stone aggregate 20 mm, Course Sand and Boulder)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Supplying and stacking of Crushed/broken stone aggregate 20mm (twenty millimeter) nominal size free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	46.24			Per cubic metre	
2	Supply and stacking of course sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	24.15			Per cubic metre	
3	Supply and stacking of boulder of specified size at the site of work of hard stone of approved quality as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	62.68			Per cubic metre	
				Total:-		


 Executive Engineer
 B&R Division, HP PWD,
 Joginder Nagar

19

Schedule of Quantity

Estimated Cost:- 253708.00
Earnest Money:- 5000.00
Time:- Three months

Name of work:- Construction of Concrete road to Jhamehar Syohi Banon Km. 0/0 to 1/000 Under MGNREGA
(SH- Supply and Stacking of Crushed stone aggregate 20 mm, Course Sand and Boulder)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Supplying and stacking of Crushed/broken stone aggregate 20mm (twenty millimeter) nominal size free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including cartage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	46.24			Per cubic metre	
2	Supply and stacking of course sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including cartage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	24.15			Per cubic metre	
3	Supply and stacking of boulder of specified size at the site of work of hard stone of approved quality as per PWD specification and as desired by the Engineer-In-Charge including cartage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	62.68			Per cubic metre	
				Total:-		

Executive Engineer
B&R Division, HP PWD,
Joginder Nagar

(20)

Schedule of Quantity

Estimated Cost:- 240640.00
Earnest Money:- 4800.00
Time:- Three months

Name of work:-Construction of concrete road Ahju to Kholi Km. 0/00 to 2/500 Under MGNREGA.
(SH: Supply and Stacking of Crushed stone aggregate 20 mm, Course Sand and Boulder)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Supplying and stacking of Crushed/broken stone aggregate 20mm (twenty millimeter) nominal size free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	54.68			Per cubic metre	
2	Supply and stacking of course sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	28.55			Per cubic metre	
3	Supply and stacking of boulder of specified size at the site of work of hard stone of approved quality as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	47.55			Per cubic metre	
Total:-						


Executive Engineer
B&R Division, HP, PWD,
Joginder Nagar

21

Schedule of Quantity

Estimated Cost:- 227225.00
Earnest Money:- 4500.00
Time:- Three months

Name of work:-Construction of concrete road Khopu to Nainidhar km 0/00 to 3/000 Under MGNREGA
(SH: Supply and Stacking of Crushed stone aggregate 20 mm, Course Sand and Boulder)

Sr. No.	Description of Item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Supplying and stacking of Crushed/broken stone aggregate 20mm (twenty millimeter) nominal size free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST.	55.01			Per cubic metre	
2	Supply and stacking of course sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriages of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST.	28.72			Per cubic metre	
3	Supply and stacking of boulder of specified size at the site of work of hard stone of approved quality as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST.	21.30			Per cubic metre	
			Total:-			

Executive Engineer
B&R Division, HP, PWD,
Joginder Nagar

22

Schedule of Quantity

Estimated Cost:- 240640.00
 Earnest Money:- 48000.00
 Time:- Three months

Name of work:- Construction of concrete road Ahju Basahi to Kholi Km. 0/00 to 1/000 Under MGNREGA.
 (SH: Supply and Stacking of Crushed stone aggregate 20 mm, Course Sand and Boulder)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Supplying and stacking of Crushed/broken stone aggregate 20mm (twenty millimeter) nominal size free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	54.68			Per cubic metre	
2	Supply and stacking of course sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	28.55			Per cubic metre	
3	Supply and stacking of boulder of specified size at the site of work of approved quality as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	47.55			Per cubic metre	
				Total:-		


 Executive Engineer
 B&R Division HP PWD,
 Joginder Nagar

23

Schedule of Quantity

Estimated Cost:- 240640 00
 Earnest Money:- 4800 00
 Time:- Three months

Name of work:-Construction of concrete link road to Baggi Km. 0/00 to 1/00 Under MGNREGA
 (SH: Supply and Stacking of Crushed stone aggregate 20 mm, Course Sand and Boulder)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Supplying and stacking of Crushed/broken stone aggregate 20mm (twenty millimeter) nominal size free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect The rate is inclusive all taxes levy by the government time to time including GST.	54.68			Per cubic metre	
2	Supply and stacking of course sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect The rate is inclusive all taxes levy by the government time to time including GST.	28.55			Per cubic metre	
3	Supply and stacking of boulder of specified size at the site of work of hard stone of approved quality as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect The rate is inclusive all taxes levy by the government time to time including GST.	47.55			Per cubic metre	
				Total:-		


 Executive Engineer
 B&R Division, HP PWD,
 Joginder Nagar

Schedule of Quantity

Estimated Cost:- 227225.00
 Earnest Money:- 4500.00
 Time:- Three months

Name of work:-Construction of concrete road Thalehad road Km. 0/0 to 1/000 Under MGNREGA
 (SH: Supply and Stacking of Crushed stone aggregate 20 mm, Course Sand and Boulder)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Supplying and stacking of Crushed/broken stone aggregate 20mm (twenty millimeter) nominal size free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper sack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding <u>including</u> GST.	55.01			Per cubic metre	
2	Supply and stacking of course sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper sack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding <u>including</u> GST.	28.72			Per cubic metre	
3	Supply and stacking of boulder of specified size at the site of work of hard stone of approved quality as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding <u>including</u> GST.	21.30			Per cubic metre	
			Total:-			


 Executive Engineer
 B&R Division HP PWD,
 Joginder Nagar

25

Schedule of Quantity

Estimated Cost:- 227225.00
Earnest Money:- 4500.00
Time:- Three months

Name of work:- Construction of Chaniya Tharu link road Tharu Km. 0/0 to 4/000 Under MGNREGA
(SH: Supply and Stacking of Crushed stone aggregate 20 mm, Course Sand and Boulder)

Sr. No.	Description of Item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Supplying and stacking of Crushed/broken stone aggregate 20mm (twenty millimeter) nominal size free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST. including GST.	55.01			Per cubic metre	
2	Supply and stacking of course sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST. including GST.	28.72			Per cubic metre	
3	Supply and stacking of boulder of specified size at the site of work of hard stone of approved quality as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST. including GST.	21.30			Per cubic metre	
Total:-						

Executive Engineer
B&R Division, HP, PWD,
Joginder Nagar

26

Schedule of Quantity

Estimated Cost:- 227225.00
Earnest Money:- 4500.00
Time:- Three months

Name of work:- M/O road Bhagehar to Lahad Km. 0/0 to 3/000 Under MGNREGA
(SH: Supply and Stacking of Crushed stone aggregate 20 mm, Course Sand and Boulder)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Supplying and stacking of Crushed/broken stone aggregate 20mm (twenty millimeter) nominal size free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	55.01			Per cubic metre	
2	Supply and stacking of course sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	28.72			Per cubic metre	
3	Supply and stacking of boulder of specified size at the site of work of hard stone of approved quality as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	21.30			Per cubic metre	
			Total:-			

Executive Engineer
B&R Division HP PWD,
Joginder Nagar

Schedule of Quantity

Estimated Cost:- 227225.00
 Earnest Money:- 4500.00
 Time:- Three months

Name of work:-Construction of concrete road with drain Suja to Sandrahal Km. 0/0 to 1/500 Under MGNREGA
 (SH: Supply and Stacking of Crushed stone aggregate 20 mm, Course Sand and Boulder)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Supplying and stacking of Crushed/broken stone aggregate 20mm (twenty millimeter) nominal size free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST. <u>including</u>	55.01			Per cubic metre	
2	Supply and stacking of course sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST. <u>including</u>	28.72			Per cubic metre	
3	Supply and stacking of boulder of specified size at the site of work of hard stone of approved quality as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST. <u>including</u>	21.30			Per cubic metre	
			Total:-			


 Executive Engineer
 B&R Division, HP. PWD.
 Joginder Nagar

24

Schedule of Quantity

Estimated Cost:- 227225 00
Earnest Money:- 4500 00
Time:- Three months

Name of work:-Construction of concrete road Khalehi to Chount road Km. 0/0 to 3/000 Under MGNREGA
(SH: Supply and Stacking of Crushed stone aggregate 20 mm, Course Sand and Boulder)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Supplying and stacking of Crushed/broken stone aggregate 20mm (twenty millimeter) nominal size free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time <u>including GST.</u> <u>included</u>	55.01			Per cubic metre	
2	Supply and stacking of course sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time <u>including GST.</u> <u>included</u>	28.72			Per cubic metre	
3	Supply and stacking of boulder of specified size at the site of work of hard stone of approved quality as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time <u>including GST.</u> <u>included</u>	21.30			Per cubic metre	
				Total:-		

Executive Engineer
B&R Division, HP PWD,
Joginder Nagar

Schedule of Quantity

Estimated Cost:- 99750.00
 Earnest Money:- 2000.00
 Time:- Two months

Name of work:- Construction of residential accommodation for Junior Engineer/Work Inspector for Chauntra Section at Bajgar store.
Sub Head: Supplying and stacking of crushed/broken stone agg. 20mm and sand

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Supplying and stacking of Crushed/broken stone aggregate 20mm (twenty millimeter) nominal size free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	25.00			Per cubic metre	
2	Supply and stacking of course sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	20.00			Per cubic metre	
			Total:-			


 Executive Engineer
 B&R Division, HP PWD,
 Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work : Restoration of rain damages on Langha School to Nichla Mandliota road km 0/00 to 1/500 (SH: Construction of Retaining wall at km 0/680 to 0/695)				Estimate Cost: Earnest Money: Time Limit :		2,67,136.00 5,300.00 Three Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	17.70	Per cubic metre			
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals . The rate is inclusive all taxes levy by the government time to time excluding GST.	47.55	Per cubic metre			

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	17.55	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D. technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	13.00	Each			
	Total					


 Executive Engineer
 B & R Division HP.PWD.
 Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work : A/R & M/O Badoun Pipli Road km 0/00 to 12/600 (SH: Construction of Breast wall at km 3/270 to 3/285)					Estimate Cost: Earnest Money: Time Limit :			1,93,108.00 3,900.00 Three Months
Sr. No.	Description of work	No. or Qty.	Unit		Rate		AMOUNT	
					Figures	Words	Rs.	P
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost.The rate is inclusive all taxes levy by the government time to time excluding GST.	16.13	Per cubic metre					
2	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	11.25	Per cubic metre					

(3)

Description of work

Sr. No.	Description of work	Qty.	Unit	Rate		Total
				Figured	Specified	
3	Providing and laying cement concrete 1:5:10 (one cement, five sand and graded crushed broken stone aggregate 60 mm (sixty millimeters) nominal size) piers and curing complete including the cost of form work in Reinforcing walls 800mm. in or under water complete including, pumping or hauling out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights depths including cost of form work as per drawings and MCO technical specifications section 401. 9/10. 1/200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levied by the government time to time excluding GST.	37.46	Per cubic meter			
4	Providing weep holes in brick masonry/some masonry/flat or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slopes of 1 in 10. 20/50 upwards bearings faces complete as per drawing and MCO technical specification clauses 504, 709 & 1206 & and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and in the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levied by the government time to time excluding GST.	11.00	Each			
	Total					

Executive Engineer
 P. & S. Division (P&S) P&S
 Hyderabad, Andhra Pradesh

SCHEDULE OF QUANTITY

Name of Work : Restoration of Rain Damages on Bella to Shamsan Ghat Karahal km 0/00 to 2/00 (Sub Head:- Construction of 900mm dia Hume Pipe at km 0/560)				Estimate Cost: 2,44,210.00 Earnest Money: 4,900.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in-excitation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting-excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	44.18	Per cubic metre			
2	Providing concrete for plain reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete Grade M-10 complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	9.73	Per cubic metre			
3	Providing and laying concrete for plain reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	19.99	Per cubic metre			

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
4	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802.803.1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded stone aggregate 40mm (forty millimetre) nominal size) complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	3.35	Per cubic metre			
5	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification. Rubble stone laid in cement mortar 1:5 (one cement : five sand) complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	0.49	Per cubic metre			
6	Providing and laying 900mm (nine hundred millimetre) diameter reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	7.50	Per running metre			
7	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	6.72	Per cubic metre			
8	Providing weep hole in brick masonry stone masonry plain reinforced concrete abutment, wing wall, return wall with 100mm dia. (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614.709.1204.3.7 including carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	8.00	Each			
	Total					


 Executive Engineer
 B & R Division HP.PWD,
 Jalandhar Nagar

33

SCHEDULE OF QUANTITY

Name of Work : Construction of Multipurpose Sports Stadium at Chauntra Distt Mandi (H.P.) (SII: Construction of Retaining wall Chauntra Side at RD 0/00 to 0/015)					Estimate Cost: Earnest Money: Time Limit :			4,33,670.00 8,700.00 Three Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P		
				Figures	Words			
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	20.40	Per cubic metre					
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	79.35	Per cubic metre					

3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	32.85	Per cubic metre		
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D. technical specification clauses 614. 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	31.00	Each		
Total					


 Executive Engineer
 B & R Division HP.PWD.
 Joginder Nagal

SCHEDULE OF QUANTITY

Name of Work: Construction & M/T of link road village Patku to Changrehar upto Galu School km 0/00 to 2/500 (Sft: Formation cutting in km 0/540 to 1/030)				Estimate Cost: Earnest Money: Time Limit :		4,02,411.00 8,000.00 Three Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 124.09 cum @ 300 - per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	1908.88	Per cubic metre			
Total						


 Executive Engineer
 B & R Division HP, PWD,
 Jodinder Nagar

35

SCHEDULE OF QUANTITY

Name of Work : Restoration of Rain Damages on Tikkar Harizan Basti via Nichla Andralu Basher (SB: Construction of Breast wall at km 1/345 to 1/360)					Estimate Cost: 2,54,665.00 Earnest Money: 5,100.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil. setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	16.43	Per cubic metre				
2	Earth work in excavation for structures in all depths as per drawing and M.O.R.D technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	18.24	Per cubic metre				

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	47.55	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time excluding GST.	12.00	Each			
Total						


 Executive Engineer
 B & R Division HP,PWD.
 Joginder Nigam

(36)

Schedule of Quantity

Estimated Cost:- Rs. 266487.00
Earnest Money:- Rs. 5300.00
Time:- Three Months

Name of work:- Construction of link road to village Lakhnot Km. 0/0 to 1/300.
Sub Head:- Construction of retaining wall at Km. 1/110 to 1/125.

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	19.73			Per cubic metre	
2	Providing and laying cement concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) with 15% (fifteen percent) plum and curing complete including cost of form work for plain/reinforced concrete in retaining walls, bresat walls, the size of plum should be 150 to 300mm (one hundred fifty to three hundred millimetre) as per drawing and HPPWD technical specifications and curing complete within all leads, lifts carriage of material and other incidentals.	47.55			Per cubic metre	
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals.	10.80			Per cubic metre	
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals.	12.00			Each	
					Total	


Executive Engineer,
 B&R Division HPPWD,
 Joginder Nagar

37

SCHEDULE OF QUANTITY

Name of Work : Construction of Veterinary dispensary at Balh Chaharg in Tehsil Joginder Nagar District Mandi (H.P.) (SH: Construction of Retaining wall for site development at RD 0/00 to 0/015)					Estimate Cost: 2,57,523.00 Earnest Money: 5,200.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P	
				Figures	Words		
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	20.70	Per cubic metre				
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	47.55	Per cubic metre				

37

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment. 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614. 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	28.00	Each			
	Total					


Executive Engineer
B & R Division HP, PWD.

Engineer Nagar

(38)

SCHEDULE OF QUANTITY

Name of Work : Restoration of Rain Damages on Badoun Pipli Road km 0/00 to 12/500 (SH: Construction of Retaining wall at km 4/410 to 4/422)					Estimate Cost: 3,62,241.00 Earnest Money: 7,200.00 Time Limit : Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	19.68	Per cubic metre			
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights depths including cost of form work as per drawings and MORID technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	63.48	Per cubic metre			

38

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	22.20	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D. technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	48.00	Each			
	Total					

Executive Engineer
B & R Division HP.PWD,
Jalandhar Nagar

(39) **SCHEDULE OF QUANTITY**

Name of Work : Restoration of Rain Damages on Drobari Salang Road km 0/00 to 9/00 (SH: Construction of Retaining wall at km 1/755 to 1/765)					Estimate Cost: 1,21,218.00 Earnest Money: 2,400.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage. rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	12.00	Per cubic metre				
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls. in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals . The rate is inclusive all taxes levy by the government time to time excluding GST.	22.50	Per cubic metre				

(39)

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	3.60	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment. wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D. technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	8.00	Each			
	Total	0.00				


 Executive Engineer
 B & R Division HP, PWD,
 Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work : Restoration of Damages due to Laying of OFC on Baijnath Lad Bharol Kandapattan Road km 0/00 to 46/00 (Sub Head:- Construction of U-Shape Darin in km 30/665 to 30/802)				Estimate Cost: 1,66,508.00 Earnest Money: 3,300.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D. technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials, and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	53.43	Per cubic metre			
2	Providing concrete for plain reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete Grade M-10 complete within all leads, lifts carriage of material and other incidentals [The rate is inclusive all taxes levy by the government time to time excluding GST].	23.16	Per cubic metre			
	Total					


 Representative Engineer
 B & R Division HP.PWD.
 Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work : Restoration of Rain Damages on Machhwal Bhararu Bihun road km-0/00 to 12/00 (SH: Construction of Retaining wall at km 6/813 to 6/820)				Estimate Cost: 2,68,365.00 Earnest Money: 5,400.00 Time Limit : Three Months			
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	14.55	Per cubic metre				
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	47.55	Per cubic metre				

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 120.4.3.8.Circular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	18.45	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614. 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time excluding GST.	28.00	Each			
Total						



 Executive Engineer
 B & R Division HP, PWD.
 Jalandhar Nagar

42

SCHEDULE OF QUANTITY

Name of Work : Restoration of rain damages on link road to Village Banogi km 0/00 to 1/500 (SH: Construction of Breast wall for protection of Existing house at km 0/915 to 0/930)				Estimate Cost: Earnest Money: Time Limit :		1,90,416.00 3,800.00 Three Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil. setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	29.70	Per cubic metre			
2	Earth work in excavation for structures in all depths as per drawing and M.O.R.D technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	7.65	Per cubic metre			

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Providing and laying cement concrete 1:5:10 (one cement: five sand: ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	35.31	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D. technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	13.00	Each			
	Total					


 Executive Engineer
 B & R Division HP.PWD.
 Jyotiinder Singh

43 SCHEDULE OF QUANTITY

Name of Work : Restoration of Rain Damages on Kamal Galu to Pantchar road km 0/00 to 2/00 (SH:Construction of Missing/ Damages 900mm CD double lane hume pipe Culvert with wing wall at km 0/300)				Estimate Cost: Earnest Money: Time Limit :			3,76,775.00 7,500.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P		
				Figures	Words			
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	50.06	Per cubic metre					
2	Providing concrete for plain reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203, Plain cement concrete Grade M-10 complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time excluding GST.	29.13	Per cubic metre					

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	20.36	Per cubic metre			
4	Providing weep hole in brick masonry/ stone masonry plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204,3.7 including carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	10.00	Each			
5	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	5.94	Per cubic metre			
6	Providing and laying 900mm (nine hundred millimetre) diameter reinforced cement concrete pipe N/P2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	15.00	Per running metre			
	Total					


 Executive Engineer
 B & R Division HP, PW D.
 Jalandhar

1781

SCHEDULE OF QUANTITY

Name of Work : Restoration of Rain Damages Joginder Nagar Sarkaghat Ghumarwin Road km 0/00 to 34/300 (OFC)				Estimate Cost:		Three Months
(SI: Construction of Damages wing wall of 3.00 mtr. Existing Culvert at km 9/580 to 9/590)				Earnest Money:		
				Time Limit :		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.					
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights depths including cost of form work as per drawings and MCORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.					

44

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.					
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P. V. C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D. technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.					
Total						

Executive Engineer
B & R Division HP.PWD.
Joginder Nafar

SCHEDULE OF QUANTITY

Name of Work : Restoration of rain damages on Bhala Ka Rihra Tikru road km 0/00 to 2/600
(Sd/- Construction of Breast wall at km 0/710 to 0/725)

Estimate Cost: 1,86,138.00
Earnest Money: 3,700.00
Time Limit : Three Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and setting out useful materials and stacking the same in all leads and lifts in required width of the road and transportation of useful material for filling in road ways, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transport or including head load or animals transport or mechanical means along with its leveling fine dressing and hauling, carriage of machineries, materials, tools equipments and safety measures. Any loss to the public or private property during the course of excavation shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time & time excluding GST.	16.50	Per cubic metre			
2	Earth work in excavation for structures in all depths as per drawing and M.O.R.D technical specification section 300 & 1600 including setting out, construction, sloping and bracing, removal of slumps and other defective materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated surplus materials. All work of rock cutting is by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to trees and other pollution etc. to fully protect stability of all side rocks shall be excavated with chiseling and wedging out rocks where blasting is prohibited. All earth work in cutting excavation including faces excavation shall be carried out true to lines, grades, side slopes, width, earthen super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, railing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time & time excluding GST.	2.75	Per cubic metre			

Source: *U.S. Census Bureau*.

2. 1998

12

1

1

1

1

2

24

1999

100

1997

Percentage

46

SCHEDULE OF QUANTITY

Item of Work: Improvement of Balck Spot on Ahju Bashai road km 0/00 to 33/00

Sl: (Improvement of Sharp Curve at km 4/005 to 4/018)

Work: Improvement of Balak Spot on Ahju Bashai road km 0/00 to 33/00 Site: Improvement of Sharp Curve at km 4/005 to 4/018)				Estimate Cost: 99,447.00 Earnest Money: 2,000.00 Time Limit : Two Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals, transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 17.89 cum @ 360 per cum shall be effected from the contractor bill on pro-rata basis for the quantity of cutting in extra work executed. Any loss to the public private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be fully compensated by him at his own cost. The rate is inclusive all taxes levy by the government upto to time excluding GST	416.41	Per cubic metre			
Total						


 B & R Division HP PWID
 Jodhpur R.G.O.-2

(47)

Schedule of Quantity

Estimated Cost:- 49530.00
Earnest Money:- 1000.00
Time:- One month

Name of work:- Construction of Ambulance road from Main road to link road Langha deposit under head SID:VKV/2019/1962 RS.0.50 lacs.
Sub Head:-Hiring of excavator cum loader for removal of slips,dressing of berms, clearing of road side drains, debris and C/O road side katcha drains etc.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of Hydraulic Excavator having capacity of 1.00 (one point zero) cubic meter loader capacity for removal of slips,dressing of berms, clearing of road side drains, debris and C/O road side katcha drains etc. i/c cost of fuel oil lubricants and wages of operating staff, any repair/breakage during operation will be carried out bt the contractor/owner at his own risk,shifting machinery from one place to other place will be absolute responsibility of the contractor, only actual working hour will be accounted for the payment. Earth cutting in all kind of soils i/c loading in to tipper/truck within all leads and lifts to the entire satisfaction of Engineer-In-Charge. The payment will be made on the submission of the copy of log book duly signed/checked by the concerned Engineer-in-Charge.The rate is inclusive of all taxes including GST levy by the Govt. time to time.	39.00			Per working hours	
				Total:-		

Executive Engineer,
B&R Division HP.PWD,
Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work : Providing way side facility on link road from Khuddi Gharloan to Nagaun Bhamori Mata Temple km:0/00 to 5/00 (SH: Construction of Rain Shelter at Bhamori Mata Km 5/00)				Estimate Cost: Earnest Money: Time Limit :		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in foundation, trenches etcetera in earth work involving all classification of soil such as pick work, pick jumper work, blasting work, soft or hard rocks including chiseling wedging out of rocks where blasting work is prohibited or any other mixed variety of intermediate soil, dewatering and removal of slush if arisen during course of construction and lifts upto all heights including stacking the excavated soil not more than three meters clear from the edge of the excavation and then returning the stacked soil in 15 cm (fifteen centimeters) thick layers when required into plinths, sides of foundation etcetera consolidating each deposited layer by ramming and watering and then disposing of all surplus excavation earth within all leads, lifts by any mode of transportation and other incidental, as per the direction and entire satisfaction of Engineer-In-Charge. Any loss to the private and public property during course of construction shall be absolute responsibility of the contractor. The rate is inclusive all taxes levy by the government time to time excluding GST.	2.49	Per Cubic Meter			2,52,922.00
2	Supplying and filling of hard stone for under floor thick at site. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	0.98	Per Cubic Meter			5,100.00
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:4:8 (one Cement isto four coarse sand) isto eight graded stone aggregate 40 mm (fourty millimeter) nominal size). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	0.59	Per Cubic Meter			
4	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (one cement isto six coarse sand isto twelve graded stone aggregate 20 mm (twenty millimeter) nominal size) upto plinth level with : Cement mortar 1:6 (one cement isto six coarse sand). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	2.49	Per Cubic Meter			

No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
5	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (one cement into one point five sand into three graded stone aggregate 20 mm (twenty millimeter) nominal size). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.66	Per Cubic Meter			
6	Centering and shuttering including strutting, propping etc. and removal of form for all heights in Lintel, Beams, Plinth beams, Girders, Cantilever etc. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	5.54	Per Square Meter			
7	Kota stone slab flooring over 20mm (twenty millimeter) (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including runbbling and polishing ocomplete with base of cement mortar 1:4 (one cement isto four coarse sand). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	11.24	Per Square Meter			
8	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	875.60	Per Kilogramme			
9	Steel work welded in built up sections framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	420.80	Per Kilogramme			
10	Providing and fixing 0.60mm (zero point six zero millimetre) thick preprinted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 (twenty) microns over 5 (five) microns primer coating to back coat of polyester 5 (five) microns over 5 (five) microns primer coating including fixing with screws preprinted iron J or L hooks, bolts and nuts 6mm (six millimetre) diameter with preprinted bimpet and rubber washers complete with all accessories as required as per the direction of Engineer-In-Charge including carriage of material within all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST.	29.38	Per Square Meter			

48

No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
11	Providing and fixing ridges or hips 60cm (sixty centimetre) overall with 0.65mm (zero point six three millimetre) thick pre-painted steel sheet in roofing with hot dipped metallic zinc coated sheets with top coat of regular modified polyester organic coating of 20 (twenty) microns over 5 (five) microns primer coating plus back coat of polyester of 5 (five) microns over 5 (five) microns primer coating including fixing with screws pre-painted iron J or L hooks, bolts and nuts 6mm (six millimetre) diameter with pre-painted G.I. limpet and bitumen washers complete with all accessories as required as per the direction of Engineer-In-Charge including carriage of material within all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST.	24.00	Per Running Meter			
12	Providing and fixing MS BP sheet 1.66mm to 2mm (one point six six millimetre to two millimetre) thick in eaves board fascia soffits ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer-In-Charge (Base members of steel work shall be measured & paid separately) including carriage of materials within all leads, lifts and other incidental charges. The rate is inclusive all taxes levy by the government time to time excluding GST.	6.14	Each			
13	Painting on Steel work with two or more coat applied at 0.90 litre/ 10 sqm (zero point nine liter per ten square meter) over an under coat of primer applied at 0.80 litre/ 10 sqm (zero point eight liter per ten square meter) of approved brand and manufacture with Deluxe Multi Surface Paint to give an even shade complete including carriage of materials within all leads, lifts and other incidental charges. The rate is inclusive all taxes levy by the government time to time excluding GST.	9.35	Per Cubic metre			
	Total					


 Executive Engineer
 B & R Division HP.PWD.
 Jodhpur Nagar

SCHEDULE OF QUANTITY

Name of Work: Construction of link road from Khuddi Charloan to Nagaun Bhamari Mata Temple km 0/00 to 5/00 (SH: Widening of Narrow curves and Construction of Unlined drain between km 2/00 to 5/00)				Estimate Cost: Earnest Money: Time Limit :		4,84,509.00 9,700.00 Three Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 102.01 cum @ 300 - per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	2040.22	Per cubic metre			
2	Construction of unlined drain of average cross section area 40sqm (fourty square meter) in soil to specified lines grade levels and dimensions . Excavated materials to be used in embankment with a lift upto 3mm (three millimeter) and lead of 50m (fifty meter) (average lead 25m (twenty five meter)) as per technical specifications clause 307(Mechanical means) within all leads, lifts carriage of material and other incidentials .The rate is inclusive all taxes levy by the government time to time excluding GST.	3000.00	Per running metre			
	Total					


 Executive Engineer
 B & R Division HP.PWD,
 Jalandhar Nagar

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : Restoration of Rain Damages on Siun Bhararpatt road km 0/00 to 2/00
(SH: Construction of Breast wall at km 0/230 to 0/250)

Sr. No.	Description of work	No. or Qty.	Unit	Rate			Estimate Cost: Earnest Money: Time Limit :	3,77,426.00 7,500.00 Three Months
				Figures	Words	AMOUNT Rs. P		
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	36.00	Per cubic metre	162.65	Rupees One Hundred Sixty Two And Paise Sixty Five Only	5,855.00		
2	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	24.50	Per cubic metre	452.95	Rupees Four Hundred Fifty Two And Paise Ninety Five Only	11,097.00		

641

E No. 385.

50

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Providing and Laying cement concrete 1:5:10 (one cement: five sand: ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	72.61	Per cubic metre	4,873.20	Rupees Four Thousand Eight Hundred Seventy Three And Paise Twenty Only	3,53,843.00
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D. technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	24.00	Each	276.30	Rupees Two Hundred Seventy Six And Paise Thirty Only	6,631.00
	Total					3,77,426.00

Prof Schedule of Quantity checked & abt for 2,77,426/-
(3 Three Lacs (seventy seven thousand four hundred twenty six) only


Executive Engineer

B & R Division HP.PWD,
Jodhpur Nagar

SCHEDULE OF QUANTITY

Name of Work : Restoration of Rain Damages on Bajinath Nohali Padhar road (MDR-56) km 0/00 to 85/00 (SH: Construction of Breast wall for protection of Existing house at km 61/210 to 61/225)					Estimate Cost: 1,87,685.00 Earnest Money: 3,800.00 Time Limit : Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	9.15	Per cubic metre			
2	Earth work in excavation for structures in all depths as per drawing and M.O.R.D technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	9.00	Per cubic metre			

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Providing and laying cement concrete 1:5:10 (one cement: five sand: ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	35.31	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	13.00	Each			
Total						


 Executive Engineer
 B & R Division HP, PWD,
 Joginder Nagar

522

SCHEDULE OF QUANTITY

Name of Work: Stock and Storage on various roads under HPPWD Division, Joginder Nagar (SH: Supply and Stacking of Warner Edge marker with 3M Reflective tape)				Estimate Cost: Earnest Money: Time Limit :		4,98,000.00 10,000.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Supplying and installation of Warner / Edge marker (road way indicators, object marker) 80-100 cm (eighty to one hundred centimeter) high above ground level, painted black and white in 15 cm (fifteen centimeter) wide strips, fitted with 80x100 mm (eighty by hundred millimeter) rectangular or 75mm (seventy five millimeter) dia episodal circular shape of 3M or its equivalent reflectorised panels at the top, buried of pressed into the ground conforming to IRC-79-2019 and the drawing, as per direction by Engineer in charge including carriage of materials, with in all leads lifts as per direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	166.00	Each				
Total							


Executive Engineer
B & R Division HP, PWD.
Joginder Nagar

53

SCHEDULE OF QUANTITY

Name of Work : Restoration of rain damages on Machhyal Bhal Jol Ropari Road km 0/00 to 9/00 Under NDRF Deposit (SH: Providing and Cement Concrete Pavement at km 5/560 to 5/700)				Estimate Cost: Earnest Money: Time Limit :		3,53,574.00 7,100.00 Three Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints. over a prepared sub base. with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383. maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	53.29	Per Cubic metre			
Total						


Executive Engineer
B & R Division HP.PWD.
Joginder Nagar

54

SCHEDULE OF QUANTITY

Name of Work : Construction of link road from Ladruihin to join Dhelu Chowki Chaurtra road Km. 0/0 to 2/300 (S.H. : Providing and laying of Wearing G-II & Cement Concrete pavement at km 0/0 to 0/425)			Estimate Cost: Earnest Money: Time Limit :			4,96,214.00 9,900.00 Three Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	107.10	Per cubic metre			-
1	Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty-hundred kilo newton) static roller in stages to proper grade and camber applying and brooming, stone screening binding materials to fillup the interstices of course aggregate watering and compacting to the required density Grading-2 (two) as per technical specification clause 405 complete in all respect including haulage of material in all leads and lifts by all modes of transportation and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	40.16	Per cubic metre			-

SCHEDULE OF QUANTITY

Name of Work : Construction of Link road to Village Sainthal Bhala ka rihra Tikruk 0/00 to 9/00 (Drobari Salang road) (S.H. : Providing and laying of Wearing G-II & Cement Concrete pavement at km 3/850 to 3/950)				Estimate Cost: Earnest Money: Time Limit :		2,96,510.00 5,900.00 Three Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty-hundred kilo newton) static roller in stages to proper grade and camber applying and brooming, stone screening, binding materials to fillup the interstices of coarse aggregate watering and compacting to the required density Grading-2 (two) as per technical specification clause 405 complete in all respect including haulage of material in all leads and lifts by all modes of transportation and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	15.36	Per cubic metre			
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade coarse and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	38.75	Per Cubic metre			
Total						


 Executive Engineer
 B & R Division HP.PWD.
 Joginder Nagar

56

SCHEDULE OF QUANTITY

Name of Work: Stock and Storage on various roads under HPPWD Division Joginder Nagar (SH: Supply and Stacking of warner Edge marker with 3M Reflective tape)					Estimate Cost: 4,98,000.00 Earnest Money: 10,000.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Supplying and installation of warner Edge marker (road way indicators, object marker) 80-100 cm (eighty to one hundred centimeter) high above ground level, painted black and white in 15 cm (fifteen centimeter) wide strips, fitted with 80x100 mm (eighty by hundred millimeter) rectangular or 75mm (seventy five millimeter) dia episodal circular sharpe of 3M or its equivalent reflectorised panels at the top, buried of pressed into the ground conforming to IRC-79-2019 and the drawing, as per direction by Engineer in charge including carriage of materials, with in all leads lifts as per direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	166.00	Each				
Total							


B & R Division Engineer
B & R Division HP.PWD.
Joginder Nagar

15.7

SCHEDULE OF QUANTITY

Name of Work: A/R & M/O various road under Joginder Nagar Sub Division HP.PWD. Joginder Nagar (Local Section) (Sub Head:- Supplying and stacking of hard fuel wood for patch work)				Estimate Cost: Earnest Money: Time Limit : Two Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Supplying and stacking at site of work dry hard fuel wood, the fuel wood shall be dry and have a minimum girth of nine inch but not exceeding one feet six inch including entire carriage of materials within all lead lifts and proper stacking at site as per the direction of Engineer-in-Charge. The rate is inclusive all taxes including GST levy by the government time to time.	133.00	Per quintal			
Total						


 Executive Engineer
 B & R Division HP.PWD.
 Joginder Nagar