



Office of
Executive Engineer B&R Division HP.PWD. Joginder Nagar
Himachal Pradesh Public Works Department, Mandi-175015
Phone & Fax No. 01908-222033 E-Mail:- ee-jog-hp@nic.in

"NOTICE INVITING TENDER"

Sealed item rate tender for the following works are hereby invited by the Executive Engineer, B&R Division HP.PWD., Joginder Nagar District Mandi (H.P) from the eligible contractors of the appropriate class registered in HP.PWD. as per revised enlistment rules so as to reach in the office of under signed on 16-02-2024 up to 11:30 A.M. and will be opened on the same day at (12:00 noon) in the presence of intending contractors. The tender application will be received in this office on 14-02-2024 up to 10.00 A.M. to 12:30 P.M. and tender form can be had from this office on 15-02-2024 from 2.00 P.M. to 5.00 P.m. The earnest money as shown against each in the shape of F.D.R of any bank in Himachal Pradesh duly pledged in the name of the under signed must accompany with each tender. The tender form will be issued to contractor giving proof of enlistment, GST. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors in the office of the under signed on any working day during the office hours.

Sr. No.	Name of work	Amount put to tender/ Estimated cost	Earnest Money	Cost of tender form	Eligible Class of Contractor	Time
1	Restoration of damages due to laying of OFC on Joginder Nagar Sarkaghat Ghumarwin road km. 0/00 to 3/300 (SH:- Construction of Retaining wall at km. 31/150 to 31/165).	Rs.3,32,891 /-	Rs.6,700/-	Rs.350/-	Class "D"	Three months
2	Construction of Link road from Sanhali to Mangyal km. 0/00 to 1/00 under Deposit (SH:- Construction of Breast wall for protection of cow shed at km. 0/720 to 0/733).	Rs.3,52,393 /-	Rs.7,000/-	Rs.350/-	Class "D"4	Three Months
3	C/o 180.00 Mtr. Span Bridge over River Beas at Sandha Tehsil Lad Bharol Distt. Mandi (SH:- Providing and laying cement concrete pavement in Approach road Sandha Side at km. 0/420 to 0/525)	Rs.4,96,128 /-	Rs.9,900/-	Rs.350/-	Class "D"	Three months
4	Restoration of rain damages on Machhyal Bhararu Bihun road km. 0/00 to 12/00 (SH:- Construction of Breast wall for protection of Patwar Khana Batari Bihun at km. 9/935)	Rs.1,89,308 /-	Rs.3,800/-	Rs.350/-	Class "D"4	Three Months
5	Restoration of Rain Damages on Dhelu Bhatehar road km. 0/00 to 13/400 (SH:- Construction of Retaining wall at km. 10/520 to 10/530).	Rs.1,25,826 /-	Rs.2,500/-	Rs.350/-	Class "D"	Three Months
6	Special repair to State Level Revenue Training Institute at Joginder Nagar Distt. Mandi (H.P.0 (SH:- Providing Wood frame ceiling, Renewing Glass panes, wooden flooring & steel work at Guest house)	Rs.3,45,828 /-	Rs.6,900/-	Rs.350/-	Class "D"	Three Months
7	Periodical Maintenance of Various Roads under Annual maintenance Plan 2023-24 Lad Bharol Sub Division HP PWD, Lad Bharol (SH:- Providing and Applying Thermoplastic Strips, Side continuous line and Zebra Crossing of Chobin Bander road km. 0/00 to 2/00, Baijnath Lad Bharol Kandapattan road km. 13/00 to 14/00 and Baijnath Padhar road km. 6/520 to 7/00).	Rs.4,99,539 /-	Rs.10,000/-	Rs.350/-	Class "D"4	Three Months
8	C/o 180.00 Mtr. Span Bridge over River Beas at Sandha Tehsil lad Bharol Distt. Mandi (SH:- Providing and laying cement concrete pavement in Approach road Sandha Side at km. 0/105 to 0/135), 0/165 to 0/210 & 0/255 to 0/285).	Rs.4,96,128 /-	Rs.9,900/-	Rs.350/-	Class "D"	Three months
9	Construction of Link roa from sanali to Mangyal km. 0/00 to 1/ under Deposit (SH:- Construction of Breast wall for protection of cow shed at km. 0/720 to 0/733).	Rs.4,58,112 /-	Rs.9,200/-	Rs.350/-	Class "D"4	Three Months
10	Stock & storage under Sub Division HP PWD, Jogidner Nagar (SH:- Providing and supplying of Sokkiya or equivalent Total Station (Model IM 55) 5 second machine battery 12 hrs alongwith stand, Prism Pole, Big Prism, Mini Prism).	Rs.4,75,000 /-	Rs.9,500/-	Rs.350/-	Class "D"4	Three Months
11.	Restoration of damages due to laying of OFC on Joginder Nagar Sarkaghat Ghumarwin road km. 0/00 to 34/300 (SH:- Construction of Retaining wall at km. 16/015 to 16/024).	Rs.4,87,930 /-	Rs.9,800/-	Rs.350/-	Class "D"4	Three Months

12.	Restoration of damages Sandapattan Bharol Bagora Bagla Hard Ropari Kolang Triambli Bashai Drubbal Charanj Banwar Kun Ka Tar Mandokhar Bhargoan Kotli road (MDR-57) km. 0/00 to 80/00 (SH:- Construction of Breast wall at km. 40/330 to 40/350) OFC Deposit.	Rs.2,63,556/-	Rs.5,300/-	Rs.350/-	Class "D"4	Three Months
13	Construction and M/T of Link rod Village Chanekar under SCSP (SH:- Providing and laying of Wearing G-II & Cement Concrete pavement at km. 2/040 to 2/090).	Rs.1,68,358 /-	Rs.3,400/-	Rs.350/-	Class "D"4	Three Months

1. Certified that tender of above works are being called of emergent nature in exigency of public interest

Terms and conditions:-

1. The contractor should produce a copy of enlistment / renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/Firm shall have his registration and GST No. the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer B&R Division HPPWD., Joginder Nagar & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
5. No tender form will be issued to the contractor without producing the work done certificate from the Executive Engineer concerned.
6. The contractor/firms are requested to insert the rate of each item in words as well as in figures failing which XEN reserves the right to accept/reject any tender without assigning any reason at any stage.
7. The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar.

District Mandi (HP) for on behalf of
Governor of Himachal Pradesh
Ph. 01908-222033

No. PW-JND-B&R-EA-I/NIT/Press/2023-24-

30/59-30208

Dated:- 2-01-2024

1. Copy to the F.C. Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
2. The Engineer-in-Chief, HPPWD, Shimla.
3. The Chief Engineer (MZ), HPPWD, Mandi.
4. The Superintending Engineer, Joginder Nagar Circle HPPWD, Joginder Nagar.
5. All the Assistant Engineer working under this Division.
6. All the Contractor working under this Division.
7. Drawing Branch in this office.
8. Notice Board.
9. The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
B&R Division HP PWD.,
Joginder

SCHEDULE OF QUANTITY

Name of Work : Restoration of damages due to laying of OFC on Joginder Ngar Sarkaghat Ghumarwin Road km 0/00 to 34/300 (SH: Construction of Retaining wall at km 31/150 to 31/165)				Estimate Cost: 3,32,891.00 Earnest Money: 6,700.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Figures	Rate	AMOUNT Rs. P
					Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	8.93	Per cubic metre			
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	62.55	Per cubic metre			

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	7.88	Per cubic metre			
5	Providing, weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D. technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	25.00	Each			
	Total	0.00				


 Executive Engineer
 B & R Division HP.PWD,
 Jalandhar Nagar

SCHEDULE OF QUANTITY

Name of Work : Construction of Link road from Sanhali to Mangyal km 0/00 to 1/00 under Deposit (SH: Construction of Breast wall for protection of cow shed at km 0/720 to 0/733)				Estimate Cost: 3,52,393.00 Earnest Money: 7,000.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	11.80	Per cubic metre			
2	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost . The rate is inclusive all taxes levy by the government time to time excluding GST.	8.10	Per cubic metre			

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete Grade M-10 complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	32.00	Per cubic metre			
4	Providing and laying cement concrete 1:5:10 (one cement: five sand: ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water, dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	29.40	Per cubic metre			
5	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20 (H) towards drainage face complete as per drawing and M.O.R.D. technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	20.00	Each			
	Total					


 Executive Engineer
 B & R Division HP.PWD,
 Jalandhar Nagar

SCHEDULE OF QUANTITY

Name of Work : Construction of 180.00 Mtr. Span Bridge over River Beas at Sandha Tehsil Lad Bharol Distt. Mandi (H.P.) (S.H. : Providing and laying Cement Concrete pavement in Approach road Sandha Side at km 0/420 to 0/525)				Estimate Cost: 4,96,128.00 Earnest Money: 9,900.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade coarse and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five milimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	74.42	Per Cubic metre			
Total						


 Executive Engineer
 B & R Division HP, PWD.
 Joginder Nagar

(4)

SCHEDULE OF QUANTITY

Name of Work : Restoration of Rain Damages on Machhyal Bhararu Bihun Road km 0/00 to 12/00 (SH: Construction of Breast wall for protection of Patwar Khana Batari Bihun at km 9/920 to 9/935)				Estimate Cost: Earnest Money: Time Limit :		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	24.75	Per cubic metre			
2	Earth work in excavation for structures in all depths as per drawing and M.O.R.D technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	7.65	Per cubic metre			

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	35.25	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time excluding GST.	13.00	Each			
Total						


 Executive Engineer
 B & R Division HP.PWD,
 Joginder Nagar

1396

ENo. 795.

5

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : Restoration of Rain Damages on Dhelu Bhatehar Road km 0/00 to 13/400 (NH) Construction of Retaining wall at km 10/520 to 10/530)				Estimate Cost: 1,25,826.00 Earnest Money: 2,500.00 Time Limit : Three Months	
Sl. No.	Description of work	No. or Qty.	Unit	Rate	
				Figures	Words
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D. technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in retaining excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	8.40	Per cubic metre	452.95	Rupees Four Hundred Fifty Two And Paise Ninety Five Only
					AMOUNT Rs. P 3,805.00
2	Providing and laying cement concrete 1:5:10 (one cement: five sand: ten graded crushed broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	23.50	Per cubic metre	4,910.00	Rupees Four Thousand Nine Hundred Ten Only
					1,15,385.00

SCHEDULE OF QUANTITY

Name of Work : Restoration of Rain Damages on Dhelu Bhatehar Road km 0/00 to 13/400 (SH: Construction of Retaining wall at km 10/520 to 10/530)				Estimate Cost: 1,25,826.00 Earnest Money: 2,500.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	8.40	Per cubic metre			
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights depths including cost of form work as per drawings and MORID technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	23.50	Per cubic metre			

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	4.50	Per cubic metre			
4	Providing weep holes in brick masonry stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	10.00	Each			
	Total	2.00				


 Executive Engineer
 B & R Division HP, PWD,
 Jodhpur Nagar

SCHEDULE OF QUANTITY

Name of Work : Special Repair to State Level Revenue Training Institute at Joginder Nagar Distt. Mandi (HP) (S.H. : Providing Wood frame ceiling, Renewing Glass panes, wooden flooring & Steel Work at Guest house)				Estimate Cost: 3,45,828.00 Earnest Money: 6,900.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Dismantling roofing including ridges, hips, valleys and gutters etc., and stacking the material within 50 (fifty) metres lead of G.S. Sheet. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	7.38	Per square metre			
2	Dismantling steel work in single sections including dismembering and stacking within 50 metres lead in Channels, angles, tees and flats. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	428.10	Per Kilogramme			
3	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	734.40	Per Kilogramme			
4	Renewing glass panes, with putty and nails wherever necessary including racking out the old putty Float glass panes of nominal thickness 4 (four) mm (weight not less than 10kg/sqm) (ten kilogramme per square meter). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	3.38	Per square metre			
5	Providing Clip-in-prelaminated wooden flooring/cement concrete base with polythine sheet and thermo sheet cushion below complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	19.13	Per square metre			
6	Providing Clip-in-prelaminated wooden skirting/cement concrete base with polythine sheet and thermo sheet cushion below complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.75	Per square metre			

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
7	Providing and fixing pre-coated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (zero point five millimeter) (+ 0.05 %) total coated thickness with zinc coating 120 (one hundred twenty) grams per sqm as per IS: 277, in 240 (two hundred forty) mpa steel grade, 5-7 (five to seven) microns epoxy primer on both side of the sheet and polyester top coat 15-18 (fifteen to eighteen) microns. Sheet should have protective guard film of 25 (twenty five) microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 (twelve) metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) (five point five by fifty five millimeter) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	14.76	Per square metre			
8	Providing and fixing pre-coated galvanised steel sheet roofing accessories 0.50 (zero point five millimeter) mm (+0.05 %) total coated thickness, Zinc coating 120 (one hundred twenty) grams per sqm as per IS: 277, in 240 (two hundred forty) mpa steel grade, 5-7 (five to seven) microns epoxy primer on both side of the sheet and polyester top coat 15-18 (fifteen to eighteen) microns using self drilling/ self tapping screws complete Ridges plain (500 - 600mm) (five hundred to six hundred millimeter). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	28.80	Per running metre			
9	G.I Metal Ceiling Lay in plain Tegular edge Global white color tiles of size 595x595 mm, and 0.5 mm thick with 8 mm drop: made of G.I sheet having galvanizing of 100 gms/sqm (both sides inclusive) and electro statically polyester powder coated of thickness 60 microns (minimum), including factory painted after bending. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	56.28	Per square metre			

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
10	Dismantling doors, windows and clerestory windows (steel or wood) shutter Of area 3 (three) square metres and below including chowkats, architrave, holdfasts etc. complete and stacking within 50 (fifty) metres lead. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	16.00	Each			
11	Providing wood work Sal wood in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately).The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.31	Per Cubic metre			
	Total					


 Executive Engineer
 B & R Division HP.PWD.
 Jhaginder Nagar

SCHEDULE OF QUANTITY


Name of Work : Periodical Maintenance of Various Roads under Annual Maintenance Plan 2023-24 Lad Bharol B Division HPPWD Lad Bharol. (SH: Providing and Applying Thermoplastic Strips, Side continuous line and Cebra Crossing on Chaubin Banander Road km 0/00 to 2/00, Baijnath Lad Bharol Kadapattan road km 3/00 to 14/00 and Baijnath Padhar Road km 6/520 to 7/00)				Estimate Cost: Earnest Money: Time Limit :		4,99,539.00 10,000.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Road marking with hot applied thermoplastic compound with relectorising glass baord on bitumenous surface. Providing and laying of hot applied thermoplastic compound 2.5mm (two point five milimeter) thick including reflectorising glass beads @ 250 gms/sqm (two hundred fifty grammes per square meter) area thickness of 2.5mm (two point five milimeter) is exclusive of surface applied glass beads as per IRC :35. The finished surface to be uniform and free from streaks and holes as per PWD specification and as directed by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respec. The rate is inclusive all taxes levy by the government time to time excluding GST.	688.45	Per cubic metre				
		Total					


Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

(8)

SCHEDULE OF QUANTITY

Name of Work : Construction of 180.00 Mtr. Span Bridge over River Beas at Sandha Tehsil Lad Bharol Distt. Mandi (H.P.) (S.H. : Providing and laying Cement Concrete pavement in Approach road Sandha Side at km 0/105 to 0/135, 0/165 to 0/210 & 0/255 to 0/285)				Estimate Cost: Earnest Money: Time Limit :			AMOUNT Rs. P	
Sr. No.	Description of work	No. or Qty.	Unit	Rate				
				Figures	Words			
1	Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	74.42	Per Cubic metre					
Total								


 Executive Engineer
 B & R Division HP.PWD,
 Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work : Construction of Link road from Sanhali to Mangyal km 0/00 to 1/00 under Deposit (SH: Construction of Breast wall for protection of cow shed at km 0/720 to 0/733)					Estimate Cost: 4,58,112.00 Earnest Money: 9,200.00 Time Limit : Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time, excluding GST.	15.34	Per cubic metre			
2	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	10.53	Per cubic metre			

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete Grade M-10 complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	41.60	Per cubic metre			
4	Providing and laying cement concrete 1:5:10 (one cement: five sand: ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	38.22	Per cubic metre			
5	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D. technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	26.00	Each			
	Total					


 Executive Engineer
 B & R Division HP.PWD.
 Jodhpur

Schedule of Quantity

Estimated Cost:- Rs 475000.00
 Earnest Money:- Rs 9500.00
 Time:- One Month

Work:- Stock & Storage under Sub Division HPPWD, Joginder Nagar

Job Head:- Providing and Supplying of Sokkiya or equivalent Total Station (Model IM 55) 5 second machine battery 12 hrs. alongwith stand, Prism pole, Big Prism, Mini Prism

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Providing and Supplying of Sokkiya or equivalent Total Station (Model IM 55) 5 (five) second machine battery 12(twelve) hours alongwith stand, Prism pole, Big Prism, Mini Prism complete set including entire carriage of materials with in all leads lifts and as per entire satisfaction of Engineer-in-Charge including all incidentals. The rate shall be including Octroi, Royalty, Malkana, Toll tax, Sale tax, and all other taxes imposed by the Government time to time but excluding GST.	1.00			Each	


 Executive Engineer,
 B&R Division, HPPWD,
 Joginder Nagar

SCHEDULE OF QUANTITY


Name of Work : Restoration of damages due to laying of OFC on Joginder Nagar Sarkaghat Ghumawin road km 0/00 to 34/300 (SH: Construction of Retaining wall at km 16/015 to 16/024)				Estimate Cost: 4,87,930.00 Earnest Money: 9,800.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		
				Figures	Words	AMOUNT Rs. P
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	47.48	Per cubic metre			
2	Providing concrete for plain reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete Grade M-10 complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	10.00	Per cubic metre			

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Providing and laying cement concrete 1:5:10 (one cement: five sand: ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	75.60	Per cubic metre			
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	9.84	Per cubic metre			
5	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D. technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	18.00	Each			
	Total					


 B & R Division HP.PWD.
 Joginder Nagar

Name of Work : Restoration of dam damages Sandapattian Bharol Bagora Bagla Hard Ropari Kolang Triambli Bashai Drubbal Charonj Banwar Kun Ka Tar Mandokhar Bhargoon Kotli Road (MDR-57) km 0/00 to 80/00 (SH: Construction of Breast wall at km 40/330 to 40/350) @ F= 3-45%				Estimate Cost: 2,63,556.00 Earnest Money: 5,300.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, culvert, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	30.30	Per cubic metre			
2	Earth work in excavation for structures in all depths as per drawing and M.O.R.D technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, culvert super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	15.00	Per cubic metre			

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. p
				Figures	Words	
3	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	47.20	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time excluding GST.	32.00	Each			
Total						


 Executive Engineer
 B & R Division HP.PWD,
 Jalandhar Nagar

SCHEDULE OF QUANTITY

Name of Work : Construction and M/T of Link road Village Chanehar Under SCSP (S.H. : Providing and laying of Wearing G-II & Cement Concrete pavement at km 2/040 to 2/090)				Estimate Cost: 1,68,358.00 Earnest Money: 3,400.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty-hundred kilo newton) static roller in stages to proper grade and camber applying and brooming, stone screening/ binding materials to fillup the interstices of course aggregate watering and compacting to the required density Grading-2 (two) as per technical specification clause 405 complete in all respect including haulage of material in all leads and lifts by all modes of transportation and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	12.01	Per cubic metre			
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five milimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	20.01	Per Cubic metre			
Total						

Executive Engineer
B & R Division HP.PWD,
Joginder Nagar