



Office of
Executive Engineer B&R Division HP,PWD, Joginder Nagar
Himachal Pradesh Public Works Department, Mandi-175015
Phone & Fax No. 01908-222033 E-Mail:- ee-jog-hp@nic.in

"NOTICE INVITING TENDER"

Sealed item rate tender for the following works are hereby invited by the Executive Engineer, B&R Division HP,PWD., Joginder Nagar District Mandi (H.P.) from the eligible contractors of the appropriate class registered in HP,PWD. as per revised enlistment rules so as to reach in the office of under signed on **24-02-2024** up to 11:30 A.M. and will be opened on the same day at (12:00 noon) in the presence of intending contractors. The tender application will be received in this office on **22-02-2024** up to 10.00 A.M. to 12:30 P.M. and tender form can be had from this office on **23-02-2024** from 2.00 P.M. to 5.00 P.m. The earnest money as shown against each in the shape of F.D.R of any bank in Himachal Pradesh duly pledged in the name of the under signed must accompany with each tender. The tender form will be issued to contractor giving proof of enlistment, GST. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors in the office of the under signed on any working day during the office hours.

Sr. No.	Name of work	Amount put to tender Estimated cost	Earnest Money	Cost of tender form	Eligible Class of Contractor	Time
1	Construction & M/T of Chanehar Bhuas Banardi Banah Bahu Badhu Bhamera road including 1 No. Bridge (60.00 mtr.) over Rana Khad at Balhi at RD. 3/930 (SH:- Preparation of Hydraulic Data of bridges).	Rs. 3,95,500/-	Rs.7,900/-	Rs. 350/-	Class "D"	Three Months
2	Construction of Bridge (75.00 mtr.) Over Rana Khad at Bhamera at km. 0/490 (SH:- Preparation of Hydraulic Data of bridges).	Rs. 3,95,500/-	Rs.7,900/-	Rs. 350/-	Class "D"	Three months
3	Construction of Multipurpose Sports stadium at Chaunta in Tehsil Joginder Nagar District (H.P.) (SH:- Geotechnical investigation for Safe Bearing Capacity).	Rs. 4,50,900/-	Rs.9,000/-	Rs. 350/-	Class "D"	One Month
4	Construction including Metalling and Tarring of Banah-Chhamb-Kuthera-Badoo road including 1 No. Bridge (75.00 mtr.) over Neri Khad at Chambi(SH:- Preparation of Hydraulic Data of Bridges).	Rs. 3,95,500/-	Rs.7,900/-	Rs. 350/-	Class "D"	Three Months
5	Construction of link road from Dughit to Bajror km.1/00 to 3/50 (SH:- Preparation of Digital Plan with including Online Submission and Digital Compensatory Afforestation maps under HP PWD Division Joginder Nagar).	Rs. 4,22,000/-	Rs.8,400/-	Rs. 350/-	Class "D"	One year
6	Construction of Link road from Tansal to Bag (Portion km. 1/00 to 4/500) (SH:- Preparation of Digital plan with including Online Submission, and Digital Compensatory Afforestation maps under HP PWD Division Joginder Nagar).	Rs. 4,22,000/-	Rs.8,400/-	Rs. 350/-	Class "D"	One year
7	Construction of link road from Kadhar to Badan km. 0/00 to 5/00 (SH:- Preparation of Forest Diversion case with including online submission) HP PWD Division Joginder Nagar).	Rs. 4,22,800/-	Rs.8,500/-	Rs. 350/-	Class "D"	One year
8	Construction of link rod from Kadhar to Badan km. 0/00 to 5/00 (SH:- (SH:- Preparation of Digital Plan with including Online Submission, and Digital Compensatory afforestation Maps under HP PWD Division Joginder Nagar).	Rs. 4,22,800/-	Rs.8,400/-	Rs. 350/-	Class "D"	One year
9	Restoration of Damages Joginder Nagar Sarkashgat Ghumanwin road km. 0/00 to 34/00 (DPC) (SH:- Construction of Damages wing wall of 3.00 mtr. Existing culvert at km. 9/580 to 9/590).	Rs. 4,57,647/-	Rs.9,200/-	Rs. 350/-	Class "D"	Three Month

1. Certified that tender of above works are being called of emergent nature in exigency of public interest.

Terms and conditions:-

- The contractor should produce a copy of enlistment / renewal letter at time of application.
- Executive Engineer reserves the right to reject/accept any or all the tenders without assigning any reasons.
- The contractor/firm shall have his registration and GST No. the copy of same be attached with the application.
- The earnest money shall be deposited duly pledged in favour of Executive Engineer B&R Division HPPWD., Joginder Nagar & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
- No tender form will be issued to the contractor without producing the work done certificate from the Executive Engineer concerned.
- The contractor/firms are requested to insert the rate of each item in words as well as in figures failing which XEN reserves the right to accept/reject any tender without assigning any reason at any stage.
- The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar,
District Mandi (HP) for on behalf of
Governor of Himachal Pradesh
Ph. 01908-222033

No. PW-JND-B&R-EA/INIT/Press/2023-24

Dated:-

- Copy to the F.C. Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
- The Engineer-in-Chief, HPPWD, Shimla.
- The Chief Engineer (MZ), HPPWD, Mandi.
- The Superintending Engineer, Joginder Nagar Circle HPPWD, Joginder Nagar.
- All the Assistant Engineer working under this Division.
- All the Contractor working under this Division.
- Drawing Branch in this office.
- Notice Board.
- The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar

Schedule of Quantity

Name of work:- Construction & M/T of Chanehar Bhiun Banerdi Banah Balhi Badhu Bhamera road including 1 No. Bridge (60.00 mtr.) over Rana Khad at Balhi at RD 3/900. (SH: Preparation of Hydraulic Data of bridges)

Estimated Cost:- 395500.00

Earnest Money:- 7900.00

Time:- Three months

Sr. No.	Description of item	Qty.	Rate	In words	Unit	Amount
1	Preparation of Hydraulic data such as contour site plan, L-section of nallah and approaches, Cross-section 7 (seven) numbers upto 500 metre up stream and 500 metre down stream, Index plan, catchment area as per survey sheet, proforma of hydraulic data duly filled properly and necessary discharge calculation sheet as required by the Engineer-in-Charge. The Hydraulic data in triplicate copy get approved from the Circle office as well as Chief office with relevant drawings and to attend all observations raised by design office till the approval of GAD which is evolved at circle/ zonal office and soft copy in the form of Compact Disc (C.D.) of above mentioned Hydraulic data including all formats and other incidental charges complete in all respect. The rate is included all taxes levy by the Govt. time to time excluding GST.	1.00			Per Job	
2	Geotechnical Investigation in manuscript form and submission of the same to higher office for approval. If any correction/ amendment has desired by the head office the same may be corrected as desired and directed by the Engineer - In -charge complete in all respect. After approval the same should be submitted in 3 copies as per conditions of TOR. (Borehole 2 nos. depth upto 15 mtr. each) The rate is inclusive all taxes levy by the government time to time excluding GST.	30.00			Per Running meter	
	Total					

 Executive Engineer,
B & R Division

HP.PWD, Joginder Nagar

Schedule of Quantity

Name of work:- Construction of Bridge (75.00 mtr.) over Rana Khad at Bhamera at KM 0/490. (SH: Preparation of Hydraulic Data of bridges)

Estimated Cost:- 395500.00

Earnest Money:- 7900.00

Time:- Three months

Sr. No.	Description of item	Qty.	Rate	In words	Unit	Amount
1	Preparation of Hydraulic data such as contour site plan, L-section of nallah and approaches, Cross-section 7 (seven) numbers upto 500 metre up stream and 500 metre down stream, Index plan, catchment area as per survey sheet, proforma of hydraulic data duly filled properly and necessary discharge calculation sheet as required by the Engineer-in-Charge. The Hydraulic data in triplicate copy get approved from the Circle office as well as Chief office with relevant drawings and to attend all observations raised by design office till the approval of GAD which is evolved at circle/ zonal office and soft copy in the form of Compact Disc (C.D.) of above mentioned Hydrayulic data including all formats and other incidental charges complete in all respect. The rate is included all taxes levy by the Govt. time to time excluding GST.	1.00			Per Job	
2	Geotechnical Investigation in manuscript form and submission of the same to higher office for approval. If any correction/ amendment has desired by the head office the same may be corrected as desired and directed by the Engineer - In -charge complete in all respect. After approval the same should be submitted in 3 copies as per conditions of TOR. (Borehole 2 nos. depth upto 15 mtr. each) The rate is inclusive all taxes levy by the government time to time excluding GST.	30.00			Per Running meter	
	Total					

 Executive Engineer,

B & R Division

HP.PWD. Jodhpur Nagar

Draft Schedule of Quantity

Estimated Cost:- 450900.00
 Earnest Money:- 9000.00
 Time:- One Month

Name of work:- Construction of Multipurpose Sports stadium at Chauntra in Tehsil Jogindernagar District (H.P.)
 (SH: Geotechnical Investigation for Safe Bearing Capacity.)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Geotechnical Investigation in manuscript form and submission of the same to higher office for approval. If any correction/ amendment has desired by the head office the same may be corrected as desired and directed by the Engineer - In -charge complete in all respect. After approval the same should be submitted in 3 copies as per conditions of TOR. (Borehole 6 nos. depth upto 9 mtr. each) The rate is inclusive all taxes levy by the government time to time excluding GST	54.00			Per Running meter	
				Total:-		

Executive Engineer,
 B & R Division
 HP.PWD. Joginder-Nagar

Schedule of Quantity

Name of work:- Construction Including Metalling and Tarring of Banah-Chhamb-Kuthera-Badoo road including 1 No. Bridge (75.00 mtr.) over Neri Khad at Chhamb. **(SH: Preparation of Hydraulic Data of bridges)**

Estimated Cost:- 395500.00
Earnest Money:- 7900.00
Time:- Three months

Sr. No.	Description of item	Qty.	Rate	In words	Unit	Amount
1	Preparation of Hydraulic data such as contour site plan, L-section of nallah and approaches, Cross-section 7 (seven) numbers upto 500 metre up stream and 500 metre down stream, Index plan, catchment area as per survey sheet, proforma of hydraulic data duly filled properly and necessary discharge calculation sheet as required by the Engineer-in-Charge. The Hydraulic data in triplicate copy get approved from the Circle office as well as Chief office with relevant drawings and to attend all observations raised by design office till the approval of GAD which is evolved at circle/ zonal office and soft copy in the form of Compact Disc (C.D.) of above mentioned Hydraulic data including all formats and other incidental charges complete in all respect. The rate is included all taxes levy by the Govt. time to time excluding GST.	1.00			Per Job	
2	Geotechnical Investigation in manuscript form and submission of the same to higher office for approval. If any correction/ amendment has desired by the head office the same may be corrected as desired and directed by the Engineer - In -charge complete in all respect. After approval the same should be submitted in 3 copies as per conditions of TOR. (Borehole 2 nos. depth upto 15 mtr. each) The rate is inclusive all taxes levy by the government time to time excluding GST.	30.00			Per Running meter	
	Total					

Executive Engineer,
 B & R Division
 HP PWD Jodhpur Nagar

SCHEDULE OF QUANTITY

Estimated Cost:

Rs. 422000.00

Earnes Money:

Rs. 8400.00

Time:

One year

Name of work:- Construction of Link Road from Dughli To Bajror Km 1/00 To 3/00. (SH):- Preparation of Digital Plan with including Online Submission, and Digital Compensatory afforestation maps under HPPWD Division Joginder Nagar .

S.N o.	Description	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Preparation of plan Geo reference/Digital map and Digital Toposheet Map and Digital Compensatory afforestation maps Global Positioning System Coordinaters collection from site including preparation of KMLs files, with printing and scanning of all papers in PDF files as per requirement and as per direction of Engineer-in-charge. The rate is included all taxes excluding GST levy by the Govt. time to time.	1.00			Job	
					Total	


Executive Engineer,
B&R Division, HP.PWD.,
Joginder nagar.

SCHEDULE OF QUANTITY

Estimated Cost:
Earnes Money:
Time:

Rs. 422000.00
Rs. 8400.00
One year

Name of work:- Construction of Link road from Tansal to Bag (Portion Km 1/00 To 4/500.). (SH:- Preparation of Digital Plan with including Online Submission, and Digital Compensatory afforestation maps under HPPWD Division Joginder Nagar .

S.N o.	Description	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Preparation of plan Geo reference/Digital map and Digital Toposheet Map and Digital Compensatory afforestation maps (Global Positioning System Coordinaters collection from site including preparation of KMLs files, with printing and scanning of all papers in PDF files as per requirement and as per direction of Engineer-in-charge. The rate is included all taxes excluding GST levy by the Govt. time to time.	1.00			Job	
					Total	

Executive Engineer,
B&R Division, HP PWD.,
Joginder nagar.

SCHEDULE OF QUANTITY

Estimated Cost:
Earning Money:
Time:

Rs. 422800.00
Rs. 8500.00
< One year

Name of work:- Construction of Link Road From Kadhar To Badan. Km. 0/0 To 5/00 (SH. Preparation of Forest Diversion case with including Online Submission) HPPWD division Joginder Nagar.

S.N o.	Description	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Preparation of Forest Diversion case under Forest Conservation Act, 1980 including preparation of revenue papers of land falling on the road alignment and collection of other field data and all relevant documents/ Formats mandatory required would be attached with the case as per latest requirement of Ministry of Environment and forest conservation Govt. of India after getting the joint inspection/ site including computer typing in 6 copies, binding complete and getting it through from HP.PWD Sub-division Joginder Nagar, HP.PWD Division Joginder Nagar, Office of range Officer Joginder Nagar, Office of DFO Joginder Nagar and Conservator of Forest Department Mandi including attending all the observations, if raised at any time by any office and to prepare the same by neatly and accurately filling in all the formats/Documents with scanning of all papers in PDF files as per requirement and as per direction of Engineer-in-charge. The rate is included all taxes excluding GST levy by the Govt. time to time.	1.00			Job	
					Total	


Executive Engineer,
B&R Division, HP.PWD.,
Joginder nagar.

SCHEDULE OF QUANTITY


Estimated Cost:
Earnes Money:
Time:

Rs. 422000.00
Rs. 8400.00

One year

Name of work:- Construction of Link Road From Kadhar To Badan. Km. 0/0 To 5/00 .(SH):- Preparation of Digital Plan with including Online Submission, and Digital Compensatory afforestation maps under HPPWD Division Joginder Nagar .

S.N o.	Description	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Preparation of plan Geo reference/Digital map and Digital Toposheet Map and Digital Compensatory afforestation maps Global Positioning System Coordinaters collection from site including preparation of KMLs files, with printing and scanning of all papers in PDF files as per requirement and as per direction of Engineer-in-charge. The rate is included all taxes excluding GST levy by the Govt. time to time.	1.00			Job	
					Total	


Executive Engineer,
B&R Division, HP.PWD.,
Joginder nagar.

SCHEDULE OF QUANTITY

Name of Work : Restoration of Bridge Damages Joginder Nagar Sarkaghat Ghumarwin Road km 0.00 to 34/300 (PFC) (SH: Construction of Damages wing wall of 3.00 mtr. Existing Culvert at km 9/580 to 9/590)					Estimate Cost: 4,57,647.00 Earnest Money: 9,200.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P	
				Figures	Words		
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge. hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	33.75	Per cubic metre				
2	Providing and laying cement concrete 1:5:10 (one cement: five sand: ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water, dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	79.80	Per cubic metre				

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	21.60	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	46.00	Each			
Total						


 Executive Engineer
 B&R Division HP.PWD,
 Jodhpur