

REGISTERED

Office of the Executive Engineer, B&R Division, HP PWD Kalpa District Kinnaur (HP)

Web:- www.hppwd.gov.in E mail:- hp-kin@nic.in

Phone No:- 01786-226027 Fax:- 01786-226027.

No:- PW/KNR-E-Tender/2023-
To

8430-32

Dated:- 24-1-2024

The Executive Engineer (IT-Cell),
HP.PWD. Shimla-2.

Subject:-

Publication of Tender Notice (OFFLINE)


Enclosed please find herewith the Tender of works costing above 1.00 Lac as given in the Notice Inviting Tender for uploading on the departmental website as per notification vide Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW(B) 1/2020 dated 16-07-2021. The works mentioned in the tender notice are urgent in nature and public interest.

**Encl:- NIT, Schedule of Quantity.
& Certificate.**


Executive Engineer,
Kalpa Division,
HP.PWD. Kalpa.

Copy forwarded for information to:-

1. The Superintending Engineer, 11th Circle, HPPWD. Rampur Bushahr.
2. Drawing Branch in this office.


Executive Engineer,
Kalpa Division,
HP. PWD, Kalpa.

HP.P.W.D. TENDER NOTICE.(offline)

Sealed item rate offline tender on form PWD-6 & 8 are hereby invited on behalf of Governor of Himachal Pradesh by the Executive Engineer, Kalpa Division, HP, PWD. Kalpa for the following works from the approved and eligible contractors enlisted in HP.PWD; so as to reach in the office of the Executive Engineer Kalpa Division HP.PWD. Kalpa on or before **03-02-2024 up to 10.30 A.M.** and shall be opened on the same day at **11:00 AM** in presence of intending contractors or their authorized representatives. The tender form documents can be had from this office (Kalpa Division, HPPWD Kalpa) against cash payment (Non-refundable) on any working day during the office hours upto **4:00 P.M.** on **02-02-2024**. No application for issue of tender forms will be received on **02-02-2024** after **4:00 PM**. If the office happens to be closed on the above mentioned dates, the tenders will be sold/ opened on the next working day at the same time and venue. The Earnest Money in the shape of National Saving Certificate, F.D.R,s any Post office/Bank in H.P. duly pledged in the name of Executive Engineer, Kalpa Division, HP.PWD. Kalpa must accompany with each tenders. Conditional tenders and application (For purchase of tender forms) received without Earnest Money summarily be rejected. The offer of the tenders shall be kept open for 90 days. The Executive Engineer Reserves (Right to accept or to reject any) or all the tenders without assigning any reasons.

Sr. No	Name of work	Estimated cost	Earnest Money	Time allowed	Cost of form	Eligible class of contract or
1	Widening of Peo Township Sector road Km. 0/00 to 2/00 (SH:- C/O R/wall in R.R. Masonry at RD. 0/765 to 0/780)	4,99,671/-	10,000/-	Three Months	350/-	D Class.
2	Widening of Peo Township Sector road Km. 0/00 to 2/00 (SH:- C/O R/wall in R.R. Masonry at RD. 0/810 to 0/825)	4,99,671/-	10,000/-	Three Months	350/-	D Class.
3	Widening of Peo Township Sector road Km. 0/00 to 2/00 (SH:- C/O R/wall in R.R. Masonry at RD. 0/880 to 0/886.50)	4,99,495/-	10,000/-	Three Months	350/-	D Class.
4	R/R damages on Jangi to Lipa road Km. 0/00 to 10/130 (SH:- C/O R/wall in R.R. Masonry at RD. 6/300 to 6/314)	4,96,843/-	10,000/-	Three Months	350/-	D Class.
5	R/R damages on Jangi to Lipa road Km. 0/00 to 10/130 (SH:- C/O R/wall in PCC at RD. 2/300 to 2/313)	4,89,203/-	10,000/-	Three Months	350/-	D Class.


6	R/R damages on Jangi to Lippa road Km. 0/00 to 10/130 (SH:- C/O R/wall in G.I. wire crate at RD. 2/350 to 2/380)	4,73,955/-	10,000/-	Three Months	350/-	D Class.
---	--	------------	----------	--------------	-------	----------

Terms and conditions:-

Following documents should accompany the application for tenders:-

1. Copy of valid enlistment/renewal order.
2. Copy of GST Registration No.
3. Proof of Valid E.P.F accounts No allotted by the Provident Fund Commissioner Shimla and copy of PAN No.
4. Ambiguous/Telegraphic/conditional tenders or tenders by fax/E-Mail shall not be entertained/considered in any case.
5. The contractors should quote the rates of each items in words as well as figures in the Schedule of quantity.
6. The earnest money must also accompany with the application for the tender documents.
7. The tender shall be issued to those contractors who have not more than two works in hand.


Executive Engineer,
Kalpa Division,
HP. PWD. Kalpa.

Dated:- 
24/1/2024

No.PW/KNR-E-Tender/NIT/2023- 8433-60

Copy forwarded for information to:-

1. The Engineer-in-Chief, HPPWD. Shimla-2.
2. The Deputy Commissioner, Kinnaur at Reckong Peo.
3. The Sub Divisional officer(Civil) Kalpa at Reckong Peo.
4. The Superintending Engineer, 11th Circle, HPPWD. Rampur.
5. The Block development officer Kalpa at Reckong Peo.
6. The Chairman, Zila Parishad, Kinnaur District at Reckong Peo.
7. The Chairman, Panchayat Samiti Kalpa at Reckong Peo.
8. Drawing Branch in this office.
9. All the Contractors under this Division.
10. Notice Board.


Executive Engineer,
Kalpa Division,
HP. PWD. Kalpa.

CERTIFICATE

Certified that the Tender for works called vide this office letter No. PW/KNR-E-Tender/ 2023-8433-60 dated 24-01-2024 from Sr. No.

1 to 6 are of urgent nature and public interest.


Executive Engineer,
Kalpa Division,
HPPWD. Kalpa.



SCHEDULE OF QUANTITY

Estimated Cost 4,99,671/-
 Earnest Money :- 10,000 /-
 Time :- Three Months

Name of work:- Widening of Peo Township Sector Road Km 0/00 to 2/00
 (SH:- C/O R/Wall in RR masonry at RD 0/765 to 0/780)

	Description of items	Qty.	Rate	Unit	Amount
			In Fig.		
1	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with all lead and lift as per drawing and technical specification Clause 1603.1, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	51.000		Per Cubic meter	
2	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth, including carriage of material within all leads and lifts, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	31.337		Per Cubic meter	
3	Providing and laying cement concrete 1:6:12 (One Cement: Six Sand: Twelve graded stone aggregate 40mm (Forty millimeter nominal size) and curing complete excluding cost of centering and shuttering in: - Foundation and plinth, as directed by Engineer-in-charge, including carriage of materials with in all leads and lifts, including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	9.45		Per Cubic meter	
4	Random rubble masonry with hard stone in foundation and plinth, including leveling up with cement concrete 1:6:12 (one cement : six coarse sand : twelve graded stone aggregate 20 mm(twenty millimeter) nominal size) upto plinth level with Cement mortar 1:6 (one cement : six coarse sand), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	87.60		Per Cubic meter	
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm(one millimeter) dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	15.00		Each	

6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 Granular material, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	2.70			Per Cubic meter	
					Total:-	


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD; Kalpa.

SCHEDULE OF QUANTITY

Estimated Cost 4,99,671/-

Earnest Money :- 10,000 /-

Time :- Three Months

Name of work:- Restoration of rain damages on Peo Township Sector Road Km 0/00 to 2/00

(SH:- C/O R/Wall in RR masonry at RD 0/810 to 0/825)

	Description of items	Qty.	Rate	Unit	Amount
			In Fig.		
			In Words		
1	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with all lead and lift as per drawing and technical specification Clause 1603.1, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	51.00		Per Cubic meter	
2	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth, including carriage of material within all leads and lifts, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	31.337		Per Cubic meter	
3	Providing and laying cement concrete 1:6:12 (One Cement: Six Sand: Twelve graded stone aggregate 40mm (Forty millimeter nominal size) and curing complete excluding cost of centering and shuttering in: -Foundation and plinth, as directed by Engineer-in-Charge, including carriage of materials with in all leads and lifts, including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	9.45		Per Cubic meter	
4	Random rubble masonry with hard stone in foundation and plinth, including leveling up with cement concrete 1:6:12 (one cement : six coarse sand : twelve graded stone aggregate 20 mm(twenty millimeter) nominal size) upto plinth level with Cement mortar 1:6 (one cement : six coarse sand), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	87.60		Per Cubic meter	
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm(one millimeter) dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	15.00		Each	

6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 Granular material, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	2.70			Per Cubic meter	
						Total:-


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD; Kalpa.



SCHEDULE OF QUANTITY

3

Estimated Cost 4,99,495/-
Earnest Money :- 10,000 /-
Time :- Three Months

Name of work:- Widening of Peo Township Sector Road Km 0/00 to 2/00
(SH:- C/O R/Wall in RR masonry at RD 0/880 to 0/886.50)

	Description of items	Qty.	Rate	Unit	Amount
			In Fig. In Words		
1	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with all lead and lift as per drawing and technical specification Clause 1603.1, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	59.866		Per Cubic meter	
2	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth, including carriage of material within all leads and lifts, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	25.806		Per Cubic meter	
3	Providing and laying cement concrete 1:6:12 (One Cement: Six Sand: Twelve graded stone aggregate 40mm (Forty millimeter nominal size) and curing complete excluding cost of centering and shuttering in:-Foundation and plinth, as directed by Engineer-in-Charge, including carriage of materials with in all leads and lifts, including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	6.04		Per Cubic meter	
4	Random rubble masonry with hard stone in foundation and plinth, including leveling up with cement concrete 1:6:12 (one cement : six coarse sand : twelve graded stone aggregate 20 mm(twenty millimeter) nominal size) upto plinth level with Cement mortar 1:6 (one cement : six coarse sand), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	89.25		Per Cubic meter	
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm(one millimeter) dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	15.00		Each	

6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 Granular material, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	12.42			Per Cubic meter	
					Total:-	


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD; Kalpa

SCHEDULE OF QUANTITY

Estimated
Cost 4,96,843/-
Earnest Money :- 10,000 /-
Time :- Three Months

Name of work:- Restoration of rain damages on Jangti to Lippa Road Km 0/00 to 10/130
(SH:- C/O R/Wall in RR masonry at RD 6/300 to 6/314)

	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with all lead and lift as per drawing and technical specification Clause 1603.1, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	47.60			Per Cubic meter	
2	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth, including carriage of material within all leads and lifts, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	29.120			Per Cubic meter	
3	Providing and laying cement concrete 1:5:10 (One Cement: five Sand: ten graded stone aggregate 40mm (Forty millimeter nominal size) and curing complete excluding cost of centering and shuttering in:- Foundation and plinth, as directed by Engineer-in-Charge, including carriage of materials with in all leads and lifts, including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	8.82			Per Cubic meter	
4	Random rubble masonry with hard stone in foundation and plinth, including leveling up with cement concrete 1:6:12 (one cement : six coarse sand : twelve graded stone aggregate 20 mm(twenty millimeter) nominal size) upto plinth level with Cement mortar 1:6 (one cement : six coarse sand), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	81.76			Per Cubic meter	
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm(one millimeter) dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	25.00			Each	

6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 Granular material, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	12.31			Per Cubic meter	
						Total:-


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD; Kalpa.

SCHEDULE OF QUANTITY

5

Estimated Cost 4,89,203 /-
 Earnest Money :- 10,000 /-
 Time :- Three Months

Name of work:- Restoration of rain damages on Jangi to Lippa Road Km 0/00 to 10/130
 (SH:- C/O R/Wall in PCC at RD 2/300 to 2/313)

	Qty.	Description of items	Rate		Unit	Amount
			In Fig.	In Words		
1	44.20	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with all lead and lift as per drawing and technical specification Clause 1603.1, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.			Per Cubic meter	
2	27.040	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth, including carriage of material within all leads and lifts, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.			Per Cubic meter	
3	75.92	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803,1202 & 1203. P.C.C. grade M10 Nominal mix 1:3:6 (one cement: three sand: six graded stone aggregate/20 mm(twenty millimeter nominal size)), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.			Per Cubic meter	
4	25.00	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm(one millimeter) dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.			Each	

5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 Granular material, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	11.43			Per Cubic meter	
				Total:-		


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD; Kalpa.

