



Himachal Pradesh
Public Works Department

No.PW-BHNR-B&R/EA-I-Tender-NIT/2023-24-9033-38
To

Dated: - 15/01/2024


The Executive Engineer,
IT Cell, HP.PWD; Shimla – 171002.

Subject: - Publication of Notice Inviting Tender.

Sir,

I am enclosing herewith the “**Notice Inviting Tender**” along with **Schedule of Quantity** for favour of information and necessary action. The work attached in list is very urgent nature. It is requested that the same may kindly be got published.


Encl: - As above


Executive Engineer,
Karchham Division
HP.PWD Bhabanagar

Copy forwarded to the following for favour of information & necessary action: -

1. Chief Engineer (SZ), HP.PWD; Shimla – 171002.
2. Superintending Engineer, 11th Circle, HP.PWD; Rampur Bushahr.
3. All the Assistant Engineers, working under this Division.
4. Drawing Branch of this office
5. Notice Board of this office.

Encl: - 1 No.


Executive Engineer,
Karchham Division
HP.PWD Bhabanagar

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

***NOTICE INVITING TENDER**


Sealed Item rate tenders on PWD form No. 6&8 are invited by the **Executive Engineer, Karchham Division, HP.PWD; Bhabanagar** on behalf of the Governor H.P for the following works reach in the office of the Executive Engineer, Karchham Division, HP.PWD; Bhabanagar on **23.01.2023** up to **1:30 P.M** and will be opened on the same day at **3:00 P.M** in the presence of the intending Contractors or their authorized representatives. The tender form can be had from the office of the **Executive Engineer, Karchham Division, HP.PWD; Bhabanagar** against cash payment (Non Refundable) on the **same day** during office hours **11:00 A.M to 12:00 P.M**. The application for obtaining the tender forms will be received on the **same day** up to **11:00 A.M**. The earnest money in the shape of fresh FDR/NSC, duly pledged in favour of undersigned must be submitted with the application for issue of tender form. **The earnest money should be submitted separately for each work.** The copy of **valid enlistment** and renewal certificate shall be attached with application form. The ambiguous/telegraphic/conditional/fax/e-mail or by post tender will also not be entertained/considered in any case. The offer of the tender shall remain open 90 days from the date of opening of the tenders. The undersigned reserves the right to reject/cancel the tenders without assigning any reason: -

Sr. No.	Name of Work.	Estimated Cost (In Rs.).	Earnest Money.	Time limit.	Cost of form.	Eligibility of Contractor.
1.	R/R damages on various roads under Karchham Division. (SH: - C/o Wangtoo side abutment on alternate route to NH - 05 from Det Sungra to Wangtoo. Phase - I.	4,91,268/-	9900/-	Two months	Rs.350/-	Class - "D".
2.	R/R damages on various roads under Karchham Division. (SH: - C/o Wangtoo side abutment on alternate route to NH - 05 from Det Sungra to Wangtoo. Phase - II.	4,62,268/-	9300/-	Two months	Rs.350/-	Class - "D".
3.	R/R damages on various roads under Karchham Division. (SH: - C/o Wangtoo side abutment on alternate route to NH - 05 from Det Sungra to Wangtoo. Phase - III.	4,99,789/-	10000/-	Two months	Rs.350/-	Class - "D".
4.	R/R damages on various roads under Karchham Division. (SH: - C/o Bhaba side abutment on alternate route to NH - 05 from Det Sungra to Wangtoo. Phase - I.	3,21,648/-	6500/-	Two months	Rs.350/-	Class - "D".
5.	R/R damages on various roads under Karchham Division. (SH: - C/o Bhaba side abutment on alternate route to NH - 05 from Det Sungra to Wangtoo. Phase - II.	3,90,184/-	7900/-	Two months	Rs.350/-	Class - "D".
6.	R/R damages on various roads under Karchham Division. (SH: - C/o Bhaba side abutment on alternate route to NH - 05 from Det Sungra to Wangtoo. Phase - III.	4,55,957/-	9200/-	Two months	Rs.350/-	Class - "D".

GENERAL TERMS AND CONDITIONS: -

1. In case office happens to closed on any of the above mentioned dates, the tenders will be opened on the next working day at same time and venue.
2. The Contractor/firms are required to quote their rates clearly both in words as well as in figures, failing which tenders are likely to be rejected.
3. No person/persons shall be allowed to give the documents with regard to tender unless he/they hold/holds the power of attorney duly registered under law.
4. The tender of those Contractors who are registered under HP Central Sales Tax Act, 1969, GST and who have been cleared all the dues on account of tax will be entertained.
5. The competent authority on behalf of Governor of HP reserves the right to reject any or all the tenders received without assigning any reason.
6. Authorized Firms/Contractor approved by HPPWD Civil will participate in Specialized Job only.
7. Permanent Account Number (PAN).
8. EPF No. & GST No.
9. Exemption Letter for payment of earnest money from competent authority if any.

The Contractor enlisted in a particulars class shall be eligible to tender for his own class and one step below. The conditional tenders or the tenders without earnest money shall be rejected.


Executive Engineer,
Karchham Division,
HP.PWD; Bhabanagala

Draft Schedule of Quantity

Estimated Cost:- 491268.00
 Earnest Money:- 9900/-
 Time:- Two Months

Name of work:- R/R damages on verious roads under Karchham Division.

Sub Head:- C/O Wangtoo side abutment on crate wall on alternate route to NH-05 from Det Sungra to Wangtoo. Phase -I

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	117.99	128.15	Rupees one hundred twenty eight and paise fifteen only	Per cubic metre	15120.00
2	Supplying, fitting and placing TMT bar reinforcement in foundation complete as per drawings and technical specifications Clauses 1000 and 1202 and carriage of materials in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	3.08	64210.60	Rupees sixty four two hundred ten and paise sixty only	Per tonne.	197769.00
3	Proiding and laying concrete for plain/reinforced cement concrete 1:1.5:3 (One cement isto one point five sand isto three graded stone aggregate 25mm.(twenty five millimetre) nominal size) in open foundation and curing complete including cost of form work in retaining walls/breast walls, as per HPPWD specification clause 802, 803, 1202 & 1203 within all leads and lifts and as per the direction of Engineer-in-charge. M-25	41.31	4458.60	Rupees four thousand four hundred fifty eight and paise sixty only	Per cubic metre	184185.00
4	Providing weep holes in brick masonry/stone masonry/plain/ reinforced concrete abutment wing wall, return wall with 100mm.(One hundred millimetre) dia PVC pipe extneiding through the full with of the structures with slope of 1 (v) : 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,12.04,3.7 within all leads and lifts and as per direction of Engineer-in-charge.	12.00	253.70	Rupees two hundred fifty three and paise seven only	Each	3044.00
5	Providing and laying boulder apron laid in wire crates with 4 mm diametre G.I. wire confirming to IS:280 and IS-4826 in 100mmx 100mm (one hundred into one hundred millimetre) mesh (woven diagonally) including 10 % (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge.	62.50	1458.40	Rupees one thousand four hundred fifty eight and paise forty only	Per cubic metre	91150.00
					Total	491268.00

Draft schedule of quantity approved by 491268.00

Executive Engineer,
 Karchham Division,
 HPPWD at Bhaba Nagar.

Draft Schedule of Quantity

Job-2

Estimated Cost:-

462268.00

Earnest Money:-

9300/-

Time:-

Two Months

Name of work:- R/R damages on verrious roads under Karchham Division.

Sub Head:- C/O Wangtoo side abutment on alternate route to NH-05 from Det Sungra to Wangtoo. Phase -II

Sr. No.	Description of Item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Proiding and laying concrete for plain/reinforced cement concrete 1:1.5:3 (One cement isto one point five sand isto three graded stone aggregate 25mm.(twenty five millimetre) nominal size) in open foundation and curing complete including cost of form work in retaining walls/breast walls, as per HPPWD specification clause 802, 803, 1202 & 1203 within all leads and lifts and as per the direction of Engineer-in-charge. M-25	103.68	4458.60	Rupees four thousand four hundred fifty eight and paise sixty only	Per cubic metre	462268.00
					Total	462268.00

Draft schedule of quantity approved for 462268/-

Executive Engineer,
Karchham Division,
HPPWD at Bhaba Nagar.

Draft Schedule of Quantity

Job- 3

Estimated Cost:-

499789.00

Earnest Money:-

10000/-

Time:-

Two Months

Name of work:- R/R damages on verious roads under Karchham Division.

Sub Head:- C/O Wangfoo side abutment and crate wall on alternate route to NH-05 from Det Sungra to Wangtoo. Phase -III

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Proiding and laying concrete for plain/reinforced cement concrete 1:1.5:3 (One cement isto one point five sand isto three graded stone aggregate 25mm. (twenty five millimetre) nominal size) in open foundation and curing complete including cost of form work in retaining walls/breast walls, as per HPPWD specification clause 802, 803, 1202 & 1203 within all leads and lifts and as per the direction of Engineer-in-charge. M-25	76.36	4458.60	Rupees four thousand four hundred fifty eight and paise sixty only	Per cubic metre	340459.00
2	Providing and laying boulder apron laid in wire crates with 4 mm diameter G.I. wire confirming to IS:280 and IS:4826 in 100mmx 100mm (one hundred into one hundred millimetre) mesh (woven diagonally) including 10 % (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge.	109.25	1458.40	Rupees one thousand four hundred fifty eight and paise forty only	Per cubic metre	159330.00
					Total	499789.00

Draft schedule of quantity approved by 499789/-

Executive Engineer,
Karchham Division,
HPPWD at Bhaba Nagar.

Executive Engineer,
Karchham Division,
HPPWD at Bhaba Nagar.

Draft Schedule of Quantity

Estimated Cost:- 321648.00
 Earnest Money:- 6500/-
 Time:- Two Months

Job-4

Name of work:- R/R damages on verious roads under Karchham Division.

Sub Head:- C/O Bhaba side abutment on alternate route to NH-05 from Det Sungra to Wangtoo. Phase -I

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of slumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	73.44	128.15	Rupees one hundred twenty eight and paise fifteen only	Per cubic metre	9411.00
2	Supplying, fitting and placing TMT bar reinforcement in foundation complete as per drawings and technical specifications Clauses 1000 and 1202 and carriage of materials in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	2.79	64210.60	Rupees sixty four two hundred ten and paise sixty only	Per tonne.	179148.00
3	Proding and laying concrete for plain/reinforced cement concrete 1:1.5:3 (One cement isto one point five sand isto three graded stone aggregate 25mm.(twenty five millimetre) nominal size) in open foundation and curing complete including cost of form work in retaining walls/breast walls, as per HPPWD specification clause 802, 803, 1202 & 1203 within all leads and lifts and as per the direction of Engineer-in-charge. M-25	29.85	4458.60	Rupees four thousand four hundred fifty eight and paise sixty only	Per cubic metre	133089.00
					Total	321648.00

Draft schedule of quantity approved for Rs. 321648.00

Executive Engineer,
 Karchham Division,
 HPPWD at Bhaba Nagar.

Draft Schedule of Quantity

Estimated Cost:-
Earnest Money:-
Time:-

Job-5
390184.00
7900/-
Two Months

Name of work:- R/R damages on verrious roads under Karchham Division.

Sub Head:- C/O Bhaba side abutment on alternate route to NH-05 from Det Sungra to Wangtoo. Phase -II

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Proiding and laying concrete for plain/reinforced cement concrete 1:1.5:3 (One cement isto one point five sand isto three graded stone aggregate 25mm.(twenty five millimetre) nominal size) in open foundation and curing complete including cost of form work in retaining walls/breast walls, as per HPPWD specification clause 802, 803, 1202 & 1203 within all leads and lifts and as per the direction of Engineer-in-charge. M-25	70.85	4458.60	Rupees four thousand four hundred fifty eight and paise sixty only	Per cubic metre	315892.00
2	Providing weep holes in brick masonry/stone masonry/plain/ reinforced concrete abutment wing wall, return wall with 100mm.(One hundred millimetre) dia PVC pipe extneidng through the full with of the structures with slope of 1 (v) : 20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 12.04.3.7 within all leads and lifts and as per direction of Engineer-in-charge.	33.00	253.70	Rupees two hundred fifty three and paise seventy only	Each	8372.00
3	Back filling behind abutment, wing wall and return wall/breast wall and retaining walls complete as per drawing and technical specification within all leads and lifts and as per the direction of Engineer-in-charge.	23.52	481.30	Rupees four hundred eighty one and paise thirty Only	Per cubic metre	11320.00
4	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge.	306.57	178.10	Rupees one hundred seventy eight and paise ten only	Per cubic metre	54600.00
					Total	390184.00

Draft schedule of quantity approved for 29/08/24

Executive Engineer,
Karchham Division,
HPPWD at Bhaba Nagar.

Executive Engineer,
Karchham Division,
HPPWD at Bhaba Nagar.

Draft Schedule of Quantity

Job-6

Estimated Cost:-

455957.00

Earnest Money:-

9200/-

Time:-

Two Months

Name of work:- R/R damages on verrious roads under Karchham Division.

Sub Head:- C/O Bhaba side abutment, R/wallfor approach road on alternate route to NH-05 from Det Sungra to Wangtoo. Phase -III

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete 1:3:6 (one cement : three sand : six graded/crushed stone aggregate 20mm (twenty millimetre) nominal mix curing complete within all leads, lifts carriage of material and other incidentals.	71.72	2928.35	Rupees two thousand nine hundred twenty eight and paise thirty five only	Per cubic metre	210021.00
2	Providing and laying concrete for plain/reinforced cement concrete 1:1.5:3 (One cement isto one point five sand isto three graded stone aggregate 25mm. (twenty five millimetre) nominal size) in open foundation and curing complete including cost of form work in retaining walls/breast walls, as per HPPWD specification clause 802, 803, 1202 & 1203 within all leads and lifts and as per the direction of Engineer-in-charge. M-25	55.16	4458.60	Rupees four thousand four hundred fifty eight and paise sixty only	Per cubic metre	245936.00
					Total	455957.00

Draft schedule of quantity approved for 455957 for

Executive Engineer,

Karchham Division,

HPPWD at Bhaba Nagar.

HPPWD at Bhaba Nagar.