



**OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG**

PH: 01907-222229 Fax: 222229, e-mail : ee-kar-hp@nic.in

No.PW-KSG-E-Tenders/2023-
To

Dated:-

19/01/24

The Executive Engineer (IT) Cell,
HPPWD, Nirman Bhawan, Nigam Vihar,
Shimla-2

Subject :-

Regarding publication of Tender on departmental site.

Enclosed please find herewith the copies of Notice Inviting Tender for the loading on departmental web-site before 26.12.2023 as per notification issued by the Pr. Secy.(PW) to the Govt. of HP vide letter No. PBW(B)A(3)1/2020 dated 16th July, 2021. It is further intimated that all the works mentioned are of urgent nature.

Encl:- As above.


Executive Engineer,
B&R Division,
HP PWD Karsog



**OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG**
PH: 01907-222229 Fax: 222229 , E-mail : ee-kar-hp@nic.in

Notice inviting tender

Sealed item rates tender on form 6 & 8 are hereby invited by the Executive Engineer, B&R Division, HPPWD Karsog on behalf of Governor of Himachal Pradesh from the approved/eligible contractors enlisted in HP,PWD for the following works so as to reach in this office on or before **08.02.2024 upto 11.00 AM** and shall be opened on the same day at **12:00 AM** in presence of the contractor or their authorized representatives who may like to be present. The tender form can be obtained from this office against cash payment (Non refundable) **upto 4.00 PM on 06.02.2024** for which the application should reach in this office **upto 1.00 PM 06.02.2024**.

The earnest money in shape of National saving certificate/time deposit account/saving account in any Nationalized Bank in H.P duly pledged in favour of the Executive Engineer Karsog Division HPPWD Karsog will be received alongwith application for obtaining tenders form. The conditional tenders will summarily be rejected. The offer of the tenders shall be kept open for 51 days from the date of opening of tender. The Executive Engineer, HP PWD, Karsog reserves the right to reject any or all tenders without assigning any reason. The contractors should append their enlistment/renewed certificates/sale Tax registration Numbers with the application for issue of tender form. If any of the date mentioned above happens to be holiday the same shall be processed on next working day.

Sr. No.	Name of work	Estimated cost	Earnest money	Time allowed	Cost of Form
1	R/R damages on Shimla Mandi via Tattapani Km. 90/00 to 115/00 (SH:- C/o R/wall at RD 93/585 to 93/595)	2,76,032/-	5,600/-	One month	350/-
2	Construction of Shana to Bahi Sarahi via Luchhadhr road in GP Bahi Sarahi (SH:- ROFD/Re-grading by formation cutting at RD 3/555 to 3/840) under SCDP	4,96,878/-	10,000/-	One month	350/-
3	R/R damages on Thakurthana to Delag road Km. 0/00 to 7/100 (SH:- C/o R/wall at RD 2/055 to 2/060)	4,97,712/-	10,000/-	One month	350/-
4	R/R damages on Thakurthana to Delag road Km. 0/00 to 7/100 (SH:- C/o R/wall at RD 2/046 to 2/050.50)	4,95,315/-	9,900/-	One month	350/-
5	R/R damages on Chouridhar Kotlu road Km. 0/00 to 7/00 (SH:- C/o R/wall at RD 0/585 to 0/590, 1/585 to 1/593, 3/015 to 3/023 & 3/255 to 3/263)	4,89,282/-	9,800/-	One month	350/-
6	R/R damages on Chouridhar Kotlu road Km. 0/00 to 7/00 (SH:- C/o B/wall at RD 1/675 to 1/682, 2/315 to 2/330, 2/980 to 2/990 & 0/585 to 0/590)	3,76,691/-	7,600/-	One month	350/-
7	R/R damages on Chouridhar Kotlu road Km. 0/00 to 7/00 (SH:- C/o B/wall at RD 0/395 to 0/420, 0/560 to 0/570 & 1/075 to 1/080)	4,06,220/-	8,200/-	One month	350/-
8	R/R damages on Chouridhar Kotlu road Km. 0/00 to 7/00 (SH:- Removal of slips at various RDs) Kelodhar Section	3,80,766/-	7,700/-	One month	350/-
9	C/o Telehan to Davaru road Km. 0/00 to 5/00 (SH:-C/o 900mm dia RCC Hume Pipe Culvert at RD 1/225)	2,25,900/-	4,600/-	One month	350/-
10	C/o Telehan to Davaru road Km. 0/00 to 5/00 (SH:-C/o 900mm dia RCC Hume Pipe Culvert at RD 0/990)	2,25,960/-	4,600/-	One month	350/-

11	R/R damages on Chouridhar Kotlu road Km. 0/00 to 7/00 (SH:- C/o R/wall at RD 0/813 to 0/828)	2,98,915/-	6,000/-	One month	350/-
12	A/R & M/O various road under Karsog Sub-Division (Painting and writing in km. stone and sign board etc.)	1,36,437/-	2,800/-	One month	350/-
13	R/R damages on ambulance road from Bagra to Lower Bagra Km. 0/00 to 1/500 (SH:- C/o R/wall at RD 0/895 to 0/907)	4,47,707/-	9,000/-	One month	350/-
14	Construction of Bagain to Pathron road Km. 0/00 to 1/500 (SH:- Providing and laying kharanja stone soling in km. 0/190 to 0/240 and 0/373 to 0/425) D.C Deposit	1,10,376/-	2,200/-	One month	350/-
15	R/R damages on Chindi Dachhain road Km. 0/00 to 8/435 (SH:- C/o B/wall at RD 0/125 to 0/142)	4,97,892/-	1,000/-	One month	350/-
16	R/R damages on Mamail Mehendi road km. 0/00 to 19/00 (SH:- C/o R/wall at RD 4/785 to 4/800)	2,95,168/-	6,000/-	One month	350/-
17	R/R damages on Seri Shout road Km. 0/00 to 18/00 (SH:- C/o R/wall at RD 17/250 to 17/262)	2,56,884/-	5,200/-	One month	350/-
18	R/R damages on Shimla Mandi road via Tattapani Km. 52/250 to 115/00 (SH:- C/o R/wall at RD 87/150 to 87/160)	1,89,092/-	3,800/-	One month	350/-
19	R/R damages on Chindi to Dachhain road Km. 0/00 to 8/435 (SH:- C/o B/wall at RD 2/980 to 3/015)	2,04,734/-	4,100/-	One month	350/-
20	R/R damages on Bhanera to Kotlu road Km. 0/00 to 2/400 (SH:- C/o R/wall at RD 1/063 to 1/075)	4,98,409/-	10,000/-	One month	350/-
21	R/R damages on Bhanthal Punni(Tawa) road Km. 0/00 to 4/00 (SH:- C/o R/wall at RD 3/805 to 3/820)	4,08,737/-	8,200/-	One month	350/-
22	R/R damages on Mahog to Gawala road Km. 10/500 to 19/00 (SH:- C/o R/wall at RD 13/853 to 13/863)	3,50,206/-	7,100/-	One month	350/-
23	C/o Alsindi Badeyog road km. 0/00 to 6/555 (SH:- F/C between Km. 5/495 to 5/555)SCDP	4,66,692/-	9,100/-	One month	350/-
24	C/o Alsindi Badeyog road km. 0/00 to 6/555 (SH:- F/C between Km. 5/555 to 5/615)SCDP	4,69,576/-	9,400/-	One month	350/-
25	R/R damages on Katanda Pokhi road Km. 0/00 to 10/00 (SH:- C/o B/wall at RD 7/885 to 7/915)	4,78,906/-	9,600/-	One month	350/-
26	R/R damages on Jachh Pressi road Km. 0/00 to 5/00 (SH:- C/o R/wall in PCC at RD 0/255 to 0/264)	4,83,800/-	9,700/-	One month	350/-
27	Construction of Chauridhar Kotlu road Km. 0/00 to 7/840 (SH:- P/L Kharanja stone soling in Km. 7/174 to 7/250 & 7/450 to 7/840) Deposit SDF 2023 (838)	4,94,934/-	9,900/-	One month	350/-
28	A/R & M/O Shimal Mandi via Tattapani Km. 52/250 to 61/00 (SH:- M/O earthen shoulder, trimming of grass, cleaning of side drain & white washing of parapets in Km. 55/500 to 61/00)	4,97,612/-	10,000/-	Two months	350/-
29	A/R & M/O Shimal Mandi via Tattapani Km. 61/00 to 80/00 (SH:- M/O earthen shoulder, trimming of grass, cleaning of side drain & white washing of parapets in Km. 61/00 to 70/00)	4,98,414/-	10,000/-	Two months	350/-
30	R/R damages on Chholdhar to Panautdehra road Km. 0/00 to 2/700 (SH:- C/o R/wall at RD 2/610 to 2/620)NDF/2022/219	1,49,623/-	3,000/-	One month	350/-

31	R/R damages on Karsog to Shopa Mashog Nali road Km. 0/00 to 2/500 (SH:- C/o R/wall at RD 2/285 to 2/305)	4,93,920/-	9,900/-	One month	350/-
32	Restoration of rain damages on Shakra Parlog road upto village Bindla Km. 0/00 to 6/250 & Dawaru Talehan road km. 0/00 to 4/500 (SH:- Hiring of JCB for removal of slips various RDs & hiring of tipper for carriage of muck/debris/slips etc.	2,26,950/-	4,600/-	One month	350/-
33	R/R damages on Shimla Mandi road via Tattapani Km. 52/250 to 115/00 (SH:- C/o B/wall at Rd 80/800 to 80/820)	3,98,584/-	8,000/-	One month	350/-
34	C/o Sainj Sayanjli via Gannu road Km. 0/00 to 5/500 (SH:- Widening of road in Km. 5/060 to 5/255)	3,76,922/-	7,600/-	One month	350/-
35	Construction of Jingal Mod to Ganufri via Kotla Katachi link road Km. 0/00 to 1/300 (SH:- Widening of the road in Km. 0/00 to 0/165)	4,99,106/-	10,000/-	One month	350/-
36	Improvement of grade and removal of formation deficiency of Galoo to Mahroo road km. 0/00 to 1/00 GP Kandha Tehsil Karsog Distt. Mandi H.P. (SH:- widening of existing road and improvement of grade at various Rds between km. 0/00 to 0/015, 0/215 to 0/245 & 0/820 to 0/855) BSP/2023-940.	1,99,863/-	4,000/-	One month	350/-
37	Construction of Sarkol Nallah to Pathron road km. 0/00 to 1/00 (SH:- C/o 900mm dia RCC Hume pipe culvert at Rd 0/375)	2,64,704/-	5,300/-	One month	350/-
38	R/R damages on Chholdhar to Panout Dehra road km. 0/00 to 2/700 (SH:- C/o R/wall at RD 2/608 to 2/614)	4,32,822/-	8,700/-	One month	350/-
39	R/R damages on Kelodhar to Chhatri road Km. 0/00 to 19/00 under Karsog Sub-Division in Kelodhar Section (SH:- Removal of slips at various RDs from km. 0/00 to 10/00)	2,38,650/-	4,800/-	One month	350/-
40	R/R damages on Kelodhar Sainj road Km. 0/00 to 19/00 (SH:- C/o R/wall at RD 12/085 to 12/088)	1,09,315)	2,200/-	One month	350/-
41	Construction of Office Building for Subject Matter Specialist Horticulture at Karsog Distt. Mandi H.P. (SH:- Providing and Fixing power fire extinguisher)	1,65,000/-	3,300/-	One month	350/-
42	Balance work on construction of SMS/HDO office building at Karsog, Tehsil Karsog Distt. Mandi H.P.(SH:- Providing and fixing 6mm thick pinewood paneling and ceiling clerk room 1 & 2) "	4,34,072/-	8,700/-	One month	350/-
43	Balance work on construction of SMS/HDO office building at Karsog, Tehsil Karsog Distt. Mandi H.P.(SH:- Providing and fixing 6mm thick pinewood paneling and ceiling on record room, HEO & SMS building)	4,97,089/-	10,000/-	One month	350/-
44	Balance work on construction of SMS/HDO office building at Karsog, Tehsil Karsog Distt. Mandi H.P.(SH:- Providing and laying stone soling & kota stone flooring)	4,67,171/-	9,400/-	One month	350/-
45	Balance work on construction of SMS/HDO office building at Karsog, Tehsil Karsog Distt. Mandi H.P.(SH:- Providing and fixing 6mm thick pinewood paneling and ceiling HDO Block 1 & 2)	3,35,725/-	6,800/-	One month	350/-

46	Repair and maintenance of road from Dev Dwahli to Nanj via Kholanal Sayanjli Jhunju Kerta and various road Kelodhar Section in Karsog Division(SH:- Maintenance of earthen shoulders, removal of land slides, slips at various RDs)BSP/2023/941	1,68,602/-	3,400/-	One month	350/-
47	Repair and maintenance of road from Mamla to Galu road under Kelodhar Section in Sub-Division Karsog (SH:- Maintenance of earthen shoulders, removal of land slides, slips at various RDs) Deposit works	1,69,247/-	3,400/-	One month	350/-
48	R/R damages on Khadargali Somakothi road Km. 0/0 to 5/540 and Thakurthana Delag road km. 0/0 to 7/100 (SH:- hiring of Tipper for disposal/carriage of material) Section Katanda	1,52,000/-	3,000/-	26 days	350/-

TERMS & CONDITIONS:-

1. No tender form will be issued to those contractors who are not registered under HPGST Act.
2. The Contractor/firm should be registered as or dealer GST NO.
3. If any of the date mentioned above happened to be Gazetted holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/ application or all tenders without assigning any reason.
5. No tender form will be issued to those contractors who are not registered under EPF Act
6. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
7. The earnest money for the above work should be attached with the application.
8. The intending contractors/firms shall have to produce the copy of latest enlistment and renewal enlisted in HP,PWD.
9. As per Govt. Notification PW/CTR/32-20Genl Inst-CPWD/2020-37996-38095 dated 13-03-2023 the tenders above 5% will be summarily rejected and tenders amounts below 30% of amount put to tender will also be accepted.


Executive Engineer
B&R Division
HPPWD Karsog, Distt.
Mandi(HP)


No. PW-E-Tender-NIT/23-

12799-808

Dated:-

19-01-24

1. Copy to the Director , Information & Publications Department, HP Shimla for favour of publication in one Regional Newspaper and one National Newspaper.
2. Copy to the Superintending Engineer, 1st Circle, HP,PWD, Mandi for information please.
3. The Sub-Divisional Officer (Civil) Karsog, Tehsil Karsog Distt. Mandi HP.
4. The Block Development Officer Karsog , Tehsil Karsog Distt. Mandi HP.
5. All the Assistant Engineers, working under this Division.
6. Copy to Drawing & Account Branch.
7. Notice board of this office.


Executive Engineer,
B&R Division,
HP PWD Karsog

Percentage Schedule Of Quantity

Name of Work:- R/R damages on Shimla Mandi road via Tattapani km 90/00 to 115/00(SH:-C/O R/Wall at RD 93/585 to 93/595)

Estimated Cost 276032
Earnest Money 5600
Time One Month

Sr.No.	Sub-Head and items of works.	Qty	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. p	Total Amount with all taxes including GST in Words
1	Earth work in excavation by mechanical means/(Hydraulic excavator)/manual means in foundation trenches or drains(not exceeding 1.5m in width or 10sqm on plan),including dressing of sides and ramming of bottoms,lift upto 1.5m,including getting out theexcavated soil and disposal of surplus excavated soil as directed,within a lead of 50 m. as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	6.90	Per Cubic Meter	207.2	1430	Rupees One Thousand Four Hundred Twenty Nine and Paise Sixty Eight Only
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	12.30	Per Cubic Meter	208.15	2560	Rupees Two Thousand Five Hundred Sixty and Paise Twenty Four Only
3	Providing and laying concrete for plain/reinforced concrete 1:5:10 (one cement : five sand : ten graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	50.70	Per Cubic Meter	5140.40	260618	Rupees Two Lakhs Sixty Thousand Six Hundred Eighteen and Paise Twenty Eight Only
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment,wing wall,return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	12.00	Nos	371.75	4461	Rupees Four Thousand Four Hundred Sixty One and Paise Zero Only
5	Providing and laying filter media with granular crushed aggerates as per specification to a thickness of not less than 600 mm with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment,wing wall,return wall to the full height,compacted to firm condition complete as per drawing and technical specification clause 1204,3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	5.45	Per Cubic Meter	1277.55	6963	Rupees Six Thousand Nine Hundred Sixty Two and Paise Sixty Four Only
Total in Figures						
Quoted Rate in Figures			Select		276032	
Quoted Rate in Words					0.00	
Zero and Paise Zero Only						


Executive Engineer,
Karsog Division,
HRPWD, Karsog.

Percentage Schedule Of Quantity

Name of Work:- Construction of Shana to Bahi-Sarahi Via Luchhadhar road in G.P Bahi-Sarahi (SH:- ROFD/ Regrading by formation Cutting at RD 3/555 to 3/840) Under SCDP

Estimated Cost
Earnest Money
Time
496878
10000
One Month

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in-charge for smooth riding. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	2979.49	Per Cubic Meter	181.28	540108.00	Rupees Five Lakhs Forty Thousand One Hundred Eight and Paise Zero Only
2	Less credit for useful stone (the recovery of useful stone shall be done as per rate basis in each running bill for item no. 1 bill of quantity.	144.10	Per Cubic Meter	300.00	43230.00	
Total in Figures					496878.00	
Quoted Rate in Figures					0.00	
Quoted Rate in Words					Zero and Paise Zero Only	


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost
Earnest Money
Time
497712
10000
One Month

Name of Work:- R/R Damages on Thakurthana to Delag road km 0/00 to 7/100 (SH:- C/O R/Wall at RD 2/055 TO 2/060)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. p	Total Amount with all taxes including GST in Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	27.25	Per Cubic Meter	379.90	10352	Rupees Ten Thousand Three Hundred Fifty Two and Paise Twenty Seven Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803 1202 and 1203 Nominal mix 1:5:10, (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials within all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	85.41	Per Cubic Meter	5140.40	439042	Rupees Four Lakhs Thirty Nine Thousand Forty One and Paise Fifty Six Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	12.00	Each	371.75	4461	Rupees Four Thousand Four Hundred Sixty One and Paise Zero Only
4	Providing and Laying filter media with granular crushed aggregate as per specification to a thickness of not less than 600mm(six hundred millimeter) with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specifications clause 1204.3.8 or as per direction of engineer in charge including carriage of materials within all lead and lifts and other incidentals.	31.75	Per Cubic Meter	1381.34	43858	Rupees Forty Three Thousand Eight Hundred Fifty Seven and Paise Fifty Four Only
Total in Figures					497712	
Quoted Rate in Figures						
Quoted Rate in Words			Select		0.00	


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Name of Work:- R/R Damages on Thakurthana to Delag road km 0/00 to 7/100 (SH:- C/O R/Wall at RD 2/046 TO 2/050.50)

Estimated Cost
Earnest Money
Time

495315
9900
One Month

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	29.48	Per Cubic Meter	379.90	11199	Rupees Eleven Thousand One Hundred Ninety Nine and Paise Forty Five Only
2	Providing and laying concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803 1202 and 1203 Nominal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	82.32	Per Cubic Meter	5140.40	423158	Rupees Four Lakhs Twenty Three Thousand One Hundred Fifty Seven and Paise Seventy Two Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment/wing wall/return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	12.00	Each	371.75	4461	Rupees Four Thousand Four Hundred Sixty One and Paise Zero Only
4	Providing and Laying filter media with granular crushed aggregate as per specification to a thickness of not less than 600mm(six hundred millimeter) with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specifications clause 1204.3.8 or as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals.	40.90	Per Cubic Meter	1381.34	56497	Rupees Fifty Six Thousand Four Hundred Ninety Six and Paise Eighty Only
Total in Figures					495315	
Quoted Rate in Figures						
Quoted Rate in Words			Select		0.00	


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost
Earnest Money
Time

489282
9800
One Month

Name of Work:- R/R Damages on Chauridhar Kotlu road km 0/00 to 7/00 (SH:- C/O R/Wall at RD 0/585 to 0/590 , 1/585 to 1/593 , 3/015 to 3/023 & 3/255 to 3/263)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	26.95	Per Cubic Meter	379.90	10238	Rupees Ten Thousand Two Hundred Thirty Eight and Paise Thirty Only
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803.1202 and 1203 Nominal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials within all lead and lifts and other incidentals as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	83.59	Per Cubic Meter	5140.40	429686	Rupees Four Lakhs Twenty Nine Thousand Six Hundred Eighty Six and Paise Three Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	32.00	Each	371.75	11896	Rupees Eleven Thousand Eight Hundred Ninety Six and Paise Zero Only
4	Providing and Laying filter media with granular crushed aggregate as per specification to a thickness of not less than 600mm(six hundred millimeter) with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specifications clause 1204.3.8 or as per direction of engineer in charge including carriage of materials within all lead and lifts and other incidentals.	27.12	Per Cubic Meter	1381.34	37462	Rupees Thirty Seven Thousand Four Hundred Sixty One and Paise Ninety Four Only
Total in Figures					489282	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words						


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 376691
Earnest Money 7600
Time One Month

Name of Work:- R/R Damages on Chauridhar Kotlu road km 0/00 to 7/00 (SH:- C/O B/Wall at RD 1/675 to 1/682 , 2/315 to 2/330 , 2/980 to 2/990 & 0/585 to 0/590)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. p	Total Amount with all taxes including GST In Words
1	Earth work in excavation by mechanical means(hydraulic excavator)/manual means in foundation trenches of drain (not exceeding 1.5 meter in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, life upto 1.5 m, including gutting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.as per direction of Engineer-in-Charge including cartage of material within all leads and lifts and other incidentals	28.03	Per Cubic Meter	208.15	5834	Rupees Five Thousand Eight Hundred Thirty Four and Paise Forty Four Only
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including cartage of material within all leads and lifts and other incidentals.	21.85	Per Cubic Meter	379.90	8301	Rupees Eight Thousand Three Hundred and Paise Eighty One Only
3	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803,1202 and 1203 Nominal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including cartage of materials with in all lead and lifts and other incidentals as per direction of Engineer-in- Charge including cartage of materials within all leads and lifts and other incidentals.	69.93	Per Cubic Meter	5140.40	359468	Rupees Three Lakhs Fifty Nine Thousand Four Hundred Sixty Eight and Paise Seventeen Only
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including cartage of materials within all leads and lifts and other incidentals.	24.00	Each	371.75	8922	Rupees Eight Thousand Nine Hundred Twenty Two and Paise Zero Only
Total in Figures					376691	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
H.P.W.D, Karsog.

Percentage Schedule Of Quantity

Estimated Cost
Earnest Money
Time

406220
8200
One Month

Name of Work:- R/R Damages on Chauridhar Kotlu road km 0/00 to 7/00 (SH:- C/O B/Mall at RD 0/395 to 0/420 , 0/560 to 0/570 & 1/075 to 1/080)

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Earth work in excavation by mechanical means(hydraulic excavator)/manual means in foundation trenches of drain (not exceeding 1.5 meter in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including galling out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m, as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals	31.35	Per Cubic Meter	208.15	6526	Rupees Six Thousand Five Hundred Twenty Five and Paise Fifty Only
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	20.90	Per Cubic Meter	379.90	7940	Rupees Seven Thousand Nine Hundred Thirty Nine and Paise Ninety One Only
3	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803 1202 and 1203 Nominal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	75.60	Per Cubic Meter	5140.40	388614	Rupees Three Lakhs Eighty Eight Thousand Six Hundred Fourteen and Paise Twenty Four Only
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment,wing wall,return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(v):20 (H-) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	26.00	Each	371.75	9666	Rupees Nine Thousand Six Hundred Sixty Five and Paise Fifty Only
Total in Figures					406220	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words						


 Executive Engineer,
 Karsog Division,
 JHPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 380766
Earnest Money 7700
Time One Month

Name of Work:- R/R Damages on Chauridhar Kotlu road km 0/00 to 7/00 (SH:- Removal of Slips at Various RD's) Section Kelodhar

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	3012.39	Per Cubic Meter	126.40	380766	Rupees Three Lakhs Eighty Thousand Seven Hundred Sixty Six and Paise Nine Only
Total in Figures					380766	
Quoted Rate in Figures						
Quoted Rate in Words			Select		0.00	


Executive Engineer,
Karsog Division,
KPPWD, Karsog.

Schedule of Quantity

Estimated Cost
Earnest Money
Time

225900
4600
One month

Name of Work:- C/O Talehan to Davaru road Km. 0/00 to 5/00 (SH:- C/O 900 mm dia RCC Hume Pipe culvert at RD 1/225)

Sr.No.	Sub-Head and items of works.	Qty.	Rate		Unit.	Amount.
			In Figure	In words		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	49.02			Per Cubic Meter	
2	Providing and laying concrete for plain/reinforced concrete 1:5:10 (one cement : five sand : ten graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	27.76			Per Cubic Meter	
3	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in double row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets as per clause 1106as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	7.50			Running Metre	
4	Providing weepholes in bricks masonry/stone masonry plain /reinforced concrete abutment wing wall,return wall with 100mm dia PVC pipe extending through the full with the structure with slope of 1(V): 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204.3.7 As per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	12.00			Each	
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	15.15			Per Cubic Meter	
	Total :-					


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Schedule of quantity

Name of Work:-C/O Talehan to Davaru road Km. 0/00 to 5/00 (SH:- C/O 900 mm dia RCC Hume Pipe culvert at RD 0/990)

Estimated Cost
Earnest Money
Time

225960
4600
One month

Sr.No.	Sub-Head and items of works.	Qty.	Rate		Unit.	Amount.
			In Figure	in words		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	49.18			Per Cubic Meter	
2	Providing and laying concrete for pain/reinforced concrete 1:5:10 (one cement : five sand : ten graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	27.76			Per Cubic Meter	
3	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in double row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets as per clause 1106as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	7.50			Running Metre	
4	Providing weepholes in bricks masonry/stone masonry plain /reinforced concrete abutment wing wall,return wall with 100mm dia PVC pipe extending through the full with the structure with slope of 1(V): 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204,3.7 As per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	12.00			Each	
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204,3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	15.15			Per Cubic Meter	
	Total :-					


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost
Earnest Money
Time

298915
6000
One Month

Name of Work:- R/R Damages on chouridhar Kotlu road km 0/00 to 7/00 (SH:- C/O R/Wall at RD 0/813 to 0/828)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. p	Total Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including cartage of material within all leads and lifts and other incidentals.	18.37	Per Cubic Meter	379.90	6979	Rupees Six Thousand Nine Hundred Seventy Eight and Paise Seventy Six Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803 1202 and 1203 Nominal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including cartage of materials within all lead and lifts and other incidentals as per direction of Engineer-in- Charge including cartage of materials within all leads and lifts and other incidentals.	49.41	Per Cubic Meter	5140.40	253987	Rupees Two Lakhs Fifty Three Thousand Nine Hundred Eighty Seven and Paise Sixteen Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including cartage of materials within all leads and lifts and other incidentals.	20.00	Each	371.75	7435	Rupees Seven Thousand Four Hundred Thirty Five and Paise Zero Only
4	Providing and Laying filter media with granular crushed aggregate as per specification to a thickness of not less than 600mm(six hundred millimeter) with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specifications clause 1204.3.8 or as per direction of engineer in charge including cartage of materials within in all lead and lifts and other incidentals.	22.09	Per Cubic Meter	1381.34	30514	Rupees Thirty Thousand Five Hundred Thirteen and Paise Eighty Only
Total in Figures					298915	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words						


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 136437
Earnest Money 2800
Time One Month

Name of Work: A/R & M/O Various road under Karsog Sub-Division (Painting and Writing in km stone and Sign Board etc.)						
Sr No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST in Rs. p	Total Amount with all taxes including GST in Words
1	Painting two coats with epoxy paint of approved brand on concrete/steel surface after through cleaning of surface to give an even shade as per drawing and technical specification clause 1701 as per direction of Engineer-in- Charge including cartage of materials within all leads and lifts and other incidentals.	18.00	Per Square Meter	152.70	2749.00	Rupees Two Thousand Seven Hundred Forty Nine and Paise Zero Only
2	Painting two coats after filling the surface with synthetic enamel paint in all shades on new plastered/concrete surface as per drawing and technical specification as per direction of Engineer-in- Charge including cartage of materials within all leads and lifts and other incidentals.	33.00	Per Square Meter	140.65	4641.00	Rupees Four Thousand Six Hundred Forty One and Paise Zero Only
3	Painting new letters and figures of any shade with syntetic enamel paint black or any other approved colour to give as even shade as per drawing and technical specification as per direction of Engineer-in- Charge including cartage of materials within all leads and lifts and other incidentals.	44499.00	Per Letter/Per Centimeter height	2.90	129047.00	Rupees One Lakh Twenty Nine Thousand Forty Seven and Paise Zero Only
Total in Figures					136437.00	
Quoted Rate in Figures					0.00	
Quoted Rate in Words			Select			
Zero and Paise Zero Only						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 447707
Earnest Money 9000
Time One Month

Name of Work:- R/R Damages on Ambulance road from Bagra to Lower Bagra Km. 0/00 to 1/500 (SH:- C/O R/Wall at RD 0/895 to 0/907)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	34.16	Per Cubic Meter	379.90	12977.00	Rupees Twelve Thousand Nine Hundred Seventy Seven and Paise Zero Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803 1202 and 1203 Nominal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials within all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	78.72	Per Cubic Meter	5140.40	404652.00	Rupees Four Lakhs Four Thousand Six Hundred Fifty Two and Paise Zero Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(v):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	24.00	Each	371.75	8922.00	Rupees Eight Thousand Nine Hundred Twenty Two and Paise Zero Only
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	16.56	Per Cubic Meter	1277.55	21156.00	Rupees Twenty One Thousand One Hundred Fifty Six and Paise Zero
Total in Figures					447707.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words			Zero and Paise Zero Only			


 Executive Engineer,
 Karsog Division,
 MPAMD, Karsog.

SCHEDULE OF QUANTITY

NAME OF WORK:- Construction of Bagain to Pathron road Km. 0/00 to 1/500 (SH:- Providing and Laying Kharania Stone Soling in Km. 0/190 to 0/240 and 0/373 to 0/425) D.C. Deposit

Estimated Cost Rs.110376/-
Earnest Money Rs.2200/-

Time:- One Month

Sr.No.	Sub-Head and items of works.	Qty.	Rate		Unit.	Amount.
			in Figure	in words		
1	Preparation of sub grade by dressing to camber(earth work for the cutting involved for sub grade to be paid for separately depending upon the classification of soil completed as per HP.PWD. Specifications or as per direction of engineer in charge including carriage of materials with in all leads, lifts and other incidentals.	385.56			Per square Meter	
2	Consolidation of sub grade with road roller including making good the undulation etc.with earth or quarry soil etc. and rerolling the sub-grade completed as per HP.PWD. Specifications or as per direction of engineer in charge including carriage of materials with in all leads, lifts and other incidentals.	385.56			Per square Meter	
3	Stone soling properly had paid filling intakes with Kharania stone and class already with prove road roller to the required graded un camber i.e. reading wastage and relling of belong naturals maousm or each etc. as per HPPWD specification 100mm speed froes (ponist ware i.e. materia and labour all leads and line or as per direction of engineer in charge including carriage of materials with in all leads, lifts and other incidentals.	57.83			Per Cubic meter	
	Total Amount					


Executive Engineer
Karsog Division
H.P.P. W.D. Karsog.

Scheduled Quantity

Estimated Cost 497892
Earnest Money 10000
Time One Month

Name of Work :- R/R damages on Chindi to Dachhain road km 0/00 to 8/435 (SH:- C/O B/Wall at RD 0125 TO 0/142)

Sr. No.	Sub-Head and items of works.	Qty.	Rate		Unit	Amount
			in Figure	in words		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to any lead dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto any depth as per direction of engineer in charge with in all lead and lifts and other incidentals.	48.20			Per Cubic meter	
2	Providing and laying concrete for pain/reinforced concrete 1:5:10 (one cement : five sand : ten graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	91.85			Per Cubic Meter	
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	20.00			Each	
Total Amount						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Name of Work:- R/R Damages on Mamail To Mehandi road Km. 0/00 to 19/00 (SH:- C/O R/Wall at RD km 4/785 to 4/800)

Estimated Cost
Earnest Money
Time

295168
6000
One Month

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. p	Total Amount with all taxes including GST in Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including cartage of material within all leads and lifts and other incidentals.	22.50	Per Cubic Meter	379.90	8548.00	Rupees Eight Thousand Five Hundred Forty Eight and Paise Zero Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803 1202 and 1203 Nominal mix 1:5:10. (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including cartage of materials within all lead and lifts and other incidentals as per direction of Engineer-in- Charge including cartage of materials	48.04	Per Cubic Meter	5140.40	246945.00	Rupees Two Lakhs Forty Six Thousand Nine Hundred Forty Five and Paise Zero Only
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including cartage of material within all leads and lifts and other incidentals.	26.40	Per Cubic Meter	1277.55	33727.00	Rupees Thirty Three Thousand Seven Hundred Twenty Seven and Paise
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(v):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including cartage of materials within all leads and lifts and other incidentals.	16.00	Each	371.75	5948.00	Rupees Five Thousand Nine Hundred Forty Eight and Paise Zero Only
Total in Figures					295168.00	
Quoted Rate in Figures					0.00	
Quoted Rate in Words						


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 256884
Earnest Money 5200
Time One Month

Name of Work:- R/R Damages on Seri Shout road km 0/00 to 18/00 (SH:- C/O R/Wall at RD 17/250 to 17/262)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	14.16	Per Cubic Meter	379.90	5379	Rupees Five Thousand Three Hundred Seventy Nine and Paise Thirty Eight Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803 1202 and 1203 Nominal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials within all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	42.82	Per Cubic Meter	5140.40	220112	Rupees Two Lakhs Twenty Thousand One Hundred Eleven and Paise Ninety Two Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall,return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	16.00	Each	371.75	5948	Rupees Five Thousand Nine Hundred Forty Eight and Paise Zero Only
4	Providing and Laying filter media with granular crushed aggregate as per specification to a thickness of not less than 600mm(six hundred millimeter) with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specifications clause 1204.3.8 or as per direction of engineer in charge including carriage of materials within in all lead and lifts and other incidentals.	18.42	Per Cubic Meter.	1381.34	25444	Rupees Twenty Five Thousand Four Hundred Forty Four and Paise Twenty Eight Only
Total in Figures					256884	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words						


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Name of Work:- R/R Damages on Shimla Mandi road Via Tattapani km 52/250 to 115/00 (C/O R/Wall at RD 87/150 to 87/160)

Estimated Cost
Earnest Money
Time

189092
3800
One Month

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. p	Total Amount with all taxes including GST in Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	12.80	Per Cubic Meter	379.90	4863	Rupees Four Thousand Eight Hundred Sixty Two and Paise Seventy Two Only
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803 1202 and 1203 Nominal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials with in all lead lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	31.70	Per Cubic Meter	5140.40	162951	Rupees One Lakh Sixty Two Thousand Nine Hundred Fifty and Paise Sixty Eight Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment,wing wall,return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(v):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	16.00	Each	371.75	5948	Rupees Five Thousand Nine Hundred Forty Eight and Paise Zero Only
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 or as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	12.00	Each	1277.55	15331	Rupees Fifteen Thousand Three Hundred Thirty and Paise Sixty Only
Total in Figures					189092	
Quoted Rate in Figures						
Quoted Rate in Words			Select		0.00	


Executive Engineer,
Karsog Division,
HPPMD, Karsog.

Percentage Schedule Of Quantity

Name of Work:- R/R Damages on Chindi to Dachhain road km. 0/00 to 8/435 (SH:- C/O B/Wall at RD 2/980 to 3/015)

Estimated Cost 204734
Earnest Money 4100
Time One Month

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST in Rs. p	Total Amount with all taxes including GST in Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to any lead dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto any depth or as per direction of Engineer-in-Charge including cartage of material within all leads and lifts and other incidentals.	27.00	Per Cubic Meter	379.90	10257	Rupees Ten Thousand Two Hundred Fifty Seven and Paise Zero Only
2	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704 704.6& 1302.5 within all leads and lifts and other incidentals	55.13	Per Cubic Meter	3527.60	194477	Rupees One Lakh Ninety Four Thousand Four Hundred Seventy Seven and Paise Zero Only
Total in Figures					204734.00	
Quoted Rate in Figures						
Quoted Rate in Words			Select		0.00	


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 498409
Earnest Money 10000
Time One Month

Name of Work:- R/R Damages on Bhanera to Kotlu road 0/00 to 2/400 (SH:- C/O R/Wall at RD 1/063 to 1/075)

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	39.60	Per Cubic Meter	379.90	15044	Rupees Fifteen Thousand Forty Four and Paise Four Only
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803 1202 and 1203 Nominal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials within all lead lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	88.56	Per Cubic Meter	5140.40	455234	Rupees Four Lakhs Fifty Five Thousand Two Hundred Thirty Three and Paise Eighty Two Only
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	16.20	Per Cubic Meter	1277.55	20696	Rupees Twenty Thousand Six Hundred Ninety Six and Paise Thirty One Only
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment,wing wall,return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	20.00	Each	371.75	7435	Rupees Seven Thousand Four Hundred Thirty Five and Paise Zero Only
Total in Figures					498409	
Quoted Rate in Words			Select		0.00	


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 408737
Earnest Money 8200
Time One Month

Name of Work:- R/R Damages on Bhanthal Punni (Tawa) road in km. 0/00 to 4/00 (SH:- C/O R/Wall at RD 3/805 to 3/820)

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	27.45	Per Cubic Meter	379.90	10428	Rupees Ten Thousand Four Hundred Twenty Eight and Paise Twenty Five Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803 1202 and 1203 Nominal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	70.88	Per Cubic Meter	5140.40	364352	Rupees Three Lakhs Sixty Four Thousand Three Hundred Fifty One and Paise Fifty Five Only
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	17.85	Per Cubic Meter	1277.55	22804	Rupees Twenty Two Thousand Eight Hundred Four and Paise Twenty Six Only
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment,wing wall,return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	30.00	Each	371.75	11153	Rupees Eleven Thousand One Hundred Fifty Two and Paise Fifty Only
Total In Figures					408737	
Quoted Rate in Figures						
Quoted Rate in Words			Select		0.00	


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 350206
Earnest Money 7100
Time One Month

Name of Work:- R/R Damages on Mahog to Gawala road Km 10/500 to 19/00(SH:- C/O R/Wall at RD 13/853 to 13/863)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit	Estimated Rate (Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	33.00	Per Cubic Meter	379.90	12537.00	Rupees Twelve Thousand Five Hundred Thirty Seven and Paise Zero Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803 1202 and 1203 Nominal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials within all leads and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials	62.06	Per Cubic Meter	5140.40	319013.00	Rupees Three Lakhs Nineteen Thousand Thirteen and Paise Zero Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment,wing wall,return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	16.00	Each	371.75	5948.00	Rupees Five Thousand Nine Hundred Forty Eight and Paise Zero Only
4	Providing and Laying filter media with granular crushed aggregate as per specification to a thickness of not less than 600mm(six hundred millimeter) with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specifications clause 1204.3.8 or as per direction of engineer in charge including carriage of materials within in all lead and lifts and other incidentals.	9.20	Per Cubic Meter	1381.34	12708.00	Rupees Twelve Thousand Seven Hundred Eight and Paise Zero Only
Total in Figures					350206.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words			Zero and Paise Zero Only			


 Executive Engineer,
 Narsog Division,
 DPMID, Karsog.

Percentage Schedule Of Quantity

2nd Copy

Estimated Cost 466692.00
Earnest Money 9100
Time One Month

Name of Work:- C/O Alsidi Badeyog Road Km. 0/00 to 6/555 (SH:- FIC 5/7 between Km. 5/495 to 5/555) SCDP
Sr.No. **Sub-Head and items of works.**

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. p	Total Amount with all taxes including GST In Words
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in-charge for smooth riding. The recovery of 241.32 cubic metre @ Rs. 300/- per cubic metre amounting to Rs. 72396/- only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1290.31	Per Cubic Meter	361.69	466692.00	Rupees Four Lakhs Sixty Six Thousand Six Hundred Ninety Two and Paise Zero Only
Total in Figures					466692.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words				Zero and Paise Zero Only		


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Name of Work:- C/O Alisidi Badeyog Road Km. 0/00 to 6/555 (SH:- F/C 5/7 between Km. 5/555 to 5/615) SCDP

Estimated Cost 469576.00
Earnest Money 9400
Time One Month

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in-charge for smooth riding. The recovery of 259.79 cubic metre @ Rs. 300/- per cubic metre amounting to Rs. 77937/- only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1230.90	Per Cubic Meter	381.49	469576.00	Rupees Four Lakhs Sixty Nine Thousand Five Hundred Seventy Six and Paise Zero Only
Total in Figures					469576.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words			Zero and Paise Zero Only			


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Name of Work:- R/R Damages on Katanda to Pokhi road km 0/00 to 10/00 (SH:- C/O B/Wall at RD 7/885 to 7/915)

Estimated Cost 478906
Earnest Money 9600
Time One Month

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Excavation work by mechanical means (Hydraulic excavator) manual means in foundation trenches or drains not exceeding 1.5 m (One Point five metre) in width or 10 sqm on plan , including dressing of sides and ramming of bottoms, lift upto 1.5 metre(one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, with in a lead of 50m. (Fifty metre) as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	37.80	Per Cubic Meter	207.20	7832.00	Rupees Seven Thousand Eight Hundred Thirty Two and Paise Zero Only
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and disposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	13.20	Per Cubic Meter	379.90	5015.00	Rupees Five Thousand Fifteen and Paise Zero Only
3	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803,1202 and 1203 Nominal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	87.05	Per Cubic Meter	5140.40	447472.00	Rupees Four Lakhs Forty Seven Thousand Four Hundred Seventy Two and Paise Zero Only
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1 (V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	50.00	Each	371.75	18588.00	Rupees Eighteen Thousand Five Hundred Eighty Eight and Paise Zero Only
Total in Figures					478906.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words				Zero and Paise Zero Only		


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 483800
Earnest Money 9700
Time One Month

Name of Work: R/R Damages on Jachh Sarzhi road km 0/00 to 5/00 (SH: C/O R/Wall in PCC at RD 0/255 to 0/264)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with in upto 1.5 mtrs and a lead up to 20 mtrs as per drawing and technical specification clause 1603.1 as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	18.72	Per Cubic Meter	207.20	3879.00	Rupees Three Thousand Eight Hundred Seventy Nine and Paise Zero Only
2	Earth work in excavation by mechanical means (Hydraulic excavator) manual means in foundation trenches of drains (not exceeding 1.5 mtrs in width 10sqm on plan) including dressing of sides and remaining of bottoms, lift upto 1.5 mtrs, including getting out the excavated soil and disposal of surplus excavated soil as directed within a lead 50mtrs as per direction of engineer in charge with in all lead and lifts and other incidentals.	17.55	Per Cubic Meter	208.15	3653.00	Rupees Three Thousand Six Hundred Fifty Three and Paise Zero Only
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:4:8 (one Cement : four coarse sand : eight graded stone aggregate 40 mm (forty millimetre) nominal size as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	24.84	Per Cubic Meter	5457.80	135572.00	Rupees One Lakh Thirty Five Thousand Five Hundred Seventy Two and Paise Zero Only
4	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803 1202 and 1203 Nominal mix 1:5:10. (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	63.33	Per Cubic Meter	5140.40	325542.00	Rupees Three Lakhs Twenty Five Thousand Five Hundred Forty Two and Paise Zero Only
5	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(v):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	12.00	Each	371.75	4461.00	Rupees Four Thousand Four Hundred Sixty One and Paise Zero Only
6	Providing and Laying filter media with granular crushed aggregate as per specification to a thickness of not less than 600mm(six hundred millimeter) with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specifications clause 1204.3.8 or as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals.	8.37	Per Cubic Meter	1277.55	10693.00	Rupees Ten Thousand Six Hundred Ninety Three and Paise Zero Only
Total in Figures					483800.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words				Zero and Paise Zero Only		


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 494934
Earnest Money 9900
Time One Month

Name of Work:- Construction of Chauridhar Kotlu road Km. 0/00 to 7/840 (SH:- P/L Kharanja stone soling in Km. 7/174 to 7/250 & 7/450 to 7/840) Deposit SDF 2023 (838)

Sub-Head and Items of works.						
Sr No.		No. Or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes	Total Amount with all taxes including GST in
1	Preparation of sub grade by dressing to camber (Earth work for the cutting involved for sub-graded to be paid for separately depending upon the classification of Engineer-in-Charge within all leads and lifts as per direction of Engineer-in-Charge including carriage of materials within all leads lifts and other incidentals.	1574.50	Per Square Meter	1.78	2803	Rupees Two Thousand Eight Hundred Two and Paise Sixty One Only
2	Consolidation of sub-grade with road roller including making good the undulation etc. with earth or quarry soil etc. and re-rolling the sub-grade completed as per HP PWD. Specifications as per direction of Engineer-in-Charge within all leads and lifts as per direction of Engineer-in-Charge including carriage of materials within all leads lifts and other incidentals.	1574.50	Per Square Meter	2.85	4487	Rupees Four Thousand Four Hundred Eighty Seven and Paise Thirty Two Only
3	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidation with power road roller to the requested gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HPPWD specification. 100 mm (one hundred millimetre) spread thickness (finished work including materials and labour) within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	226.17	Per Cubic Meter	2064.80	487644	Rupees Four Lakhs Eighty Seven Thousand Six Hundred Forty Three and Paise Eighty One Only
Total in Figures					494934	
Quoted Rate in Figures						
Quoted Rate in Words			Select		0.00	


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Name of Work:- A/R & To Shimla Mandi road via Tattapani km. 52/250 to 61/00 (SH:- M/O Earthen shoulder , Trimming of grass , cleaning of side drain & white washing of parapets in km 55/500 to 61/00)

Estimated Cost 497612
Earnest Money 10000
Time Two Months

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	7950.00	Per Square Meter	32.75	260363	Rupees Two Lakhs Sixty Thousand Three Hundred Sixty Two and Paise Fifty Only
2	The maintenance of drains include erosion, repair , cleaning, clearing, reshaping regrading , deepening of side drains as well as catch water drains as per technical specification clause 1907 within all leads and lifts and other incidentals as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	5000.00	Per Running Meter	5.25	26250	Rupees Twenty Six Thousand Two Hundred Fifty and Paise Zero Only
3	Trimming of grass and weeds from the shoulder/berms and disposing off the same to suitable locations as per technical specification clause 1914 within all leads and lifts and other incidentals as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	16140.00	Per Square Meter	4.37	70532	Rupees Seventy Thousand Five Hundred Thirty One and Paise Eighty Only
4	White washing two coats as parapets walls and tree ,trunks including preparation of surface by cleaning scraping etc. as per technical specification clause 1915 within all leads and lifts and other incidentals as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	3532.00	Per Square Meter	39.77	140468	Rupees One Lakh Forty Thousand Four Hundred Sixty Seven and Paise Sixty Four Only
Total in Figures					497612	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Name of Work:- A/R & /o Shimla Mandi road via Tattapani km. 61/00 to 80/00 (SH:- M/O Earthen shoulder , Trimming of grass , cleaning of side drain & white washing of parapets in km 61/00 to 70/00)

Estimated Cost 498414
Earnest Money 10000
Time Two Months

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	9720.00	Per Square Meter	32.75	318330	Rupees Three Lakhs Eighteen Thousand Three Hundred Thirty and Paise Zero Only
2	The maintenance of drains include erosion, repair , cleaning, clearing, reshaping regrading , deepening of side drains as well as catch water drains as per technical specification clause 1907 within all leads and lifts and other incidentals as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	6500.00	Per Running Meter	5.25	34125	Rupees Thirty Four Thousand One Hundred Twenty Five and Paise Zero Only
3	Trimming of grass and weeds from the shoulder/berms and disposing off the same to suitable locations as per technical specification clause 1914 within all leads and lifts and other incidentals as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	16200.00	Per Square Meter	4.37	70794	Rupees Seventy Thousand Seven Hundred Ninety Four and Paise Zero Only
4	White washing two coats as parapets walls and tree ,trunks including preparation of surface by cleaning scraping etc. as per technical specification clause 1915 within all leads and lifts and other incidentals as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	1890.00	Per Square Meter	39.77	75165	Rupees Seventy Five Thousand One Hundred Sixty Five and Paise Thirty Only
Total in Figures					498414	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Name of Work:- R/R Damages on Chholdahr to Panautdehra road Km. 0/00 to 2/700 (SH:- C/O R/Wall) at RD 2/610 to 2/620) NDF/2022/219

Estimated Cost 149623
Earnest Money 3000
Time One Month

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes	Total Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	12.00	Per Cubic Meter	379.90	4559.00	Rupees Four Thousand Five Hundred Fifty Nine and Paise Zero Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803 1202 and 1203 Noimnal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	27.00	Per Cubic Meter	5140.40	138791.00	Rupees One Lakh Thirty Eight Thousand Seven Hundred Ninety One and Paise Zero Only
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	2.00	Per Cubic Meter	1277.55	2555.00	Rupees Two Thousand Five Hundred Fifty Five and Paise Zero Only
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment,wing wall,return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(v):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	10.00	Each	371.75	3718.00	Rupees Three Thousand Seven Hundred Eighteen and Paise Zero Only
Total in Figures					149623	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words			Zero and Paise Zero Only			


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 493920
Earnest Money 9900
Time One Month

Name of Work:- R/R Damages on Karsog to Shopa Mashog Nallil road km 0/00 to 2/500 (SH:- C/O R/Wall at RD 2/285 to 2/305)

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	49.60	Per Cubic Meter	379.90	18843	Rupees Eighteen Thousand Eight Hundred Forty Three and Paise Four Only
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202 and 1203 Nominal mix 1:5:10, (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials within all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	81.90	Per Cubic Meter	5140.40	420999	Rupees Four Lakhs Twenty Thousand Nine Hundred Ninety Eight and Paise Severy Six Only
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204, 3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	33.60	Per Cubic Meter	1277.55	42926	Rupees Forty Two Thousand Nine Hundred Twenty Five and Paise Sixty Eight Only
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	30.00	Each	371.75	11153	Rupees Eleven Thousand One Hundred Fifty Two and Paise Fifty Only
Total in Figures					493920	
Quoted Rate in Words			Select		0.00	


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 226950
Earnest Money 4600

Time One Month

Name of Work:- Restoration of rain damages on Shakra Parlog road upto village Bindla Km. 0/00 to 6/250 & Dawaru Talehan road km. 0/00 to 4/500 (SH:- Hiring of JCB for removal of slips various Rds & Hiring of tipper for carriage of muck/debris/slips etc.)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. p	Total Amount with all taxes including GST In Words
1	Hiring of JCB/Excavator for removal of slips road side, Katcha drain and boulders in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts as per direction and entire satisfactions of Engineer-In-Charge. any loss to the public 7 private property and accident etc. the contractors is fully responsible during the execution of work. the fuel and operation staff for the machine and repair charges of machinery during the execution of work will be burn by the contractor. the useful materials shall be stacked along the road side as per the direction of Engineer-In-Charge.	85	hours	1150.00	97750.00	Rupees Ninety Seven Thousand Seven Hundred Fifty and Paise Zero Only
2	Hiring of Tipper for disposal of earthen materials or slips having capacity 5.50 cum per trip and minimum working hours @ 8.00 hrs. (eight hours) per day which shall include all expenses on account of establishment POL, repair and other over head charges, the Tipper has to be perform not less than as prescribed in the rooms of HP and as per the direction of Engineer-In-Charge, including carriage of materials and all labour equipment to various location through all modes of transportation in all leads and lifts, as per the direction of Engineer-In-Charge.	34	Days	3800.00	129200.00	Rupees One Lakh Twenty Nine Thousand Two Hundred and Paise Zero Only
Total in Figures					226950.00	
Quoted Rate in Figures			Select			
Quoted Rate in Words					0.00	


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 398584
Earnest Money 8000
Time One Month

Name of Work:- R/R Damages on Shimla Mandi road Via Tattapani Km. 52/250 to 115/00 (SH:- C/O B/Mail at RD 80/800 to 80/820)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes including GST in Rs. p	Total Amount with all taxes including GST in Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	61.88	Per Cubic Meter	379.90	23508.00	Rupees Twenty Three Thousand Five Hundred Eight and Paise Zero Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803 1202 and 1203 Nominal mix 1:5:10. (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials with in all leads and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials	71.52	Per Cubic Meter	5140.40	367641.00	Rupees Three Lakhs Sixty Seven Thousand Six Hundred Forty One and Paise Zero Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment,wing wall,return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	20.00	Each	371.75	7435.00	Rupees Seven Thousand Four Hundred Thirty Five and Paise Zero Only
Total in Figures					398584.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words			Zero and Paise Zero Only			


Executive Engineer,
Karsog Division,
HPWD, Karsog.

Percentage Schedule Of Quantity

Name of Work:- C/O Saini Synjli via Gannu road Km. 0/00 to 5/500 (SH:- Widening of raod in Km. 5/060 to 5/255)

Estimated Cost Rs.
Earnest Money cost Rs.
Time

376922
7600
One Month

Sr.No.	Description Work	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes	Total Amount with all taxes including GST in Rupees Three Lakhs Seventy Six Thousand Nine Hundred Twenty Two and Paise Zero Only
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in-charge for smooth riding. The recovery of 305.94 cubic metre @ Rs. 300/- per cubic metre amounting to Rs. 191783/- only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1390.65	Per Cubic Meter	271.04	376922.00	
Total in Figures					376922	
Quoted Rate in Figures						
Quoted Rate in Words			Select		0.00	


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost
Earnest Money
Time

499106
10000
One Month

Name of Work:- Construction of Jingal Mod to Ganufri via Kotla Katachi link road km.0/00 to 1/300 (SH:- Widening of the road in km. 0/00 to 0/165)

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. p	Total Amount with all taxes including GST in Words
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, bindage and finishing of the road to specified dimensions or as directed by the Engineer-in-charge for smooth riding. The recovery of 274.12 cubic metre @ Rs. 300/- per cubic metre amounting to Rs. 82236/- only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1265.16	Per Cubic Meter	394.50	499106.00	Rupees Four Lakhs Ninety Nine Thousand One Hundred Six and Paise Zero Only
Total in Figures					499106.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words				Zero and Paise Zero Only		


Executive Engineer,
Karsog Division,
HPPMD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 199863
Earnest Money 4000
Time One Month

Name of Work:- Improvement of grade and removal of formation deficiency of Galoo to Mahroo road km 0/00 to 1/00 GP Kandha Tehsil Karsog Distt. Mandi (HP) (SH:- Widening of existing road and improvement of grade at various RDs between km 0/00 to 0/015 , 0/215 to 0/245 & 0/820 to 0/855) BSP/2023-940

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in charge for smooth riding. The recovery of 38.77 cubic metre @ Rs. 300/- per cubic metre amounting to Rs. 11631/- only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	801.80	Per Cubic Meter	249.27	199863.00	Rupees One Lakh Ninety Nine Thousand Eight Hundred Sixty Three and Paise Zero Only
Total in Figures					199863.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words			Zero and Paise Zero Only			


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost
Earnest Money
Time

264704
5300
One Month

Name of Work:- Construction of Sarkol Nallah to Pathron road km 0/00 to 1/00 (SH:- C/O 900 mm dia RCC Hume Pipe Culvert at RD 0/375)

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Excavation in soil in hilly area by mechanical mean including cutting and trimming of side slope and disposing of excavated earth with any lift and any lead as per technical specification clause 1603.1 as per direction of engineer in charge within in all lead and lift As per direction of Engineer-in- Charge including cartage of materials within all leads and lifts and other incidentals.	46.99	Per Cubic Meter	379.90	17852	Rupees Seventeen Thousand Eight Hundred Fifty One and Paise Fifty Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803 1202 and 1203 Nominal mix 1:6:12 (one cement: six sand: twelve graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including cartage of materials within in all lead and lifts and other incidentals As per direction of Engineer-in- Charge including cartage of materials within all leads and lifts and other incidentals.	2.17	Per Cubic Meter	5073.50	11009	Rupees Eleven Thousand Nine and Paise Forty Nine Only
3	Providing and laying concrete for plain/reinforced concrete 1:5:10 (one cement : five sand : ten graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802,803, 1202 and 1203 as per direction of Engineer-in-Charge including cartage of material within all leads and lifts and other incidentals.	30.22	Per Cubic Meter	5217.60	157676	Rupees One Lakh Fifty Seven Thousand Six Hundred Seventy Five and Paise Eighty Seven Only
4	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in double row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets as per clause 1106as per direction of Engineer-in-Charge within in all leads and lifts and other incidentals.	12.50	Per Running Meter	5437.60	67970	Rupees Sixty Seven Thousand Nine Hundred Seventy and Paise Zero Only
5	Providing and Laying filter media with granular crushed aggregate as per specification to a thickness of not less than 600mm(six hundred millimeter) with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specifications clause 1204.3.8 or as per direction of engineer in charge including cartage of materials within in all lead and lifts and other incidentals.	5.60	Per Cubic Meter	1289.00	7218	Rupees Seven Thousand Two Hundred Eighteen and Paise Forty Only
6	Providing weepholes in bricks masonry/stone masonry plain /reinforced concrete abutment wing wall,return wall with 100mm dia PVC pipe extending through the full with the structure with slope of 1(V): 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204.3.7 As per direction of Engineer-in- Charge including cartage of materials within all leads and lifts and other incidentals.	8.00	Each	372.40	2979	Rupees Two Thousand Nine Hundred Seventy Nine and Paise Twenty Only
Total in Figures					264704	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words						


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Scheduled Quantity

Estimated Cost
Earnest Money
Time

432822
8700
one Month

Name of Work:- R/R Damages on Chholdhar to Panaut dhahra road Km. 0/00 to 2/700 (SH:- C/O RWall at RD 2/608 to 2/619)

Sr. No.	Sub-Head and items of works.	Qty.	Rate		Unit	Amount
			in Figure	in words		
1	Earth work in excavation by mechanical means (Hydrolic excavator) manual means in foundation trenches of drains (not exceeding 1.5 mtrs in width 10sqm on plan)including dressing of sides and remaining of bottoms, lift upto 1.5 mtrs, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead 50mtrs as per direction of engineer in charge with in all lead and lifts and other incidentals.	52.20			Per Cubic Meter	
2	Providing and laying cement concrete 1:5:10 (one cement : five sand : ten graded stone aggregle 40 mm nominal size) curing complete including cost of form work in retaining walls, breast walls as per HPPWD specification clause 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	75.15			Per Cubic Meter	
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	17.40			Each	
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(v):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	12.00			nos	
Total Amount						


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Name of Work:- R/R Damages on Kelodhar to Chhatri road km. 0/00 to 19/00 under Karsog Sub-Division in Kelodhar Section (SH:- Removal of slips at various RDs from km. 0/00 to 10/00) **BC**

Deposited No. **72923451**

Estimated Cost **238650**
Earnest Money **4800**
Time **One Month**

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Removal of land slide slip clearance:- Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	1888.05	Per Cubic Meter	126.40	238650.00	Rupees Two Lakhs Thirty Eight Thousand Six Hundred Fifty and Paise Zero Only
Total in Figures					238650.00	
Quoted Rate in Figures					0.00	
Quoted Rate in Words			Select			
			Zero and Paise Zero Only			


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost
Earnest Money
Time

109315
2200
One Month

Name of Work:- R/R Damages on Kelodhar Sainj road km. 0/00 to 19/00 (SH:- C/O R/Wall at RD 12/085 to 12/088)

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. p	Total Amount with all taxes including GST in Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	6.71	Per Cubic Meter	379.90	2549	Rupees Two Thousand Five Hundred Forty Nine and Paise Twelve Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803 1202 and 1203 Nominal mix 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimeter) nominal size as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	18.45	Per Cubic Meter	5140.40	94840	Rupees Ninety Four Thousand Eight Hundred Forty and Paise Thirty Eight Only
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment,wing wall,return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1 (v):20 (H) towards drawing face complete as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	8.00	Each	371.75	2974	Rupees Two Thousand Nine Hundred Seventy Four and Paise Zero Only
4	Providing and Laying filter media with granular crushed aggregate as per specification to a thickness of not less than 600mm(six hundred millimeter) with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specifications clause 1204.3.8 or as per direction of engineer in charge including carriage of materials with in all lead and lifts and other incidentals.	6.48	Per Cubic Meter	1381.34	8951	Rupees Eight Thousand Nine Hundred Fifty One and Paise Eight Only
Total in Figures					109315	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words						


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 165000
Earnest Money 3300
Time One month

Name of Work:- Construction of Office Building for Subject Matter Specialist Horticulture at Karsog Dist. Mandi (H.P.) (Sub Head:- Providing and fixing Power Fire Extinguisher)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Providing and fixing power fire extinguisher (stored pressure type) capacity 9 kg (nine kilogram) ISI Marked conforming to ISI: 15683:2006, with IS 14609, ISI marked powder complete with squeeze grip release valve, discharge pipe locking arrangement ,pressure gauge , opration manual,braket with two screw and sleeve as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	15.00	Each	11000.00	165000	Rupees One Lakh Sixty Five Thousand and Paise Zero Only
Total in Figures					165000	
Quoted Rate in Figures						
Quoted Rate in Words			Select		0.00	


 Executive Engineer,
 Karsog Division,
 H.P.PWD, Karsog.

Percentage Schedule Of Quantity

Name of Work:- Balance work on Construction of SMS/HDO office building at Karsog, Tehsil Karsog Distt. Mandi HP (SH:- Providing and fixing 6mm thick pinewood panelling and ceiling clerk room 1 & 2)

Estimated Cost
Earnest Money
Time

434072

8700

One Month

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes	Total Amount with all taxes including GST in Words
1	Providing and fixing 6 mm (six millimeter) pinewood panelling of approved quality with butt jointing over 19 mm (nineteen millimeter) thick hard board and nails etc as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	95.55	Per Square Meter	1992.62	190395.00	Rupees One Lakh Ninety Thousand Three Hundred Ninety Five and Paise Zero Only
2	Providing and fixing 6 mm (six millimeter) thick pinewood ceiling of approved quality with butt jointing and nails etc over 19 mm (nineteen millimeter) thick hard board of 19mm thick including nuts and screw etc for ceiling support as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	21.00	Per Square Meter	2059.67	43253.00	Rupees Forty Three Thousand Two Hundred Fifty Three and Paise Zero Only
3	Providing and fixing plain square edged cover fillets (beading) 40mm x4mm (forty millimeter into four millimeter) section with wood screws in ceiling and lining including mitring at junction as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals	112.20	Per Running Meter	463.20	51971.00	Rupees Fifty One Thousand Nine Hundred Seventy One and Paise Zero Only
4	Varnishing two coats (excluding priming coat) on new wood and wood based surfaces, under coating, with flattening varnish and finishing coat with varnish to give an even surface including cleaning the surfaces of all dirt, dust and sand papering so as to produce a smooth, dry and matt surface as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals	116.55	Per Square Meter	774.98	90324.00	Rupees Ninety Thousand Three Hundred Twenty Four and Paise Zero Only
5	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately) as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	0.70	Per Cubic Meter	83042.00	58129.00	Rupees Fifty Eight Thousand One Hundred Twenty Nine and Paise Zero Only
Total in Figures					434072	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words			Zero and Paise Zero Only			


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 497089
Earnest Money 10000
Time One Month

Name of Work:- Balance work on Construction of SMS/HDO office building at Karsog, Tehsil Karsog Distt. Mandi HP (Sh:- Providing and fixing 6mm thick pinewood panelling and ceiling on Record room, HEO & SMS building)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes	Total Amount with all taxes including GST In Words
1	Providing and fixing 6 mm (six millimeter) pinewood panelling of approved quality with butt jointing over 19 mm (nineteen millimeter) thick hard board and nails etc as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	109.40	Per Square Meter	1992.62	217993.00	Rupees Two Lakhs Seventeen Thousand Nine Hundred Ninety Three and Paise Zero Only
2	Providing and fixing 6 mm (six millimeter) thick pinewood ceiling of approved quality with butt jointing and nails etc over 19 mm (nineteen millimeter) thick hard board of 19mm thick including nuts and screw etc for ceiling support as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	36.75	Per Square Meter	2059.67	75693.00	Rupees Seventy Five Thousand Six Hundred Ninety Three and Paise Zero Only
3	Providing and fixing plain square edged cover fillets (beading) 40mm x4mm (forty millimeter into four millimeter) section with wood screws in ceiling and lining including mitring at junction as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals	96.00	Per Running Meter	463.20	44467.00	Rupees Forty Four Thousand Four Hundred Sixty Seven and Paise Zero Only
4	Varnishing two coats (excluding priming coat) on new wood and wood based surfaces, under coating, with flattening varnish and finishing coat with varnish to give an even surface including cleaning the surfaces of all dirt, dust and sand papering so as to produce a smooth, dry and matt surface as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals	146.15	Per Square Meter	774.98	113263.00	Rupees One Lakh Thirteen Thousand Two Hundred Sixty Three and Paise Zero Only
5	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately) as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	0.55	Per Cubic Meter	83042.00	45673.00	Rupees Forty Five Thousand Six Hundred Seventy Three and Paise Zero Only
Total in Figures					497089	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words			Zero and Paise Zero Only			


 Executive Engineer,
 Karsog Division,
 APPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 467171
Earnest Money 9400
Time One Month

Name of Work:- Balance work on Construction of SMS/HDO office building at Karsog, Tehsil Karsog Distt. Mandi HP (SH:- Providing and laying stone soling & Kotla stone Flooring)

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes	Total Amount with all taxes including GST in Words
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, any lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, within any lead as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	99.75	Per Cubic Meter	212.75	21222.00	Rupees Twenty One Thousand Two Hundred Twenty Two and Paise Zero Only
2	Boulder filling dry hand packed tightly as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	27.75	Per Cubic Meter	1500.68	41644.00	Rupees Forty One Thousand Six Hundred Forty Four and Paise Zero Only
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:6:12 (one cement : six coarse sand: twelve graded stone aggregate) 20 mm (twenty millimeter) nominal size) as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	13.88	Per Cubic Meter	5071.00	70385.00	Rupees Seventy Thousand Three Hundred Eighty Five and Paise Zero Only
4	Kota stone slab flooring over 20 mm (twenty millimeter) (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (one cement : four coarse sand) as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	205.00	Per Square Meter	1628.88	333920.00	Rupees Three Lakhs Thirty Three Thousand Nine Hundred Twenty and Paise Zero Only
Total in Figures					467171	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words		Zero and Paise Zero Only				


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost
Earnest Money
Time
335725
6800
One Month

Name of Work:- Balance work on Construction of SMS/HDO office building at Karsog, Tehsil Karsog Distt. Mandi HP (SH:- Providing and fixing 6mm thick pinewood panelling and ceiling HDO Block 1 & 2)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes	Total Amount with all taxes including GST in Words
1	Providing and fixing 6 mm (six millimeter) pinewood panelling of approved quality with butt jointing over 19 mm (nineteen millimeter) thick hard board and nails etc as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	68.37	Per Square Meter	1992.62	136235.00	Rupees One Lakh Thirty Six Thousand Two Hundred Thirty Five and Paise Zero Only
2	Providing and fixing 6 mm (six millimeter) thick pinewood ceiling of approved quality with butt jointing and nails etc over 19 mm (nineteen millimeter) thick hard board of 19mm thick including nuts and screw etc for ceiling support as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	21.00	Per Square Meter	2059.67	43253.00	Rupees Forty Three Thousand Two Hundred Fifty Three and Paise Zero Only
3	Providing and fixing plain square edged cover fillets (beading) 40mm x4mm (forty millimeter into four millimeter) section with wood screws in ceiling and lining including mitring at junction as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals	82.00	Per Running Meter	463.20	37982.00	Rupees Thirty Seven Thousand Nine Hundred Eighty Two and Paise Zero Only
4	Varnishing two coats (excluding priming coat) on new wood and wood based surfaces, under coating with flattening varnish and finishing coat with varnish to give an even surface including cleaning the surfaces of all dirt, dust and sand papering so as to produce a smooth, dry and matt surface as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals	89.37	Per Square Meter	774.98	69260.00	Rupees Sixty Nine Thousand Two Hundred Sixty and Paise Zero Only
5	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately) as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	0.59	Per Cubic Meter	83042.00	48995.00	Rupees Forty Eight Thousand Nine Hundred Ninety Five and Paise Zero Only
Total in Figures					335725	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words			Zero and Paise Zero Only			


Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost
Earnest Money
Time
168602
3400
One Month

Name of Work:- Repair and maintenance of road from Dev Dwahli to Naini via Khola Nal Syanjali Jhurjuru Kerta and various roads Kelodahr Section in Karsog Division (SH:-
Maintenance of earthen shoulders, removal of land slide slips at various RD's) BSP/2023/941

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes	Total Amount with all taxes including GST In Words
1	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	2277.00	Per Square Meter	32.75	74572.00	Rupees Seventy Four Thousand Five Hundred Seventy Two and Paise Zero Only
2	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	567.47	Per Cubic Meter	165.70	94030.00	Rupees Ninety Four Thousand Thirty and Paise Zero Only
Total in Figures					168602.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words				Zero and Paise Zero Only		


 Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost
Earnest Money

169247
3400

Time

One Month

Name of Work:- Repair and maintenance of road from Mamla to Galu road under Kelodahr Section in Sub Division Karsog (SH:- Maintenance of earthen shoulders, removal of land slide slips at various RD's) Deposit work

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes	Total Amount with all taxes including GST In Words
1	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	2415.00	Per Square Meter	32.75	79091.00	Rupees Seventy Nine Thousand Ninety One and Paise Zero Only
2	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	544.09	Per Cubic Meter	165.70	90156.00	Rupees Ninety Thousand One Hundred Fifty Six and Paise Zero Only
Total in Figures					169247.00	
Quoted Rate in Figures			Select			
Quoted Rate in Words			Zero and Paise Zero Only			
					0.00	


 Executive Engineer,
 Karsog Division,
 HRPWD, Karsog.

D.N.I.T / SCHEDULE OF QUANTITY

Estimated Cost Rs :-152000/-
Earnest money:-3000/-

Time :- 26 Days

Name of Work :- R.R. Damages on Khadargali Somakothi Road Km 0/0 to 5/540 and Thakurthana Delog Road Km 0/0 to 7/100 (SH.:- Hiring of Tipper for disposal/carriage of Material) Section Katanda

S.No.	Description of Item.	Qty.	Rate.		Unit.	Amount
			In figure	In Words		
1.	Hiring of Tipper on daily wages basis for carriage of materials le. Aggregate, stone, mud etc. up to any leads and lifts and as per direction of Engineer-in-Charge to Tipper should work 8 Hours daily. Any loss of public property and accident etc. The contractor is fully responsible during the execution of work the fuel and operation staff for the Tipper will be provided by the owner. The repair charges of machinery during the execution of work will be Borne by the owner. The useful material shall be stacked along the road side and as per the direction of Engineer-in-Charge.	40 Days			Per day.	
Total						


Karsog Division
Executive Engineer
HPPWD K.