


HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT (B&R) DIVISION KOTKHAHAI



H.P.PWD TENDERS

Sealed percentage rate tenders on form No. 6 are invited by the Executive Engineer, Kotkhai Division, HPPWD: Kotkhai for the following works from the approved and eligible contractors enlisted in HP:PWD, so as to reach in his office on or **before 07-02-2024 upto 11:00 A.M. and will be opened on the same day at 12:00 noon**, in the presence of the intending contractors or their authorized representatives. The tender forms can be had from his office against cash payment on **06-02-2024 upto 10:30 A.M. to 3:30 P.M.** The earnest money in the shape of National Saving Certificate / Time deposit account / saving bank account / FDR in any of the Post Office in Himachal Pradesh duly pledged in the name of the undersigned must accompany with each tenders. The tender form will be issued on contractor giving proof of enlistment, GST. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 10 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors in the office of the undersigned on any working day during the office hours.

Job No.	Name of Work	Estimated Cost	Earnest Money	Cost of Tender	Time	Eligible class of Contractor
1.	R/R Damages on Link road Marathu Tharolla Road to Govt. Sr. Sec. School, Tharolla Panchyat Ghar in K.M. 0/00 to 0/645 (SH:-C/o, R/Wall at R.D. 0/005 to 0/014.80)	Rs. 4,92,760/-	Rs. 9900/-	Rs. 350/-	Two Months	Class D & Class C
2.	C/O Link Road Raj Darbar to Kharapather via Balog Mohal Km 0/00 to 1/680 (SH:- Formation cutting 5/7 meter in Km 0/00 to 0/210)	Rs. 4,88,642/-	Rs. 9,800/-	Rs. 350/-	Two Months	Class D & Class C
3.	C/O Link Road from Chaithla road to sanot 18 Bawri road 0/00 to 1/500 (SH:- F/C 5/7 meter in km 0/00 to 0/165)	Rs. 4,63,638/-	Rs.9,300 /-	Rs. 350/-	Two Months	Class D & Class C
4.	C/o link road from Santiban to Goyal Road 0/00 to 1/093 (SH:- F/C 5/7 mtr in Km 0/00 to 0/210)	Rs. 4,24,110/-	Rs.8,500 /-	Rs. 350/-	Two Months	Class D & Class C
5.	Improvement of Majholi link road km 0/00 to 0/500 (SH:- C/o R/wall at RD 0/00 to 0/015 and PCC edging at 0/075 to 0/090)	Rs. 4,96,181/-	Rs. 10,000/-	Rs. 350/-	Two Months	Class D & Class C
6.	Improvement of Bamtari link Road Km 0/00 to 0/600 (SH:- C/o R/wall at RD 0/190 to 0/200, 0/250 to 0/252.50)	Rs. 2,95,667/-	Rs.6,000 /-	Rs. 350/-	Two Months	Class D & Class C
7.	Improvement of Bamtari link Road Km 0/00 to 0/600 (SH:- C/o Wire crate B/wall at RD 0/270 to 0/290)	Rs. 2,06,508/-	Rs.4,200 /-	Rs. 350/-	Two Months	Class D & Class C

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT (B&R) DIVISION KOTKHAHAI

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT (B&R) DIVISION KOTKHAI

8.	R/R Damages on Bantoth Link Road Km 0/00 to 1/00 (SH:- C/o R/wall and B/wall at Various Rd's)	Rs. 4,83,170/-	Rs.9,700 /-	Rs. 350/-	Two Months	Class D & Class C
9.	A/R & M/O FRU Building of Hospital at Kotkhai Distt. Shimla. (SH:- Repair Work)	Rs. 4,95,001/-	Rs.9,900 /-	Rs. 350/-	Two Months	Class D & Class C
10.	C/O Link Road Shwal Nalla to Jhrani Km 0/00 to 0/750 (SH:- Formation cutting 5/7 meter in Km 0/00 to 0/105)	Rs. 4,73,689/-	Rs. 9,500/-	Rs. 350/-	Two Months	Class D & Class C
11.	R/R Damages on Devgarh Beon road km 0/00 to 7/885 (SH:- C/o R/wall at Rd 2/320 to 2/340)	Rs. 4,52,869/-	Rs. 9,100/-	Rs. 350/-	Two Months	Class D & Class C
12.	R/R Damages on link road from Dharonk kanchi to Sherdoli via Bandli road km 0/00 to 5/00 (SH:- C/o R/wall at Rd 1/160 to 1/170 & 1/270 to 1/281)	Rs. 4,51,754/-	Rs.9,100/-	Rs. 350/-	Two Months	Class D & Class C
13.	C/o Gazta Joney Gareog Nihari Road Km 0/0 to 16/00 (SH:- C/o Culvert at RD 5/030 with wing wall)	Rs. 2,41,811/-	Rs. 4,900/-	Rs. 350/-	Two Months	Class D & Class C
14.	R/R Damages on Ghunda Talka road km 0/00 to 2/300 (SH:- R/wall at Rd 0/937 to 0/947)	Rs. 4,17,713/-	Rs. 8,400/-	Rs. 350/-	Two Months	Class D & Class C
15.	R/R Damages on Bareonghat to bareon link road km 0/00 to 1/930 (SH:- C/o R/wall at RD 1/300 to 1/312)	Rs. 2,99,534/-	Rs.6,000 /-	Rs. 350/-	Two Months	Class D & Class C
16.	R/R damages on link road Saintari Km 0/00 to 0/315 (SH:- C/o R/wall at RD 0/010 to 0/017.50 & 0/128 to 0/135.50)	Rs. 4,07,027/-	Rs. 8,200/-	Rs. 350/-	Two Months	Class D & Class C
17.	R/R Damages on Chhol to Kotkhai Bazar road Km 0/00 to 1/600 (SH:- C/o R/wall at RD 0/585 to 0/600)	Rs. 4,87,043/-	Rs.9,800 /-	Rs. 350/-	Two Months	Class D & Class C
18.	R/R Damages on Gumma Jashla Reoghati road Km 0/00 to 29/600 (SH:- C/o R/wall at RD 10/560 to 10/570)	Rs. 4,66,271/-	Rs.9,400 /-	Rs. 350/-	Two Months	Class D & Class C
19.	R/R Damages on Gazta Darkoti Jandoli road km 0/00 to 6/300 (SH:- C/o R/wall at Rd 2/780 to 2/787.60 and 3/255 to 3/232.50)	Rs. 4,54,182/-	Rs.9,100 /-	Rs. 350/-	Two Months	Class D & Class C
20.	R/R Damages on Kua jubbar Shakrala road km 0/00 to 1/740 (SH:- C/o R/wall at RD 1/720 to 1/740)	Rs. 4,23,598/-	Rs.8,500 /-	Rs. 350/-	Two Months	Class D & Class C
21.	R/R Damages on Kotkhai Deori Khanety Deorighat km 0/00 to 22/00 (SH:- C/o R/wall at RD 4/866 to 4/878)	Rs. 4,40,373/-	Rs.8,900 /-	Rs. 350/-	Two Months	Class D & Class C
22.	R/R Damages on Marathu Tharolla Tahu Km 0/00 to 17/100 (SH:- C/o R/wall at RD 0/791 to 0/800)	Rs. 4,62,808/-	Rs.9,300 /-	Rs. 350/-	Two Months	Class D & Class C
23.	R/R Damages on Chol Badrooni Gehrog Bari road Km 0/00 to 3/375 (SH:- C/o R/wall at Rd 2/315 to 2/329)	Rs. 4,85,996/-	Rs.9,800 /-	Rs. 350/-	Two Months	Class D & Class C
24.	R/R Damages on link road from Dharonk Kanchi to Sheroli via Bandli road Km 0/00 to 7/00 (SH:- C/o R/wall at RD 5/585 to 5/605)	Rs. 4,96,998/-	Rs.10,000/-	Rs. 350/-	Two Months	Class D & Class C

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT (B&R) DIVISION KOTKHAI

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT (B&R) DIVISION KOTKHAI

25.	R/R Damages on Koku Nalla Dharonk road km 0/00 to 8/500 (SH:- C/o R/wall at Rd 1/031.5 to 1/035.25)	Rs. 2,03,641/-	Rs.4,100/-	Rs. 350/-	Two Months	Class D & Class C
26.	R/R Damages on Devgarh Beon road Km 0/00 to 7/885 (SH:- B/Wall at RD 4/765 to 4/795)	Rs. 4,04,529/-	Rs.8,100/-	Rs. 350/-	Two Months	Class D & Class C
27.	R/R Damages on Kotla Pali road km 0/00 to 3/300 (SH:- C/o B/wall at RD 3/035 to 3/065)	Rs. 4,93,293/-	Rs.9,900/-	Rs. 350/-	Two Months	Class D & Class C
28.	R/R Damages on Ghunda Talka road km 0/00 to 2/300 (SH:- R/wall at Rd 0/990 to 1/00)	Rs. 4,17,713/-	Rs.8,400/-	Rs. 350/-	Two Months	Class D & Class C
29.	R/R Damages on Barvi Garaog road Km 0/00 to 7/00 (SH:- C/o B/wall at RD 2/325 to 2/333 & R/wall at Rd 2/320 to 2/335)	Rs. 4,90,258/-	Rs.9,900/-	Rs. 350/-	Two Months	Class D & Class C
30.	R/R Damages on Kiari Bhalidhar road km 0/00 to 4/500 (SH:- C/o R/wall at Rd 3/175 to 3/187)	Rs. 4,29,804/-	Rs.8,600/-	Rs. 350/-	Two Months	Class D & Class C
31.	R/R Damages on Ghasigaon Dhanroti Purag road km 0/00 to 3/390 (SH:- PCC R/wall at RD Km 2/875 to 2/885 and B/wall at 0/718 to 0/735)	Rs. 4,06,502/-	Rs.8,200/-	Rs. 350/-	Two Months	Class D & Class C
32.	R/R Damages on Ghasigaon Dhanroti road km 0/00 to 3/300 (SH:- C/o R/wall at Rd Km 0/705 to 0/715)	Rs. 3,33,015/-	Rs.6,700/-	Rs. 350/-	Two Months	Class D & Class C
33.	R/R Damages on Himri Valley road Km 0/00 to 17/400 (SH:- C/o R/wall at RD 17/096 to 17/105 and 17/243 to 17/250)	Rs. 4,90,224/-	Rs.9,900/-	Rs. 350/-	Two Months	Class D & Class C
34.	R/R Damages on Reog Link road in K.M.0/00 to 4/900 (SH:- C/o, R/Wall at R.D. 4/660 to 4/673, 4/420 to 4/435)	Rs. 4,69,807/-	Rs. 9400/-	Rs. 350/-	Two Months	Class D & Class C
35.	R/R Damages on Reog Link road in K.M. 0/00 to 4/900 (SH:- C/o, R/Wall at R.D. 4/840 to 4/850, 4/455 to 4/470)	Rs. 4,52,850/-	Rs. 9100/-	Rs. 350/-	Two Months	Class D & Class C
36.	R/R Damages on Reog link road in K.M. 0/00 to 4/900 (SH:-C/o, R/Wall at R.D. 4/405 to 4/420)	Rs. 2,91,575/-	Rs. 5900/-	Rs. 350/-	Two Months	Class D & Class C
37.	R/R Damages on Sholvi Dalsar Hatli Road in K.M. 0/00 to 4/675 (SH:- C/o, R/Wall at R.D. 0/070 to 0/080)	Rs. 3,34,278/-	Rs. 6700/-	Rs. 350/-	Two Months	Class D & Class C
38.	C/o Link road Shawal Nallah Bauti Jubbar Road in K.M. 0/00 to 0/540 (SH:- Formation Cutting in 5/7 mtr road in K.M. 0/00 to 0/200)	Rs. 4,91,540/-	Rs. 9900/-	Rs. 350/-	Two Months	Class D & Class C
39.	C/o Link road Khaneti Barnog Bag Road in K.M. 0/00 to 0/075 (SH:- Formation cutting in 5/7 mtr. wide road in K.M. 0/00 to 0/075)	Rs. 3,18,784/-	Rs. 6400/-	Rs. 350/-	Two Months	Class D & Class C
40.	C/o Bari Gahrog Sarandhar Road in K.M. 0/00 to 1/185 (SH:- C/o 5/7 mtr. wide road in K.m. 0/915 to 1/180)	Rs. 4,04,790/-	Rs. 8100/-	Rs. 350/-	Two Months	Class D & Class C
41.	M/T on Kahnog to Nagan Road in K.M. 0/00 to 0/600 (SH:- providing laying GSB road in K.M.. 0/00 to 0/600)	Rs. 4,72,712/-	Rs. 9500/-	Rs. 350/-	Two Months	Class D & Class C

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT (B&R) DIVISION KOTKHAI



HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT (B&R) DIVISION KOTKHAJ

42.	R/R Damages on pali Kotla Road in K.M. 0/00 to 3/00 (SH:- C/o. R/Wall at R.D. 0/290 to 0/309.50)	Rs. 4,99,794/-	Rs. 10,000/-	Rs. 350/-	Two Months	Class D & Class C
43.	R/R Damages on Reog link road in K.M. 0/00 to 5/00 (SH:- C/o R/Wall at R.D. 3/960 to 3/978)	Rs. 4,24,784/-	Rs. 8500/-	Rs. 350/-	Two Months	Class D & Class C
44.	R/R Damages on Badroonighati to Badrooni Road in K.M. 0/00 to 2/995 (SH:- C/o. R/Walla t R.D. 0/005 to 1/020)	Rs. 3,56,982/-	Rs. 7200/-	Rs. 350/-	Two Months	Class D & Class C

Certified that tender of above works are being called of emergent nature in exigency of public interest.

Terms and Conditions: -

1. The contractor should produce a copy of enlistment / renewal letter at time of application.
2. Executive Engineer reserves the right to reject / cancel any or all the tenders without assigning any reasons.
3. The contractor / firm shall have his registration and GST No., the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Division Kotkhaj, HPPWD Kotkhaj and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The applications received without earnest money and cost of tender form shall be similarly rejected.
5. The contractor / firms are requested to insert the rate of each item in words as in figures failing which XEN reserves the rights to accept / reject any tender without assigning any reasons at any stage.
6. The tender shall be issued to those contractors who have not more than three works in hand.
7. If any date mentioned above happens to be a holiday, the same will be processed on the next day.

Executive Engineer,
(B&R) Division, HPPWD,
Kotkhaj.

Dated:- 23/01/2024

No:- PW-KD-E-Tender/2023-24:- 7014-21

Copy forwarded to the following for information and necessary action to:-

1. The Chief Engineer (SZ), HPPWD, Nirman Bhawan, Nigam Vihar, Shimla-II.
2. The Superintending Engineer, 14th Circle, HPPWD Rohru.
3. The Director, Information and Public Relations, Suchna Avam Jan Sampark Bhawan, Near H.P. Administrative Tribunal, Shimla, through iproams.himachalpr.gov.in for publishing in the weekly as well as daily leading news papers / Giri Raj both in Hindi /English as per status of the tenders in pursuance to the standing instruction.
4. The Executive Engineer (IT) O/o Engineer-in-Chief HPPWD Shimla through email-eeict-pwd-shi@hp.gov.in & cc-pwd-hp@nic.in for uploading the same on HPPWD web portal.
5. All the Assistant Engineer working under this Division.
6. Drawing Branch in this office.
7. Notice Board.

Executive Engineer,
(B&R) Division, HPPWD,
Kotkhaj.

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT (B&R) DIVISION KOTKHAJ



SCHEDULE OF QUANTITY

Job No 1

Estimated cost:- 492760.00
Earnest money:- 9900.00
Time:- Two Month

Name of Work :R/R Damages On link road Marathu Tharolla road to Govt.Sr.Sec School Tharolla Panchyat Ghar Tharolla Km 0/00 to 0/645 (SH:- C/o R/wall at RD 0/05 to 0/014.80)

Sr.No	Description of Items	Qty.	Unit	Rates i/c GST & all taxes		Amount.
				Rate (in figure)	Rate (in words)	
1	Excavation in Hill area by manual/mechanical means:- Excavation in soil in hill areas all heights and depth in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiselling and wedging out rock (where blasting is prohibited) including cutting and trimming of side slopes and disposing of excavated earth with a lift upto all heights and all leads as directed by the Engineer-in-Charge, in conformately with the requirement of technical specification of rural roads clause 1603.1 all useful material such as stone, shingle, aggregates & slate etc. shall be sorted out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	38.03	Per Cubic metre.	195.95	Rupees One Hundred NinetyFive Paise NinetyFive Only	7452
2	Earth work in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads, dressing of sides and bottom and back filling in trenches with excavated suitable material in ordinary soil upto all depth, as directed by the Engineer-in-Charge. all useful material such as stone, shingle, aggregates & slate etc. shall be sorted out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	50.03	Per Cubic metre.	489.20	Rupees Four Hundred EightyNine Paise Twenty Only	24475
3	Providing & making Gabion structure with mechanically woven Double Twisted Hexagonal Shaped Wire mesh Gabion Boxes as per IS 16014:2012, MORTH Clause 2500, of required size, Mesh Type 10x12 (D=100mm with tolerance of = 2%) Zinc+coated, Mesh wire diameter 2.7/3.7mm, Mechanically edged/selvedged with partitions at every 1 m interval and shall have minimum 10 numbers of openings per meter of mesh perpendicular to twist, tying with lacing wire of diameter 2.2/3.2mm (ID/OD), supplied @ 3% by weight of Gabion boxes, filled with boulders with least dimension of 200 mm, as per drawing, all complete as per direction of Engineer-in-charge.	137.81	Per Cubic metre.	3210.20	Rupees Three Thousand Two Hundred Ten Paise Twenty Only	442398
4	Backfilling /Filter media with granular material behind retaining wall/breast wall as per specification 1204.3.8 in a width of 600 mm. including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	13.48	Per Cubic metre.	1367.60	Rupees One Thousand Three Hundred SixtySeven Paise Sixty Only	18435
Total in Figures						492760
Rate quoted by contractor +/-				Percent		
Quoted rate in figure						
Quoted rate in words						

Executive Engineer,
Kotkhai Division (B&R)
H.P.PWD, Kotkhai.

SCHEDULE OF QUANTITY

Estimated cost:-

488642.00

Earnest money:-

9800.00

Time:-

Two month

Name of work:- C/O Link Road Raj Darbar to Kharapather via Balog Mohal Km 0/00 to 1/680 (SH;- Formation cutting 5/7 meter in Km 0/00 to 0/210)

Sr.No	Description of items	Qty.	Unit	Rates i/c GST & all taxes		Amount.
				Rate (in figure)	Rate (in words)	
1	Cutting in earth work in all heights and all kinds of soils such as spade work, pick work, jumper work, blastingwork, soft rock, hard rock chiseling work and wedging out of rocks where blasting is prohibited including their intermediate classification of soil including saturated soil and disposal of all excavated unserviceable material all leads and lifts to avoid damages to the properties of the public and Govt. and any case damages takes place the contractor is liable for it. All useful material/stones available from blasting/chiseling shall be property of department and minimum 294.07 Cum stones available from blasting shall have neatly stacked at suitable place as directed by the Engineer-in-Charge. Otherwise recovery @ 300/- per cubic meter shall be effected from the bill of the contractor. The road 5/7 meter wide 5 meter in straight and 7 meter in curves.	1633.72	Per Cubic metre.	299.10	Rupees Two Hundred NinetyNine Paise Ten Only	488642
	Total in Figures					488642
	Rate quoted by contractor +/-			Percent		
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Kotkhai Division (B&R)
P.PWD, Kotkhai.

SCHEDULE OF QUANTITY

Job No 3

Estimated cost:-
Earnest money:-
Time:-

463638.00
9300.00
Two month

Name of work:- C/O Link Road from Chaithla road to sanot 18 Bawri road 0/00 to 1/500 (SH;- F/C 5/7 meter in km 0/00 to 0/165)

Sr.No	Description of items	Qty.	Unit	Rates i/c GST & all taxes		Amount.
				Rate (in figure)	Rate (in words)	
1	Cutting in earth work in all heights and all kinds of soils such as spade work, pick work, jumper work, blastingwork, soft rock, hard rock chiseling work and wedging out of rocks where blasting is prohibited including their intermediate classification of soil including saturated soil and disposal of all excavated unserviceable material all leads and lifts to avoid damages to the properties of the public and Govt. and any case damages takes place the contractor is liable for it. All useful material/stones available from blasting/chiseling shall be property of department and minimum 267.64 Cum stones available from blasting shall have neatly stacked at suitable place as directed by the Engineer-in-Charge. Otherwise recovery @ 300/- per cubic meter shall be effected from the bill of the contractor. The road 5/7 meter wide 5 meter in straight and 7 meter in curves.	1958.32	Per Cubic metre.	236.75	Rupees Two Hundred ThirtySix Paise SeventyFive Only	463638
	Total in Figures					463638
	Rate quoted by contractor +/-			Percent		
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Kotkhai Division (B&R)
H.P.W.D, Kotkhai.

SCHEDULE OF QUANTITY

Job No 4

Estimated cost:-
Earnest money:-
Time:-

424110.00
8500.00
Two month

Name of work:- C/o link road from Santiban to Goyal Road 0/00 to 1/093 (SH:- F/C 5/7 mtr in Km 0/00 to 0/210)

Sr.No	Description of items	Qty.	Unit	Rates i/c GST & all taxes		Amount.
				Rate (in figure)	Rate (in words)	
1	Cutting in earth work in all heights and all kinds of soils such as spade work, pick work, jumper work, blastingwork, soft rock, hard rock chiseling work and wedging out of rocks where blasting is prohibited including their intermediate classification of soil including saturated soil and disposal of all excavated unserviceable material all leads and lifts to avoid damages to the properties of the public and Govt. and any case damages takes place the contractor is liable for it. All useful material/stones available from blasting/chiseling shall be property of department and minimum 244.82 Cum stones available from blasting shall have neatly stacked at suitable place as directed by the Engineer-in-Charge. Otherwise recovery @ 300/- per cubic meter shall be effected from the bill of the contractor. The road 5/7 meter wide 5 meter in straight and 7 meter in curves.	1791.36	Per Cubic metre.	236.75	Rupees Two Hundred ThirtySix Paise SeventyFive Only	424110
	Total in Figures					424110
	Quoted rate by contractor +/-			Percent		
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Kodhai Division (B&R)
P.P.W.D., Kodhai.

SCHEDULE OF QUANTITY

Job No 5

Estimated cost:- 496181.00
Earnest money:- 10000.00
Time:- Two Month

Name of Work :-Improvement of Majholi link road km 0/00 to 0/500 (SH:- C/o R/wall at RD 0/00 to 0/015 and PCC edging at 0/075 to 0/090)

Sr.No	Description of items	Qty.	Unit	Rates i/c GST & all taxes		Amount.
				Rate (in figure)	Rate (in words)	
1	Earth work in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads , dressing of sides and bottom and back filling in trenches with excavated suitable material in ordinary soil upto all depth. as directed by the Engineer-in-Charge.all useful material such as stone, shingle, aggregates& slate etc. shall be sorted out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absoulte responsibility of the contractor which shall have to be duly compensated by him in all cases.	158.70	Per Cubic metre.	489.20	Rupees Four Hundred EightyNine Paise Twenty Only	77636
2	Providing and laying cement concrete 1:6:12 (1 cement:6 sand : 12 graded stone 40mm agregate nominal size) for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803, 1202 and 1203.including the cost of form work and hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	9.59	Per Cubic metre.	4805.90	Rupees Four Thousand Eight Hundred Five Paise Ninety Only	46089
3	Providing and laying in position cement concrete of specified grade including the cost of form work in R/walls 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 25 mm nominal size)including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	29.95	Per Cubic metre.	5274.95	Rupees Five Thousand Two Hundred SeventyFour Paise NinetyFive Only	157985
4	Random rubble masonry Stone masonry work in cement mortar in foundation complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203 with randum rubble masonry in cement mortar 1:6 (1 cement :6 sand) . including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	27.63	Per Cubic metre.	4602.90	Rupees Four Thousand Six Hundred Two Paise Ninety Only	127178
5	Construction of dry rubble masonry for retaining walls, breast walls , revetment walls and parapets etc for substructure and superstructure complete as per drawings and technical specifications Clause 704.6& 1302.5 including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	24.96	Per Cubic metre.	2968.80	Rupees Two Thousand Nine Hundred SixtyEight Paise Eighty Only	74101
6	Backfilling /Filter media with granular material behind retaining wall/breast wall as per specification 1204.3.8 in a width of 600 mm. including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	5.40	Per Cubic metre.	1367.60	Rupees One Thousand Three Hundred SixtySeven Paise Sixty Only	7385

7	Providing weep holes in brick/ stone / plain reinforced concrete abutment, wing wall, return walls with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1V : 20H towards drawing face complete as per drawing and technical specifications clauses 614, 709 and 1204.3.7 including carriage of material within all leads and lifts and other incidentals. including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	15.00	Each	387.10	Rupees Three Hundred EightySeven Paise Ten Only	5807.00
	Total in Figures					496181
	Rate quoted by contractor +/-			Percent		
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Kotkhai Division (B&R)
HP.PWD, Kotkhai.

SCHEDULE OF QUANTITY

Job No 6

Estimated cost:- 295667.00
Earnest money:- 6000.00
Time:- Two Month

Name of Work :- Improvement of Bamtari link Road Km 0/00 to 0/600 (SH:- C/o R/wall at RD 0/190 to 0/200, 0/250 to 0/252.50)

Sr.No	Description of items	Qty.	Unit	Rates i/c GST & all taxes		Amount.
				Rate (in figure)	Rate (in words)	
1	Earth work in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads, dressing of sides and bottom and back filling in trenches with excavated suitable material in ordinary soil upto all depth, as directed by the Engineer-in-Charge.all useful material such as stone, shingle, aggregates& slate etc. shall be sorted out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	22.50	Per Cubic metre.	489.20	Rupees Four Hundred EightyNine Paise Twenty Only	11007
2	Providing and laying cement concrete 1:6:12 (1 cement:6 sand : 12 graded stone 40mm aggregate nominal size) for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803, 1202 and 1203 including the cost of form work and hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	4.50	Per Cubic metre.	4805.90	Rupees Four Thousand Eight Hundred Five Paise Ninety Only	21627
3	Providing and laying in position cement concrete of specified grade including the cost of form work in R/walls 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	5.43	Per Cubic metre.	5274.95	Rupees Five Thousand Two Hundred SeventyFour Paise NinetyFive Only	28643
4	Stone masonry work in cement mortar in foundation complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203 with random rubble masonry in cement mortar 1:6 (1 cement :6 sand) . including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	18.60	Per Cubic metre.	4602.90	Rupees Four Thousand Six Hundred Two Paise Ninety Only	85614
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc for substructure and superstructure complete as per drawings and technical specifications Clause 704.6& 1302.5 including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	44.9	Per Cubic metre.	3019.00	Rupees Three Thousand Nineteen Only	135674
6	Backfilling /Filter media with granular material behind retaining wall/breast wall as per specification 1204.3.8 in a width of 600 mm. including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	6.75	Per Cubic metre.	1367.60	Rupees One Thousand Three Hundred SixtySeven Paise Sixty Only	9231

7	Providing weep holes in brick/ stone / plain reinforced concrete abutment, wing wall, return walls with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1V : 20H towards drawing face complete as per drawing and technical specifications clauses 614, 709 and 1204.3.7 including carriage of material within all leads and lifts and other incidentals, including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	10.00	Each	387.10	Rupees Three Hundred EightySeven Paise Ten Only	3871
	Total In Figures					
	Quoted rate in figure			Percent		295667
	Quoted rate in words					

Executive Engineer,
Kotkhal Division (B&R)
AP.PWD, Kotkhal.

SCHEDULE OF QUANTITY

Job No 7

Estimated cost:-
Earnest money:-
Time:-

206508.00
4200.00
Two Month

Name of Work :- Improvement of Bamtari link Road Km 0/00 to 0/600 (SH:- C/o Wire crate B/wall at RD 0/270 to 0/290)

Sr.No	Description of items	Qty.	Unit	Rates i/c GST & all taxes		Amount.
				Rate (in figure)	Rate (in words)	
1	Earth work in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads , dressing of sides and bottom and back filling in trenches with excavated suitable material in ordinary soil upto all depth. as directed by the Engineer-in-Charge.all useful material such as stone, shingle, aggregates& slate etc. shall be sorted out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absoulte responsibility of the contractor which shall have to be duly compensated by him in all cases.	12.00	Per Cubic metre.	489.20	Rupees Four Hundred EightyNine Paise Twenty Only	5870
2	Providing and laying boulder apron laid in wire crates mate with G.I.wire confirming to IS :280 & IS 4826 in 100mmx100mm mesh (weaved diagonally including 10% extra for laps and joints laid with stone boulder weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 including the cost form work and hauling of materials through all modes of transportation within all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	62.50	Per Cubic metre.	3210.20	Rupees Three Thousand Two Hundred Ten Paise Twenty Only	200638
	Total in Figures					206508
	Rate quoted by contractor +/-			Percent		
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Kotkhai Division (B&R)
H.P.PWD, Kotkhai.

SCHEDULE OF QUANTITY

Job No 8

Estimated cost:- 483170
Earnest money:- 9700.00
Time:- Two Month

Name of Work :R/R Damages on Bantoth Link Road Km 0/00 to 1/00 (SH:- C/o R/wall and B/wall at Various Rd's)

Sr.No	Description of items	Qty.	Unit	Rates i/c GST & all taxes		Amount.
				Rate (in figure)	Rate (in words)	
1	Excavation in Hill area by manual/mechanical means:- Excavation in soil in hill areas all heights and depth in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hardd rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiselling and wedging out rock(where blasting is prohibited) including cutting and trimming of side slopes and disposing of excavated earth with a lift upto all heights and all leads as directed by the Engineer-in-Charge, in conformately with the requirement of technical specification of rural roads clause 1603.1 all useful material such as stone, shingle, aggregates& slate etc. shall be sorted out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absoulte responsibility of the contractor which shall have to be duly compensated by him in all cases.	19.04	P/Cum	195.95	Rupees One Hundred NinetyFive Paise NinetyFive Only	3731
2	Earth work in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads , dressing of sides and bottom and back filling in trenches with excavated suitable material in ordinary soil upto all depth. as directed by the Engineer-in-Charge.all useful material such as stone, shingle, aggregates& slate etc. shall be sorted out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absoulte responsibility of the contractor which shall have to be duly compensated by him in all cases.	53.62	Per Cubic metre.	489.20	Rupees Four Hundred EightyNine Paise Twenty Only	26231
3	Providing and laying cement concrete 1:6:12 (1 cement:6 sand : 12 graded stone 40mm agregate nominal size) for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803, 1202 and 1203.including the cost of form work and hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	7.20	P/Cum	4805.90	Rupees Four Thousand Eight Hundred Five Paise Ninety Only	34602
4	Stone masonry work in cement mortar in foundation complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203 with randum rubble masonry in cement mortar 1:6 (1 cement :6 sand) . including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	87.58	P/Cum	4602.90	Rupees Four Thousand Six Hundred Two Paise Ninety Only	403122



5	Providing weep holes in brick/ stone / plain reinforced concrete abutment, wing wall, return walls with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1V : 20H towards drawing face complete as per drawing and technical specifications clauses 614, 709 and 1204.3.7 including carriage of material within all leads and lifts and other incidentals. including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	40.00	Each	387.10	Rupees Three Hundred EightySeven Paise Ten Only	15484
	Total in Figures					483170
	Rate quoted by contractor +/-			Percent		
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Kotkhai Division (B&R)
H.P.W.D, Kotkhai.



SCHEDULE OF QUANTITY

Job No 9

Estimated cost:-
Earnest money:-
Time:-

495001
9900.00
Two Month

Name of Work :-A/R & M/O FRU Building of Hospital at Kotkhai Distt. Shimla. (SH:- Repair Work)

Sr.No	Description of items	Qty.	Unit	Rates i/c GST & all taxes		Amount.
				Rate (in figure)	Rate (in words)	
1	Providing and fixing prepainted steel work hot drips metallic zinc sheet roofing with thoughted ferro colour finish bonded polyster coated (40 micron t op coat 20micron bottom coat with UV resident pgiment having having 990mm covered width 10.35mm overall width 51 mm thought depth) manufacture by hand castle galvanised steel in approved colour and fixed with J or L hooks and G.I limpet washers and with white lead complete as per directection of Engineer-In-Charge including all leads and lifts.	144.00	Per Sqm.	1250.00	Rupees One Thousand Two Hundred Fifty Only	180000
2	Steel work welded in built up sections, trusses and framed work including cutting hoisting, fixing in position and applying a priming coat of lead paint in beans joints channels angles tees flats with connection plates or angle cleats as in main and cross beams, hip and jack rafters, purlins and connected to common rafters and the like as per specification of HP PWD, specification of 1990 volume-I as per specification of Engineer-In-Charge.(i) In Beams.	2811.25	P/Kg	112.05	Rupees One Hundred Twelve Paise Five Only	315001
	Total in Figures					495001
	Rate quoted by contractor +/-			Percent		
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Kotkhai Division (B&R)
HP.PWD, Kotkhai.

SCHEDULE OF QUANTITY

Job No 10

Estimated cost:-

473689.00

Earnest money:-

9500.00

Time:-

Two month

Name of work:- C/O Link Road Shwal Nalla to Jhrani Km 0/00 to 0/750 (Sh:- Formation cutting 5/7 meter in Km 0/00 to 0/105)

Sr.No	Description of Items	Qty.	Unit	Rates i/c GST & all taxes		Amount.
				Rate (in figure)	Rate (in words)	
1	Cutting in earth work in all heights and all kinds of soils such as spade work, pick work, jumper work, blastingwork, soft rock, hard rock chiseling work and wedging out of rocks where blasting is prohibited including their intermediate classification of soil including saturated soil and disposal of all excavated unserviceable material all leads and lifts to avoid damages to the properties of the public and Govt. and any case damages takes place the contractor is liable for it. All useful material/stones available from blasting/chiseling shall be property of department and minimum 262.73Cum stones available from blasting shall have neatly stacked at suitable place as directed by the Engineer-in-Charge. Otherwise recovery @ 300/- per cubic meter shall be effected from the bill of the contractor. The road 5/7 meter wide 5 meter in straight and 7 meter in curves.	1428.25	Per Cubic metre.	331.66	Rupees Three Hundred ThirtyOne Paise SixtySix Only	473689
	Total in Figures					473689
	Rate quoted by contractor +/-			Percent		
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Kotkhai Division (B&R)
HP.PWD, Kotkhai.

SCHEDULE OF QUANTITY

Job No 11

Estimated cost:-
Earnest money:-
Time:-

452868.00
9100.00
Two Month

Name of Work :R/R Damages on Devgarh Beon road km 0/00 to 7/885 (Sh:- C/o R/wall at Rd 2/320 to 2/340)

Sr.No	Description of items	Qty.	Unit	Rates i/c GST & all taxes		Amount.
				Rate (in figure)	Rate (in words)	
1	Earth work in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads, dressing of sides and bottom and back filling in trenches with excavated suitable material in ordinary soil upto all depth. as directed by the Engineer-in-Charge.all useful material such as stone, shingle, aggregates& slate etc. shall be sorted out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absoulte responsibility of the contractor which shall have to be duly compensated by him in all cases.	51.00	Per Cubic metre.	489.20	Rupees Four Hundred EightyNine Paise Twenty Only	24949
2	Providing and laying cement concrete 1:6:12 (1 cement:6 sand : 12 graded stone 40mm agregate nominal size) for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803, 1202 and 1203.including the cost of form work and hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	5.10	Per Cubic metre.	4805.90	Rupees Four Thousand Eight Hundred Five Paise Ninety Only	24510
3	Stone masonry work in cement mortar in foundation complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203 with randum rubble masonry in cement mortar 1:6 (1 cement :6 sand) . including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	80.00	Per Cubic metre.	4602.90	Rupees Four Thousand Six Hundred Two Paise Ninety Only	368232
4	Providing weep holes in brick/ stone / plain reinforced concrete abutment, wing wall, return walls with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1V : 20H towards drawing face complete as per drawing and technical specifications clauses 614, 709 and 1204.3.7 including carriage of material within all leads and lifts and other incidentals. including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	40.00	Each	387.10	Rupees Three Hundred EightySeven Paise Ten Only	15484
5	Backfilling /Filter media with granular material behind retaining wall/breast wall as per specification 1204.3.8 in a width of 600 mm. including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	14.40	Per Cubic metre.	1367.60	Rupees One Thousand Three Hundred SixtySeven Paise Sixty Only	19693
Total in Figures						452868
Rate quoted by contractor +/-				Percent		
Quoted rate in figure						
Quoted rate in words						

Executive Engineer,
Kotkhai Division (B&R)
H.P.WD, Kotkhai.

SCHEDULE OF QUANTITY

Job No 12

Estimated cost:- 451754.00
Earnest money:- 9100.00
Time:- Two Month

Name of Work :R/R Damages on link road from Dharonk kanchi to Sherdoli via Bandli road km 0/00 to 5/00 (Sh:- C/o R/wall at Rd 1/160 to 1/170 & 1/270 to 1/281)

Sr.No	Description of Items	Qty.	Unit	Rates i/c GST & all taxes		Amount.
				Rate (in figure)	Rate (in words)	
1	Earth work in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads , dressing of sides and bottom and back filling in trenches with excavated suitable material in ordinary soil upto all depth. as directed by the Engineer-in-Charge.all useful material such as stone, shingle, aggregates& slate etc. shall be sorted out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absoulte responsibility of the contractor which shall have to be duly compensated by him in all cases.	21.99	P/Cum	489.20	Rupees Four Hundred EightyNine Paise Twenty Only	10758
2	Providing and laying in position cement concrete of specified grade including the cost of form work in R/walls 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	3.45	P/Cum	5274.95	Rupees Five Thousand Two Hundred SeventyFour Paise NinetyFive Only	18199
3	Stone masonry work in cement mortar in foundation complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203 with randum rubble masonry in cement mortar 1:6 (1 cement :6 sand) . including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	41.47	P/Cum	4602.90	Rupees Four Thousand Six Hundred Two Paise Ninety Only	190882
4	Providing & making Gabion structure with mechanically woven Double Twisted Hexagonal Shaped Wire mesh Gabion Boxes as per IS 16014:2012 ,MORTH Clause 2500, of requred size, Mesh Type 10x12 (D=100mm with tolerance of = 2%) Zinc+coated, Mesh wire diameter 2.7/3.7mm, Mechanically edged/selvedged with paritions at every 1 m interval and shall have minimum 10 numbers of openings per meter of mesh perpendicular to twist, tying with lacing wire of diameter 2.2/3.2mm (ID/OD), supplied @ 3% by weight of Gabion boxes, filled with boulders with least dimension of 200 mm, as per drawing , all complete as per direction of Engineer-in-charge.	62.50	P/Cum	3210.20	Rupees Three Thousand Two Hundred Ten Paise Twenty Only	200638
5	Backfilling /Filter media with granular material behind retaining wall/breast wall as per specification 1204.3.8 in a width of 600 mm. including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	22.87	P/Cum	1367.60	Rupees One Thousand Three Hundred SixtySeven Paise Sixty Only	31277
	Total in Figures					451754
	Rate quoted by contractor +/-			Percent		
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Kotkhai Division (B&R)
H.P.PWD, Kotkhai.

SCHEDULE OF QUANTITY

Job No 13

Estimated cost:-
Earnest money:-
Time:-

241811.00
4900.00
Two Month

Name of Work :C/o Gazta Joney Gareog Nihari Road Km 0/0 to 16/00 (SH:- C/o Culvert at RD 5/030 with wing wall)

Sr.No	Description of items	Qty.	Unit	Rates i/c GST & all taxes		Amount.
				Rate (in figure)	Rate (in words)	
1	Earth work in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads, dressing of sides and bottom and back filling in trenches with excavated suitable material in ordinary soil upto all depth. as directed by the Engineer-in-Charge.all useful material such as stone, shingle, aggregates& slate etc. shall be sorted out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	46.78	Per Cubic metre.	489.20	Rupees Four Hundred EightyNine Paise Twenty Only	22885
2	Providing and laying in position cement concrete of specified grade including the cost of form work in R/walls 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	4.83	Per Cubic metre.	5274.95	Rupees Five Thousand Two Hundred SeventyFour Paise NinetyFive Only	25478
3	Random rubble masonry Stone masonry work in cement mortar in foundation complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203 with random rubble masonry in cement mortar 1:6 (1 cement :6 sand) . including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	22.72	Per Cubic metre.	4602.90	Rupees Four Thousand Six Hundred Two Paise Ninety Only	104578
4	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc for substructure and superstructure complete as per drawings and technical specifications Clause 704.6& 1302.5 including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	10.19	Per Cubic metre.	2968.80	Rupees Two Thousand Nine Hundred SixtyEight Paise Eighty Only	30252
5	Backfilling /Filter media with granular material behind retaining wall/breast wall as per specification 1204.3.8 in a width of 600 mm. including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	6.48	Per Cubic metre.	1367.60	Rupees One Thousand Three Hundred SixtySeven Paise Sixty Only	8862
6	Providing Laying of reinforced cement concrete pipe NP-2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets cause 1108:900mm. including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	7.50	Per Cubic metre.	6634.10	Rupees Six Thousand Six Hundred ThirtyFour Paise Ten Only	49756
	Total in Figures					241811
	Rate quoted by contractor +/-			Percent		
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Kotkhai Division (B&R)
H.P.P.W.D, Kotkhai.

SCHEDULE OF QUANTITY

Job No 14

Estimated cost:-
Earnest money:-
Time:-

417713.00
8400.00
Two Month

Name of Work :-R/R Damages on Ghunda Talka road km 0/00 to 2/300 (SH:- R/wall at Rd 0/937 to 0/947)

Sr.No	Description of items	Qty.	Unit	Rates i/c GST & all taxes		Amount.
				Rate (in figure)	Rate (in words)	
1	Earth work in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads, dressing of sides and bottom and back filling in trenches with excavated suitable material in ordinary soil upto all depth. as directed by the Engineer-in-Charge.all useful material such as stone, shingle, aggregates& slate etc. shall be sorted out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	49.70	Per Cubic metre.	489.20	Rupees Four Hundred EightyNine Paise Twenty Only	24313
2	Providing and laying in position cement concrete of specified grade including the cost of form work in R/walls 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	70.00	Per Cubic metre.	5274.95	Rupees Five Thousand Two Hundred SeventyFour Paise NinetyFive Only	369247
3	Providing weep holes in brick/ stone / plain reinforced concrete abutment, wing wall, return walls with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1V : 20H towards drawing face complete as per drawing and technical specifications clauses 614, 709 and 1204.3.7 including carriage of material within all leads and lifts and other incidentals. including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	20.00	Each	387.10	Rupees Three Hundred EightySeven Paise Ten Only	7742
4	Backfilling /Filter media with granular material behind retaining wall/breast wall as per specification 1204.3.8 in a width of 600 mm. including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge	12.00	Per Cubic metre.	1367.60	Rupees One Thousand Three Hundred SixtySeven Paise Sixty Only	16411
	Total in Figures					417713
	Rate quoted by contractor +/-			Percent		
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Kotkhai Division (B&R)
MP.PWD, Kotkhai.

SCHEDULE OF QUANTITY

Job No 15

Estimated cost:-
Earnest money:-
Time:-

299534.00
6000.00
Two Month

Name of Work :R/R Damages on Bareonghat to bareon link road km 0/00 to 1/930 (SH:- C/o R/wall at RD 1/300 to 1/312)

Sr.No	Description of items	Qty.	Unit	Rates i/c GST & all taxes		Amount.
				Rate (in figure)	Rate (in words)	
1	Earth work in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads, dressing of sides and bottom and back filling in trenches with excavated suitable material in ordinary soil upto all depth, as directed by the Engineer-in-Charge.all useful material such as stone, shingle, aggregates& slate etc. shall be sorted out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	30.48	Per Cubic metre.	489.20	Rupees Four Hundred EightyNine Paise Twenty Only	14911
2	Providing and laying cement concrete 1:6:12 (1 cement:6 sand : 12 graded stone 40mm aggregate nominal size) for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803, 1202 and 1203 including the cost of form work and hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	3.15	Per Cubic metre.	4805.90	Rupees Four Thousand Eight Hundred Five Paise Ninety Only	15139
3	Stone masonry work in cement mortar in foundation complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203 with random rubble masonry in cement mortar 1:6 (1 cement :6 sand) . including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	52.80	Per Cubic metre.	4602.90	Rupees Four Thousand Six Hundred Two Paise Ninety Only	243033
4	Providing weep holes in brick/ stone / plain reinforced concrete abutment, wing wall, return walls with 100 mm dia PWC pipe extending through the full width of the structure with slope of 1V : 20H towards drawing face complete as per drawing and technical specifications clauses 614, 709 and 1204.3.7 including carriage of material within all leads and lifts and other incidentals. including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	20.00	Each.	387.10	Rupees Three Hundred EightySeven Paise Ten Only	7742
5	Backfilling /Filter media with granular material behind retaining wall/breast wall as per specification 1204.3.8 in a width of 600 mm. including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	13.68	Per Cubic metre.	1367.60	Rupees One Thousand Three Hundred SixtySeven Paise Sixty Only	18709
	Total in Figures					299534
	Rate quoted by contractor +/-			Percent		
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Kotkhai Division (B&R)
HP.PWD, Kotkhai.

SCHEDULE OF QUANTITY

Job No 16

Estimated cost:-
Earnest money:-
Time:-

407027.00
8200.00
Two Month

Name of Work :R/R Damages on link road to Saintari km 0/00 to 0/315 (SH:- C/o R/wall at Rd 0/010 to 0/017.50 & 0/128 to 0/135.50)

Sr.No	Description of items	Qty.	Unit	Rates i/c GST & all taxes		Amount.
				Rate (in figure)	Rate (in words)	
1	Earth work in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads , dressing of sides and bottom and back filling in trenches with excavated suitable material in ordinary soil upto all depth. as directed by the Engineer-in-Charge.all useful material such as stone, shingle, aggregates& slate etc. shall be sorted out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absoulte responsibility of the contractor which shall have to be duly compensated by him in all cases.	14.07	Per Cubic metre.	489.20	Rupees Four Hundred EightyNine Paise Twenty Only	6883
2	Providing & making Gabion structure with mechanically woven Double Twisted Hexagonal Shaped Wire mesh Gabion Boxes as per IS 16014:2012 ,MORTH Clause 2500, of required size, Mesh Type 10x12 (D=100mm with tolerance of = 2%) Zinc+coated, Mesh wire diameter 2.7/3.7mm, Mechanically edged/selvedged with paritions at every 1 m interval and shall have minimum 10 numbers of openings per meter of mesh perpendicular to twist, tying with lacing wire of diameter 2.2/3.2mm (ID/OD), supplied @ 3% by weight of Gabion boxes, filled with boulders with least dimension of 200 mm, as per drawing , all complete as per direction of Engineer-in-charge.	123.05	Per Cubic metre.	3210.20	Rupees Three Thousand Two Hundred Ten Paise Twenty Only	395015
3	Backfilling /Filter media with granular material behind retaining wall/breast wall as per specification 1204.3.8 in a width of 600 mm. including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	3.75	Per Cubic metre.	1367.60	Rupees One Thousand Three Hundred SixtySeven Paise Sixty Only	5129
	Total in Figures					407027
	Rate quoted by contractor +/-			Percent		
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Kotkhai Division (B&R)
H.P.PWD, Kotkhai.

SCHEDULE OF QUANTITY

Job No 17

Estimated cost:-
Earnest money:-
Time:-

487043.00
9800.00
Two Month

Name of Work :R/R Damages on Chhol to Kotkhai Bazar road km 0/00 to 1/600 (SH:- C/o R/wall at Rd 0/585 to 0/600)

Sr.No	Description of items	Qty.	Unit	Rates i/c GST & all taxes		Amount.
				Rate (in figure)	Rate (in words)	
1	Earth work in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads , dressing of sides and bottom and back filling in trenches with excavated suitable material in ordinary soil upto all depth. as directed by the Engineer-in-Charge.all useful material such as stone, shingle, aggregates& slate etc. shall be sorted out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absoulte responsibility of the contractor which shall have to be duly compensated by him in all cases.	52.80	Per Cubic metre.	489.20	Rupees Four Hundred EightyNine Paise Twenty Only	25830
2	Providing and laying cement concrete 1:6:12 (1 cement:6 sand : 12 graded stone 40mm agregate nominal size) for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803, 1202 and 1203.including the cost of form work and hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	4.28	Per Cubic metre.	4805.90	Rupees Four Thousand Eight Hundred Five Paise Ninety Only	20569
3	Random rubble masonry Stone masonry work in cement mortar in foundation complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203 with randum rubble masonry in cement mortar 1:6 (1 cement :6 sand) . including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	90.00	Per Cubic metre.	4602.90	Rupees Four Thousand Six Hundred Two Paise Ninety Only	414261
4	Providing weep holes in brick/ stone / plain reinforced concrete abutment, wing wall, return walls with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1V : 20H towards drawing face complete as per drawing and technical specifications clauses 614, 709 and 1204.3.7 including carriage of material within all leads and lifts and other incidentals. including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	30.00	Each	387.10	Rupees Three Hundred EightySeven Paise Ten Only	11613
5	Backfilling /Filter media with granular material behind retaining wall/breast wall as per specification 1204.3.8 in a width of 600 mm. including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	10.80	Per Cubic metre.	1367.60	Rupees One Thousand Three Hundred SixtySeven Paise Sixty Only	14770
	Total in Figures					487043
	Rate quoted by contractor +/-			Percent		
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Kotkhai Division (B&R)
P.PWD, Kotkhai.

SCHEDULE OF QUANTITY

Job No 18

Estimated cost:-
Earnest money:-
Time:-

466271.00
9400.00
Two Month

Name of Work :R/R Damages on Gumma Pujali Reoghati road Km 0/00 to 29/600 (SH:- R/wall at RD 10/560 to 10/570)

Sr.No	Description of items	Qty.	Unit	Rates i/c GST & all taxes		Amount.
				Rate (in figure)	Rate (in words)	
1	Earth work in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads , dressing of sides and bottom and back filling in trenches with excavated suitable material in ordinary soil upto all depth. as directed by the Engineer-in-Charge.all useful material such as stone, shingle, aggregates& slate etc. shall be sorted out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absoulte responsibility of the contractor which shall have to be duly compensated by him in all cases.	49.40	Per Cubic metre.	489.20	Rupees Four Hundred EightyNine Paise Twenty Only	24166
2	Providing and laying in position cement concrete of specified grade including the cost of form work in R/walls 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 25 mm nominal size)including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	34.20	Per Cubic metre.	5274.95	Rupees Five Thousand Two Hundred SeventyFour Paise NinetyFive Only	180403
3	Random rubble masonry Stone masonry work in cement mortar in foundation complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203 with random rubble masonry in cement mortar 1:6 (1 cement :6 sand) . including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	52.50	Per Cubic metre.	4602.90	Rupees Four Thousand Six Hundred Two Paise Ninety Only	241652
4	Backfilling /Filter media with granular material behind retaining wall/breast wall as per specification 1204.3.8 in a width of 600 mm. including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	9.00	Per Cubic metre.	1367.60	Rupees One Thousand Three Hundred SixtySeven Paise Sixty Only	12308
5	Providing weep holes in brick/ stone / plain reinforced concrete abutment, wing wall, return walls with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1V : 20H towards drawing face complete as per drawing and technical specifications clauses 614, 709 and 1204.3.7 including carriage of material within all leads and lifts and other incidentals. including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	20.00	Each	387.10	Rupees Three Hundred EightySeven Paise Ten Only	7742
	Total in Figures					466271
	Rate quoted by contractor +/-			Percent		
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Kotkhai Division (B&R)
HP.PWD, Kotkhai.



SCHEDULE OF QUANTITY

Job No 19

Estimated cost:- 454182.00
Earnest money:- 9100.00
Time:- Two Month

Name of Work :R/R Damages on Gazta Darkoti Jandoli road Km 0/0 to 6/300 (SH:- C/o R/wall at RD 2/780 to 2/787.60 and 3/255 to 3/232.50)

Sr.No	Description of items	Qty.	Unit.	Rates i/c GST & all taxes		Amount.
				Rate (in figure)	Rate (in words)	
1	Excavation in Hill area by manual/mechanical means:- Excavation in soil in hill areas all heights and depth in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiselling and wedging out rock(where blasting is prohibited) including cutting and trimming of side slopes and disposing of excavated earth with a lift upto all heights and all leads as directed by the Engineer-in-Charge, in conformately with the requirement of technical specification of rural roads clause 1603.1 all useful material such as stone, shingle, aggregates& slate etc. shall be sorted out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	12.14	Per Cubic metre.	195.95	Rupees One Hundred NinetyFive Paise NinetyFive Only	2379
2	Earth work in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads , dressing of sides and bottom and back filling in trenches with excavated suitable material in ordinary soil upto all depth. as directed by the Engineer-in-Charge.all useful material such as stone, shingle, aggregates& slate etc. shall be sorted out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	10.94	Per Cubic metre.	489.20	Rupees Four Hundred EightyNine Paise Twenty Only	5352
3	Providing and laying in position cement concrete of specified grade including the cost of form work in R/walls 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 25 mm nominal size)including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	28.60	Per Cubic metre.	5274.95	Rupees Five Thousand Two Hundred SeventyFour Paise NinetyFive Only	150864
4	Stone masonry work in cement mortar in foundation complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203 with randum rubble masonry in cement mortar 1:6 (1 cement :6 sand) . including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	56.96	Per Cubic metre.	4602.90	Rupees Four Thousand Six Hundred Two Paise Ninety Only	262181
5	Backfilling /Filter media with granular material behind retaining wall/breast wall as per specification 1204.3.8 in a width of 600 mm. including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	17.35	Per Cubic metre.	1367.60	Rupees One Thousand Three Hundred SixtySeven Paise Sixty Only	23728



6	Providing weep holes in brick/ stone / plain reinforced concrete abutment, wing wall, return walls with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1V : 20H towards drawing face complete as per drawing and technical specifications clauses 614, 709 and 1204.3.7 including carriage of material within all leads and lifts and other incidentals. including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	25.00	Each	387.10	Rupees Three Hundred Eighty Seven Paise Ten Only	9678
	Total In Figures					454182
	Rate quoted by contractor +/-			Percent		
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Kotkhai Division (B&R)
HP.PWD, Kotkhai.

SCHEDULE OF QUANTITY

Job No 20

Estimated cost:-

423598.00

Earnest money:-

8500.00

Time:-

Two Month

Name of Work :R/R Damages on Kua jubbar Shakrala road Km 0/00 to 1/740 (SH:- C/o R/wall at Rd 1/720 to 1/740)

Sr.No	Description of items	Qty.	Unit	Rates i/c GST & all taxes		Amount.
				Rate (in figure)	Rate (in words)	
1	Earth work in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads , dressing of sides and bottom and back filling in trenches with excavated suitable material in ordinary soil upto all depth. as directed by the Engineer-in-Charge.all useful material such as stone, shingle, aggregates& slate etc. shall be sorted out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	59.76	Per Cubic metre.	489.20	Rupees Four Hundred EightyNine Paise Twenty Only	29235
2	Providing and laying cement concrete 1:6:12 (1 cement:6 sand : 12 graded stone 40mm aggregate nominal size) for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803, 1202 and 1203.including the cost of form work and hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	7.20	Per Cubic metre.	4805.90	Rupees Four Thousand Eight Hundred Five Paise Ninety Only	34602
3	Providing and laying in position cement concrete of specified grade including the cost of form work in R/walls 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 25 mm nominal size)including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	8.69	Per Cubic metre.	5274.95	Rupees Five Thousand Two Hundred SeventyFour Paise NinetyFive Only	45839
4	Random rubble masonry Stone masonry work in cement mortar in foundation complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203 with random rubble masonry in cement mortar 1:6 (1 cement :6 sand) . including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	39.50	Per Cubic metre.	4602.90	Rupees Four Thousand Six Hundred Two Paise Ninety Only	181815
5	Construction of dry rubble masonry for retaining walls, breast walls , revetment walls and parapets etc for substructure and superstructure complete as per drawings and technical specifications Clause 704.6& 1302.5 including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	40.50	Per Cubic metre.	2968.80	Rupees Two Thousand Nine Hundred SixtyEight Paise Eighty Only	120236
6	Backfilling /Filter media with granular material behind retaining wall/breast wall as per specification 1204.3.8 in a width of 600 mm. including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	5.85	Per Cubic metre.	1367.60	Rupees One Thousand Three Hundred SixtySeven Paise Sixty Only	8000



7	Providing weep holes in brick/ stone / plain reinforced concrete abutment, wing wall, return walls with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1V : 20H towards drawing face complete as per drawing and technical specifications clauses 614, 709 and 1204.3.7 including carriage of material within all leads and lifts and other incidentals. including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	10.00	Each	387.10	Rupees Three Hundred Eighty Seven Paise Ten Only	3871
	Total in Figures					423598
	Rate quoted by contractor +/-			Percent		
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Kotkhai Division (B&R)
HP.PWD, Kotkhai.

SCHEDULE OF QUANTITY

Job No 21

Estimated cost:-
Earnest money:-
Time:-

440373.00
8900.00
Two Month

Name of Work :R/R Damages on Kotkhai Deori Khanety Deorighat km 0/00 to 22/00 (Sh:- C/o R/wall at Rd 4/866 to 4/878)

Sr.No	Description of items	Qty.	Unit	Rates i/c GST & all taxes		Amount.
				Rate (in figure)	Rate (in words)	
1	Earth work in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads, dressing of sides and bottom and back filling in trenches with excavated suitable material in ordinary soil upto all depth. as directed by the Engineer-in-Charge.all useful material such as stone, shingle, aggregates& slate etc. shall be sorted out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absoulte responsibility of the contractor which shall have to be duly compensated by him in all cases.	42.24	P/Cum	489.20	Rupees Four Hundred EightyNine Paise Twenty Only	20664
2	Providing and laying cement concrete 1:6:12 (1 cement:6 sand : 12 graded stone 40mm agregate nominal size) for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803, 1202 and 1203.including the cost of form work and hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	3.96	P/Cum	4805.90	Rupees Four Thousand Eight Hundred Five Paise Ninety Only	19031
3	Stone masonry work in cement mortar in foundation complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203 with randum rubble masonry in cement mortar 1:6 (1 cement :6 sand) . including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	82.80	P/Cum	4602.90	Rupees Four Thousand Six Hundred Two Paise Ninety Only	381120
4	Providing weep holes in brick/ stone / plain reinforced concrete abutment, wing wall, return walls with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1V : 20H towards drawing face complete as per drawing and technical specifications clauses 614, 709 and 1204.3.7 including carriage of material within all leads and lifts and other incidentals. including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	20.00	Each	387.10	Rupees Three Hundred EightySeven Paise Ten Only	7742
5	Backfilling /Filter media with granular material behind retaining wall/breast wall as per specification 1204.3.8 in a width of 600 mm. including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	8 64	P/Cum	1367.60	Rupees One Thousand Three Hundred SixtySeven Paise Sixty Only	11816
	Total in Figures					440373
	Rate quoted by contractor +/-			Percent		
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Kotkhai Division (B&R)
H.P.WD, Kotkhai.

SCHEDULE OF QUANTITY

Job No 22

Estimated cost:-
Earnest money:-
Time:-

462808.00
9300.00
Two Month

Name of Work :R/R Damages on Marathu Tharolla Tahu Km 0/00 to 17/100 (Sh:- C/o R/wall at Rd 0/791 to 0/800)

Sr.No	Description of items	Qty.	Unit	Rates i/c GST & all taxes		Amount.
				Rate (in figure)	Rate (in words)	
1	Earth work in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads, dressing of sides and bottom and back filling in trenches with excavated suitable material in ordinary soil upto all depth. as directed by the Engineer-in-Charge.all useful material such as stone, shingle, aggregates& slate etc. shall be sorted out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	17.53	P/Cum	489.20	Rupees Four Hundred EightyNine Paise Twenty Only	8576
2	Providing and laying in position cement concrete of specified grade including the cost of form work in R/walls 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 25 mm nominal size)including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	52.11	P/Cum	5274.95	Rupees Five Thousand Two Hundred SeventyFour Paise NinetyFive Only	274878
3	Stone masonry work in cement mortar in foundation complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203 with random rubble masonry in cement mortar 1:6 (1 cement :6 sand) . including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	32.39	P/Cum	4602.90	Rupees Four Thousand Six Hundred Two Paise Ninety Only	149088
4	Backfilling /Filter media with granular material behind retaining wall/breast wall as per specification 1204.3.8 in a width of 600 mm. including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	16.47	P/Cum	1367.60	Rupees One Thousand Three Hundred SixtySeven Paise Sixty Only	22524
5	Providing weep holes in brick/ stone / plain reinforced concrete abutment, wing wall, return walls with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1V : 20H towards drawing face complete as per drawing and technical specifications clauses 614, 709 and 1204.3.7 including carriage of material within all leads and lifts and other incidentals. including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	20.00	Each	387.10	Rupees Three Hundred EightySeven Paise Ten Only	7742
	Total in Figures					462808
	Rate quoted by contractor +/-			Percent		
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Kotkhai Division (B&R)
H.P.PWD, Kotkhai.

SCHEDULE OF QUANTITY

Job No 23

Estimated cost:-
Earnest money:-
Time:-

485996.00
9800.00
Two Month

Name of Work :R/R Damages on Chol Badrooni Gehrog Bari road Km 0/00 to 3/375(SH:- C/o R/wall at Rd 2/315 to 2/329)

Sr.No	Description of items	Qty.	Unit	Rates i/c GST & all taxes		Amount.
				Rate (in figure)	Rate (in words)	
1	Earth work in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads , dressing of sides and bottom and back filling in trenches with excavated suitable material in ordinary soil upto all depth. as directed by the Engineer-in-Charge.all useful material such as stone, shingle, aggregates& slate etc. shall be sorted out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	45.22	Per Cubic metre.	489.20	Rupees Four Hundred EightyNine Paise Twenty Only	22122
2	Providing and laying in position cement concrete of specified grade including the cost of form work in R/walls 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 25 mm nominal size)including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	84.00	Per Cubic metre.	5274.95	Rupees Five Thousand Two Hundred SeventyFour Paise NinetyFive Only	443096
3	Providing weep holes in brick/ stone / plain reinforced concrete abutment, wing wall, return walls with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1V : 20H towards drawing face complete as per drawing and technical specifications clauses 614, 709 and 1204.3.7 including carriage of material within all leads and lifts and other incidentals. including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	24.00	Each	387.10	Rupees Three Hundred EightySeven Paise Ten Only	9290
4	Backfilling /Filter media with granular material behind retaining wall/breast wall as per specification 1204.3.8 in a width of 600 mm. including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	8.40	Per Cubic metre.	1367.60	Rupees One Thousand Three Hundred SixtySeven Paise Sixty Only	11488
	Total in Figures					485996
	Rate quoted by contractor +/-			Percent		
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Kotkhai Division (B&R)
ITP.PWD, Kotkhai.

SCHEDULE OF QUANTITY

Job No 24

Name of Work :R/R Damages on link road from Dharonk Kanchi to Sherdoli via Bandli road km 0/00 to 7/00 (SH:- C/o R/wall at Rd 5/585 to 5/605)

Estimated cost:- 496998.00
Earnest money:- 10000.00
Time:- Two Month

Sr.No	Description of items	Qty.	Unit	Rates i/c GST & all taxes		Amount
				Rate (in figure)	Rate (in words)	
1	Earth work in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads, dressing of sides and bottom and back filling in trenches with excavated suitable material in ordinary soil upto all depth, as directed by the Engineer-in-Charge-all useful material such as stone, shingle, aggregates, slate etc. shall be sorted out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	30.96	Per Cubic metre.	489.20	Ruppes Four Hundred EightyNine Paise Twenty Only	15146
2	Providing and laying in position cement concrete of specified grade including the cost of form work in R/walls 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	8.28	Per Cubic metre.	5274.95	Ruppes Five Thousand Two Hundred SeventyFour Paise NinetyFive Only	43677
3	Stone masonry work in cement mortar in foundation complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203 with randum rubble masonry in cement mortar 1:6 (1 cement :6 sand) . including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	89.67	Per Cubic metre.	4602.90	Ruppes Four Thousand Six Hundred Two Paise Ninety Only	412742
4	Backfilling /Filter media with granular material behind retaining wall/breast wall as per specification 1204.3.8 in a width of 600 mm. including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	11.52	Per Cubic metre.	1367.60	Ruppes One Thousand Three Hundred SixtySeven Paise Sixty Only	15755
5	Providing weep holes in brick/ stone / plain reinforced concrete abutment, wing wall, return walls with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1V : 20H towards drawing face complete as per drawing and technical specifications clauses 614, 709 and 1204.3.7 including carriage of material within all leads and lifts and other incidentals. including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	25.00	Each	387.10	Ruppes Three Hundred EightySeven Paise Ten Only	9678
	Total in Figures					496998
	Rate quoted by contractor +/-			Percent		
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Kothnai Division (B&R)
#P.PWD, Kothnai.

SCHEDULE OF QUANTITY

Job No 25

Name of Work :R/R Damages on Koku Nalla Dharonk road km 0/00 to 8/500 (SH:- C/o R/wall at Rd 1/031.5 to 1/035.25)

Estimated cost:- 203641.00
Earnest money:- 4100.00
Time:- Two Month

Sr.No	Description of items	Qty.	Unit	Rates i/c GST & all taxes		Amount
				Rate (in figure)	Rate (in words)	
1	Earth work in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads, dressing of sides and bottom and back filling in trenches with excavated suitable material in ordinary soil upto all depth as directed by the Engineer-in-Charge all useful material such as stone, shingle, aggregates, slate etc. shall be sorted out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	9.00	Per Cubic metre.	489.20	Rupees Four Hundred Eighty/Time Paise Twenty Only	4403
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size)including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	15.00	Per Cubic metre.	5757.80	Rupees Five Thousand Seven Hundred FiftySeven Paise Eighty Only	86367
3	Providing & making Gabion structure with mechanically woven Double Twisted Hexagonal Shaped Wire mesh Gabion Boxes as per IS 16014:2012, MORTH Clause 2500, of required size, Mesh Type 10x12 (D=100mm with tolerance of = 2%) Zinc+coated, Mesh wire diameter 2.7/3.7mm, Mechanically edged/selvedged with paritions at every 1 m interval and shall have minimum 10 numbers of openings per meter of mesh perpendicular to twist, tying with lacing wire of diameter 2.2/3.2mm (ID/OD), supplied @ 3% by weight of Gabion boxes, filled with boulders with least dimension of 200 mm, as per drawing, all complete as per direction of Engineer-in-charge.	35.16	Per Cubic metre.	3210.20	Rupees Three Thousand Two Hundred Ten Paise Twenty Only	112871
	Total in Figures					203641
	Rate quoted by contractor +/-			Percent		
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Kothhai Division (B&R)
HP PWD, Kothhai.



SCHEDULE OF QUANTITY

Job No 26

Name of Work :R/R Damages on Devgarh Beon road km 0/00 to 7/885. (SH:- C/o B/wall at Rd 4/765 to 4/795)

Estimated cost:- 404529.00
Earnest money:- 8100.00
Time:- Two Month

Sr.No	Description of Items	Qty.	Unit	Rates i/c GST & all taxes		Amount
				Rate (in figure)	Rate (in words)	
1	Excavation in Hill area by manual/mechanical means:- Excavation in soil in hill areas all heights and depth in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiselling and wedging out rock(where blasting is prohibited) including cutting and trimming of side slopes and disposing of excavated earth with a lift upto all heights and all leads as directed by the Engineer-in-Charge, in conformably with the requirement of technical specification of rural roads clause 1603.1 all useful material such as stone, shingle, aggregates& slate etc. shall be sorted out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	39.00	Per Cubic metre.	195.95	Rupees One Hundred NinetyFive Paise NinetyFive Only	7642
2	Earth work in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads, dressing of sides and bottom and back filling in trenches with excavated suitable material in ordinary soil upto all depth. as directed by the Engineer-in-Charge.all useful material such as stone, shingle, aggregates& slate etc. shall be sorted out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	36.00	Per Cubic metre.	489.20	Rupees Four Hundred EightyNine Paise Twenty Only	17611
3	Providing and laying cement concrete 1:6:12 (1 cement:6 sand : 12 graded stone 40mm aggregate nominal size) for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803, 1202 and 1203.including the cost of form work and hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	7.20	Per Cubic metre.	4805.90	Rupees Four Thousand Eight Hundred Five Paise Ninety Only	34602
4	Stone masonry work in cement mortar in foundation complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203 with randum rubble masonry in cement mortar 1:6 (1 cement :6 sand) . including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	73.20	Per Cubic metre.	4602.90	Rupees Four Thousand Six Hundred Two Paise Ninety Only	336932



5	Providing weep holes in brick/ stone / plain reinforced concrete abutment, wing wall, return walls with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1V : 20H towards drawing face complete as per drawing and technical specifications clauses 614, 709 and 1204.3.7 including carriage of material within all leads and lifts and other incidentals including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	20.00	Each	387.10	Rupees Three Hundred Eighty Seven Paise Ten Only	7742
		Total in Figures				404529
		Rate quoted by contractor +/-				
		Quoted rate in figure		Percent		
		Quoted rate in words				

Executive Engineer,
Kothai Division (B&R)
HP.PWD, Kothai.

SCHEDULE OF QUANTITY

Job No 27

Name of Work: R/R Damages on Kotla Pali road km 0/00 to 3/300 (SH:- C/o B/wall at RD 3/035 to 3/065)

Estimated cost:- 493293.00
Earnest money:- 9900.00
Time:- Two Month

Sr.No	Description of items	Qty.	Unit	Rates i/c GST & all taxes		Amount.
				Rate (in figure)	Rate (in words)	
1	Excavation in Hill area by manual/mechanical means:- Excavation in soil in hill areas all heights and depth in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiselling and wedging out rock (where blasting is prohibited) including cutting and trimming of side slopes and disposing of excavated earth with a lift upto all heights and all leads as directed by the Engineer-in-Charge. In conformably with the requirement of technical specification of rural roads clause 1603.1 all useful material such as stone, shingle, aggregates, slate etc shall be sorted out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	181.00	Per Cubic metre.	195.95	Rupees One Hundred Nine/Five Paise Nine/Five Only	35467
2	Earth work in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads, dressing of sides and bottom and back filling in trenches with excavated suitable material in ordinary soil upto all depth, as directed by the Engineer-in-Charge. all useful material such as stone, shingle, aggregates, slate etc. shall be sorted out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	40.50	Per Cubic metre.	489.20	Rupees Four Hundred Eighty/Nine Paise Twenty Only	19813
3	Providing and laying cement concrete 1:6:12 (1 cement:6 sand : 12 graded stone 40mm aggregate nominal size) for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802.803, 1202 and 1203 including the cost of form work and hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	8.10	Per Cubic metre.	4805.90	Rupees Four Thousand Eight Hundred Five Paise Nine Only	38928
4	Random rubble masonry Stone masonry work in cement mortar in foundation complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203 with random rubble masonry in cement mortar 1:6 (1 cement :6 sand) . Including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	84.18	Per Cubic metre.	4602.90	Rupees Four Thousand Six Hundred Two Paise Nine Only	387472
5	Providing weep holes in brick/ stone / plain reinforced concrete abutment, wing wall, return walls with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1V : 20H towards drawing face complete as per drawing and technical specifications clauses 614, 709 and 1204.3.7 including carriage of material within all leads and lifts and other incidentals, including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	30.00	Each	387.10	Rupees Three Hundred EightySeven Paise Ten Only	11613
	Total in Figures					493293
	Rate quoted by contractor +/-			Percent		
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Kotthal Division (B&R)
He. PWD, Kotthal.

Job No 28

417713.00
8400.00
Two Month

Description of items

Rate quoted by contractor +/-

Executive Engineer,
Kotthal Division (B&R)
Kotthal PWD, Kotthal

SCHEDULE OF QUANTITY

Job No 29

Estimated cost- 490258.00
Earnest money- 9900.00
Two Month

Name of Work- R/R Damages on Barvi Garaga road km 0/00 to 7/00 (Sta- C/o B/wall at Rd 2/325 to 2/333 & R/wall at Rd 2/320 to 2/335)

Sl. No	Description of items	Qty.	Unit	Rates (Rs. per unit)		Amount
				Rate (Rs. per unit)	Rate (Rs. per unit) + GST & all taxes	
1	Earth work in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of slumps and other deleterious material and disposal upto all leads, dressing of sides and bottom and back filling in trenches with excavated suitable material in ordinary soil upto all depth as directed by the Engineer-in-Charge all useful material such as stone, shingle, aggregates, stone etc. shall be stored out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absolute responsibility of the contractor which shall have to be fully compensated to him in all cases.	27.48	Per Cubic meter	489.20	Rs. 13546	13546
2	Providing and laying in position cement concrete of specified grade including the cost of form work in R/walls 1:4:8 (1 Cement : 4 coarse sand : 3 graded stone aggregate 40 mm nominal size) including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	8.28	Per Cubic meter	5274.95	Rs. 43677	43677
3	Stone masonry work in cement mortar in foundation complete as per drawing and technical specifications Clauses 702, 704, 1102 & 1203 with random rubble masonry in cement mortar 1:6 (1 cement 6 sand), including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	90.25	Per Cubic meter	4602.90	Rs. 415412	415412
4	The entire satisfaction and direction of the Engineer-in-Charge. Providing weep holes in brick/ stone / plain reinforced concrete abutment wing wall, return walls with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1V : 20H towards drawing face complete as per drawing and technical specifications clauses 654, 709 and 1204.3.7 including carriage of material within all leads and lifts and other incidentals including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	15.00	Each	387.18	Rs. 5807	5807
5	Backfilling / Filter media with granular material behind retaining wall/breast wall as per specification 1204.3.8 in a width of 600 mm, including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	8.44	Per Cubic meter	1367.60	Rs. 11816	11816
Total in Figures						490258
Rate quoted by contractor +/-				Percent		
Quoted rate in figure						
Quoted rate in words						

Executive Engineer,
Karnal Division (208)
P.W.D. Karnal

SCHEDULE OF QUANTITY

Job No 30

Estimated cost:- 429804.00
Earnest money:- 86000.00
Time:- Two Month

Name of Work: R/R Damages On Kari Bahidhar road Km 0/00 to 4/500 (SH:- C/o R/wall at Rd 3/175 to 3/187)
Description of items

Sr.No	Description of items	Qty.	Unit	Rate (in figure)	Rate (in words)	Amount
1	Earth work in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads, dressing of sides and bottom and back filling in trenches with excavated suitable material in ordinary soil upto all depth, as directed by the Engineer-in-Charge; all useful material such as stone, shingle, aggregates, slate etc. shall be sorted out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	46.92	Per Cubic metre	489.20	Ruppes Four Hundred Eighty Nine Paise Twenty Only	22953
2	Providing and laying in position cement concrete of specified grade including the cost of form work in R/walls 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 25 mm nominal size) including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	51.00	Per Cubic metre	5274.95	Ruppes Five Thousand Two Hundred Seventy Four Paise Ninety Five Only	269022
3	Providing & making Gabion structure with mechanically woven Double Twisted Hexagonal Shaped Wire mesh Gabion Boxes as per IS 16014:2012, MORTH Clause 2500, of required size, Mesh Type 10x12 (D=100mm with tolerance of = 2%) Zinc-coated, Mesh wire diameter 2.7/3.2mm. Mechanically edged/self-edged with partitions at every 1 m interval and shall have minimum 10 numbers of openings per meter of mesh perpendicular to twist, tying with lacing wire of diameter 2.2/3.2mm (ID/OD), supplied @ 3% by weight of Gabion boxes, filled with boulders with least dimension of 200 mm as per drawing, all complete as per direction of Engineer-in-Charge. Providing weep holes in brick/stone / plain reinforced concrete abutment, wing wall, return walls with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1V : 20H towards drawing face complete as per drawing and technical specifications clauses 614, 709 and 1204.3.7 including carriage of material within all leads and lifts and other incidentals, including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	37.50	Per Cubic metre	3210.20	Ruppes Three Thousand Two Hundred Ten Paise Twenty Only	120383
4	Providing weep holes in brick/stone / plain reinforced concrete abutment, wing wall, return walls with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1V : 20H towards drawing face complete as per drawing and technical specifications clauses 614, 709 and 1204.3.7 including carriage of material within all leads and lifts and other incidentals, including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	12.00	Each	387.10	Ruppes Three Hundred Eighty Seven Paise Ten Only	4645
5	including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	9.36	Per Cubic metre	1367.60	Ruppes One Thousand Three Hundred Sixty Seven Paise Sixty Only	12801
	Total in Figures					429804
	Rate quoted by contractor +/-			Percent		
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Roads Division (B&K)
PPWU, Kolihai

Job No 31

406502.00
8200.00
Two Month

Time:

Executive Engineer,
Kotkhai Division (B&R)
B&RWD, Kotkhai.

SCHEDULE OF QUANTITY

Job No 32

Estimated cost:- 333015.00
Earnest money:- 6700.00
Time:- Two Month

Name of Work :R/R Damages on Ghasi Gaon Dhanroti road km 0/00 to 3/00 (SH:-C/o R/wall at Rd km 0/705 to 0/0715)

Sr.No	Description of items	Qty.	Unit	Rates i/c GST & all taxes		Amount.
				Rate (in figure)	Rate (in words)	
1	Earth work in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads, dressing of sides and bottom and back filling in trenches with excavated suitable material in ordinary soil upto all depth, as directed by the Engineer-in-Charge all useful material such as stone, shingle, aggregates, slate etc. shall be sorted out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	17.22	Per Cubic metre	4997.20	Bugies Four Thousand Three Hundred Forty Nine Paise Twenty Only	86424
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size) including carriage of material within all leads and lifts and as per HP.PWD, specifications of 1990 volume-I and as per direction of Engineer-in-Charge.	60.64	Per Cubic metre	4997.20	Bugies Four Thousand Three Hundred Forty Nine Paise Twenty Only	299562
3	Backfilling /Filter media with granular material behind retaining wall/breast wall as per specification 1204.3.8 in a width of 600 mm.	9.81	Per Cubic metre	1367.60	Bugies One Thousand Three Hundred Sixty Seven Paise Six Only	13416
4	Including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge. Providing weep holes in brick/ stone / plain reinforced concrete abutment, wing wall, return walls with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1V : 20H towards drawing face complete as per drawing and technical specifications clauses 614, 709 and 1204.3.7 including carriage of material within all leads and lifts and other incidentals, including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	30.00	Each	367.10	Bugies Three Hundred Eighty Seven Paise Ten Only	11613
	Total in Figures					333015
	Rate quoted by contractor +/-			Percent		
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Kodhal Division (B&R)
HP.PWD, Kodhal.

SCHEDULE OF QUANTITY

Job No 33
490224.00
9900.00
Two Month

Name of Work :R/R Damages on Himni valley road Km 0/00 to 17/400 (SH- C/o R/wall at RD 17/096 to 17/105 and 17/243 to 17/250)

Sr.No	Description of Items	Qty.	Unit	Rates i/c GST & all taxes		Amount
				Rate (in figure)	Rate (in words)	
1	Earth work in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads, dressing of sides and bottom and back filling in trenches with excavated suitable material in ordinary soil upto all depths, as directed by the Engineer-in-Charge, all useful material such as stone, shingle, aggregates& slate etc. shall be sorted out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	88.20	Per Cubic metre	489.20	Rupess Four thousand Eight Hundred Five Paise Nine Only	43147
2	Providing and laying cement concrete 1:6:12 (1 cement:6 sand : 12 graded stone 40mm aggregate nominal size) for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802.803, 1202 and 1203 including the cost of form work and hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	5.04	Per Cubic metre	4805.90	Rupess Four Thousand Eight Hundred Five Paise Ninety Only	24222
3	Random rubble masonry Stone masonry work in cement mortar in foundation complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203 with random rubble masonry in cement mortar 1:6 (1 cement :6 sand) . including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	85.40	Per Cubic metre	4602.90	Rupess Four Thousand Six Hundred Two Paise Ninety Only	393088
4	Providing weep holes in brick/ stone / plain reinforced concrete abutment, wing wall, return walls with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1V : 20H towards drawing face complete as per drawing and technical specifications clauses 614, 709 and 1204.3.7 including carriage of material within all leads and lifts and other incidentals. Including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	15.00	Each	387.10	Rupess Three Hundred EightySeven Paise Ten Only	5807
5	Backfilling /Filter media with granular material behind retaining wall/breast wall as per specification 1204.3.8 in a width of 600 mm. including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	17.52	Per Cubic metre	1367.60	Rupess One Thousand Three Hundred SixtySeven Paise Sixty Only	23960
	Total in Figures					490224
	Rate quoted by contractor +/-			Percent		
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Koththal Division (B&R)
H.P.W.D, Koththal.



10th NO 34

Name of Work	R/R Damages on Road	Lost Time	Earned money
...	...	...	...

Si:No

Si:No

Executive Engineer,
Kotkhai Division (B&R)
HP.PWD, Kotkhai.

SCHEDULE OF QUANTITY

Job No 35

Estimated cost:- 451084.00
Earnest money:- 9100.00
Time:- Two Month

Name of Work : R/R Damages on Reog link road Km 0/00 to 4/900 (SH:- C/o R/wall at RD 4/840 to 4/850, 4/455 to 4/470)

Description of Items

Sr.No	Description of Items	Qty.	Unit	Rate (in figure)	Rate (in words)	Amount.
1	Earth work in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads, dressing of sides and bottom and back filling in trenches with excavated suitable material in ordinary soil upto all depth, as directed by the Engineer-in-Charge, all useful material such as stone, shingle, aggregates & slate etc. shall be sorted out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	24.50	Per Cubic metre	489.20	Rupess Four Thousand Eight Hundred Five Paise Ninety Only	11985
2	Providing and laying cement concrete 1:6:12 (1 cement:6 sand : 12 graded stone 40mm aggregate nominal size) for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802.803, 1202 and 1203 including the cost of form work and hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	7.99	Per Cubic metre	4805.90	Rupess Four Thousand Eight Hundred Five Paise Ninety Only	38399
3	coarse sand : 8 graded stone aggregate 25 mm nominal size) including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	4.91	Per Cubic metre	5274.95	Rupess Five Thousand Two Hundred Seventy-four Paise Ninety-five Only	25900
4	Random rubble masonry Stone masonry work in cement mortar in foundation complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203 with random rubble masonry in cement mortar 1:6 (1 cement:6 sand) . including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	53.96	Per Cubic metre	4602.90	Rupess Four Thousand Six Hundred Two Paise Ninety Only	248372
5	Construction of dry rubble masonry for retaining walls, breast walls, . revetment walls and parapets etc for substructure and superstructure complete as per drawings and technical specifications Clause 704.6& 1302.5 including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	35.18	Per Cubic metre	2968.80	Rupess Two Thousand Nine Hundred Sixty-eight Paise Eighty Only	104442
6	Backfilling /Filter media with granular material behind retaining wall/breast wall as per specification 1204.3.8 in a width of 600 mm. including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	9.00	Per Cubic metre	1367.60	Rupess One Thousand Three Hundred Sixty-seven Paise Sixty Only	12308
7	Providing weep holes in brick/ stone / plain reinforced concrete abutment, wing wall, return walls with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1V : 20H towards drawing face complete as per drawing and technical specifications clauses 614, 709 and 1204.3.7 including carriage of material within all leads and lifts and other incidentals, including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	25.00	Each	387.10	Rupess Three Hundred Eighty-seven Paise Ten Only	9678
	Total in Figures					451084
	Rate quoted by contractor +/-			Percent		
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Kajkhal Division (B&R)
H.P.P.W.D, Kothhal.

SCHEDULE OF QUANTITY

Job No 36

Estimated cost:-
Earnest money:-
Time:-

290515.00
5900.00
Two Month

Name of Work :R/R Damages on Reog link road Km 0/00 to 4/900 (SH:- C/o R/wall at RD 4/405 to 4/420)

Sr.No	Description of Items	Qty.	Unit	Rates i/c GST & all taxes		Amount.
				Rate (In figure)	Rate (In words)	
1	Earth work in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads, dressing of sides and bottom and back filling in trenches with excavated suitable material In ordinary soil upto all depth. as directed by the Engineer-in-Charge.all useful material such as stone, shingle, aggregates& slate etc. shall be sorted out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	14.70	Per Cubic metre	489.20	Rupees Four Hundred EightyNine Paise Twenty Only	7191
2	Providing and laying cement concrete 1:6:12 (1 cement:6 sand : 12 graded stone 40mm aggregate nominal size) for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803, 1202 and 1203.Including the cost of form work and hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	4.79	Per Cubic metre	4805.90	Rupees Four Thousand Eight Hundred Five Paise Ninety Only	23020
3	Providing and laying in position cement concrete of specified grade including the cost of form work in R/walls 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 25 mm nominal size)Including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	2.95	Per Cubic metre	5274.95	Rupees Five Thousand Two Hundred SeventyFour Paise NinetyFive Only	15561
4	Random rubble masonry Stone masonry work in cement mortar in foundation complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203 with random rubble masonry in cement mortar 1:6 (1 cement :6 sand) . Including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	36.69	Per Cubic metre	4602.90	Rupees Four Thousand Six Hundred Two Paise Ninety Only	168880
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc for substructure and superstructure complete as per drawings and technical specifications Clause 704.6& 1302.5 including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	21.11	Per Cubic metre	2968.80	Rupees Two Thousand Nine Hundred SixtyEight Paise Eighty Only	62671
6	Backfilling /Filter media with granular material behind retaining wall/breast wall as per specification 1204.3.8 in a width of 600 mm. Including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	5.40	Per Cubic metre	1367.60	Rupees One Thousand Three Hundred SixtySeven Paise Sixty Only	7385
7	Providing weep holes in brick/ stone / plain reinforced concrete abutment, wing wall, return walls with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1V : 20H towards drawing face complete as per drawing and technical specifications clauses 614, 709 and 1204.3.7 including carriage of material within all leads and lifts and other incidentals. including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	15.00	Each	387.10	Rupees Three Hundred EightySeven Paise Ten Only	5807
	Total in Figures					290515
	Rate quoted by contractor +/-			Percent		
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Kotkhai Division (B&R)
HP.PWD, Kotkhai.

SCHEDULE OF QUANTITY

Job No 37

Estimated cost:-
Earnest money:-
Time:-

334270.00
6700.00
Two Month

Name of Work :-R/R damages on Sholvi Dalsar Hatli road km 0/00 to 4/675 (Sh:- C/o R/wall at Rd 0/070 to 0/080)

Sr.No	Description of Items	Qty.	Unit	Rates i/c GST & all taxes		Amount.
				Rate (in figure)	Rate (in words)	
1	Earth work in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads, dressing of sides and bottom and back filling in trenches with excavated suitable material in ordinary soil upto all depth. as directed by the Engineer-in-Charge.all useful material such as stone, shingle, aggregates& slate etc. shall be sorted out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	39.70	P/Cum	489.20	Rupees Four Hundred EightyNine Paise Twenty Only	19421
2	Providing and laying cement concrete 1:6:12 (1 cement:6 sand : 12 graded stone 40mm aggregate nominal size) for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803, 1202 and 1203.including the cost of form work and hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	3.30	P/Cum	4805.90	Rupees Four Thousand Eight Hundred Five Paise Ninety Only	15859
3	Stone masonry work in cement mortar 1:6 (1 cement :6 sand) . including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	61.10	P/Cum	4602.90	Rupees Four Thousand Six Hundred Two Paise Ninety Only	281237
4	Providing weep holes in brick/ stone / plain reinforced concrete abutment, wing wall, return walls with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1V : 20H towards drawing face complete as per drawing and technical specifications clauses 614, 709 and 1204.3.7 including carriage of material within all leads and lifts and other incidentals. including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	20.00	Each	387.10	Rupees Three Hundred EightySeven Paise Ten Only	7742
5	Backfilling /Filter media with granular material behind retaining wall/breast wall as per specification 1204.3.8 in a width of 600 mm. including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	7.32	P/Cum	1367.60	Rupees One Thousand Three Hundred SixtySeven Paise Sixty Only	10011
	Total in Figures					334270
	Rate quoted by contractor +/-			Percent		
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Kotkhal Division (B&R)
H.P.W.D, Kotkhal.

SCHEDULE OF QUANTITY

Job No 39

Estimated cost:- 380718
Earnest money:- 7700.00
Time:- Two month

Name of work:- C/o link Road Khaneti Barnog Bag road Km 0/00 to 0/075 (SH:- F/C 5/7 metre wide in km 0/00 to 0/075)

Sr.No	Description of Items	Qty.	Unit	Rates i/c GST & all taxes		Amount.
				Rate (in figure)	Rate (in words)	
1	Cutting in earth work in all heights and all kinds of soils such as spade work, pick work, jumper work, blastingwork, soft rock, hard rock chiseling work and wedging out of rocks where blasting is prohibited including their intermediate classification of soil including saturated soil and disposal of all excavated unserviceable material all leads and lifts to avoid damages to the properties of the public and Govt. and any case damages takes place the contractor is liable for it. All useful material/stones available from blasting/chiseling shall be property of department and minimum 206.42 Cum stones available from blasting shall have neatly stacked at suitable place as directed by the Engineer-in-Charge. Otherwise recovery @ 300/- per cubic meter shall be effected from the bill of the contractor. The road 5/7 meter wide 5 meter in straight and 7 meter in curves.	1130.28	Per Cubic metre.	336.83	Rupess Three Hundred Thirtysix Paice EightyThree Only	380718
	Total in Figures					380718
	Rate quoted by contractor +/-			Percent		
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Kothnai Division (B&R)
PW.D, Kothnai.

SCHEDULE OF QUANTITY

Job No 40

Estimated cost:- 404790.00
Earnest money:- 8100.00
Time:- Two month

Name of work:- C/o of Bari Gahrog Sarandhar road Km 0/00 to 1/185 (SH:- C/o 5/7 mtr wide road in km 0/915 to 1/180)

Sr.No	Description of Items	Qty.	Unit	Rates (i/c GST & all taxes)		Amount.
				Rate (in figure)	Rate (in words)	
1	Cutting in earth work in all heights and all kinds of soils such as spade work, pick work, jumper work, blasting work, soft rock, hard rock chiseling work and wedging out of rocks where blasting is prohibited including their intermediate classification of soil including saturated soil and disposal of all excavated unserviceable material all leads and lifts to avoid damages to the properties of the public and Govt. and any case damages takes place the contractor is liable for it. All useful material/stones available from blasting/chiseling shall be property of department and minimum 203.48 Cum stones available from blasting shall have neatly stacked at suitable place as directed by the Engineer-in-Charge. Otherwise recovery @ 300/- per cubic meter shall be effected from the bill of the contractor. The road 5/7 meter wide 5 meter in straight and 7 meter in curves.	1542.24	Per Cubic metre.	262.47	Rupees Two Hundred SixtyTwo FourtySeven Only	404790
	Total in Figures					404790
	Rate quoted by contractor +/-			Percent		
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Kotkhat Division (B&R)
HPTWD, Kotkhat.



SCHEDULE OF QUANTITY

Job No 41

Estimated cost:- 472712.00
 Earnest money:- 9500.00
 Time:- Two month

Name of work:- M/T on Khong to Nagan Road Km 0/00 to 0/600 (SH:- Providing laying GSB Km 0/00 to 0/600)

Sr.No	Description of Items	Qty.	Unit	Rates i/c GST & all taxes		Amount.
				Rate (in figure)	Rate (in words)	
1	Construction of granular sub-base grading-I by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401 including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	221.10	Per Cubic metre.	2138.00	Rupees Two Thousand One Hundred ThirtyEight Only	472712
	Total in Figures					472712
	Rate quoted by contractor +/-			Percent		
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
 Kothai Division (B&R)
 HP&WD, Kothai.

Job No 42

Estimated cost:-	499794.00
Earnest money:-	10000.00
Time:-	Two Month

Executive Engineer,
Kotkhai Division (B&R)
M.P.W.D, Kotkhai.

Job No 43

Estimated cost:-	424783.00
Earnest money:-	8500.00
Time:-	Two Month



SCHEDULE OF QUANTITY

Job No 44

Name of Work :- R/R Damages on Badroonighati to Badrooni road km 0/00 to 2/995 (SH:- C/o R/wall at RD 1/005 to 1/020)

Estimated cost:- 356982.00
 Earliest money:- 7200.00
 Time:- Two Month

Earth work in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads, dressing of sides and bottom and back filling in trenches with excavated suitable material in ordinary soil upto all depth, as directed by the Engineer-in-Charge; all useful material such as stone, shingle, aggregates, slate etc. shall be sorted out and stacked along the road side properly. Any loss to the public and private property to during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.		Qty.	Unit	Rate (in figure)	Rate (in words)	Amount.
1		35.70	P/Cum	489.20	Ruppes Four Hundred EightyNine Paise Twenty Only	17464
2	Providing and laying cement concrete 1:6:12 (1 cement:6 sand : 12 graded stone 40mm aggregate nominal size) for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803, 1202 and 1203,including the cost of form work and hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	3.83	P/Cum	4805.90	Ruppes Four Thousand Eight Hundred Five Paise Ninety Only	18407
3	Stone masonry work in cement mortar in foundation complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203 with random rubble masonry in cement mortar 1:6 (1 cement :6 sand) . including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	63.00	P/Cum	4602.90	Ruppes Four Thousand Six Hundred Two Paise Ninety Only	289983
4	Providing weep holes in brick/ stone / plain reinforced concrete abutment, wing wall, return walls with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1V : 20H towards drawing face complete as per drawing and technical specifications clauses 614, 709 and 1204.3.7 including carriage of material within all leads and lifts and other incidentals, including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	20.00	No	387.10	Ruppes Three Hundred EightySeven Paise Ten Only	7742
5	Backfilling /Filter media with granular material behind retaining wall/breast wall as per specification 1204.3.8 in a width of 600 mm, including hauling of material in all leads and lifts as per the entire satisfaction and direction of the Engineer-in-Charge.	17.10	Per Cubic metre	1367.60	Ruppes One Thousand Three Hundred SixtySeven Paise Sixty Only	23386
	Total in Figures					356982
	Rate quoted by contractor +/-			Percent		
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
 Kothari Division (B&R)
 P.P.W.D, Kothari.

