

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

Sealed **percentage rate** tender on form No. 6 and 7/8 are hereby invited by the **Executive Engineer (NH) Division HPPWD Nahan** on behalf of Governor of HP for the following works from approved and eligible contractor enlisted in HPPWD, so as to reach in this office on **09-02-2024** up to 11:00 AM and shall be opened on the same day at 11.30 AM in the presence of intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (non refundable) up to **08-02-2024 04:00 PM**

The earnest money in the shape of FDR/TDR of any Bank in H.P. duly pledged in favour of Executive Engineer NH Division HP.PWD Nahan must be accompanied with the each tender. Conditional tender and tender received without earnest money will be rejected. The undersigned reserves the right to reject any or all tenders without assigning the reason. The offer of the tender will be kept opened for 75 days.


Sr. No.	Name of works	Estimated Cost	Earnest Money	Time Limit	Eligible Class of contractor	Cost of Form
1	Ordinary repair to Kala Amb Paonta Sahib Dehradun road on NH-72 (New NH 07) Km 46/00 to 103/00 (SH:- Dismantling steel railing and providing & fixing M.S. steel railing in Tokiyon Bridge at RD 87/015, Meliyon Bridge at RD 88/900, Johdon Bridge at RD 92/670 & Surajpur Bridge at RD 94/030)	3,99,515/-	8000/-	01 Month	"C" & "D"	350/-
2	Ordinary repair to Nahan Do Sarka Sarahan Kumarhatti road on NH 907A Km 0/00 to 78/00 (SH:- Construction of PCC Breast wall at RD 33/464 to 33/480)	4,15,782/-	8500/-	01 Month	"C" & "D"	350/-
3	Ordinary repair to Nahan Do Sarka Sarahan Kumarhatti road on NH 907A Km 0/00 to 78/00 (SH:- Construction of PCC Breast wall at RD 33/444 to 33/462)	4,66,640/-	9500/-	01 Month	"C" & "D"	350/-
4	Ordinary repair to Kala Amb Paonta Sahib Dehradun road on NH 72 (New NH-07) Km 46/00 to 103/00 (SH:- Providing and applying painting on existing steel railing, providing and fixing hazard marker and white washing at various RD 46/00 to 96/00).	4,23,725/-	8500/-	15 days	"C" & "D"	350/-

CERTIFICATE:- It is certified that the tenders of above work are exigency/emergent nature and in public interest.

Terms & Conditions:-

1. The Contractors/Bidders must quoted their Permanent Income Tax Account Number/ GST number on the tender alongwith copy of the same be attached with the application.
2. The Contractors/Firms should attach copy of the Registration/Renewal with the application.
3. The contractor/bidders should quote his rates Both in Figures and words, where there is any discrepancy between the rates in figures and words, the rates in words will be governed.
4. The contractors/bidders must inspect the site to ascertain/familiar the site conditions, accessibility etc. before quoting the bid/tender.
5. Conditional and telegraphic tender shall not be accepted and rejected straightway. Tender received after due date and time will be rejected.
6. The contractor/firms should have to produce the details of works in hand in HP. PWD, and its position thereof alongwith application.


7. The tender documents shall be issued to only those contractors who does not have more than two works in hand in any PWD Circle/ Division worth Rs. 1.00 Crore each.
8. The Contractor shall have to establish testing laboratory at site for the day to day testing of material.
9. The offer shall remain valid upto 75 days.
10. The provision of guidelines issued vide the Principal Secretary (PW) to the Govt. of H.P, Shimla vide notification No. PBW (B) A (3) 1/2020-I dated Shimla-2 the 22nd July, 2020 and 07.10.2021 regarding adoption of CPWD work manual 2019 & other publication of CPWD in HPPWD and others as published by the Govt. from time to time Shall also be applicable.
11. The Executive Engineer reserve the right to reject any or all the tenders without assigning any reason.


Executive Engineer
NH Division HPPWD
Nahan
Tele No. 01702-222202

For & on behalf of Governor of Himachal Pradesh

No. PW/NHD-NHN/TA-Tender Notice/ 2023-24: 5137-77 dated:- **24-01-2024**
Copy along with NIT is forwarded to the following for kind information and necessary action please:-

- 1 The Engineer in Chief HPPWD Nirman Bhawan, Niagam Bihar Shimla.
- 2 The Chief Engineer (NH) HPPWD Shimla please.
- 3 The Deputy Commissioner, Sirmour at Nahan please.
- 4 The Superintending Engineer (NH) Circle HPPWD Shimla.
- 5 The Executive Engineer (IT Cell), to the Engineer-in-Chief HPPWD, Nigam Vihar, HPPWD Shimla-2 alongwith Schedule of Quantity through (email) for taking necessary action in view of Principal Secretary (PW) to the H.P. notification No. PBW (B) A (3) dated 16 July, 2021 for uploading of Notice Inviting Tender on departmental website please.
- 6 The Sub-Divisional Magistrate Nahan/ Paonta Sahib/Pachhad please.
- 7 The District Panchayat Officer, Nahan please.
- 8 The Executive Officer, Municipal Committee Nahan/ Paonta Sahib please.
- 9 All the Assistant Engineer under this division to display on their respective Notice Boards.
- 10 Notice Board of this Office.


Executive Engineer
NH Division HPPWD
Nahan

Job No. 1

SCHEDULE OF QUANTITY						
Name of work:- Ordinary Repair to Kala Amb Paonta Sahib Dehradun road on NH-72 (New NH 07) Km 46/00 to 103/00 (SH:- Dismantling steel Railing and Providing and fixing M.S. steel Railing in Tokiyon Bridge at RD 87/015, Meliyon Bridge at RD 88/900, Johdon Bridge at RD 92/670 & Surajpur Brodge at RD 94/030)						
Sr.No	Description of item/Sub Head	Quantity	Unit	Estimated cost :- Earnest Money :-		One Month Total Amount in word
				Estimate Rate	Total Amount	
1	2	3		4	5	7
1	Dismantling guard rails by manual means and disposal of dismantled material with all lifts and up to a lead of 1000 metres, stacking serviceable materials and unserviceable materials separately including all leads, lifts and carriage of all labour equipments and materials to various locations including all leads, lifts and carriage of all labour equipments and materials to various locations including all taxes, MC taxes etc through all modes of transportation, including all incidental charges as per the direction and entire satisfaction of the Engineer-in-charge.	65.00	Per Rmt	138.85	9025.00	Nine thousand twenty five only
2	Providing and fixing in position pipe railing consisting of IS Rolled steel joist posts designation IS MB 100 (100x75) at 1.5 m interval height 1.60 mtr. and three rows of 50 mm dia steel pipes (light) including fixing in position on bridge deck complete as per drawing and technical specifications Clause 1208.2 including all leads, lifts and carriage of all labour equipments and materials to various locations including all taxes, MC taxes etc through all modes of transportation, including all incidental charges as per the direction and entire satisfaction of the Engineer-in-charge.	95.00	Per Rmt	2957.35	280948.00	Two lakh eighty thousand nine hundred forty eight only
3	Providing and laying P.C.C grade M 15 concrete graded crushed stone aggregate 20mm (Twent millimetre) nominal size for plain/reinforced concrete in open foundations and drain complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 including all leads, lifts and carriage of all labour equipments and materials to various locations including all taxes, MC taxes etc through all modes of transportation, including all incidental charges as per the direction and entire satisfaction of the Engineer-in-charge.	11.25	Per Cum	6128.30	68943.00	Sixty eight thousand nine hundred forty three only
4	Providing concrete for plain / reinforced (R.C.C. M-20) (twenty) cement at the rate of 6.60 bags per cubic metre nominal mix 1:2:4 (one cement: two sand : four trusted stone aggregate twenty millimetres nominal size) in open foundations complete as per drawings and technical specifications clause 802, 1202 and 1203 including all leads, lifts and carriage of all labour equipments and materials to various locations including all taxes, MC taxes etc through all modes of transportation, including all incidental charges as per the direction and entire satisfaction of the Engineer-in-charge.	5.70	Per Cum	7122.65	40599.00	Forty thousand five hundred ninety nine only
Total :-					399515.00	Three lakh ninety nine thousand five hundred fifteen only
Quoted Rate % (Percentage) in Figures		(+) / (-)				
Quoted Rate % (Percentage) in Words						

The contractor shall procure all the materials conforming to specification MORT&H at his own risk and cost. All the rates including octroi, royalty, malikhana, toll tax, GST or other taxes imposed by the Government.

Executive Engineer
NH Division
HPPWD Nahan

Name of Work: Ordinary repair to Nahan Do Sarka Sarahan Kumarhatti road on NH 907		SCHEDULE OF QUANTITY
PCC Breast wall at RD 33/464 to 33/480)		

The contractor shall procure all the materials conforming to specification MORT&H at his own risk and cost. All the rates including octroi, royalty, malikana, toll tax, GST or other taxes imposed by the Government.

Nase
Executive Engineer
NH Division
HPPWD Nahan

Job No. 3

SCHEDULE OF QUANTITY									
Name of Work:- Ordinary repair to Nahar Do Sarka Sarahan Kumarhatti road on NH 907A Km 0/00 to 78/00 (SH:- Construction of PCC Breast wall at RD 33/444 to 33/462)									
Estimated cost :- Earnest Money :-		Time Limit :-							
One Month.		Total Amount in word							
Sr.No	Description of item/Sub Head	Quantity	Unit	Estimate Rate	Total Amount				
1	2	3		4	5	7			
1	Excavation for roadwork in soil with hydraulic excavator including cutting and loading in tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transporting to the embankment location including all leads, lifts and carriage of all labour equipments and materials to various locations including all taxes, MC taxes etc through all modes of transportation, including all incidental charges as per the direction and entire satisfaction of the Engineer-in-charge.	32.76	Per Cubic metre	175.95	5764.00	Five thousand seven sixty four only			
2	Providing and laying P.C.C grade M 15 concrete graded crushed stone aggregate 20mm (Twent millimetre) nominal size for plain/reinforced concrete in open foundations and drain complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 including all leads, lifts and carriage of all labour equipments and materials to various locations including all taxes, MC taxes etc through all modes of transportation, including all incidental charges as per the direction and entire satisfaction of the Engineer-in-charge.	67.47	Per Cubic metre	6703.90	452312.00	Four lakh fifty two thousand three hundred twelve only			
3	Providing weep holes in Brick masonry/Plain/ Reinforced concrete abutment, wing wall/ return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V: 20H towards drawing face. Complete as per drawing and Technical Specifications including all leads, lifts and carriage of all labour equipments and materials to various locations including all taxes, MC taxes etc through all modes of transportation, including all incidental charges as per the direction and entire satisfaction of the Engineer-in-charge.	34.20	Each	250.40	8564.00	Eight thousand five hundred sixty four only			
Total :-					466640.00	Four lakh sixty six thousand six hundred forty only			
Quoted Rate % (Percentage) in Figures		(+) / (-)							
Quoted Rate % (Percentage) in Words									

The contractor shall procure all the materials conforming to specification MORT&H at his own risk and cost. All the rates including octroi, royalty, malikhana, toll tax, GST or other taxes imposed by the Government.


Executive Engineer
NH Division
HPPWD Nahar

Job No. 4

SCHEDULE OF QUANTITY

Name of Work:- Ordinary repair to Kala Amb Paonta Sahib Dehradun road on N.H. 72 (New NH-07) KM 46/0 to 103/0 (SH :- Providing and applying painting on existing steel railing, Providing and fixing hazard marker and white washing at various RD 46/00 to 96/00).

Sr.No	Description of item/Sub Head	Quantity	Unit	Estimated cost :- Earnest Money :-		Rs.423725/- only RS.8500/-only
				Time Limit :- Estimate Rate	Total Amount	Total Amount in word
1	2	3		4	5	7
1	Clearing and Grubbing Road Land:- Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned, up to a lead of 1000 metres including removal and disposal of top organic soil not exceeding 150 mm in thickness. including all leads, lifts and carriage of all labour equipments and materials to various locations including all taxes, MC taxes etc through all modes of transportation, including all incidental charges as per the direction and entire satisfaction of the Engineer-in-charge.	9000.00	Per Sqm	4.35	39150.00	Thirty nine thousand one hundred fifty only
2	Painting on steel surface :- Providing and applying two coats of ready mix paint of approved brand on steel surface after thorough cleaning of surface to give an even shade including all leads, lifts and carriage of all labour equipments and materials to various locations including all taxes, MC taxes etc through all modes of transportation, including all incidental charges as per the direction and entire satisfaction of the Engineer-in-charge.	1116.19	Per Sqm	68.00	75901.00	Seventy five thousand nine hundred one only
3	Painting Two Coats on New Concrete Surfaces:- Painting two coats after filling the surface with synthetic enamel paint in all shades on new plastered concrete surfaces including all leads, lifts and carriage of all labour equipments and materials to various locations including all taxes, MC taxes etc through all modes of transportation, including all incidental charges as per the direction and entire satisfaction of the Engineer-in-charge.	1740.00	Per Sqm	99.35	172869.00	One lakh seventy two thousand eight hundred sixty nine only
4	White washing with lime two coats on parapets walls, road side drains, guide stones and trees trunk etc. including preparation of surface by cleaning scraping etc. thoroughly brooming the surface and remove all dirt, dust, mortar dirt and other foreign matter including carriage of material by mechanical means including all leads, lifts and carriage of all labour equipments and materials to various locations including all taxes, MC taxes etc through all modes of transportation, including all incidental charges as per the direction and entire satisfaction of the Engineer-in-charge.	972.90	Per Sqm	26.20	25490.00	Twenty five thousand four hundred ninety only
5	Providing and fixing hazard marker of size 900x300mm made of 2mm thick aluminum sheet with back support of M.S angle 25x25x3mm as per clause 800 of MoRT&H specifications complete board process by heat treatment process. Hi grade sheeting of front side and provided with by post of Ht. 1.50mtr. made of M.S angle 50x50x6 mm fixed in C.C 1:2:4 back of size 600x600x600 including all leads, lifts and carriage of all labour equipments and materials to various locations including all taxes, MC taxes etc through all modes of transportation, including all incidental charges as per the direction and entire satisfaction of the Engineer-in-charge.	20.00	Nos	5515.75	110315.00	One lakh ten thousand three hundred fifteen only
Total :-					423725.00	Four lakh twenty three thousand seven hundred twenty five only
Quoted Rate % (Percentage) in Figures						
Quoted Rate % (Percentage) in Words						

The contractor shall procure all the materials conforming to specification MORT&H at his own risk and cost. All the rates including octroi, royalty, malkhana, toll tax, GST or other taxes imposed by the Government.

Executive Engineer
NH Division
HPPWD Nahan