

Himachal Pradesh
Public Works Department
PW-RD-GA-Tender-2023-24-
To

20827

dated:- 17-1-2024


The Executive Engineer (IT Cell)
Nigam Bihar, Shimla-2.

Subject: - Tender notice.

Enclosed please find herewith the tender notice of work as given in the notice inviting tender for uploading on department website as per notification Pr. Secy. (PW) to the Govt. of H.P. letter N. PBW (B) A (3) 1/2020 dated Shimla-2 the 16th July 2021.

1. Certified that the tender mentioned in the notice is exigencies/emergency are urgent nature and in public interest.

DA:- Notice inviting tender & schedule of quantity.


Executive Engineer,
B&R Division, HPPWD,
Rohru

**Himachal Pradesh
Public Works Department
"NOTICE INVITING TENDERS"**

*Sealed item rate tender on form PWD 6&8 are invited by the Executive Engineer
Rohru Division HPPWD, on behalf of Governor of H.P. for the following works from the approved and
eligible contractors enlisted in HPPWD, So as to reach in this office as per time schedule given below:-*

1. Date of receipt of applications for tender forms:- 29.01.2024 upto 1:00PM
2. Date of issue/sale of tender forms:- 29.01.2024 upto 2:00PM to 3.00PM
3. Date of receipt of tender:- 30.01.2024 upto 3:30PM

Sl. No.	Name of work	Estimated cost	Earnest money	Time allowed
1	R/R damages on Banoti Kandra road km 0/0 to 5/0 (SH:- C/o B/Wall in wire crate at RD. 0/440 to 0/480)	471160	9423	Two Months
2	C/o Link road from Kuradi gard to Udru road km 0/0 to 1/700 (SH:- C/o 5/7 mtr wide formatoin cutting at RD 0/0 to 0/090)	465976	9320	Two Months
3	R/R damages on Badiyara Jangla Todsa Devidhar Banoti road km 0/0 to 11/0 (SH:- Removal of slips at various RD. 0/795 to 1/300)	433055	8661	Two Months
4	R/R damages on Bsiyara Jangla Todsa Devidhar Banoti road km 0/0 to 11/0 (SH:- Removal of slips at various RD. 1/970 to 10/830)	430338	8607	Two Months
5	C/O RCD. Road km 0/0 to 21/195 (SH:- Removal of slips between Km RD. 16//650 to 16/680, 16/810 to 16/825, 17/825 to 17/855, 18/975 to 18/990, 19/570 to 19/600.)	203899	4078	Two Months
6	C/O Link road Harbal Gardan to Mangil Ambushau km 0/0 to 3/0 (SH:- F/c 5/7 mtr.wide road km 1/180 to 1/285)	499721	9994	Two Months
7	C/O Link road Harbal Gardan to Mangil Ambushau km 0/0 to 3/0 (SH:- C/O R/wall at RD. 1/105 jto 1/135)	434885	8698	Two Months
8	R/R damages on various road under Badiyara Section Chirgaon Sub-Division (SH:- Hiring of JCB for removal of slips & dressing of road surface)	495000	9900	Two Months
9	C/O Link road to Parsa Lowerkoti Chuppari km 0/0 to 10/0 (SH:- C/O R/Wall in PCC 1:4:8 at RD 0/265 to 0/275)	370884	7418	Two Months
10	C/O link road to Parsa Lowerkoti Chuppari km 0/0 to 10/0 (SH:- C/O R/Wall in PCC 1:4:8 at RD 0/280 to 0/290)	379976	7600	Two Months
11	R/R damages to various Roads Under Samoli section sub-Division Rohru (SH:- Hiring of JCB for removal of slips and land maintenance of road)	495000	9900	Two Months
12	R/R damages to various Roads Under Samoli section sub-Division Rohru (SH:- Hiring of Tipper for carriage of excavated earth muck etc.)	279000	5580	Two Months
13	R/R damages to various roads under Chirgaon Sub-Divn (In Badiyara Section) (SH:- Hiring of Tipper for carraige of muck / Slips)	495000	9900	Two Months

14	R/R damages to various roads under Chirgaon Sub-Divn (In Badiyara Section) (SH:- Removal of snow/slips by JCB at various RDs and spreading of earth /sand on slippry road surface)	487200	9744	Two Months
15	C/o Bautinallah Kanda road km 0/0 to 2/500 (SH:- P/L local GSB at RD 0/730 to 1/460)	352211	7044	Two Months
16	C/o Bautinallah Kanda road km 0/0 to 2/500 (SH:- P/L local GSB at RD 2/190 to 2/500)	166701	3334	Two Months
17	R/R damages to various roads under Chirgaon Sub-Divn (In Badiyara Section) (SH:- Removal of snow/slips by JCB at various RDs and spreading of earth /sand on slippry road surface)	487200	9744	Two Months
18	R/R damages to various roads under Chirgaon Sub-Divn (In Badiyara Section) (SH:- Removal of snow/slips by JCB at various RDs and spreading of earth /sand on slippry road surface)	487200	9744	Two Months
19	C/o Samoli Sainji Bhatwari road km /0 to 7/ (SH:- P/L GSB. With local materials at various RDs. Bwteen km RD. 0/0 to 2/0)	367584	7352	Two Months

Certified that the tender mantioned in the notice is exigencies/emergency are urgent nature and in public interest.

Terms and conditions:-The tender doucument shellbe issued only to these contractors/firms who fulfill the following criteria and submit the following doucument with the application.

1. The Earnest-money for the above works should be submitted with the application for the purchase of the tender-documents.
2. The Contractors should quoted the rates of all the items in the tenders both in figures and words.
3. Income tax & GST No latest clearance certificate.
4. The contrs / firm shall accompany his enlistment/renewal & EPF submit before the award of tender.
5. The contractors should apply for two works only at a time for tenders.
6. The Executive Engineer reserves the right to accept/rejected any tender/application or all tenders without assigning any reason.

Executive Engineer,
B&R Divisio HPPWD,
Rohru

NO.:-PW-RD-AB-Tender /2023-24-20727-20826

Dated:- 17-1-2024

Copy forwarded for information and wide publicity to:-

1. The Chief-Engineer(S), HPPWD, Shimla-2.
3. The S E 14th Circle HPPWD, Rohru
4. All the E.E.'s under 14th Circle, HPPWD, Rohru
5. All the A.E.'s working under this Division (B&R).
6. The Sub Divisional Magistrate, Rohru.
7. The B.D.O. Rohru and Chirgaon.
8. The Tehsildhar, Rohru/Chirgaon and Tikkar.
9. The Chairman, N.A.C. Rohru.
10. A/B. and D/B. in this Office.
11. Notice-Board.

Executive Engineer,
B&R Division HPPWD
Rohru.

DRAFT SCHEDULE OF QUANTITY

Estimated cost Rs. 4,71,160/-
Earnest Money Rs. 94500/-
Earnest Money Rs. 5600/-

Name of work :- R/R Damages to Banoti Kandra road km 0/0 to 3/0 (SH- B/wall in wire crate at Rd 0/440 to 0/480)

Sr No	Description of items	Quantity	Rate in Figure.	Rate in Words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per drawing and Technical Specification Clause 1603.1 and as per the direction of the Engineer-in-Charge including carriage of material through all modes of transportation within all leads and lifts and other incidentals	49.40	186.32	Rs one hundred eighty six & paise thirty two only	per cubic metre	7900
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in ordinary rocks up to 3 mtr depth within all leads and lifts as per directions of Engineer in charge	16.80	407.00	Rs four hundred seven only	per cubic metre	6838
3	Providing and laying of boulder apron laid in wire crates 4mm dia G.I wire conforming to IS 280 and IS 4826 in 100mmx100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specification clause 1301 within all leads and lifts as per directions of Engineer in charge	125.00	2890.00	Rs two thousand eight hundred ninety	per cubic metre	361250
4	Removal of land slide /slips clearance Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal material within a lifts upto 1.5 miles and land upto 1000 metre as per technical specifications as per directions of Engineer	660.00	144.20	Rs one hundred forty four & paise twenty only	per cubic metre	95172
						471160

DNTT NO Approved for Rs. 4,71,160/- for the year 2023-24

Quoted Rate in figure	(+) (+)	%
Quoted Rate in Words	(+) (+)	%

Signature of Contractor with full Address

Executive Engineer
B&R Divn HP, PWO
Rohru

DNT/ SCHEDULE OF QUANTITY

Job No.

Estimated Cost:-465977/-
Earnest Money:-9400/-

Time:-One Month

NAME OF WORK:-C/O link road from Kuradi Gard to I dru road km.0/0 to 1/700 (SH:-Formation cutting 5/7 mtrs. Wide at RD. 0/0 to 0/20)

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, graded width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification Clause 300.1603.1.1603.2, sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road way, embankment for grade improvements and disposal of all unuseful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, along with its levelling fine dressing and carriage of machineries, materials tools equipments and safety means and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work hard rock 1/6th (One sixth) blasting work soft rock 1/10th (one 10th) jumper work in all cases failing which recovery shall be effected on the prevailing market rates. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the entire Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate including octroi, royalty, Markana, toll tax sale tax or other taxes imposed by the Government A recovery of useful stones 271.43 cum metre @ Rs. 300/- Per cubic metre shall be done on pro-rata basis in each running bill for this item. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The serviceable material will be stacked out specified dimension in all leads and lift as per the direction of Engineer in charge	1592.93	292.528	Rupess:- Two Hundred Ninety Two and Paisa Five Two Eight only	Cum	465977
Total:-						465977

DNT No.

Approved for Rs.465977/- only for the Year 2023-2024

Quoted rate in figure
 Quoted rate in words
 Signature of contractor with address:-

Executive Engineer
B&R Division
HP, PM D Kohru

DRAFT SCHEDULE OF QUANTITY

Estimated cost Rs 4,33,055/-
 Earnest Money Rs 8600/-
 Time one Month

Name of work :- R/R Damages Badiyara Jangla Todsa Devdhar Banoti road km 0/0 to 11/0(SH- Removal of sops at various RD 0/795 to 1/300

Sr No	Description of Items	Quantity	Rate in Figure.	Rate in Words	Unit	Amount
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means in cluding culging and timing of sops and disposal of cut materials within all lifts 1.5 metres leads upto 100m as per technical specifications 302.2.5 and 1611 within all leads and lifts as per directions of Engineer in charges	1874.70	231.00	Rs two hundred thirty one only	per cubic metre	433055
DNIT NO Approved for Rs 4,33,055/- for the year 2023-24						433055

Quoted Rate in figure	(+) (-)	%
Quoted Rate in Words	(+) (-)	%

Signature of Contractor with full Address

Executive Engineer
 B&R Dym HP,PWD
 Rohru

DRAFT SCHEDULE OF QUANTITY

Estimated cost Rs 4,30,338.00
 Earnest Money Rs 8600/-
 Time one Month

Name of work :- R/R Damages Badiyara Jangla Todsa Devidhar Banoli road km 0/0 to 11/0(SH- Removal of slips at various RD 1/970 to 10/830

No	Description of Items	Quantity	Rate in Figure.	Rate in Words	Unit	Amount
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means in cluding cutting and timing of slips and disposal of cut materials within all lifts 1.5 metres leads upto 100m as per technical specifications 302.25 and 1611 within all leads and lifts as per directions of Engineer in charges	1862.94	231.00	Rs two hundred thirty one only	per cubic metre	430338
DNIT NOApproved for Rs 4,30,338.00 for the year 2023-24						430338

Quoted Rate in figure (+) (-)	%
Quoted Rate in Words (+) (-)	%

Signature of Contractor with full Address

Executive Engineer
 B&R Dwn HP, PWD
 Rohru

5

22

5

Job No.

DNIT/ SCHEDULE OF QUANTITY

A.R. Duggal

Estimated Cost:-203899/-

Earnest Money:-4100/-

Time:-One Month

NAME OF WORK:- ~~CCA~~ RCD Road road km. (SH:- Removal of slips at various RDs. 16/650 to 680 , 16/810 to 825, 17/825 to 855, 18/975 to 990 , 19/570 to 600)

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slope and disposal of cut material with in all leads and lifts upto 1.5m and lead upto 100 m as per technical specification 302.305 and 1611 as per directed by the Engineer in charge	882.68	231.00	Rupees:- Two Hundred Thirty One and Paise /zero only	Per Cum	203899

DNIT No.

Approved for RS.203899/- only for the Year 2023-2024

	Quoted rate in figure	%
	Quoted rate in words	%
	Signature of contractor with address	

Executive Engineer
B&R Division
A.W.D Rohru

SCHEDULE OF QUANTITY.

Estimated cost Rs 499421/-
Earnest money Rs 10000/-
TIME : Two month

2

Name of work :- C/O link road Harban Garden to Mangli Ambushau km 0/0 to 3/0 (SH-F/C 5/7 metre wide road at Rd 1/1/80 to 1/2/85)

Sr No	Description of Items	Quantity	Rate in Figure	Rate in Words	unit	Amount
1	Excavation in earth work in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side. Water pollution, etc and to protect soil stability of hill side rock shall be excavated with chiseling and wedging our rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to line, grades, slopes, width, camber, super elevation and level as shown on the drawing as per direction of Engineer in Charge in conformity with the requirement of technical specification for rural roads august 2004 clause 16.2 of general conditions of contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and stage. disposal of unsuitable cut material in specified manner. trimming/filling of unevenness bludge and finishing of the road to specified dimensions or as directed by Engineer in charge for smooth riding The recovery of useful stones shall be made from the contractor and recovery 241.307 cubic meter useful stones shall be made @300/-per cubic meter on pro rata basis in each running bill. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The serviceable material will be stacked out specified dimension in all leads and lifts as per the direction of Engineer in Charge.	1765.80			per cubic metre	
	Total:-					

Executive Engineer
BAR Divn HP PWD
Rohru

DRAFT OF SCHEDULE OF QUANTITY

Estimated cost Rs 434859—
Earnest money Rs 8600/-
Time one Month

Name of work : C/O link rod Harbal Gardan to Mangli Ambushau road km 0/0 to 3/0 (SH- R/wall at Rd 1/105 to 1/135)

Sr No	Description of Items	Quantity	Rate in Figure	Rate in Words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per drawing and Technical Specification Clause 1603.1 and as per the direction of the Engineer-in-Charge including carriage of material through all modes of transportation within all leads and lifts and other incidentals.	40.50	195.30	Rs one hundred ninety six & paise thirty only	per cubic metre	7950
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in ordinary rocks up to 3 m depth within all leads and lifts as per directions of Engineer in charge	21.30	566.97	Rs five hundred sixty six & paise ninety seven only	per cubic metre	12076
3	Providing and laying of boulder apron laid in wire grate with 4mm G.I wire conforming to IS 280mm IS 4828 100mm mesh (woven diagonally) including 10 percent extra laps and joints and wire somme boulders weighing not less than 25kg as per drawing technical specification clause 1301 within all leads and lifts as per direction of Engineer in charge	140.63	2950.00	Rs two thousand nine hundred thirty only	per cubic metre	414859
	Total					434859

DNIT NO Approved for Rs 434859 under the year 2023-2024

1720

Executive Engineer
B&R Divn HP.PWD
Rohru

2

①

⑧

Job No.

DNIT/ SCHEDULE OF QUANTITY

Estimated Cost:- 495000/-

Earnest Money:- 9900/-

Time:- Three Months

NAME OF WORK:- R/R damages to various road under Badiyara Section Chirgaon Sub-Division (Slt:- Hiring of JCB for removal of slits/drain & dressing of road surface)

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Hiring of J.C.B (Excavator cum-loader) having bucket capacity 0.45 cum including POL charges shifting charge and other ancillary equipments as required at site as per instruction of the Engineer in charge including all leads and lifts.	450.00	1100.00	Rupees:- One Thousand One Hundred and Paise / zero only	Per Hour	495000
Total:-						495000
DNIT No. _____ Approved for Rs.495000/- only for the Year 2023-2024						
Quoted rate in figure _____ %						
Quoted rate in words _____ %						
Signature of contractor with address:- _____						

Executive Engineer
B&R Division
H.P. PM D Rohru

✓

11

9

DNIT/ SCHEDULE OF QUANTITY

NAME OF WORK:- C/O link road to Parsa Lowerkot Chuppari km. 0/0 to 10/0 (SH:-C/O R/W all in PCC 1:4:8 at RD.0/265 to 0/275)

Job No. _____

Estimated Cost:-370884/-

Earnest Money:-7500/-

Time:-One Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material as directed by the Engineer-in-Charge	22.50	407.00	Rupees:-Four Hundred Seven and Paisa Zero only	Cum	9158
2	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	2.70	6314.00	Rupees:-Six Thousand Three Hundred Forteen and Paisa Zero only	Cum	17048
3	Plain/reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	49.35	6656.00	Rupees:-Six Thousand Six Hundred Fifty Six Paisa Zero Only.	Cum	328474
4	Providing and laying of back filling behind abutment wing wall and return walls with granular material complete as per MORID technical specification clause 1204.3.8 as directed by the Engineer-in-Charge	6.50	1474.00	Rupees:-One Thousand Four Hundred Seventy Four Paisa Zero only.	Cum	9581
5	Providing weephole in brick masonry /stone masonry ,plain/ reinforced concrete abutment wing wall, return wall with 100mm dia AC pipe extending through the full width of the structures with slope of 1 (V):20(H) towards drawing face complete as per drawings and technical specification Clauses614.709, 1204.3.7 as directed by the Engineer-in-Charge	16.00	414.00	Rupees:-Four Hundred Forteen Paisa Zero only.	No.	6624
				Total:-		370884
		DNIT No. _____ Approved for Rs.494573/- only for the Year 2023-2024				
</						

Executive Engineer
B&R Division
HP, PWD Rohru

42-10

DNIT/SCHEDULE OF QUANTITY

NAME OF WORK:- C/O link road to Parsa Lowerkotli Chuppari km. 0/0 to 10/0 (S.H.-C/O RAW all in PCC 1:4:8 at RD.0/280 to 0/290)

Job No. _____
Estimated Cost:-379976/-
Earnest Money:-7600/-
Time:-One Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material as directed by the Engineer-in-Charge	22.50	407.00	Rupees:-Four Hundred Seven and Paise Zero only	Cum	9158
2	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	4.14	6314.00	Rupees:-Six Thousand Three Hundred Forteen and Paise Zero only	Cum	26140
3	Plain/reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	49.35	6656.00	Rupees:-Six Thousand Six Hundred Fifty Six Paise Zero Only	Cum	328474
4	Providing and laying of back filling behind abutment wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3.8 as directed by the Engineer-in-Charge	6.50	1474.00	Rupees:-One Thousand Four Hundred Seventy Four Paise Zero only.	Cum	9581
5	Providing weep hole in brick masonry, stone masonry, plain/ reinforced concrete abutment wing wall, return wall with 100mm dia AC pipe extending through the full width of the structures with slope of 1 (V):20(H) towards drawing face complete as per drawings and technical specification Clauses 614, 709, 1204.3.7 as directed by the Engineer-in-Charge	16.00	414.00	Rupees:-Four Hundred Forteen Paise Zero only.	No.	6624
Total:-						379976
DNIT No. _____ Approved for Rs.379976/- only for the Year 2023-2024						
Quoted rate in figure		%				
Quoted rate in words		%				
Signature of contractor with address:-						

Executive Engineer
B&R Division
HP.PWD Rohru

SCHEDULE OF QUANTITY

Name of work :- R/R to various road under Samoli section sub Division samoli (SH-Hiring of JCB for removal of slips and land slide mainteance of road

Estimate Cost Rs 4,95,000/-
Earnest Money 9000/-
Time :- 60 days

Sr No.	Sub-Head and Item of works	Quantity	Rate in figures.	Rate in words.	Unit	Amount.
1	Hiring of J.C.B (Excavator-Cum-Loader) having bucket capacity 0.45 including P.O.L charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum single boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road burns. Minimum 18.00 cubic meter of earth work shall be done by machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts	450.00	1100.00	One thousand one hundred only	per day	495000.00
					Total	495000.00

Quoted Rate in figure (+/-)	%
Quoted Rate in Words (+/-)	%

Signature of Contractor with full Address

Executive Engineer
B&R Divn HP PWD
Rohru

SCHEDULE OF QUANTITY.

Estimate Cost 2,79,000/-
Earnest Money 5500/-
Time 60 days

(12)

Name of work :R/R Damages to various road Samoli section sub Division Rohru (SH- Hiring of Tipper for carriage of Execavated earth muck etc						
Sr.No.	Sub-Head and Item of works	Quantity	Rate in figures	Rate in words.	Unit	Amount
1	Hiring of Tipper for carriage of material having capacity 400cft including P.L.O charges shifting charges and other ancillary equipment at site of work. The work shall have to carried out as per ministry of Transport specifications of Engineer in charge within all leads and lifts	45.00	6200.00	Six thousand two hundred only	per days	279000.00
Total					Total	279000.00
<div> <div>Quoted rate in Fig (+)(-)</div> <div>%</div> <div>Quoted rate in words (+)(-)</div> <div>Signature of Contractor with full Address</div> </div>						


 Executive Engineer
 B&R Divn HP PWD
 Rohru

SCHEDULE OF QUANTITY.

(13)

Estimate Cost 4,95,000/-
 Earnest Money 1,00,000/-
 Time 90 days

Name of work :- R/R Damages to various road under Chingason sub Divn (in Badiyara Section)(Hiring of Tipper for carriage of Muck /slips					
Sl.No.	Sub-Head and Item of works	Quantity.	Rate in figures.	Rate in words.	Unit
1	Hiring of Tipper for carriage of material having capacity 400cft including P.L.O charges shifting charges and other ancillary equipment at site of work. The work shall have to carried out as per ministry of Transport specifications of Engineer in charge within all leads and lifts	76.00	6600.00	Six thousand six hundred only	per days
Total					485000.00

Quoted rate in Fig (+) (-)	%
Quoted rate in words (+) (-)	
Signature of Contractor with full Address	

Executive Engineer
 B&R Divn HP, PWD
 Rorlu

SCHEDULE OF QUANTITY

Name of work :- R/R to various road under sub Division chitgaon sub Divn (in Baidyara section)(SH- Removal of slips /and slide road surface)

Estimate Cost Rs 4,87,200/-
Earnest Money 10000/-
Time :- 60 days

(14)

Sr.No.	Sub-Head and Item of works	Quantity	Rate in figures.	Rate in words.	Unit	Amount
1	Hiring of J.C.B.(Excavator-Cum-Loader) having bucket capacity 0.45 including P.O.L charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road burms. Minimum 18.00 cubic meter of earth work shall be done by machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.	58.00	8400.00	Rs eight thousand four hundred only	per day	487200.00
					Total	487200.00

Quoted Rate in figure (+/-)	%
Quoted Rate in Words (+/-)	%

Signature of Contractor with full Address

Executive Engineer
B&R Divn HP PWD
Rehnu

DRAFT SCHEDULE OF QUANTITY

Estimated cost Rs. 3,52,211/-
Current money Rs 7000/-

Time :- one month

Name of work : - C/o Bautinallah Kanda road km 0/0 to 2/0(SH- P/L local GSB at Rd 0/730 to 1/460)

Sr No	Description of Items	Quantity	Rate in Figure.	Rate in Words	Unit	Amount
1	Preparation of sub grade by dressing to camber (earth work for the cutting involved for sub grade to be paid for separately) (upon upon the classification of soil complete as per HP, PWD specification including carriage of materials within all leads and lifts as per direction of Engineer in charge	2690.05	2.08	Rs two & paise eight only	per square	5595
2	Consolidation of sub grade with road roller making good the undulation etc with earth quarry soil etc and re-rolling the sub grade complete as per HP, PWD specification within all leads asnd lifts as per directions of Engineer in charge	2690.00	1.35	Rs one & paise thirty five only	per square	3632
3	Construction of granular sub base by surface courses with local materials table 400.13 mixing in place method normal construction granular sub base by providing local materials spreading in uniform layer with motor grader on prepared surface mixing by mix in place method with reclaimer at once and comp-acting with smooth wheel roller to achieve the desired density complete as per clause 401.4 as per technical specification clause 408 within all leads and lifts as per direction of Engineer in charge	403.51	850.00	Rs eight hundred fifty only	per cubic metre	342984
Total:-						352211

DNT NO. Approved for Rs 3,52,211/- for the year 2023-24

Quoted Rate in Figure (+) (-)

Quoted Rate in Words (+) (-)

%

Signature of Contractor with full Address

Executive Engineer
BGR Divn HP, PWD
Rohru

DRAFT SCHEDULE OF QUANTITY

Estimated cost Rs. 1,66,701/-
 Earnment money Rs 3500/-
 Time :- one month

Name of work : - C/o Bauti Nalliah Kanda road km 0/0 to 2/500-4 SH- P/L local GSB at RD 2/190 to 2/500

Sl.No	Description of Items	Quantity	Rate in Figure.	Rate in Words	Unit	Amount
1	Preparation of sub grade by dressing to camber (earth work for the cutting involved for sub grade to be paid for separately) upon the classification of soil complete as per HP PWD specification including carriage of materials within all leads and lifts as per direction of Engineer in charge	1142.35	2.08	Rs two & paise eight only	per square	2376
2	Consolidation of sub grade with road roller making good the undulation etc with earth quarry soil etc and re-rolling the sub grade complete as per HP PWD specification within all leads and lifts as per directions of Engineer in charge	1142.00	1.35	Rs one & paise thirty five only	per square	1542
3	Construction of granular sub base by surface courses with local materials table 400.13 mixing in place method normal construction granular sub base by providing local materials spreading in uniform layer with motor grader on prepared surface mixing by mix in place method with rotovator at once and comp-acting with smooth wheel roller to achieve the desired density complete as per clause 401.4 as per technical specification clause 408 within all leads and lifts as per direction of Engineer in charge	171.35	950.00	Rs nine hundred fifty only	per cubic metre	162783
Total:						166701/-

DNIT NO. Approved for Rs 1,66,701/- for the year 2023-24

Quoted Rate in figure	(+) (-)	%
Quoted Rate in Words	(+) (-)	%
Signature of Contractor with full address		

Executive Engineer
 B&R Divn HP PWD
 Rohru

16

SCHEDULE OF QUANTITY

Name of work :- R/R to various road under sub Division chirgaon sub Divn (in Baidyara section) Removal of slips /land slide road surface)

Estimate Cost Rs 4.87, 200/-
Earnest Money 10000/-
Time :- 60 days

Sr.No.	Sub-Head and Item of works	Quantity	Rate in figures.	Rate in words.	Unit	Amount.
1	Hitting of J.C.B(Excavator-Cum-Loader) having bucket capacity 0.45 including P.O.L charges, shifting changes and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road burms. Minimum 18 Decubic meter of earth work shall be done by machine in one hour, other wise number of hour shall be reduced accordingly The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-in-Charge including all leads and lifts	58.00	8400.00	Rs eight thousand four hundred on ly	per day	487200.00
					Total	487200.00

Quoted Rate in figure (+/-)	%
Quoted Rate in Words (+/-)	%

Signature of Contractor with full Address

Executive Engineer
B&R Divn HP PWD
Rd

SCHEDULE OF QUANTITY

Name of work :- R/R to various road under sub Division chingon sub Divn (in Baidyara section)(Sh- Removal of slips /land slide road surface)

Estimate Cost Rs 4.87, 200/-
Earnest Money 10000/-
Time :- 60 days

Sr.No	Sub-Head and Item of works	Quantity	Rate in figures.	Rate in words.	Unit	Amount
1	Hiring of J.C.B.(Excavator-Cum-Loader) having bucket capacity 0.45 including P.O.L charges, shifting changes and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road burms. Minimum 18.00 cubic meter of earth work shall be done by machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.	58.00	8400.00	Rs eight thousand four hundred on ly	per day	487200.00
					Total	487200.00

Quoted Rate in figure (*//-)	%
Quoted Rate in Words (*//-)	%

Signature of Contractor with full Address

Executive Engineer
B&R Divn HP PWD
Baidyara

19

DNTT/ SCHEDULE OF QUANTITY

Job No. _____
Estimated Cost:-367584/-
Earnest Money:-7400/-
Time:-One Month

NAME OF WORK:- C/O Samoli Sainji Bhartwari road km: 0/0 to 7/0 (SH:-P/L GSB with local material at various RDs between km.0/0 to 2/00)

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
3	Construction of granular sub-base by surface courses with local material table 400.13 by mixing in place method normal construction of granular sub base by providing local material spreading in uniform layer with motor graderon prepared surface mixing by mix in place method with reovator at once and compacting with smooth wheel roller to achieve the desire density complete as per clause 401.4 as per technical specification clause 408 including all leads and lifts as directed by the Engineer-in-Charge	386.93	950.00	Rupees:-Nine Hundred Fifty Paise Zero only.	Cum	367584
Total:-						367584
DNTT No. _____ Approved for Rs.367584/- only for the Year 2023-2024						
1713						
Quoted rate in figure %						
Quoted rate in words %						
Signature of contractor with address:-						

Executive Engineer
B&R Division
H.P.PWD Rohru