

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT.
NOTICE INVITING TENDER

Sealed percentage rate tenders are hereby invited on Form No.7 & 8 by the undersigned on behalf of the Governor of Himachal Pradesh for the following works from the registered contractors of appropriate class enlisted in H.P.PWD, so as to reach in this office on 29.01.2024 upto 11:00 A.M and shall be opened on the same day on 11:30 P.M. in the presence of the intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (Non- refundable) during the working hours.

The earnest money in the shape of National Saving Certificate, FDRs/TDRs/Account/Saving account in any of the Post Office/ Nationalized Bank in H.P. duly pledged in favour of the Executive Engineer, (B&R) Division, H.P.PWD, Sarahan must accompany with each applications/tender. Conditional tenders and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 75 days. The undersigned reserves the right to reject the any or all tender without assigning any reason.

S.No.	Tender Schedule				
1	Last date for tender receipt of application for tender form	24-01-2024 up to 4:00 PM			
2	Last date of sale of tender forms	27-01-2024 up to 4:00 PM			
3	Date of receipt of tender forms	29-01-2024 up to 11:00 P.M			
4	Date of opening of tenders	29-01-2024 at 11:30 PM			
Sr. No	Name of Work	Estimated cost	Earnest Money	Time Limit	Cost of Form
1	R/R Damages on Kanyo Anji Shirla road km 0/00 to /480 (SH:- Improvement of curve in km 0/00 to 4/00 at various Rd's & C/O R/Wall at RD 4/375 to 4/390)	4,40,207/-	9000	Three Month	350/-
2	R/R Damages on Dungaghat Bagthan road km 0/0 to 12/480 & BBRC Road km 7/0 to 28/0 (SH:- Clearance of side drains, Maintenance of earthen shoulders and clearing of vegetation in various kms)	4,97,850/-	10000	Two Month	350/-
3	R/R Damages on Kanyo Anji Shirla road km 0/00 to 6/480 (SH:- C/O wire crate at RD 4/870 to 4/882 & 2/910 to 2/925)	4,97,828/-	10000	Two Month	350/-
4	R/R Damages on Narag Wasni Dinger Road km 0/0 to 17/600 (SH:- P/L Paver block between km 0/100 to 0/200)	4,82,570/-	10000	Three Month	350/-
5	R/R Damages on Banethi Bagthan Rajgarh Chandol road 7/0 to 28/00 (SH:- C/O PCC R/Wall at RD 7/610 to 7/625)	4,01,787/-	8000	Three Month	350/-
6	R/R Damages on Narag Wasni Dinger Road km 0/0 to 17/600 (SH:- P/L Paver block between km 0/00 to 0/100)	4,82,570/-	10000	Three Month	350/-
7	R/R Damages on Kalaghat Ganyar road km 0/0 to 4/750 (SH:- C/O PCC R/Wall at RD 1/555 to 1/568)	4,78,134/-	9600	Three Month	350/-
8	R/R Damages on Kalaghat Ganyar road km 0/0 to 4/750 (SH:- C/O PCC R/Wall at RD 1/969 to 1/977)	2,93,467/-	6000	Three Month	350/-
9	R/R Damages on Kalaghat Ganyar road km 0/0 to 4/750 (SH:- C/O PCC R/Wall at RD 1/960 to 1/969)	3,30,454/-	7000	Three Month	350/-
10	R/R Damages on Kalaghat Ganyar road km 0/0 to 4/750 (SH:- C/O PCC R/Wall at RD 1/568 to 1/580)	4,41,415/-	9000	Three Month	350/-
11	R/R Damages on Kalaghat Ganyar road km 0/0 to 4/750 (SH:- C/O PCC B/Wall at RD 2/555 to 2/585)	4,07,176/-	8000	Three Month	350/-
12	R/R Damages on Prem Nagar Chandog Girdh Sandrol road km 0/0 to 15/0 (SH:- Removal of slips in km 10/435 to 14/590)	475452/-	10000	One Month	350/-
13	R/R Damages on Kalaghat Ganyar road km 0/0 to 4/750 (SH:- C/O PCC B/Wall at RD 2/585 to 2/615)	4,07,446/-	9000	Three Month	350/-


14	R/R Damages on Banethi Bagthan Rajgarh Chandol road 7/0 to 28/00 (SH:- C/O PCC R/Wall at RD 26/210 to 26/225)	4,80,022/-	10000	Three Month	350/-
15	R/R Damages on Prem Nagar Chandog Girdh Sandrol road km 0/0 to 15/0 (SH:- Removal of slips in km 5/015 to 9/980)	495977/-	10000/-	One Month	350/-
16	R/R Damages on Machher Jabiyana Wasni road Km 0/0 to 9/00 (SH:- C/O PCC drain in Km 0/00 to 0/950)	495837/-	10000/-	Three Month	350/-
17	R/R Damages on Bhagyanghat Lana Miun road Km 0/0 to 5/00 (SH:- C/O PCC R/Wall at RD 0/830 to 0/839)	431694/-	9000/-	Three Month	350/-
18	R/R Damages on Mari Ghat Sultanpur road portion Dilman to deol Tikkeri Km 0/0 to 7/00 (SH:- C/O B/Wall in Km 2/600 to 2/635)	476801/-	10000	Three Month	350/-
19	R/R Damages on Mehlog Dllman Kujji road Km 0/00 to 4/750 (SH:-C/O B/wall in Km 3/160 to 3/195)	475175/-	9000/-	Three Month	350/-
20	R/R Damages on Kalaghat Ganyar road km 0/0 to 4/750 (SH:- C/O PCC B/Wall in Km 2/195 to 2/210)	203453/-	4000/-	Three Month	350/-
21	R/R Damages on Mari Ka Ghat Kerry Shutiya road Km 0/0 to 23/0 (SH:- C/O 900 mm dia RCC Hume Pipe culvert alongwith wing walls at Rd 9/200)	291647/-	6000/-	Three Month	350/-
22	R/R Damages on Sirmouri Mandir Bagthan road Km 0/20 to 10/375 (SH:- Removal of slips in various Kms).	414901/-	9000/-	Three Month	350/-
23	R/R Damages to Dhabara Bari Bhun Pandh road Km 0/0 to 2/200 (SH:- C/O PCC B/wall in Km 1/180 to 1/190)	101017/-	2000/-	One Month	350/-
24	R/R Damages on Banethi Bagthan Rajgarh Chandol road km 7/00 to 28/00 (SH:- C/O wire crate at RD 7/385 to 7/399 height 6.25	491683/-	10000/-	One Month	350/-
25	R/R Damages on Banethi Bagthan Rajgarh Chandol road km 7/00 to 28/00 (SH:- Improvement of curves at various RD's , C/o wire crate B/wall at Rd 12/410 to 12/421 Height 2.50 mtr, RD 12/430 to 12/440 Height 2.50 mtr	499678/-	10000/-	One Month	350/-
26	R/R damages on Mari Ka Ghat Chando Jagangi ki ser road Km 0/0 to 8/00 (SH:- C/O R/wall of G.I wire crate at Rd 0/940 to 0/960)	494612/-	10000/-	Three Month	350/-
27	R/R damages on Mari Ka Ghat Chando Jagangi ki ser road Km 0/0 to 8/00 (SH:- C/O R/wall of G.I wire crate at Rd 0710 to 0/729)	469896	10000/-	Three Month	350/-
28	R/R damages on Mari Ka Ghat Dinger Mathanan road Km 0/0 to 22/00 (SH:- C/O PCC R/wall at RD 2/460 to 2/473)	486779/- 489562	10000/-	Three Month	350/-
29	R/R damages on Jaman Ki Ser Harkaghat road upto Galanaghat road /0 to 11/200 (SH:- Unlined surface drain at Rd 4/00 to 11/200)	213200/-	5000/-	One Month	350/-
30	A/R & M/O Macher Jabiyana Wasni road Km 0/0 to 9/0 (SH:- C/O unlined drain from Rd 2/250 to 9/0, berm dressing at various RD,s) under 500	496128/-	10000/-	One Month	350/-
31	C/O Naina Tikker Dagothar road Km 0/0 to 7/00 (SH:- ROFD in Km RD 0/650 to 0/718)	497781/-	10000/-	Three Month	350/-
32	Repair & Maintenance of Civil Hospital Sarahan (Pachhad), Distt. Sirmour (SH:- Plastering, Distempering, Paint work and roof treatment of Dental room and OPD Block-A	145657/-	3000/-	Two Month	350/-

33	C/O Helipad at Kawagdhar at Sarahan in tehsil Pachhad Distt. Sirmour H.P (SH:- Balance work cement concrete 1:2:4 thermoplastic paint and U shape drain	499956/-	10000/-	Two Month	350/-
34	Providing CGI roofing on first slab of Sub Treasury Building at Sarahan (SH:- Balance work including built up steel CGI sheets).	499811/-	10000/-	Three Month	350/-

Certificate:-It is certified that the tender of above work are exigency/emergent nature and in public interest.

Terms & conditions:-

1. The contractors/Bidders must submit their Permanent Income Tax Account Number/GST number on the tender along with copy of the same be attached with the application.
2. The contractor/Firms should attached copy of the Registration/Renewal with the application.
3. The contractors/bidders must inspect the site to ascertain/familiar the site conditions, accessibility etc. Before quoting the bid/tender.
4. Conditional and telegraphic tender will not be accepted and rejected straightway. Tender received after due date and time shall not entertained.
5. The contractor/firm should have to produce the detail of work in hand in HPPWD and its position therefore along with application.
6. The tender document shall be issued to only those contractors who does not have more than two works in hand in HPPWD Circle/ Division.
7. The contractor shall have to establish testing laboratory at site for the day to day testing of material.
8. The Executive Engineer reserves the right to reject or cancel any or all the tenders without assigning any reason.


Executive Engineer
HPPWD Division Sarahan
Distt. Sirmour HP


Dated:- 16/01/24

No.PW/SRN/Estt-Tender/2022-23-

8313-55

Copy forwarded for information and necessary action to:-

1. The Engineer-in-Chief, HP.PWD.Shimla-171002.
2. The Chief Engineer (South) HP.PWD.Shimla-171002.
3. The Superintending Engineer, 12th Circle HPPWD Nahan.
4. The Executive Engineer (IT Cell), Nigam Vihar, HPPWD Shimla-2 for uploaded of Notice Inviting Tenders on Departmental website please.
5. All the Assistant Engineers working under this Division.
6. All Head of Branches of this office.
7. All Intending Bidders/Contractors.
8. Notice Board.


Executive Engineer
HPPWD Division Sarahan
Distt Sirmour HP

SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Kanyo Anji Shirila road km 0/00 to 6/480 (SH:- Improvement of curve in km 0/00 to 4/00 at various Rd's & C/O R/Wall at RD 4/375 to 4/390)


Estimated cost:-Rs.4,40,207/-

Earnest money:- Rs. 9,000

Time Limit:- three Month.

Sr. No	Description Items of work	Qty.	Unit	in figures.	Rate	Amount
					in words	
1	2	3	4	5	6	7
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried, out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, in conformit with the requirements of technical specification for Rural Road. clause 1603.1 and 1603.2 of General conditions for contract to achieve designed formation width including hauling and safe disposal of unsuitable cut materials upto all lead and lifts in specified manner i/c arrangement of dumping site trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer -in -Charge for smooth riding. The recovery for stones, whether useful or not, for 89.51 cum (eighty nine point fifty one) in all cases, @ rupees 170/- only (Rupees one hundred seventy only) per cubic meter shall be effected on pro- rata basis. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall compensated by him in all cases.	1491.83✓	Per Cubic Metre.	159.00	Rupees one hundred fifty nine and paise nil only.✓	237201✓
2	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	9.65✓	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only.✓	1872✓
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	39.36✓	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only ✓	185669 ✓

4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)),including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	12.000✓	Each	270.30	Rs. Two Hundred seventy and paise thirty only.✓	3244✓
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in-Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	16.56✓	Per Cubic Metre.	738.00	Rupees seven Hundred thirty eight and paise zero Only.✓	12221✓
						440207.00✓


 Executive Engineer
 K. Sarahan Division
 HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Dungaghat Bagthan road km 0/0 to 12/480 & BBRC Road km 7/0 to 28/0 (SH:- Clearance of side drains, Maintenance of earthen shoulders and clearing of vegetation in various kms)

Estimated cost:-Rs. 4,97,850/-

Earnest money: - Rs. 10,000/-
Time Limit: - Two Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Removal of earth from the choked hill side drain as well as catch water drain and spreading it on the depressed berms (wherever required and disposing of supulous soil on th valley side manually , as per the directions of the Engineer in Charge including carriage of all labour equipments and material to various locations through all model of transportation in all leads and lidts including all incidental charges	11500	Per Running Metre	17.10	Rupees seventeen and paise ten only.	196650.00
2	Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903	13620.00	Per Square Metre.	14.00	Rupees fourteen and paise only	190680.00
3	Clearing jungle including uprooting of rank vegetation, grass , brush wood , trees and saplings of girth upto 30 cm measured at a height of one metre above ground level and removal of rubbish upto distance of 50 metre outside the pre ferry of the area cleared	15350.00	Per Square Metre.	7.20	Rupees seven and paise twenty only.	110520.00
						497850.00


Executive Engineer
K Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Kanyo Anji Shirila road km 0/00 to 6/480 (SH:- C/O wire crate at RD 4/870 to 4/882 & 2/910 to 2/925)

Estimated cost:-Rs. 4,97,828/-

Earnest money:- Rs. 10,000/-

Time Limit:- Two Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	50.76✓	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only.✓	9847.00
2	Providing and laying of boulder apron laid in wire creates with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification clause 1301 as per drawing and HP PWD technical specifications in carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	168.00✓	Per Cubic Metre.	2846.40	Rupees two thousand eight hundred forty six and paise forty only.✓	478195.00
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in-Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	13.26✓	Per Cubic Metre.	738.00	Rs. seven hundred thirty eight and paise nil only ✓	9786.00
						497828.00

Executive Engineer
KSSarahah Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Narag Wasni Dinger Road km 0/0 to 17/600 (SH:- P/L Paver block between km

RD 01/100 to 01/200)

Estimated cost:-Rs 4,82,570/-

Earnest money: - Rs. 10,000-

Time Limit: - Three Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	4.00	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only.	776.00
2	Providing and laying Concrete PCC grade M-20 grade 1:2:4 (one cement: Twenty millimeter) nominal size for Four graded hard stone aggregate) M-20 (Twenty millimeter) nominal size for plain/reinforced concrete in open foundation complete as per drawing and HP PWD technical specifications clause 802, 803, 1202 & 1203 i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	8.00	Per Cubic Metre.	5819.60	Rupees Five thousand eight hundred nineteen and paise six only.	46557.00
3	Providing and laying of interlocking concrete block pavement having thickness 80mm as per drawing and technical specification clause 1504 including carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	363.00	Per Square metre	1199.00	Rupees One thousand one Hundred ninety nine and paise zero Only.	435237.00
						482570.00


Executive Engineer
KS Sarahan Division
HP, PWD, Sarahan

5

SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Banethi Bagthan Rajgarh Chandol road 7/0 to 28/00 (SH:- C/O PCC R/Wall at RD 7/610 to 7/625)

Estimated cost:-Rs.4,01,787/-

Earnest money:- Rs. 8,200
Time Limit:- three Month.


Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	44.25	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only	8585.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	79.50	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only	375017.00
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)).including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge	21.000	Each	270.30	Rs. Two Hundred seventy and paise thirty only	5676.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in-Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	16.95	Per Cubic Metre.	738.00	Rupees seven Hundred thirty eight and paise zero Only.	12509.00
						401787.00

Executive Engineer
KS Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Narag Wasni Dinger Road km 0/0 to 17/600 (SH:- P/L Paver block between km 0/0 to 17/600) Estimated cost:-Rs 4,82,570/-
 Earnest money:- Rs. 10,000/-
 Time Limit:- Three Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	4.00	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only.	776.00
2	Providing and laying Concrete PCC grade M-20 grade 1:2:4 (one cement: Two sand: Four graded hard stone aggregate) M-20 (Twenty millimeter) nominal size for plain/reinforced concrete in open foundation complete as per drawing and HP PWD technical specifications clause 802, 803, 1202 & 1203 i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	8.00	Per Cubic Metre.	5819.60	Rupees Five thousand eight hundred nineteen and paise six only.	46557.00
3	Providing and laying of interlocking concrete block pavement having thickness 80mm as per drawing and technical specification clause 1504 including carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge	363.00	Per Square metre	1199.00	Rupees One thousand one Hundred ninety nine and paise zero Only.	435237.00
						482570.00


 Executive Engineer
 K.S. Sarahan Division
 HP, PWD, Sarahan

SCHEDULE OF QUANTITY


Name of work:- R/R Damages on Kalaghat Ganyar road km 0/0 to 4/750 (SH:- C/O PCC R/Wall at RD 1/555 to 1/568)

Estimated cost:- Rs. 4,78,134/-

Earnest money:- Rs 9,600

Time Limit:- Three Months.

Sr. No	Description-Items of work	Qty.	Unit	Rate		Amount
				In figures.	In words	
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause: Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	55.32	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only.	10732.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C-802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	94.250	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only.	444596.00
3	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full width of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)), including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	29.000	Each	270.30	Rs. Two Hundred seventy and paise thirty only.	7839.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	20.28	Per Cubic Metre.	738.00	Rupees seven Hundred thirty eight and paise zero Only.	14967.00
						478134.00


 Executive Engineer
 KS Sarahan Division
 HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Kalaghat Ganyar road km 0/0 to 4/750 (SH:- C/O PCC R/Wall at RD 1/969 to 1/977)

Estimated cost:-Rs. 2,93,467/-
Earnest money:- Rs 6,000 ✓
Time Limit:- Three Months.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				In figures.	In words	
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	34.04 ✓	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only. ✓	6604.00 ✓
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three and Eight hundred Four) One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	58.000 ✓	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only. ✓	273598.00 ✓
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)),including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge	15.000 ✓	Each	270.30	Rs. Two Hundred seventy and paise thirty only. ✓	4055.00 ✓
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in-Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	12.48 ✓	Per Cubic Metre.	738.00	Rupees seven Hundred thirty eight and paise zero Only. ✓	9210.00 ✓
						293467.00 ✓

Executive Engineer
Saraha Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:-R/R Damages on Kalaghat Ganyar road km 0/0 to 4/750 (SH:- C/O PCC R/Wall at RD 1/960 to 1/969)

Estimated cost:-Rs. 3,30,454/-
Earnest money:- Rs 6,800
Time Limit:- Three Months.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1.	Earth work in excavations for structure as per drawing and technical specifications (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	38.30	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only.	7430.00
2.	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	65.250	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only.	307797.00
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)).including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge	18.000	Each	270.30	Rs. Two Hundred seventy and paise thirty only.	4865.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in-Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	14.04	Per Cubic Metre.	738.00	Rupees seven Hundred thirty eight and paise zero Only.	10362.00
						330454.00

Executive Engineer
Sarhan Division
HP, PWD, Sarhan

SCHEDULE OF QUANTITY


Name of work:- R/R Damages on Kalaghat Ganyar road km 0/0 to 4/750 (SH:- C/O PCC R/Wall at RD 1/568 to 1/580)

Estimated cost:- Rs. 4,41,415/-

Earnest money:- Rs 9,000

Time Limit:- Three Months.

Sr. No.	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Earth work in excavations for structure as per drawing and technical specifications, clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	51.06	Per Cubic Metre.	194.00	Rupees one hundred Ninety four and paise zero only.	9906.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	87.000	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only.	410396.00
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven) ,including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	27.000	Each	270.30	Rs. Two Hundred seventy and paise thirty only.	7298.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	18.72	Per Cubic Metre.	738.00	Rupees seven Hundred thirty eight and paise zero Only.	13815.00
						441415.00



 Executive Engineer
 KS Sarahan Division
 HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Kalaghat Ganvar road km 0/0 to 4/750 (SH:- C/O PCC B/Wall at RD 2/555 to 2/585)

Estimated cost:-Rs. 4,07,176/-
Earnest money:- Rs 8,200 ✓
Time Limit:- Three Months.

Sr. No.	Description Items of work	Qty.	Unit	Rate		Amount
				in figures	in words	
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	55.20 ✓	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only. ✓	10709.00 ✓
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications. C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	82.500 ✓	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only. ✓	389169.00 ✓
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)),including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	27.000 ✓	Each	270.30	Rs. Two Hundred seventy and paise thirty only. ✓	7298.00 ✓
						407176.00 ✓


Executive Engineer
KS Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Prem Nagar Chandog Girdh Sandrol road km 0/0 to 15/0 (SH:- Removal of slips in km 10/435 to 14/590)

Estimated cost:-Rs. 4,75,452/-

Earnest money:- Rs 9,600

Time Limit:- one Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Removal of landslides /slip clearance. clearance of drain, Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611	3	4	5	6	7
		5224.75	Per Cubic Metre.	91.00	Rupees ninety one and paise nil only	475452.00
						475452.00


Executive Engineer
K. Sarahan Division
HP, PWD, Sarahan

13

SCHEDULE OF QUANTITY

Name of work:-R/R Damages on Kalaghat Ganyar road km 0/0 to 4/750 (SH:- C/O PCC B/Wall at RD 2/585 to 2/615)

Estimated cost:-Rs. 4,07,446/-
Earnest money:- Rs 8,200 ✓
Time Limit:- Three Months.

Sr. No	Description items of work	Qty.	Unit	Rate		Amount
				In figures.	In words	
1	Earth work in excavations for structure as per drawing and technical specifications clause-305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	55.20 ✓	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only. ✓	10709.00 ✓
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	82.500 ✓	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only. ✓	389169.00 ✓
3	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)),including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge	28.000 ✓	Each	270.30	Rs. Two Hundred seventy and paise thirty only. ✓	7568.00 ✓
						407446.00 ✓


Executive Engineer
KS Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

*Name of work:- R/R Damages on Banethi Bagthan Rajgarh Chandol road 7/0 to 28/00 (SH:- C/O PCC R/Wall at RD 26/210 to 26/225)

Estimated cost:-Rs.4,80,022/-

Earnest money:- Rs. 9,700

Time Limit:- three Month.

Sr. No	Description Items of work	Qty.	Unit	in figures.	Rate		Amount
					in words	6	
1	2	3	4	5			7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	56.29	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only.		10920.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	95.03	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only.		448276.00
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven))including hauling /carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge	27.000	Each	270.30	Rs. Two Hundred seventy and paise thirty only.		7298.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in-Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	18.33	Per Cubic Metre.	738.00	Rupees seven Hundred thirty eight and paise zero Only.		13528.00
							480022.00

Executive Engineer
KS Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Prem Nagar Chandog Girdh Sandrol road km 0/0 to 15/0 (SH:- Removal of slips in km 5/015 to 9/980)

Estimated cost:- Rs. 4,95,977/-

Earnest money:- Rs 10,000

Time Limit:- one Month

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2.	3	4	5	6	7
1	Removal of landslides / slip clearance. clearance of drain, Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611	5450.30	Per Cubic Metre.	91.00	Rupees ninety one and paise nil only	495977.00
						495977.00


Executive Engineer
Saraha Division
HP, PWD, Saraha

SCHEDULE OF QUANTITY

Estimated cost:- Rs. 4,95,837/-

Name of work:- -R/R Damges on Macher Jabiyana Wasni road km 0/0 to 9/00 (SH:-C/O PCC drain in km

Earnest money:- - 10,000

Time Limit:- Three Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	114.00	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise . zero only.	22116.00
2	Providing and laying Plain Cement Concrete 1:3:6(one cement: three sand: six graded hard stone aggregate 20mm(twenty) millimeter)nominal size} and curing complete including the cost of formwork for plain/reinforced concrete as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	85.50	Per Cubic Metre.	5540.60	Rupees five thousand five hundred forty and paise sixty only.	473721.00
						495837.00

Executive Engineer
Sarahan Division
HP, PWD, Sarahan

(17)

SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Bhagayanghat Lana Miun road km0/0 to 5/00 (SH:- C/O PCC R/Wall at RD 0/830 to 0/839)

Estimated cost:- Rs.4,31,694/-

Earnest money:- Rs 8,700

Time Limit:- Three Months.

Sr.	Description Items of work	Qty.	Unit	in figures.	in words	Amount
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	28.08	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only.	5448.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	86.40	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only.	407566.00
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)),including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge	18.000	Each	270.30	Rs. Two Hundred seventy and paise thirty only.	4865.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in-Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	18.72	Per Cubic Metre.	738.00	Rupees seven Hundred thirty eight and paise zero Only.	13815.00
						431694.00

Executive Engineer,
K. Sarahan Division,
H.P. PWD Sarahan

Estimated cost: Rs 4,76,804.00
 Estimated Mchgt: Rs 2,600.00
 Time Limit: Three Months

SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Madighat Sultanpur road portion Dilman to Deol Tikkeri km 0/0 to 7/00 (SH:- C/O B/Wall in km 2/600 to 2/635)

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	72.80	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only. ✓	14123.00 ✓
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	96.25	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only. ✓	454031.00 ✓
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)).including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	32.000	Each	270.30	Rs. Two Hundred seventy and paise thirty only. ✓	8650.00 ✓
						476804.00 ✓

Executive Engineer
 KS Sarahan Division
 HP, PWD, Sarahan

Estimated cost :- Rs 475,175.00
 Earliest Money :- Rs 9,600.00
 Time Limit :- Three Months

(19)

SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Mehlog Dilman Kuiji road km 0/00 to 4/750 (SH:- C/O B/Wall in km 3/160 to 3/195)

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	64.40	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only. ✓	12494.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	96.25	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only. ✓	454031.00
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)).including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge	32.000	Each	270.30	Rs. Two Hundred seventy and paise thirty only. ✓	8650.00
						475175.00


Executive Engineer
KS Sarahan Division
 HP, PWD, Sarahan

26
Estimated cost:- Rs 2,03,453.00
Earliest Money:- Rs 4,200.00
Time Limit:- Three Months

SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Kalaghat Ghanyar road km 0 /0 to 4/750 (SH:- C/O Breast Wall in km 2/195 to 2/210)

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	27.60	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only. ✓	5354.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	41.25	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only. ✓	194585.00
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full width of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)),including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	13.000	Each	270.30	Rs. Two Hundred seventy and paise thirty only. ✓	3514.00
						203453.00


Executive Engineer
KSSarahan Division
HP, PWD, Sarahan

Estimated cost: Rs 2,91,647.00
 Earliest Mobilization: Rs 6000.00
 Time Limit: Three Months

SCHEDULE OF QUANTITY

Name of Work:- R/R Damages on Mari ka gaht Kerry Shutiya road km 0/0 to 23/0 (SH:- C/O 900 mm dia RCC Hume pipe culvert along with wing walls at RD 9/200)

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	61.87	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise nil only ✓	12003.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	35.05	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only. ✓	165338.00
3	Providing and laying Plain Cement Concrete 1:3:6 (one cement: three sand: six graded hard stone aggregate 20mm (twenty) millimeter) nominal size} and curing complete including the cost of formwork for plain/reinforced concrete as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	10.86	Per cubic metre	5540.60	Rupees five thousand five hundred forty and paise sixty only ✓	60171.00

4	Providing and laying cement concrete 1:6:12 {One cement: Six sand: twelve graded crushed stone aggregate 40(Forty) millimeter nominal size} in open foundation and curing complete excluding cost of form work complete as per drawing and technical specification clause 802,803,1202 and 1203 including carriage of all labour equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge	2.40	Per cubic meter.	3873.00-	Rupees three thousand eight hundred seventy three and paise nil only. ✓	9295.00
5	Laying reinforced cement concrete 900 mm (Nine Hundred millimeter) diameter pipe class NP-2(Non Presseure- Two), including jointing for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2(one cement: two sand) including back filling but excluding excavations, protection works, concrete and masonry works in head walls and parapets as per drawings and technical specifications C - 1108. all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge,	10.00	Per Running Metre.	3731.40	Rupees three thousand seven hundred thirty one and paise forty only	37314.00
6	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)),including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	6.000	Each	270.30	Rupees two hundred seventy and paise thirty only	1622.00
7	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	8.00	Per Cubic Metre.	738.00	Rupees seven hundred thirty eight and paise nil only	5904.00
					Total	291647.00

Executive Engineer
Ks Sarahan Division,
HP.PWD., Sarahan

Estimated Cost: Rs 4,14,901.00
 Earliest Money: Rs 8,500.00
 Time Limit: Three Months

SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Sirmouri Mandir Bagthan road km 0/0 to 10/375 (SH:- Removal of slips in various km)

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611	4559.35	Per Cubic Metre	91.00	Rupees ninety one and paise nil only.	414901.00
						414901.00


 Executive Engineer
 KS Sarahan Division
 HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- R/R Damages to Dhabra Bari Bhun Pandh road km 0/0 to 2/200 (SH:- C/O PCC B/Wall in km 1/180 to 1/190

Estimated cost:-Rs. 101017/-

Earnest money:- Rs 2000/-

Time Limit:- one Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	5.90	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise nil only.	1145.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	21.00	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and twenty paise only.	99061.00
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)),including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge	3.00	Each	270.30	Rupees two hundred seventy and thirty paise only.	811.00
						101017.00

Executive Engineer
Sarhan Division
HP, PWD, Sarhan

SCHEDULE OF QUANTITY

Name of work:- R/R Damages on BBRC road km 7/00 to 28/00 (SH:- C/O of wire create B/Wall at RD 7/385 to 7/399 Height 6.25
 Estimated cost:-Rs. 491683/-
 Earnest money:- Rs 10000/-
 Time Limit:- one Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	31.50	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise nil only ✓	6111.00
2	Providing and laying of boulder apron laid in wire creates with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification clause 1301 as per drawing and HP PWD technical specifications in carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	161.88	Per Cubic Metre.	2846.40	Rupees two thousand eight hundred forty six and forty paise only. ✓	460775.00
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	33.60	Each	738.00	Rupees seven hundred thirty eight and paise nil only ✓	24797.00
						491683.00 ✓


 Executive Engineer
 K. Sarahan Division
 HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- R/R Damages on BBRC road km 7/00 to 28/00 (SH:- Improvement of curve at various RD,s C/O of wire create B/Wall at RD 12/410 to 12/421 Hieght 2.50m ,RD 12/430 to 12/440 Height -2.50 m

Estimated cost:-Rs. 499678/-

Earnest money:- Rs 10000/-
Time Limit:- one Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried, out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, in conformit with the requirement of technical specification for Rural Road. clause 1603.1 and 1603.2 of General conditions for contract to achieve designed formation width including hauling and safe disposal of unsuitable cut materials upto all lead and lifts in specified manner i/c arrangement of dumping site trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer -in -Charge for smooth riding. The quantity of stone that is 143.86 cum (one hundred forty three point eighty six) in all cases, @ rupees 170/- only (Rupees one hundred seventy only) per cubic meter shall be effected on pro- rata basis. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall compensated by him in all cases.	187.655	Cum	159.00	Rupees one hundred fifty nine and paise nil only. ✓	29837.00
	Jumber work	750.62	Cum	263.00	Rupees two eight hundred sixty three and paise nil only	198014.00
	Blastic work	143.86	Cum	170.00		
2	Recovery for usefull stones JW =187.655/10=18.76, BW =750.62/6=125.10=JW+BW=143.86 m3 Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	34.01	Per Cubic Metre.	194.00	Rupees one hundred ninety four paise nil only	6598.00
3	Providing and laying of boulder apron laid in wire creates with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification clause 1301 as per drawing and HP PWD technical specifications in carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	89.26	Cum	2846.40	Rupees two thousand eight hundred forty six and paise nil only	254070.00

filling behind abutment, wing wall and return wall complete as per drawings & technical specification use 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	15.12	Cum	738.00	Rupees seven hundred thirty eight and paise nil only	11159.00
				Total	499678.00


 Executive Engineer
 KSSaraham Division
 HP, PWD, Saraham

SCHEDULE OF QUANTITY

Name of work:- -R/R Damages On Mari ka ghatChando Jaganji ki ser road km 0/0 to 8/00 (SH:- C/O R/Wall of G.I Wire crate at RD 0/940 to 0/960)

Estimated cost:-Rs.4,94612/-

Earnest money:- Rs. 10,000/-

Time Limit:- Two Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	55.00	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only.	10670.00
2	Providing and laying of boulder apron laid in wire creates with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification clause 1301 as per drawing and HP PWD technical specifications in carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	162.50	Cum	2846.40	Rupees two thousand eight hundred forty six and paise nil only.	462540.00
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	29.00	Per Cubic Metre.	738.00	Rupees seven Hundred thirty eight and paise zero Only.	21402.00
						494612.00


 Executive Engineer
 K. Sarahan Division
 HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- R/R Damages On Mari ka ghatChando Jaganji ki ser road km 0/0 to 8/00 (SH:- C/O R/Wall of G.I Wire crate at RD 0/710 to 0/729)

Estimated cost:-Rs.469,896/-

Earnest money:- Rs. 9,500/-

Time Limit:- Two Month.

Sl. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	52.25	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only.✓	10137.00
2	Providing and laying of boulder apron laid in wire creates with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification clause 1301 as per drawing and HP PWD technical specifications in carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	154.38	Cum	2846.40	Rupees two thousand eight hundred forty six and paise nill only.✓	439427.00
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	27.55	Per Cubic Metre.	738.00	Rupees seven Hundred thirty eight and paise zero Only.✓	20332.00
						469896.00


 Executive Engineer
 K. Sarahan Division
 HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- R/R Damages On Mari ka ghat Dinger Mathanan road km 0/0 to 22/0(SH:- C/O R/Wall at RD 2/460 to 2/473)

Estimated cost:-Rs.4,89,562/-
Earnest money:- Rs. 10,000/-
Time Limit:- Two Month.


Sr. No	Description Items of work	Qty.	Unit	in figures.	Rate		Amount
					in words		
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	3	4	5	6	7	
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	56.29	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only.✓	10920.00	✓
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	95.03	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only.✓	448276.00	✓
3	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven) ,including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge	52.000	Each	270.30	Rs. Two Hundred seventy and paise thirty only.✓	14056.00	✓
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	22.10	Per Cubic Metre.	738.00	Rupees seven Hundred thirty eight and paise zero Only.✓	16310.00	✓
						489562.00	✓


Executive Engineer
Ks Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Estimated cost:-Rs. 213200/-
Earnest Money :-Rs.4500/-
Time Limit:- One Month

Name of Work:- R/R Damages on Jaman ki ser Harkaghat road upto Galanaghat road 0/0 to 11/200 (SH:- Unlined surface drain at RD 4/00 to 11/200)						
Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Construction of unlined surface drain of average cross-sectional area 0.2 sqm in ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	5200.00	Rmt	41.00	Rupees forty one and paise nil only	213200.00
						213200.00


Executive Engineer
KS Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O Macher Jabiyana Wasni road km 0/0 to 9/0 (SH:-C/O Unlined drain from RD 2/250 to 9/0, berm dressing at various RD,S)

Estimated cost:-Rs.4,96,128/-

Earnest money:- Rs. 10000/-

Time Limit:- One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Construction of unlined surface drain of average cross-sectional area 0.2 sqm in ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	6432.00	Per Running Metre	41.00	Rupees forty one and paise only.	263712.00
2	Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903	6697.86	Per Square metre	34.70	Rupees thirty four and paise seventy only .	232416.00
						496128.00


Executive Engineer
Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- C/O Naina Tikker Dagothar road km 0/0 to 7/00 (SH:- ROFD in km RD 0/650 TO 0/718

Estimated cost:-Rs.497781/-
Earnest money:- Rs. 10000/-
Time Limit:- One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried, out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, in conformit with the requirement of technical specification for Rural Road. clause 1603.1 and 1603.2 of General conditions for contract to achieve designed formation width including hauling and safe disposal of unsuitable cut materials upto all lead and lifts in specified manner i/c arrangement of dumping site trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer -in -Charge for smooth riding. The recovery for stones, whether useful or not, for 297.36 cum (two hundred ninety seven point thirty six) in all cases, @ rupees 170/- only (Rupees one hundred seventy only) per cubic meter shall be effected on pro- rata basis. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall compensated by him in all cases.					
2	Blastic work	1784.16	Cum	279.00	Rupees two hundred seventy nine and paise nill only.	497781.00
3	Recovery for usefull stones, =1784.16 m3/6=297.36m3@Rs.170/-	297.36	Cum	170.00		
						497781.00

Executive Engineer
K. Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- Repair & Maintenance of Civil Hospital Sarahan (Pachhad) Distt. Sirmour (SH:- Plastering, Distempring, Paint work and roof treatment of Dental Room and OPD Block -A)


Estimated cost:- Rs.145657/-

Earnest money:- Rs. 2950/-

Time Limit:- Two Month.

Sr. No	Description Items of work	Qty.	Unit	in figures.	Rate		Amount
					in words		
1	2	3	4	5	6	7	
1	15 mm cement plaster on the rough side of single or half brick wall of mix :1:6 (1 cement: 6 fine sand) including carriage of all labour equipment and material to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of the Engineer-in-Charge.	104.105	Sqm	265.00	Rupees two hundred sixty five and paise zero only.	27588.00	
2	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete. including carriage of all labour equipment and material to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of the Engineer-in-Charge.	121.065	Sqm	78.90	Rupees seventy eight and paise ninety only.	9552.00	
3	Finishing walls with Acrylic Smooth exterior paint of required shade :New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm) complete as per Engineer in Charge. including carriage of all labour equipment and material to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of the Engineer-in-Charge.	121.065	Sqm	168.70	Rs. one Hundred sixty eight and paise seventy only.	20424.00	
4	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS:15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/sqm including grouting the joints with white cement and matching pigments etc., complete Size of Tile 500x500 mm including carriage of all labour equipment and material to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of the Engineer-in-Charge.	17.60	Sqm	1598.00	Rupees one thousand five Hundred ninety eight and paise zero Only.	28125.00	
5	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S.15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joint with white cement & matching pigments etc. complete	5.19	Sqm	1623.00	Rupees one thousand six Hundred twenty three and paise zero Only.	8423.00	
6	6 mm cement plaster of mix 1:3 (1 cement : 3 fine sand) complete as per Engineer in Charge. including carriage of all labour equipment and material to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of the Engineer-in-Charge.	16.96	Sqm	192.00	Rupees one hundred ninety two and paise zero only.	3256.00	
7	Structural steel work in single section, fixed with or without connecting plate, without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete as per Engineer in Charge.	75.64	Kg	97.00	Rupees ninety seven and paise zero only.	7337.00	

8	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:1½:3 (1 Cement: 1½ coarse sand) : 3 graded stone aggregate 20 mm nominal size) as per Engineer in Charge.	4.14	Cum	8307.00	Rupees eight thousand three Hundred seven and paise zero Only. ✓	34391.00 ✓
9	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes 150 mm diameter including carriage of all labour equipment and material to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of the Engineer-in-Charge.	10 Rmt		656.1	Rupees six hundred fifty six and paise one ^{ten} only. ✓	6561.00 ✓
						145657.00 ✓


 Executive Engineer
 K. Sarahan Division
 HP, PWD, Sarahan

33

SCHEDULE OF QUANTITY

Estimated cost:-Rs.499956/-
 Earnest Money - Rs.10000/-
 Time Limit: - One Month.

Name of Work:- C/O of Helipad at Kawagdhara at Sarahan in Tehsil Pachhad Distt. Sirmour (H.P.) (SH:- Balance Work cement concrete 1:2:4 thermoplastic paint and U shape drain)

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	54.60	Per cubic metre	194.00	Rupees one hundred ninety four and paise only	10592.00
2	Providing and applying 2.5 mm thick road marking strip (retro-reflective) of specified shade/ colour using of thermoplastic material by fully/ semi automatic thermoplastic paint applicator machine fitted with profile shoe, glass beads dispenser, propane tank heater and profile shoe. heater, driven by experienced operator on road surface including cost of material, labour, T&P, cleaning the road surface of all dirt, seal, oil, grease and foreign material etc. complete as per direction of Engineer -in charge and accordance with applicable specifications.	54.00	Per square Metre.	590.70	Rupees five hundred ninety and paise seventy only.	31898.00
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering -all work up to plinth level 1:2:4 (1 cement :2 coarse sand) :4 graded stone aggregate 20mm nominal size) all leads and lifts as per Engineer in charge.	67.96	Per cubic metre	6731.40	Rupees. six thousand seven hundred thirty one and paise fourty only.	457466.00
						499956.00

Executive Engineer
 Ks Sarahan Division
 HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- Providing CGI Roofing on first slab of Sub Treasury building at Sarahan. (SH:-Balance work including built up steel, C.G.I sheets.)


Job No.

Estimated cost:-Rs499811/-

Earnest money:- Rs.10000/-

Time Limit:- Three Months

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2 steel work welded in built up sections, trusses and framed work, including cutting, hoisting in hall heights and levels, fixing in position and applying a priming coat of red led paint completer in all respect. In beams joints channel angles tee flates with connecting plates or angle cleats in main and cross beams. as per structural design , drawing, direction of the Engineer -in Charge and as per HPPWD. Specification 1990 (one thousand nine hundred ninty) volume-1(one) including carriage of all labour equipement and material to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	3 4261.783	4 KG	5 111.00	6 Rupees one hundred eleven and paise only.	7 473058.00
1						
2	Providing corrugated G.S sheet roofing including vertical/ curved surface fixed with polymer coated J or L hooks, bolts and nuts 8mm diameter with bitumen and G.I limpet washers or with G.I limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/vertical or curved surface),excluding the cost of purlines, rafters and trusses and including cutting to size and shape wherever required 1.00 mm thick with zinc coating not less than 275 gm/m ² 0.63 mm thick with zinc coating not less than 275 gm/m ² .	31.00	Per Square metre	863.00	Rupees eight hundred sixty three and paise nil only.	26753.00
					Total	499811.00


 Executive Engineer
 Division Sarahan
 HPPWD Sarahan