

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT.
NOTICE INVITING TENDER**

Sealed percentage rate tenders are hereby invited on Form No.7 & 8 by the undersigned on behalf of the Governor of Himachal Pradesh for the following works from the registered contractors of appropriate class enlisted in H.P.PWD, so as to reach in this office on 15.01.2024 upto 11:00 A.M and shall be opened on the same day on 11:30 P.M. in the presence of the intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (Non- refundable) during the working hours.


The earnest money in the shape of National Saving Certificate, FDRs/TDRs/Account/Saving account in any of the Post Office/ Nationalized Bank in H.P. duly pledged in favour of the Executive Engineer, (B&R) Division, H.P.PWD, Sarahan must accompany with each applications/tender. Conditional tenders and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 75 days. The undersigned reserves the right to reject the any or all tender without assigning any reason.

S.No.	Tender Schedule				
1	Last date for tender receipt of application for tender form 11-01-2024 up to 4:00 PM				
2	Last date of sale of tender forms 12-01-2024 up to 4:00 PM				
3	Date of receipt of tender forms 15-01-2024 up to 11:00 A.M				
4	Date of opening of tenders 15-01-2024 at 11:30 A.M				
Sr. No	Name of Work	Estimated cost	Earnest Money	Time Limit	Cost of Form
1	C/o of Helipad at Kawagdhara at Sarahan in tehsil Pachhad Distt. Sirmour (SH:- C/O Balance work cement concrete 1:2:4) Job No 01	499941/-	10000	One Month	350/-
2	C/o of Helipad at Kawagdhara at Sarahan in tehsil Pachhad Distt. Sirmour (SH:- C/O Balance work cement concrete 1:2:4) Job No 02	499941/-	10000	One Month	350/-
3	C/o of Helipad at Kawagdhara at Sarahan in tehsil Pachhad Distt. Sirmour (SH:- C/O Balance work cement concrete 1:2:4) Job No 03	499941/-	10000	One Month	350/-
4	C/o of Helipad at Kawagdhara at Sarahan in tehsil Pachhad Distt. Sirmour (SH:- C/O Balance work cement concrete 1:2:4) Job No 04	499941/-	10000	One Month	350/-
5	C/O Naina Tikker Chadyar road km 0/0 to 2/300 (SH:- ROFD in km 0/230 to 0/310)	4,98,606/-	10000	Three Month	350/-
6	R/R Damages on Banethi Bagthan Rajgarh Chandol road km 7/00 to 28/00 (SH:- C/O wire crate at RD 7/385 to 7/397)	3,94,961/-	8000	Three Month	350/-
7	C/O Naina Tikker Dagothar road km 0/0 to 11/0 (SH:- ROFD in km 0/460 to 0/545)	4,98,584/-	10000	Three Month	350/-
8	C/O Naina Tikker Dagothar road via Kanchi More km 0/0 to 11/0 (SH:- ROFD in km 0/545 to 0/650)	4,99,577/-	10000	Three Month	350/-
9	C/O Naina Tikker Chadyar road km 0/0 to 2/300 (SH:- ROFD in km 0/160 to 0/230)	4,97,220/-	10000	Three Month	350/-
10	R/R Damages on Banethi Bagthan Rajgarh Chandol road km 7/00 to 28/00 (SH:- C/O wire crate at RD 10/105 to 10/125)	4,32,236/-	8700	Three Month	350/-
11	R/R Damages on Various Roads under Dilman Sub Division (SH:- Hiring of JCB for removal of slips, debris and dressing of berms)	2,45,700/-	5000	One Month	350/-
12	R/R Damages on Deed Gluth road km 0/0 to 4/0 (SH:- C/O R/wall in km 1/200 to 1/225)	492071/-	10000/-	Three Month	350/-
13	R/R Damages on Sarahan Nāvgarh Mandi Kharana road km 0/0 to 10/700 (SH:- Removal of slips and C/o Unlined drain in various kms)	471806/-	9500/-	Three Month	350/-

Certificate:- It is certified that the tender of above work are exigency/emergent nature and in public interest.

Terms & conditions:-

1. The contractors/Bidders must submit their Permanent Income Tax Account Number/GST number on the tender along with copy of the same be attached with the application.
2. The contractor/Firms should attached copy of the Registration/Renewal with the application.
3. The contractors/bidders must inspect the site to ascertain/familiar the site conditions, accessibility etc. Before quoting the bid/tender.
4. Conditional and telegraphic tender will not be accepted and rejected straightway. Tender received after due date and time shall not entertained.
5. The contractor/firm should have to produce the detail of work in hand in HPPWD and its position therefore along with application.
6. The tender document shall be issued to only those contractors who does not have more than two works in hand in HPPWD Circle/ Division.
7. The contractor shall have to establish testing laboratory at site for the day to day testing of material
8. The Executive Engineer reserves the right to reject or cancel any or all the tenders without assigning any reason.



Executive Engineer
HPPWD Division Sarahan
Distt. Sirmour HP

Dated:- 06-01-2024

No.PW/SRN/Estt-Tender/2022-23- 7950-8000

Copy forwarded for information and necessary action to:-

1. The Engineer-in-Chief, HP.PWD.Shimla-171002.
2. The Chief Engineer (South) HP.PWD.Shimla-171002.
3. The Superintending Engineer, 12th Circle HPPWD Nahan.
4. The Executive Engineer (IT Cell), Nigam Vihar, HPPWD Shimla-2 for uploaded of Notice Inviting Tenders on Departmental website please.
5. All the Assistant Engineers working under this Division.
6. All Head of Branches of this office.
7. All Intending Bidders/Contractors.
8. Notice Board.


Executive Engineer
HPPWD Division Sarahan
Distt. Sirmour HP

SCHEDULE OF QUANTITY

Name of work:- C/O of Helipad at Kawagdhara at Sarahan in Tehsil Pachhad Distt. Sirmour (H.P) (SH:- C/O Balance work cement concrete 1:2:4) (J6BND 1)

Estimated cost:-Rs. 4,99,941/-

Earnest money:- Rs 10,000

Time Limit:- one Month.

Sr. No	Description items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering -all work up to plinth level 1:2:4 (1 cement :2 coarse sand) :4 graded stone aggregate 20mm nominal size) all leads and lifts as per Engineer in charge.	74.27	Per Cubic Metre.	6731.40	Rupees six thousand seven hundred thirty one and paise forty only	499941.00
						499941.00

Executive Engineer
Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- C/O of Helipad at Kawagdhara at Sarahan in Tehsil Pachhad Distt. Sirmour (H.P) (SH:- C/O Balance work cement concrete 1:2:4) (JBBN1022)

Estimated cost:-Rs. 4,99,941/- ✓

Earnest money:- Rs 10,000

Time Limit:- one Month.

Sr. No.	Description Items of work	Qty.	Unit	Rate		Amount
				In figures.	In words	
1	2	3	4	5	6	7
1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering -all work up to plinth level 1:2:4 (1 cement :2 coarse sand) :4 graded stone aggregate 20mm nominal size) all leads and lifts as per Engineer in charge.	74.27	Per Cubic Metre.	6731.40	Rupees six thousand seven hundred thirty one and paise forty only	499941.00
						499941.00


 Executive Engineer
 KS Sarahan Division
 HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- C/O of Helipad at Kawagdhara at Sarahan in Tehsil Pachhad Distt. Sirmour (H.P) (SH:- C/O Balance work cement concrete 1:2:4) 30 10 3

Estimated cost:-Rs. 4,99,941/-

Earnest money:- Rs 10,000

Time Limit:- one Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering -all work up to plinth level 1:2:4 (1 cement :2 coarse sand) :4 graded stone aggregate 20mm nominal size) all leads and lifts as per Engineer in charge.	74.27	Per Cubic Metre.	6731.40	Rupees six thousand seven hundred thirty one and paise forty only.	499941.00
						499941.00


 Executive Engineer
 Sarahan Division
 HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:-- C/O of Helipad at Kawagdhari at Sarahan in Tehsil Pachhad Distt. Sirmour (H.P) (SH:- C/O Balance work cement concrete 1:2:4) (JDBN04)

Earnest money: - Rs 10,000

Earnest money: - Rs 10,000
Time Limit: - one Month.


Executive Engineer
Sarhan Division
HP, PWD, Sarhan

Estimate No. 1-10, 000/-
 Earnest money 1-10, 000/-
 Time limit 1-10, 000/-

SCHEDULE OF QUANTITY

Name of work:- C/O Naina Tikker Chadyar road km 0/0 to 2/30 (SH:- ROFD in km 0/230 to 0/310)

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried, out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, in conformit with the requirement of technical specification for Rural Road. clause 1603.1 and 1603.2 of General conditions for contract to achieve designed formation width including hauling and safe disposal of unsuitable cut materials upto all lead and lifts in specified manner i/c arrangement of dumping site trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer -in -Charge for smooth riding. The recovery for stones, whether useful or not, for 297.85 cum (two hundred ninety seven point eighty five) in all cases, @ rupees 170/- only (Rupees one hundred seventy only) per cubic meter shall be effected on pro- rata basis. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall compensated by him in all cases.	1787.12	Per cubic Metre	279.00	Rupees two hundred seventy nine and paise nil only. ✓	498606.00
	Total					498606.00


 Executive Engineer
 Sarahan Division
 HP, PWD, Sarahan

SCHEDULE OF QUANTITY


Name of work:- R/R Damages on Banethi Bagthan Rajgarh Chandol road km 7/00 to 28/00 (SH:- C/O wire crate at RD 7/385 to 7/397)✓

Estimated cost:- Rs. 3,94,961/-✓

Earnest money:- Rs. 8,000✓

Time Limit:- three Months.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	31.50✓	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only.✓	6111.00
2	Providing and laying of boulder apron laid in wire creates with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification clause 1301 as per drawing and HP PWD technical specifications in carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	133.50✓	Per Cubic Metre.	2846.40	Rupees two thousand eight hundred forty six and paise forty only.✓	379994.00
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in-Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	12.00✓	Per Cubic Metre.	738.00	Rs. seven hundred thirty eight and paise nil only.✓	8856.00
						394961.00✓


 Executive Engineer
 KS Sarahan Division
 HP, PWD, Sarahan

SCHEDULE OF QUANTITY


Name of work:- C/O Naina Tikker Dagother road km 0/0 to 11/0 (SH:- ROFD in km 0/460 to 0/545)

Estimated cost:-Rs.4,98,584/-

Earnest money:- Rs. 10,000/-

Time Limit:- three Month.

Sr.	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2 Excavation in earth work in hilly area in all heights and depths in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried, out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, in conformit with the requirement of technical specification for Rural Road. clause 1603.1 and 1603.2 of General conditions for contract to achieve designed formation width including hauling and safe disposal of unsuitable cut materials upto all lead and lifts in specified manner i/c arrangement of dumping site trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer -in -Charge for smooth riding. The recovery for stones, whether useful or not, for 297.84 cum (two hundred ninety seven point zero eighty four) in all cases, @ rupees 170/- only (Rupees one hundred seventy only) per cubic meter shall be effected on pro- rata basis. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall compensated by him in all cases.	1787.04	Per cubic Metre	279.00	Rupees two hundred seventy nine and paise nil only	498584.00
	Total					498584.00


 Executive Engineer
 K.S. Sarahan Division
 HP, PWD, Sarahan

Estimate rates:- 4,99,577/- (2)

Earnest money :- 10,000/-

Time limit :- three months

SCHEDULE OF QUANTITY

Name of work:- C/O Naina Tikker Dagother road via Kanchi More km 0/0 to 11/0 (SH:- ROFD in km 0/545 to 0/650)

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side,water pollution, etcetra and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried, out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, in conformit with the requirement of technical specification for Rural Road. clause 1603.1 and 1603.2 of General conditions for contract to achieve designed formation width including hauling and safe disposal of unsuitable cut materials upto all lead and lifts in specified manner i/c arrangement of dumping site trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer -in -Charge for smooth riding. The recovery for stones,whether useful or not, for 298.43 cum (two hundred ninety eight point forty three) in all cases, @ rupees 170/- only(Rupees one hundred seventy only) per cubic meter shall be effected on pro- rata basis. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall compensated by him in all cases.	1790.60	Per cubic Metre	279.00	Rupees two hundred seventy nine and paise nil only.✓	499577.00
	Total					499577.00

Executive Engineer
KS Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- C/O Naina Tikker Chadyar road km 0/0 to 2/300 (SH:- ROFD in km 0/160 to 0/230)

Estimated cost:-Rs.4,97,220/-

Earnest money:- Rs. 10,000

Time Limit:- three Month.

Sr.	Description Items of work	Qty.	Unit	in figures.	Rate	Amount
				in words.	in words	
1	2	3	4	5	6	7
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried, out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, in conformit with the requirement of technical specification for Rural Road. clause 1603.1 and 1603.2 of General conditions for contract to achieve designed formation width including hauling and safe disposal of unsuitable cut materials upto all lead and lifts in specified manner i/c arrangement of dumping site trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer -in -Charge for smooth riding. The recovery for stones, whether useful or not, for 297.03 cum (two hundred ninety seven pointzero three) in all cases, @ rupees 170/- only(Rupees one hundred seventy only) per cubic meter shall be effected on pro- rata basis. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall compensated by him in all cases.	1782.15	Per cubic Metre	279.00	Rupees two hundred seventy nine and paise nil only	497220.00
	Total					497220.00

Executive Engineer
KS Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY


Name of work:- R/R Damages on Banethi Bagthan Rajgarh Chandol road km 7/00 to 28/00 (SH:- C/O wire crate at RD 10/105 to 10/125)

Estimated cost:- Rs. 4,32,236/-

Earnest money:- Rs. 8,700

Time Limit:- three Months.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	21.67	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only.	4204.00
2	Providing and laying of boulder apron laid in wire creates with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification clause 1301 as per drawing and HP PWD technical specifications in carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	147.75	Per Cubic Metre.	2846.40	Rupees two thousand eight hundred forty six and paise forty only.	420556.00
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in-Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	10.13	Per Cubic Metre.	738.00	Rs. seven hundred thirty eight and paise nil only.	7476.00
						432236.00


 Executive Engineer
 KS Sarahan Division
 HP, PWD, Sarahan

DRAFT SCHEDULE OF QUANTITY

Name of Work :- R/R Damages on Various Roads under Diltman Sub Division
(SH:- Hiring of JCB for removal of slips, debris and dressing of berms)

Estimated Cost :- 2,45,700/-
Earnest Money Rs.5,000/-
Time :- One Month

Description of Items.	Quantity	Unit	Rate In Figures.	Rate In words	Amount
Hiring of Excavator cum loader for cutting in hill roads in all kinds of soil removal of slips, removal of debris, dressing of berms and clearing of drains with minimum capacity 18.00 to 25.00 cum per hour, minimum six hours per day including pay of operators, POL charges: Maintenance or any minor or major accidents and other damages to private and govt property is the whole responsibility of the contractor. The work shall be executed as per the PWD specification and the direction of Engineer-in-Charge.	260.00	Hour	945.00	Rs. nine hundred forty five and paise nil only ✓	245700.00 ✓
Total					245700.00 ✓

Terms and Conditions :-

Hire charges should include expenses on account of establishment POL Major and minor repairs /over hauling and replacement of tyres and batteries if reqd.
Hire charges should also include Insurance of machinery/vehicles and establishment and the department shall not be responsible for any fatal/non fatal accidents.
Hire charges should also include all local or out side taxes including of road tax entry tax and other taxes if any.
Hire charges shall be payable only on signing of contract agreement and bringing the machinery/vehicles to the site as per the direction of Engineer-in-Charge.
Minimum work as per PWD norms must be executed by the machinery hired.
The bucket and loader capacity of JCB cum-excavator should not be less than 0.24 cum and one cum. Respectively and BHP is 72.

DNIT - No - 228

Sr. No (D) for the year 2023-24
D.N.I.T. approved for RS 2,45,700/- only.


Executive Engineer
K Division Sarahan
HPPWD Sarahan



Estimated cost Rs 492,071.00
 Estimated Money: Rs 10,000.00
 Time Limit: Three Months

SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Deed Galuth Road km 0/0 to 4/0 (SH:- C/O R/Wall in km 1/200 to 1/225)

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	46.00	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only. ✓	8924.00 ✓
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	96.25	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only. ✓	454031.00 ✓
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full width of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)),including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	34.000	Each	270.30	Rs. Two Hundred seventy and paise thirty only, ✓	9190.00 ✓
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in-Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	27.00	Per Cubic Metre.	738.00	Rupees seven Hundred thirty eight and paise zero Only. ✓	19926.00 ✓
						492071.00 ✓

Executive Engineer
 KS Sarahan Division
 HP, PWD, Sarahan

Estimated cost:- Rs 4,71,806.00
 Earliest Money:- Rs 9500.00
 Time Limit:- One Month

SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Sarahana Navgarh Mandi Kharana Road km 0/0 to 10/700 SH:- Removal of slips and C/O unlined drain in various km)

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611	3833.03	Per Cubic Metre	91.00	Rupees ninety one and paise nil only.	348806.00
2	Construction of unlined surface drain of average cross-sectional area 0.2 sqm in ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	3000.00	Per Running Metre	41.00	Rupees forty one and paise nil only	123000.00
						471806.00

Executive Engineer
 KS Sarahan Division
 HP, PWD, Sarahan