



OFFICE OF THE EXECUTIVE ENGINEER

B & R DIVISION, HPPWD, SOLAN-173212

TEL.NO:- 01792-223811 E-MAIL:- ee-sol-hp@nic.com

No.PW-SD/CB-Tender/-2023-24- 14247-51

Dated:- 24-01-24


To

The Executive Engineer (IT Cell),
Nigam Vihar, Nirman Bhawan,
HPPWD, Shimla-2,
Email ID:-cc-pwd-hp@nic.in

Subject: - Publication of e-Tender Notice.

Enclosed please find herewith the Tender Notice of the works as given in the Notice inviting Tender for uploading on departmental website as per Notification Pr. Secy(PW) to the Govt. of HP letter NO.PBW(B)A(3)1/2020 dated: 19th June, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

Encl: - Schedule of quantities.


Executive Engineer,
B&R Division,
HP.PWD, Solan.

Copy along with tender notice forwarded for information and necessary action please to:-

1. The Chief Engineer (S.Z), HP.PWD, Nirman Bhawan, Nigam Vihar, Shimla.
2. The Superintending Engineer, 3rd HP.PWD, Solan.
3. The Drawing Branch & Accounts Branch of this office.
4. Notice Board.


Executive Engineer,
B&R Division,
HP.PWD, Solan.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Exigency

Sealed item rate tenders are hereby invited on Form No.6 & 8 by the Executive Engineer, Solan B&R Division, H.P. PWD, Solan (H.P.) on behalf of the Governor of Himachal Pradesh for the following works from the registered contractors of appropriate class enlisted in H.P.PWD, whose registrations stood renewed as per revised instructions and also registered dealers under the Himachal Pradesh, General Sales Tax Act, 1968. The important dates of tender are as under:

Sr.No.	Tender Schedule	Dates	Time
1	The last date for receipt of application for tender form.	30.01.2024	Upto 3.00 P.M.
2	The last date sale of tender forms.	31.01.2024	Upto 4.00 P.M.
3	The date for receipt of tender forms.	01.02.2024	Upto 10.30 P.M.
4	The date of opening of tender	01.02.2024	At 11.00 A.M.

The tender shall be received upto 10.30 A.M. on 01.02.2024 and will be opened on the same day at 11.00 AM in the presence of office against cash payment as shown below (Non-refundable) during the working hours. The earnest money in the shape of National Saving Certificate, FDRs/Account/Saving account in any of the Post Office/ Nationalized Bank in H.P. duly intending contractors or their authorized representatives who may like to be present. The tender form can be had from this pledged in favour of the Executive Engineer, (B&R) Division, H.P.PWD, Solan must accompany with each tender, conditional tenders and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 120 days. The Executive Engineer reserves the right to reject the tender without assigning any reason.

Sr. No	Name of work	Estimated Cost. (Rs.)	Earnest Money (Rs.)	Time	Cost of Form
1.	Annual and repair and maintenance of Chhob to Bhura road Km.0/00 to 3/510 (SH: - Construction of PCC Breast Wall at Rd.0/100 to 0/120)	Rs. 287512/-	Rs. 5800/-	Two months	Rs.350/-
2.	Restoration of Rain damages on Nandalghar Plasho road Km.0/00 to 0/750 (SH: - Construction of PCC Retaining wall at Rd.0/455 to 0/464.50)	Rs. 490734/-	Rs. 9800/-	Two months	Rs.350/-
3.	Restoration of Rain damages on link road from Gaura Reh Ka Katal via Dhara Chakla Km. 0/00 to 6/00 (SH: - Construction of PCC Breast Wall over existing Breast wall for protection of house at Rd.2/315 to 2/335)	Rs. 453151/-	Rs. 9000/-	Two months	Rs.350/-
4.	Construction of link road to village Dharan from Rihaldhar Km.0/00 to 1/110 under SCSP (SH:-C/o 900 mm dia Hume pipe culvert at Rd.0/450 alongwith wing wall)	Rs. 319651/-	Rs. 6400/-	Two months	Rs.350/-

TERMS & CONDITIONS:-

1. The tender form will not be issued to those contractors whose performance has been found unsatisfactory.
2. The contractor should have submitted the proof of registration, EPF No. & GST No. at the time of tender application. Failure should not be issued tender forms.
3. Application without earnest money will not be entertained.
4. Executive Engineer reserves the right to reject or cancel any or all the tenders without assigning any reasons.

[Signature]
Executive Engineer
Solan B & R Division
H.P.P.W.D Solan

Draft Schedule of Quantity						
Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :-				Estimated Cost :-		287512.00
				Earnest Money :-		5800.00
				Time limit :-		Two months
Name of Work :- Annual and repair and maintenance of Chhob to Bhuira road Km.0/00 to 3/510 (SH: - Construction of PCC Breast Wall at Rd.0/100 to 0/120)						
1	Earthwork in excavation for all type of road astructures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited). Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and its disposal including dressing of sides and bottom and backfilling in trenches with excavated suitable material, trimming, filling of unevenness blindages and finishing of the road to specified dimensions. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	31.80	Per Cubic Meter	387.00	Rupees Three Hundred Eighty Seven Only	12307.00
2	Providing and laying Plain Cement Concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded stone aggregate 25mm (twenty five milimeters) nominal size) Mechanically mixed and vibrated for plain/reinforced concrete and curing complete in open foundations and plinths for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	63.00	Per Cubic Meter	4229.00	Rupees Four Thousand Two Hundred Twenty Nine Only	266427.00

3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One verticle into twenty horizontal) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7(six hundred fourteen, seven hundred nine, one thousand two hundred four point three point seven) or as directed by the Engineer-in-Charge including carriage of materials with in all lead and lift and other incidentals.	38.00	Each	231.00	Rupees Two Hundred Thirty One Only	8778.00
	Total:-					287512.00
Rupees Two Lakhs Eighty Seven Thousand Five Hundred Twelve Only						

T/S No.114 for the 2023-24.
Sr. No. 401 for the year 2023-24

Draft Schedule of Quantity approved for Rs. 287512.00 only.


Executive Engineer
B&R Division, HP.PWD. Solan.


Draft Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :-				Estimated Cost: -		490734.00
				Earnest Money: -		9800.00
				Time limit: -		Two months
Name of Work :- Restoration of Rain damages on Nandalghat Plasho road Km.0/00 to 0/750 (SH:- Construction of PCC Retaining wall at Rd.0/455 to 0/464.50)						
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited). Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and its disposal including dressing of sides and bottom and backfilling in trenches with excavated suitable material, trimming, filling of unevenness blindages and finishing of the road to specified dimensions. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	42.66	Per Cubic Meter	387.00	Rupees Three Hundred Eighty Seven Only	16509.00
2	Providing and laying Plain Cement Concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded stone aggregate 25mm (twenty five millimeters) nominal size) Mechanically mixed and vibrated for plain/reinforced concrete and curing complete in open foundations and plinths for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	106.12	Per Cubic Meter	4229.00	Rupees Four Thousand Two Hundred Twenty Nine Only	448781.00

Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One verticle into twenty horizontal) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7(six hundred fourteen, seven hundred nine, one thousand two hundred four point three point seven) or as directed by the Engineer-in-Charge including carriage of materials with in all lead and lift and other incidentals,	27.00	Each	231.00	Rupees Two Hundred Thirty One Only	6237.00
Backfilling behind abutment, wing wall and return wall, breast walls, retaining walls and parapets up to all heights, depths and levels complete as per HP.PWD. Specification clause 1204.3.8 (one thousand two hundred four point three point eight) Granular material, including carriage of all labour equipment and material to various locations through all modes of transportation in all lead and lift and all incidental charges.	18.24	Per Cubic Meter	1053.00	Rupees One Thousand Fifty Three Only	19207.00
Total:-					490734.00
Rupees Four Lakhs Ninety Thousand Seven Hundred Thirty Four Only					

T/S No.206 for the 2023-24.
Sr. No. 402 for the year 2023-24

Draft Schedule of Quantity approved for Rs. 490734.00 only.


Executive Engineer
B&R Division, HP.PWD. Solan.

Draft Schedule of Quantity						
Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :-				Estimated Cost :-		319651.00
				Earnest Money :-		6400.00
				Time limit :-		Two months
Name of Work :- Construction of link road to village Dharan from Rihaldhar Km.0/00 to 1/110 under SCSP (SH:-C/o 900 mm dia Hume pipe culvert at Rd.0/450 alongwith wing wall)						
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited). Dimensions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and its disposal including dressing of sides and bottom and backfilling in trenches with excavated suitable material, trimming, filling of unevenness blindages and finishing of the road to specified dimensions. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	66.49	Per Cubic Meter	387.00	Rupees Three Hundred Eighty Seven Only	25732.00
2	Providing and laying Plain Cement Concrete nominal mix 1:6:12 (one cement into six sand into twelve graded stone aggregate 40mm (fourty millimeters) nominal size) Mechanically mixed, vibrated and curing complete in open foundations and plinths for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidental charges.	3.72	Per Cubic Meter	3789.00	Rupees Three Thousand Seven Hundred Eighty Nine Only	14095.00
3	Providing and laying plain cement concrete Grade M- 10 (Ten) nominal mix 1:3:6 (one cement into three sand into six graded crushed hard stone aggregate 40mm (forty millimetre) nominal size) mechanically mixed, vibrated and curing complete in open foundations including form work as per drawings and MORD Technical Specifications Clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) and as per the direction of the Engineer-in-Charge including carriage of material through all modes of transportation within all leads and lifts and other incidentals.	10.22	Per Cubic Meter	4884.00	Rupees Four Thousand Eight Hundred Eighty Four Only	49914.00

4	Providing and laying Plain Cement Concrete nominal mix 1:4:8 (one cement into four sand into eight graded stone aggregate 25mm (twenty five millimeters) nominal size) Mechanically mixed and vibrated for plain/reinforced concrete and curing complete in open foundations and plinths for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	41.99	Per Cubic Meter	4291.00	Rupees Four Thousand Two Hundred Ninety One Only	186179.00
5	Providing and laying (to level or slope) reinforced cement concrete pipe NP2- 900 mm (nine hundred milimeter) diameter for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement into two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets as per technical specification clause 1108(one thousand one hundred eight), or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	7.50	Per Running Meter	4214.00	Rupees Four Thousand Two Hundred Fourteen Only	31605.00
6	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One verticle into twenty horizontal) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7(six hundred fourteen, seven hundred nine, one thousand two hundred four point three point seven) or as directed by the Engineer-in-Charge including carriage of materials with in all lead and lift and other incidentals.	24.00	Each	231.00	Rupees Two Hundred Thirty One Only	5544.00
7	Backfilling behind abutment, wing wall and return wall, breast walls, retaining walls and parapets up to all heights, depths and levels complete as per HP.PWD. Specification clause 1204.3.8 (one thousand two hundred four point three point eight) Granular material, including carriage of all labour equipment and material to various locations through all modes of transportation in all lead and lift and all incidental charges.	11.96	Per Cubic Meter	1052.00	Rupees One Thousand Fifty Two Only	12582.00
Total:-						319651.00
Rupees Three Lakhs Nineteen Thousand Six Hundred Fifty One Only						

T/S No.273 for the 2023-24.

Sr. No. 408 for the year 2023-24

Draft Schedule of Quantity approved for Rs. 319651.00 only.


A. N. S.
Executive Engineer
B&R Division, HP.PWD. Solan.

Draft Schedule of Quantity						
Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :-				Estimated Cost :-		453151.00
				Earnest Money :-		9000.00
				Time limit :-		Two months
Name of Work :- Restoration of Rain damages on link road from Gaura Reh Ka Katal via Dhara Chakla Km. 0/00 to 6/00 (SH: - Construction of PCC Breast Wall over existing Breast wall for protection of house at Rd.2/315 to 2/335)						
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited). Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and its disposal including dressing of sides and bottom and backfilling in trenches with excavated suitable material, trimming, filling of unevenness blindages and finishing of the road to specified dimensions. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	66.00	Per Cubic Meter	387.00	Rupees Three Hundred Eighty Seven Only	25542.00
2	Providing and laying Plain Cement Concrete nominal mix 1:4:8 (one cement into four sand into eight graded stone aggregate 25mm (twenty five millimeters) nominal size) Mechanically mixed and vibrated for plain/reinforced concrete and curing complete in open foundations and plinths for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	98.00	Per Cubic Meter	4229.00	Rupees Four Thousand Two Hundred Twenty Nine Only	414442.00

3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One verticle isto twenty horizontal) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7(six hundred fourteen, seven hundred nine, one thousand two hundred four point three point seven) or as directed by the Engineer-in-Charge including carriage of materials with in all lead and lift and other incidentals.	57.00	Each	231.00	Rupees Two Hundred Thirty One Only	13167.00
Total:-						453151.00
Rupees Four Lakhs Fifty Three Thousand One Hundred Fifty One Only						

T/S No.270 for the 2023-24.
Sr. No. 405 for the year 2023-24

Draft Schedule of Quantity approved for Rs. 453151.00 only.



Executive Engineer
B&R Division, HP.PWD. Solan.

Exigency Certificate

It is certified that the tenders which were invited vide this office
NTT No.PW-SD/CB-Tender/2023-24- ~~14247-9~~ Dated: ~~24/01/24~~ are of emergent nature of work and in
public interest.

Dated:- 28.11.2023

Place:- Solan


Executive Engineer
B&B Division
HPWD, Solan