

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Seked item rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, H.P. PWD Division Tanda at Nagrota Bagwan on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HP PWD (B & R) whose registration stood renewed as per revised rules so as to reach in his office on or before on 19.01.2024 up to 11:00 A.M. And the same shall be opened on the same day at 04:00 P.M. in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on 18.01.2024 up to 4:00 P.M. and the application for issue of tender form shall be received on 17.01.2024 up to 12:00 noon. The applications for issue of tender forms accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificate/Saving Account of the Post Office/Time Deposit account/FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, H.P. PWD Division Tanda at Nagrota Bagwan

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 120 days

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time limit
1	Construction of Type-III Ours. in Dr R.P. Govt. Medical College at Tanda near Daroon Bridge in Distt Kangra (HP) (SI)-Construction of Boundary wall and other work (Deposit work)	499912/-	10000/-	Two months
2	Construction of link road from Mundla Tikka Dhar to connect village Lully Amritar Km 2.900 to 5/660 in Distt Kangra (HP) (SI)-Construction of retaining wall at RD 3/460 to 3/475	286672/-	5750/-	Two months
3	Construction of link road Kanar to Saroot road Km 0/000 to 8/000 in Distt Kangra (HP) (SI)-Improvement of road width by providing retaining wall in Km 7/623 to 7/639	491762/-	9850/-	Two months
4	Restoration of rain damages on Pucca Path from Satsang Bhawan Ward No.4 Sunhi in Distt Kangra (HP) under deposit head) (SI)-Improvement of road width by providing retaining wall at RD 0/000 to 6/024	253186/-	5100/-	Two months
5	Construction of grate work near Jaggal Khad Mohal in Gram Panchayat Mumia in Distt Kangra (HP) under deposit (SID/2023/570). (SI)-Providing wire crates protection work).	498342/-	10000/-	Two months
6	Construction of link road NH-88 Paika Chowk to Harizan Basti Balugola in Distt Kangra (HP) (SI)-Providing and laying cement concrete pavement road at RD 1/200 to 1/350) under SC/SP Head	473124/-	9500/-	Two months
7	Restoration of rain damages on link road from Chughera Kandl Km 0/000 to 2/000 in Distt Kangra (HP) (SI)-Construction of retaining wall in Km 4/225 to 4/240	338877/-	6700/-	Two months
8	Special repair of 200 Reddell Hospital Building in Dr R.P. Govt. Medical College Tanda in Tehsil Nagrota Bagwan Distt Kangra (HP) Deposit work(SI)-Painting and distemper in 4 th floor female Medicine ward Doctor duty room and corridor etc.)	281511/-	5700/-	Two months
9	Restoration of rain damages in Nagrota Chani Padhar road Km 0/000 to 4/300 in District Kangra (HP) (SI)-Construction of protection work at RD 0/510 to 5/50	245882/-	4950/-	Two months

Terms & Conditions:-

- The contractor/firm should be registered as or dealer GST No
- The intending contractor / firm have to produce the copy of latest enlistment and renewal enlisted in HPPWD
- If any of the date mentioned above happened to be a gazetted Holiday the same shall be processed on next working day
- The Executive Engineer reserves the right to accept/reject any tender application or all tenders without assigning any reason
- The Contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand
- Next tender will be issued only after completion of previous works in hand

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**


No. PW/NBD/TA/Tender/NT/2023-24- **13521-50**

Copy to the following for information and necessary action:-

- The Principal Secy (PW) to the Govt. of H.P. Shimla.
- The Engineer-in-Chief, HPPWD, Shimla
- The Chief Engineer (KZ), HPPWD, Dharamshala
- The Director, Information & Publications Department H.P. Shimla
- The Executive Engineer (IT), Nigam Vihar Shimla 2 for information. He is requested to upload the same on the department website
- The Superintending Engineer, S&C Circle, HPPWD, Palampur
- The Principal, Dr. R.P.G.M.C. Tanda
- The Deputy Commissioner, Kangra at Dharamshala
- All the S.E., E.S under North Zone
- The Sub-Divisional Officer(C) Nagrota Bagwan
- The Block Development Officer Nagrota Bagwan
- All the Assistant Engineer under this Division
- The Drawing /Accounts Branch in this office
- The Contractors concerned.
- Notice Board

Executive Engineer
H.P. PWD Tanda Division
at Nagrota Bagwan
(On behalf of Governor of Himachal Pradesh)

Dated/ **10-1-2024**


Executive Engineer
H.P. PWD Tanda Division
at Nagrota Bagwan

Schedule of Quantity

ESTIMATED COST :- ₹ 499912.00
 EARNEST MONEY :- ₹ 10000.00
 TIME LIMIT : TWO MONTHS

Construction of Type-III Qtrs in Dr. R.P. Govt. Medical College at Tanda near Daroon Bridge in Distt. Kangra (H.P.).

SUB HEAD :- Construction of Boundary wall and other work. (DEPOSIT WORK)

S. No.	Description of Items	Quantity	Rate	In fig.	In words	Unit	Amount
1	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering. Plain cement concrete 1:3:6 (One Cement : Three coarse sand : Ten graded stone aggregate 20 mm (Twenty millimetres) nominal size complete as per drawing and HP.PWD technical specifications and as directed by Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	Cubic 6.08		3	4	Per cubic metre	
2	Brick work with common burnt clay machine moulded perforated bricks of class designation 12.5 conforming to IS: 2222 in superstructure above plinth level up to floor five level in cement mortar 1:6 (1 cement : 6 coursesand) With F.P.S.(non modular) bricksas per drawing and HP.PWD technical specifications and as directed by Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	Cubic 12.29				Per cubic metre	
3	15mm thick cement plaster in single coat on fair side of brick/concrete/stone walls for exterior plastering upto all floor level including arises, internal rounded angles, chamfers and or rounded angles not exceeding 80mm in girth and finished even and smooth with cement mortar 1:4 (1 cement: 4 sand) complete as per drawing and HP.PWD technical specifications and as directed by Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	Square 240.00				Per square metre	
4	Providing and laying 50mm (Fifty millimetres) thick cement concrete topping 1:2:4 (One cement : Two sand : Four graded stone aggregate 20 mm nominal size) laid in one layer finished with a floating coat of neat cement within all leads, lifts of materials and other incidentals.	Square 21.00				Per square metre.	
5	Providing and laying Polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm (Eighteen millimetres) thick stone slab over 20 mm (Twenty millimetres) (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing, polishing and moulding in single or double layer etc. all complete as specified and as directed by the Engineer-in-Charge Polished Granite stone slab jet Black, Cherry Red, Elite Brown, Cal Eye or equivalent complete as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals.	Square 29.98				Per Square metre	
6	Providing and laying 60mm thick cement concrete paver block of M-35 grade with approved colour, design and pattern factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand complete as per drawing and HP.PWD technical specifications and as directed by Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	Square 96.15				Per square metre	

7	Providing and fixing curve stones in PCC 1:2:4 (One cement : Two coarse sand : Four graded stone aggregate 20 mm (Twenty millimetres) nominal size) 30x30x10cm (Thirty into thirty into ten centimetre) size including complete fixing cement concrete as directed by the Engineer-in-Charge, including entire carriage of materials within all leads, lifts and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge	Numbers	250.00			Each
8	Providing and fixing conscaled light including necessary fitting complete including entire carriage of materials within all leads, lifts and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge	Numbers	10			Each
9	Providing and fixing C.I. pipes , cast iron grill including necessary fitting complete including entire carriage of materials within all leads, lifts and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge	Kilogram	111.50			Per kilo-
10	Providing and laying Autoclaved cellular Aerated concrete blocks conforming to IS:2185 (iii) 1984 bonded together with polymer based mortar and finished with 12mm (Twelve millimetre) thick cement plaster 1:6 on both side complete as per HPPWD specifications or as directed by the Engineer-in-Charge, including carriage of material within all leads, lifts and other incidental.	Cubic metres	2.50			Per square metre
TOTAL :-						

Executive Engineer,
H.P.P.W.D., Division,
Tanda al Nagaria Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 286672.00
EARNEST MONEY :- ₹ 5750.00
TIME LIMIT : TWO MONTHS

NAME OF WORK :- Construction of link road from Mundla Tikka Dhar to connect village Lilly Amtrar Km 2/900 to 5/660 in Distt. Kangra (H.P.)

SUB-HEAD :- Construction of Retaining wall at RD 3/460 to 3/475

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within any lead including entire carriage of materials within all leads, lifts and other incidentals.	30.11	4	5	Per cubic metre	7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (One cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimetres nominal size) as per drawing and HP.PWD technical specifications and as directed by Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	70.19			Per cubic metre	
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals.	22.00			Per running metre	
5	Backfilling with granular material behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8, granular material as per drawing and HP.PWD technical specifications and as directed by Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	14.35			Per cubic metre	
TOTAL :-						

Executive Engineer,
H.P.D.W.D., Division,
Tanda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST :- ₹ 491762.00
EARNEST MONEY :- ₹ 9850.00
TIME LIMIT :- TWO MONTHS

NAME OF WORK :- Construction of link road from Kandi to Saroot road Km 0/000 to 8/000 in Distt. Kangra (H.P.)
SUB HEAD :- Improvement of road with by providing Retaining wall in Km 7/623 to 7/639

S. No.	Description of items	Quantity	Rate	Unit	Amount
		In fig.	In words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within any lead including entire carriage of materials within all leads, lifts and other incidentals.	32.64 Cubic meters		Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (One cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimetres nominal size) as per drawing and H.P.PWD technical specifications and as directed by Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	122.64 Cubic metres		Per cubic metre	
3	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals.	40.95 Running metres		Per running metre	
4	Backfilling with granular material behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8, granular material as per drawing and H.P.PWD technical specifications and as directed by Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	21.12 Cubic metres		Per cubic metre	
TOTAL :-					

Executive Engineer,
H.P.P.W.D., Division,
Tanda at Nagra Bagwan.

Schedule of Quantity

ESTIMATED COST: -Rs.
 EARNEST MONEY : -Rs.
 TIME LIMIT :-
 253186.00
 5100.00
 TWO MONTHS

Restoration of rain damages on Pucca Path from Satsang Bhawan Ward No-4 Sunhi in Distt. Kangra (H.P.) under Deposit Head

NAME OF WORK:-
 SUB HEAD:-

Improvement of road width by providing retaining wall at RD 0/000 to 0/024

Sr. No.	Description	Quantity	Rate	Unit	Amount
		In fig.	In words		
1	2	3	4	5	6
					7
1	Excavation work by mechanical means (Hydraulic excavator) manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within any lead including entire carriage of materials within all leads, lifts and other incidentals.	28.08	Cubic metres	Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering	59.96	Cubic metres	Per cubic metre	
	All work up to plinth level 1:5:10 (One cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimetres nominal size) as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.				
3	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals.	20.90	Running metres	Per running metre	
4	Backfilling with granular material behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8, granular material as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	22.46	Cubic metres	Per cubic metre	
TOTAL:-					

Executive Engineer,
 H.P.P.W.D Division,
 Tanda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST:- ₹ 498342.00
 EARNEST MONEY:- ₹ 10000.00
 TIME LIMIT :- TWO MONTHS

Construction of Crate work near Joggal Khad Mohal in Gram Panchayat Mundla in Distt. Kangra (H.P.) under deposit (SDP/2023/570).

NAME OF WORK :- SUB HEAD :- Providing wire crates protection work.

S. No.	Description of items	Quantity	In fig.	Rate In words	Unit	Amount
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within any lead including entire carriage of materials within all leads, lifts and other incidentals.	56.25	3	4	Per cubic metre	7
2	Providing & making Gabion structure with Mechanically Woven Double Twisted Hexagonal Shaped Wire mesh Gabion Boxes as per IS 16014:2012, MORTH Clause 2500, of required size, Mesh Type 10x12 (D=100 mm with tolerance of $\pm 2\%$) Zinc coated, Mesh wire diameter 3.0 mm, mechanically edged/selfedged with partitions at every 1m interval and shall have minimum 10 numbers of openings per meter of mesh perpendicular to twisting with lacing wire of diameter 2.2mm, supplied @ 3% by weight of Gabion boxes, filled with boulders with least dimension of 200 mm, as per drawing, all complete as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals.	179.69			Per cubic metre	
3	Filling available excavated earth (excluding rock) intrenches or embankment in layers (each layer should not exceed 15 cm), with intermediate layer of compacted earth (Soil density of 98%) after every four layers of compacted depth of fly ash, sides & top layer of filling shall be done with earth having total minimum compacted thickness 30 cm or as decided by Engineer-in-charge, including compacting each layer by rolling/ ramming and watering, all complete as per drawing and direction of Engineer -in - charge, as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	45.00			Per cubic metre	
TOTAL :-						

Executive Engineer,
 H.P.W.D., Division,
 Tanda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST:- RS. 473124.00
EARNEST MONEY :- RS. 9500.00
TIME LIMIT : TWO MONTHS

NAME OF WORK : Construction of link road from NH-88 Palsa Chowk to Harizan Basti Balugala in Distt. Kangra (H.P.)
SUB HEAD :- Providing and laying cement concrete pavement road at RD 1/200 to 1/350
Code SOSP Head

S. No.	Description of items	Quantity	In fig.	Rate In words	Unit	Amount
1	Providing, laying, spreading and compacting stone aggregate of size 63mm to 45mm (sixty three millimeter to forty five millimeter) Grading-II size [75mm (seventy five millimeters) compacted thickness] to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber applying and brooming, stone screening type-A of size 13.2mm (thirteen point two millimeters) nominal size at the rate of 0.22 cum (zero point twenty two) cubic metres per 10 sqm (per ten square metres) and binding material at the rate 0.06 cum (zero point zero six cubic metre) to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specifications clause No. 405 including carriage of materials within all leads and lifts and other incidental.	35.44 Cubic metres	3	4	Per cubic metre	7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering. All work up to plinth level 1:2:4 (One Cement : Two coarse sand : Four graded stone aggregate 20mm) (Twenty millimetres) nominal size as per HPPWD technical specification and within all leads, lifts and other incidentals as per approved drawing, design and as directed by the Engineer-in-charge.	70.88 Cubic metres			Per cubic metre	
TOTAL :-						

Executive Engineer,
H.P.P.W.D., Division,
Tanda at Nagro, Bagwan.

Schedule of Quantity

ESTIMATED COST: - ₹ 333877.00
EARNEST MONEY :- ₹ 6700.00
TIME LIMIT :- TWO MONTHS

NAME OF WORK:- Restoration of rain damages on link road from Chhughera Kandi Km 0/000 to 20/000 in Distt. Kangra (H.P.)
SUB HEAD:- Construction of Retaining wall in Km 4/225 to 4/240

Sr. No.	Description	Quantity	Rate	Unit	Amount
		In fig.	in words		
1	Excavation work by mechanical means (Hydraulic excavator) manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within any lead including entire carriage of materials within all leads, lifts and other incidentals.	33.84		Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (One cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimetres nominal size) as per drawing and HP.PWD technical specifications and as directed by Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	79.42		Per cubic metre	
3	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals.	48.36		Per running metre	
4	Backfilling with granular material behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8, granular material as per drawing and HP.PWD technical specifications and as directed by Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	24.66		Per cubic metre	
TOTAL:-					7

Executive Engineer,
H.P.P.W.D Division,
Tanda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST :- Rs. 284511.00
 EARNEST MONEY :- Rs. 5700.00
 TIME LIMIT : TWO MONTHS

Name of Work:- Special repair of 500 Bedded Hospital Building in Dr. R.P. Govt. Medical College Tanda in Tehsil Nagrota Bagwan, Distt. Kangra (H.P.) DEPOSIT WORK

Sub Head:- Painting and distemper in 4th Floor Female Medicine Ward, Doctor Duty room and Corridor etc;

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	Square 2223.79			Per square metre	
2	Providing and applying J.K./Birla white cement based wall care putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete, as directed by the Engineer- In-charge, including carriage of materials within all leads, lifts and other incidentals.	Square 667.14			Per square metre	
3	Wall painting(Two coats) with plastic emulsion paint of approved brand and manufacture on un-decorated wall surface to give an even shade including thoroughly brushing the surface clean of all dirt grease,loose pieces of scale and sand papered smooth including applying of putty as required for making the surface complete as per direction of Engineer-In-Charge, including carriage of material within all leads, lifts and other incidentals.	Square 2223.79			Per square metre	
4	Painting two coat (excluding priming coat) on new steel and other metal surface under coat with ready mixed paint brushing to give an even shade including cleaning the surface all dirt, dust and other foreign matter with ready mixed paint than white complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	Square 1062.09			Per square metre	
Total:-						

Executive Engineer,
 H.P.P.W.D. Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST :- Rs. 245882.00
 EARNEST MONEY :- Rs. 4950.00
 TIME LIMIT : TWO MONTHS

NAME OF WORK :- Restoration of rain damages on Nagrota Chari Pathiar road km. 0/00 to 4/300 in District Kangra, (H.P.).
 SUB-HEAD :- (Construction of protection work at RD 1/610 to 1/660)

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, fill upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within a any lead as directed by the Engineer-in-charge, within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	14.25	Cubic metres		Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - aggregate 40mm (Forty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	17.98	Cubic metres		Per cubic metre	
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:3:6 (One cement: three sand: six graded broken/crushed stone aggregate 40mm (Forty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	42.65	Cubic metres		Per cubic metre	
TOTAL :-						

Executive Engineer,
 H.P.P.W.D. Division,
 Tanda at Nagrota, Kangra.