

Himachal Pradesh
Public Works Department

NO/PW/TLD/Tender/2022:- 14472-81
To

Dated:- 29-01-2024


Executive Engineer IT Cell),
Nirman Bhawan, Nigam Vihar, Shimla-2

Subject:- Publishing of Tender Notice.

Dear Sir,

Enclosed please find herewith the tender Notice of work as given in the Notice Inviting Tender for uploading on Department website as per Notification No. Principal Secretary (PW), to the Govt. of HP letter No. PBW (B) 1/2020 dated Shimla-2 the 16th July, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA:- NIT.


Executive Engineer,
Thalout Division, HPPWD,
Thalout.


HPPWD Mandi for information please.

Copy is forwarded to Superintending Engineer, 1st Circle,

Division.

Copy to All the Assistant Engineers working under this

Copy to AB/DB in this office.
Copy to Notice board.

Executive Engineer,
Thalout Division, HPPWD,
Thalout 

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
"NOTICE INVITING TENDER"**

Sealed item rate tender on form No. 6&8 for the following works detailed in the table below hereby invited by the Executive Engineer, Thalout Division, HPPWD, Thalout on behalf of Governor of Himachal Pradesh from the eligible contractors of appropriate Class registered in HPPWD as per revised enlistment rule so as to reach in his office on 08.02.2024 at 11.00 A.M. The tenders shall be opened on the same date at 11.30 A.M. in the presence of intending contractors or their authorized representative. The application for the tender form must reach in this office alongwith FDR on 06.02.2024 upto 3.00 PM and that tender documents can be had from his office on cash payment noted against each (Non-Refundable) on 07.02.2024 up to 5.00 P.M on any working day. Notice Inviting Tender and other specification and conditions of the tender can be seen by the contractor in the office of the Executive Engineer, Thalout Division, HPPWD, Thalout during office hour on any working day.

Sr. No.	Name of work	Estimated cost	Earnest money	Cost of form	Time Period for completion	Form No.	Eligibility of Contractors
1	BSP/2023/962 construction of road Panarsa Sojha Rahdi km 0/0 to 11/640 (SH-C/O R/wall at RD 8/262 to 8/271.50).	290417	6000	Rs. 350/-	One month	6&8	Class C & D enlisted in HPPWD
2	BSP/2023/962 construction of road Panarsa Sojha Rahdi km 0/0 to 11/640 (SH-C/O R/wall at RD 8/271.50 to 8/281).	290417	6000	Rs. 350/-	One month	6&8	-do-
3	RRD on various roads under Panarsa section (SH- Removal of slips,muck/debries at various RDs).	499200	10000	Rs. 350/-	One month	6&8	-do-
4	RRD on Nagwain to Balu road km 0/0 to 12/500 (SH- C/O B/wall in wire crate at RD 6/558 to 6/570).	334587	7000	Rs. 350/-	One month	6&8	-do-
5	RRD on Kathiyari to Ansar road km 0/0 to 3/0 (SH- C/O B/wall in wire crate at RD 0/0 to 0/035).	480357	10000	Rs. 350/-	One month	6&8	-do-
6	RRD on Pandoh to Shiva road km 0/0 to 13/0 (SH- C/O R/wall at RD 12/207 to 12/215.50).	354335	7500	Rs. 350/-	One month	6&8	-do-
7	RRD on Pandoh, Takoli, Kullu by pass road km 222/700 to 232/500 (SH- C/O R/wall at RD 227/470 to 227/475).	491007	10000	Rs. 350/-	One month	6&8	-do-
8	RRD on link road from Deoli to Phadidhar Kalakut HB km 0/0 to 2/0 (SH_ Hiring of Excavator cum loader for removal of slips, muck debries etc. at various RDs) Job No.1	499200	10000	Rs. 350/-	One month	6&8	-do-
9	RRD on Kuklah to Baggi road km 0/0 to 8/0 (SH- C/O R/wall at RD 5/240 to 5/254.40).	412724	8400	Rs. 350/-	One month	6&8	-do-
10	RRD on Pandoh, Takoli, Kullu by pass road km 222/700 to 232/500 (SH- C/O R/wall at RD 227/475 to 227/480).	499943	10000	Rs. 350/-	One month	6&8	-do-
11	RRD on Bhatwari to Rensh road km 0/0 to 8/640 (SH- C/O crated R/wall at RD 6/590 to 6/620)	467778	10000	Rs. 350/-	One month	6&8	-do-
12	RRD on Bhatwari to Rensh road km 0/0 to 8/640 (SH- C/O crated R/wall at RD 5/755 to 5/770).	253923	5500	Rs. 350/-	One month	6&8	-do-
13	BSP/2023/1039 construction of Sojha Rahdi road km 0/0 to 11/640 (SH- C/O PCC R/wall at RD 8/310 to 8/322) Deposit.	349330	7000	Rs. 350/-	One month	6&8	-do-
14	RRD on Satuir to Thatta road km 0/0 to 5/0 (SH- C/O R/wall at RD 1/451 to 1/458.50).	333411	7000	Rs. 350/-	One month	6&8	-do-
15	RRD on Jala Khini road km 0/0 to 2/465 (SH- C/O crated R/wall at RD 0/770 to 0/782.50).	348516	7000	Rs. 350/-	One month	6&8	-do-

16	RRD on Jala Khini road km 0/0 to 2/465 (SH- C/O crated B/wall at RD 0/885 to 0/897.50).	312747	6500	Rs. 350/-	One month	6&8	-do-
17	RRD on Auit Takoli Prasher road km 0/0 to 27/0 (SH- C/O balance work of R/wall & B/wall at RD 22/415 to 22/425 & crated R/wall at RD 22/855 to 22/870) at RD 21/578 to 21/583).	381594	8000	Rs. 350/-	One month	6&8	-do-
18	RRD on Sansoi to Kashana road km 0/0 to 6/250 (Balance work) (SH- C/O R/wall at RD 3/683 to 3/705).	413547	8500	Rs. 350/-	One month	6&8	-do-
19	RRD on Sansoi to Kashana road km 0/0 to 6/250 (Balance work) (SH- C/O R/wall at RD 3/645 to 3/664).	493180	10000	Rs. 350/-	One month	6&8	-do-
20	RRD on road from Mahudhar to Nalwagi km 0/0 to 4/265 (SH- C/O B/wall at RD 3/980 to 4/005).	177422	3700	Rs. 350/-	One month	6&8	-do-
21	RRD on various road under Nagwain section (SH- Hiring of JCB for removal of slips/muck debris in various RDs).	199200	4000	Rs. 350/-	One month	6&8	-do-
22	RRD on Sansoi to Kashana road km 0/0 to 6/250 (SH- C/O crated B/wall at RD 3/165 to 3/185).	240666	5000	Rs. 350/-	One month	6&8	-do-
23	RRD on Rahla Shayari road km 0/0 to 2/500 (SH- C/O crated B/wall at RD 0/465 to 0/485).	497070	10000	Rs. 350/-	One month	6&8	-do-
24	RRD on Nagwain to Balu road km 0/0 to 12/500 (SH- C/O B/wall in wire crate at RD 1/700 to 1/720).	217317	4500	Rs. 350/-	One month	6&8	-do-
25	C/O Panarsa Sojha Rahdi road to link road Nichala Surth km 0/0 to 0/370 (SH- P/L 80 mm thick precast cement concrete inter locking paver in M-50 grade between RD 0/0 to 0/065).	364962	7500	Rs. 350/-	One month	6&8	-do-
26	C/O Panarsa Sojha Rahdi road to link road Nichla Surth km 0/0 to 0/370 (SH- P/L 80 mm thick precast cement concrete inter locking paver in M-50 Grade between RD 0/065 to 0/130).	364962	7500	Rs. 350/-	One month	6&8	-do-
27	Preparation of DPR for balance work Up-gradation of Thalout Panjain Thachi Naraingaloo Shetadhar Chet Chiuni Lambathach road km 0/0 to 75/0 (Portion Thalout to Thachi in km 0/0 to 22/500) (SH- Preparation of detailed project report and drawings span, L-section & X-section in km 0/0 to 22/500).	450000	9000	Rs. 350/-	One month	6&8	-do-
28	RRD on Pandoh Takoli Kullu by pass NH-21 km 222/700 to 228/500 (SH- C/O R/wall in wire crate at RD 223/049 to 223/051.50).	143527	3000	Rs. 350/-	One month	6&8	-do-
29	BSP/2023/1040 Construction of Panarsa Sojha Rahdi road km 0/0 to 11/640 (SH- C/O PCC R/wall at RD 8/322 to 8/334) Deposit.	349330	7000	Rs. 350/-	One month	6&8	-do-
30	RRD on Aut Takoli Prasher road km 0/0 to 27/0 (SH- C/O crated R/wall alongwith PCC Toe wall at RD 22/415 to 22/433).	495497	10000	Rs. 350/-	One month	6&8	-do-
31	RRD on Sudhrani to Thatta road km 0/0 to 5/500 (SH- C/O R/wall at RD 1/240 to 1/250).	220212	4500	Rs. 350/-	One month	6&8	-do-
32	RRD on Bali Thachi road km 0/0 to 25/0 (SH- C/O R/wall at RD 5/540 to 5/550).	461507	9200	Rs. 350/-	One month	6&8	-do-

33	RRD on Pandoh to Shiva road km 0/0 to 13/0 (SH- C/O R/wall at RD 5/533 to 5/541.80).	360696	7500	Rs. 350/-	One month	6&8	-do-
34	RRD on Pandoh to Shiva road km 0/0 to 13/0 (SH- C/O R/wall at RD 5/525 to 5/533).	255160	5500	Rs. 350/-	One month	6&8	-do-
35	Restoration of damages on various roads under Pandoh S/Divn (SH- Hiring of JCB for removal of slips/muck debries in various roads under Pandoh section-II) Job No.1	499200	10000	Rs. 350/-	One month	6&8	-do-
36	RRD on Pandoh to Shiva road km 0/0 to 13/0 (SH- C/O R/wall at RD 4/818 to 4/826.20).	293841	6000	Rs. 350/-	One month	6&8	-do-
37	RRD on Shiva to Gharan road km 0/0 to 10/100 (SH- C/O R/wall at RD 2/120 to 2/135).	412165	8500	Rs. 350/-	One month	6&8	-do-
38	Restoration of damages on various roads under Pandoh S/Divn (SH- Hiring of JCB for removal of slips/muck debries in various roads under Pandoh section-I) Job No.1	499200	10000	Rs. 350/-	One month	6&8	-do-
39	RRD on Pandoh to Shiva road km 0/0 to 13/0 (SH- C/O R/wall in wire crate at RD 4/620 to 4/634.50).	312404	6500	Rs. 350/-	One month	6&8	-do-
40	RRD on Shiva to Gharan road km 0/0 to 10/100 (SH-C/O R/wall at RD 10/090 to 10/100).	379402	8000	Rs. 350/-	One month	6&8	-do-
41	RRD on Bakhali to Kholanal road km 0/0 to 8/600 (SH- C/O R/wall at RD 1/105 to 1/114.60).	374582	7500	Rs. 350/-	One month	6&8	-do-
42	RRD on Jala to Khini road km 0/0 to 2/465 (SH- C/O R/wall in wire crate at RD 0/615 to 0/625).	115637	2500	Rs. 350/-	One month	6&8	-do-
43	RRD on Bali to Thachi road km 0/0 to 25/0 (SH- C/O PCC protection wall at RD 14/710 to 14/727).	489454	9800	Rs. 350/-	One month	6&8	-do-
44	RRD on Bhurah to Panjain road km 0/0 to 11/0 (SH- C/O B/wall at RD 0/474 to 0/488).	458264	9200	Rs. 350/-	One month	6&8	-do-

TERMS & CONDITIONS: -

1. The Tender form will not be issued to those contractors whose performance is not found satisfactory.
2. The Contractor whose rates are abnormally low may be asked to furnish the full justification of his rate failing which he will be debarred to complete in tendering for four months.
3. The Contractor must be ensured that he is not having more than two works in hand and their detail must be prescribed in the proforma & attached with the application and only upto completion of work Satisfactory including adherence to quality parameters further work will be awarded to him & two jobs shall be considered in one application subject to above.
4. The rates beyond the limit over +5% will be rejected besides this the Additional Performance security will have to borne @ 20 % & 30 % for unbalanced bid in case the rates is lower than 10 % but upto 20 % & lower than 20 % upto 30 % respectively. The tender will be accepted beyond the limit of -30 % also.

Executive Engineer,
Thalout Division,
HPPWD Thalout

NO/PW/TLD/Tender/2023:-14452-71

Dated: - 29.01.2024

Copy forwarded to the following for information and necessary action:-


1. The Engineer-in-Chief HPPWD Shimla.
2. The Deputy Commissioner Mandi Distt. Mandi HP.
3. The Sub Divisional Officer Balichowki, Distt. Mandi HP.
4. The Chief Engineer, (MZ) HPPWD Mandi.
5. The Superintending Engineer, 1st Circle, HPPWD Mandi HP.
6. The Distt. Panchayat Officer Mandi HP.
7. All AEs under this Division.
8. The President of Contractor's Association.
9. Notice Board/Accounts Branch/Drawing Branch/Supdt. With spare copies.

Executive Engineer,
Thalout Division,
HPPWD Thalout

Certificate

Certified that the tender called vide this office letter NO.

PW/TLD/Tender/2023-14452-71 dated 29.01.2024 is emergent nature and in Public interest.


Executive Engineer,
Thalout Division, HPPWD,
Thalout.

①

SCHEDULE OF QUANTITY

Name of work:- BSP/2023/962 (Construction of road Panarsa Sojha Rahdi Km 0/00 to 11/640 (SH: - C/O R/wall at RD 8/262 to 8/271.50)

Estimated Cost:-2,90,417.00
Earnest Money :-6,000.00

Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per dfg. and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 metre (fifty meter) dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil and with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge	51.49	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	20503.00
2	Providing and laying concrete for plain/reinforced concrete in 1:6:12 (one cement: six sand: Twelve crushed / stone aggregate) 40 mm (forty millimetre) nominal size open foundation complete as per drawing and technical specification Clause 802.803.1202 and 1203 with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge	3.69	4400.60	Rs. four Thousand four hundred and paise Sixty only	Per Cubic Metre	16238.00
3	Providing and laying concrete for plain/reinforced concrete in 1:4:8 (one cement: four sand: eight crushed/ stone aggregate) 40 mm (fourty millimeter) nominal size in open foundation complete as per drawing and technical specification Clause 802.803.1202 and 1203 with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	50.26	4891.60	Rs. Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	245852.00
4	Providing weepholes in brick masonry/stone masonry /plain reinforced cement abutment wing wall, return wall with 100 mm (hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One vertical : twenty horizontal) with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	20	391.20	Rs. Three hundred ninty one and paise twenty only	Each	7824.00
					Total	290417.00

Executive Engineer,
Thalout Division,
HP, PWD, Thalout

2

SCHEDULE OF QUANTITY

Name of work:- BSP/2023/962 (Construction of road Panarsa Sojha Rahdi Km 0/00 to 1/640 (SH:- C/O R/wall at RD/27/5oto 8/281)

Estimated Cost:-2,90,417.00
Earnest Money :-6,000.00
Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per dfg. and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 metre (fifty meter) dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil and with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge	51.49	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	20503.00
2	Providing and laying concrete for plain/reinforced concrete in 1:6:12 (one cement: six sand: Twelve crushed / stone aggregate) 40 mm (forty millimetre) nominal size open foundation complete as per drawing and technical specification Clause 802.803,1202 and 1203 with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	3.69	4400.60	Rs. four Thousand four hundred and paise Sixty only	Per Cubic Metre	16238.00
3	Providing and laying concrete for plain/reinforced concrete in 1:4:8 (one cement: four sand: eight crushed/ stone ssgregate) 40 mm (fourty millimeter) nominal size in open foundation complete as per drawing and technical specification Clause 802.803,1202 and 1203 with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	50.26	4891.60	Rs. Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	245852.00
4	Providing weepholes in brick masonry/stone masonry /plain reinforced cement abutment wing wall, return wall with 100 mm (hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One vertical : twenty horizontal) with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	20	391.20	Rs. Three hundred ninety one and paise twenty only	Each	7824.00
Total						290417.00

Executive Engineer,
Thalout Division
HP, PWD, Thalout

Name of work:- RRD on various roads under Panarasa section (SH: -Removal of slips, muck/debris at various RDs)
--

[illegible]

(4)

SCHEDULE OF QUANTITY

Name of work:- RRD on Nagwain to Balu road Km 0/0 to 12/500 (SH:- C/O B/wall in wire crate at RD 6/558 to 6/570)

Estimated Cost: 334587.00

Earnest Money :- 7000.00

Time :- One Month

S. No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.	84.60	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	33688.00
2	Providing and laying of Boulder upon laid in wire crates with 4 mm dia G.I.wire conforming to IS : 280 and IS:4826 in 150 mm x 150 mm mesh (woven) diagonally) including 10 percent extra for laps and joints laid with stones boulders weighting not less than 25 kg each as per drawing and technical specifications clause 1301 within all leads, lifts,carriage of materials and other incidental complete.	93.75	3098.00	Rs. Three thousand ninety eight and paise zero only	Per Cubic Metre	290438.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 including all lead and lift and as per the entire satisfaction and direction of Engineer-in-Charge.	8.28	1263.40	Rs. One Thousand two hundred sixty three and paise Forty only	Per Cubic Metre	10461.00
Total in figures					Total	334587.00
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Thalout Division
P.W.D., Thalout

5

SCHEDULE OF QUANTITY

Name of work:- RRD on Kathiyari to Ansar road Km 0/0 to 3/00 (SH:- C/O B/wall in wire crate at RD 0/00 to 0/035)

Estimated Cost: 480357.00
Earnest Money :- 10000.00

Time :- One Month

S. No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Excavation in soil in hilly area by mechanical means i/c cutting and trimming of side slopes and disposing of excavated earth with a lift up to 1.5 metre (One point five meter) and a lead upto 20 metre (Twenty meter) as per technical specification clause 1603.1 + 1603.2 and with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	65.63	140.20	Rs. one hundred forty and paise twenty only	Per Cubic Metre	9201.00
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.	28.35	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	11289.00
3	Providing and laying of Boulder upron laid in wire crates with 4 mm dia G.I. wire conforming to IS : 280 and IS:4826 in 150 mm x 150 mm mesh (woven) diagonally) including 10 percent extra for laps and joints laid with stones boulders weighting not less then 25 kg each as per drawing and technical specifications clause 1301 within all leads , lifts,carriage of materials and other incidental complete.	148.44	3098.00	Rs. Three thousand ninety eight and paise zero only	Per Cubic Metre	459867.00
Total in figures					Total	480357.00
Quoted rate in figure						
Quoted rate in words						
Rate quoted by contractor +/-						

Executive Engineer,
Thalout Division
P.P.W.D., Thalout

6

SCHEDULE OF QUANTITY

Name of work:- R.R.D on Pandoh to Shiva road Km 0/00 to 13/00 (SH:- C/o R/wall at RD. 12/207 to 12/215.50).

Estimated Cost:-354335.00
Earnest Money :-7500.00
Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per dtg. and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 metre dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	24.65	398.20	Rs.Three hundred ninety eight and paise twenty only	Per Cubic Metre	9816
2	Providing and laying dowel bar in foundation in hard rock including making holes for dowel bar and fixing 25mm dia for steel in cement slurry with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	20.00	850.00	Rs. Eight hundred fifty and paise zero only	Each	17000
3	Providing and laying concrete for plain/reinforced concrete in 1:4:8 (one cement: four sand: eight crushed/ stone sggregate) 40 mm (fourty millimeter) nominal size in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	63.78	4891.60	Rs. Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	311986
4	Providing weepholes in brick masonry/stone masonry /plain reinforced cement abutment wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1:20 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	15.00	391.20	Rs.Three hundred ninety one and paise Twenty only	Each	5868
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	7.65	1263.40	Rs.One Thousand two hundred sixty three and paise Forty only	Per Cubic Metre	9665
Total in figures						354335.00
	Quoted rate in figure		Percent			
	Quoted rate in words					

Executive Engineer,
Thalout Division,
HP,PWD,Thalout.

(7)

SCHEDULE OF QUANTITY

Name of work:- R.R.D on Pandoh, Takoli, Kullu by pass road Km 222/700 to 232/500 (SH.- C/o R/wall at RD. 227/470 to 227/475).

Estimated Cost:-491007.00
Earnest Money :-10000.00
Time :- One Month

S.No	Description of item	Quantity	In figure	Rate		Unit	Amount
				In word			
1	Earth work in excavation for structure as per dig. and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other detarious material and disposal up to a lead of 50 metre dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	16.40	398.20	Rs. Three hundred ninety eight and paise twenty only		Per Cubic Metre	6530
2	Providing and laying concrete for plain/reinforced concrete in 1:3:6 (one cement: three sand: six crushed/ stone ssgregate) 40 mm (fourty millimeter) nominal size in open foundation complete as per drawing and technical specification Clause 802.803,1202 and 1203 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	64.80	5771.80	Rs. Five thousand seven hundred seventy one and paise eighty only		Per Cubic Metre	374013
3	Providing weepholes in brick masonry/stone masonry /plain reinforced cement abutment wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1:20 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	12.00	391.20	Rs. Three hundred ninety one and paise twenty only		Each	4694
4	Providing and laying of Boulder upron laid in wire crates with 4 mm dia G.I.wire conforming to IS : 280 and IS.4826 in 100 mm x 100 mm mesh (woven) diagonally) including 10 percent extra for laps and joints laid with stones boulders weighing not less than 25 kg each as per drawing and technical specifications clause 1301 within all leads , lifts,carriage of materials and other incidental complete.	31.24	3254.70	Rs. Three thousand two hundred fifty four and paise seventy only		Per Cubic Metre	101677.00
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	3.24	1263.40	Rs. One thousand two hundred sixty three and paise Forty only		Per Cubic Metre	4093
Total in figures							491007.00
Rate quoted by contractor +/-			Percent				
Quoted rate in figure							
Quoted rate in words							

Executive Engineer,
Thalout Division,
HP PWD, Thalout.

28

SCHEDULE OF QUANTITY

Estimated Cost:- Rs. 499200.00
Earnest Money :- Rs. 10000.00
Time :- Two Months

Name of work:- RRD on link road from Deoli to Phaidhar Kalakut HB Km. 0/0 to 2/0
(SH:- Hitting of Excavator cum loader for removal of slips, muck debris etc. at various RD's) Job No. 1

Sr. No.	Description	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hitting of Excavator- cum- loader for removal of slips/ debris / Muck, road side berms, Katcha drain and boulder in all kinds of soil including rocky portion and saturated soil and disposing of all excavated earth or unserviceable materials from the road surface upto any leads and lifts in emergent cases as and when required or as per direction of Engineer-in-charge. The machine should work 6 (Six) hours daily and remove at least 25.00 (Twenty five) cubic metre quantity of soil per hour. Any loss of public property or any accident etc. the contractor is fully responsible during the execution of work. The fuel /POL charges and operational staff for the machine will be provided by the owner. The repair and other incidental charges of machinery during the execution of work will be borne by the contractor. While making the/ record entry, it may be ensured that the quantum of work done shall be minimum prescribed quantity and not less than 25.00 (Twenty five) cubic metre per hour .	416	1200.00	Rupees one thousand two hundred and paise zero only.	Per Hour	499200.00
					Total:-	499200.00
	Rate Quoted by contractor (+/-)					
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
T.P. PWD Thalout

9

SCHEDULE OF QUANTITY

Name of work:- RRD on Kukiah to Baggi road Km. 0/0 to 8/0 (SH:- C/O R/ wall at RD 5/240 to 5/254.40

Estimated Cost:- Rs.	412724.00
Earnest Money :- Rs.	8400.00
Time :- One Month	

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto in all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	27.17	398.20	Rupees Three hundred ninety eight and paise twenty only.	Per Cubic Metre	10819.00
2	Providing and laying of Boulder upon laid in wire crates with 4 mm (Four millimetre) dia G.I. wire conforming to IS : 280 and IS-4826 in 150 mm x 150 mm (one hundred fifty millimetre x one hundred fifty millimetre) mesh (woven) diagonally) including 10 (Ten) percent extra for laps and joints laid with stones boulders weighting not less than 25 kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	114.05	3098.00	Rs. Three thousand ninety eight and paise zero only	Per Cubic Metre	353327.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and as per the entire satisfaction and direction of Engineer-in-Charge.	38.45	1263.40	Rupees One thousand two hundred sixty three and paise forty only	Per Cubic Metre	48578.00
					Total	412724.00
	Rate Quoted by contractor (+/-)					
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalour Division
FPWD, Thalour

Name of work:- R.R.D on Pandoh, Takoli, Kullu by pass road Km 222/700 to 232/500 (SH:- C/o R/wall at RD. 227/475 to 227/480).

SCHEDULE OF QUANTITY

Estimated Cost:-49943.00
Earnest Money :-10000.00
Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per dig. and technical specification clause 305.1 i/c setting out construction of shoing and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 metre dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	18.25	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	7267
2	Providing and laying dowel bar in foundation in hard rock including making holes for dowel bar and fixing 25mm dia for steel in cement slurry with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	25.00	850.00	Rs. Eight hundred fifty and paise zero only	Each	21250
3	Providing and laying concrete for plain/reinforced concrete in 1:3:6 (one cement: three sand: six crushed/ stone ssgregate) 40 mm (fourty millimeter) nominal size in open foundation complete as per drawing and technical specification Clause 802.803.1202 and 1203 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	62.46	5771.80	Rs. Five thousand seven hundred seventy one and paise eighty only	Per Cubic Metre	360507
4	Providing weepholes in brick masonry/stone masonry /plain reinforced cement abutment wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1:20 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	12.00	391.20	Rs. Three hundred ninety one and paise Twenty only	Each	4694
5	Providing and laying of Boulder upon laid in wire crates with 4 mm dia G.I. wire conforming to IS : 280 and IS:4826 in 100 mm x 100 mm mesh (woven) diagonally including 10 percent extra for laps and joints laid with stones boulders weighing not less than 25 kg each as per drawing and technical specifications clause 1301 within all leads , lifts, carriage of materials and other incidental complete	31.24	3254.70	Rs. Three thousand two hundred fifty four and paise seventy only	Per Cubic Metre	101677.00
6	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	3.60	1263.40	Rs. One Thousand two hundred sixty three and paise Forty only	Per Cubic Metre	4548
Total in figures						49943.00
Rate quoted by contractor +/-			Percent			
Quoted rate in figure						
Quoted rate in words						

Executive Engineer,
Talabot Division,
R.P.W.D. Thalabot

(11)

SCHEDULE OF QUANTITY

Rajendra Singh

Name of work:- Rep. of Resistor of Bhatwari to Rensh road Km 0/0 to 8/640 (SH:- C/o created R/wall at RD 6/590 to 6/620).

Estimated Cost: 467778.00
Earnest Money :- 10000.00

Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.	80.55	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	32075.00
2	Providing and laying of Boulder upron laid in wire crates with 4 mm dia G.I.wire conforming to IS : 280 and IS:4826 in 150 mm x 150 mm mesh (woven) diagonally) including 10 percent extra for laps and joints laid with stones boulders weighting not less than 25 kg each as per drawing and technical specifications clause 1301 within all leads , lifts,carriage of materials and other incidental complete.	140.64	3098.00	Rs. Three thousand ninety eight and paise zero only	Per Cubic Metre	435703.00
Total in figures					Total	467778.00
Rate quoted by contractor +/-						
Quoted rate in figure						
Quoted rate in words						

Executive Engineer,
Thalout Division,
MP, PWD, Thalout

(12)

SCHEDULE OF QUANTITY

R.R. D. an.

Name of work:- Bhatwari to Rensh road Km 0/0 to 8/640 (SH:- C/o created R/wall at RD 5/755 to 5/770).

Estimated Cost: 253923.00
Earnest Money :- 5500.00

Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.	57.75	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	22996.00
2	Providing and laying of Boulder upon laid in wire crates with 4 mm dia G.I.wire conforming to IS : 280 and IS:4826 in 150 mm x 150 mm mesh (woven) diagonally) including 10 percent extra for laps and joints laid with stones boulders weighing not less than 25 kg each as per drawing and technical specifications clause 1301 within all leads , lifts,carriage of materials and other incidental complete.	70.32	3098.00	Rs. Three thousand ninty eight and paise zero only	Per Cubic Metre	217851.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 including all lead and lift and as per the entire satisfaction and direction of Engineer-in-Charge.	10.35	1263.40	Rs. One thousand two hundred sixty three and paise forty only	Per Cubic Metre	13076.00
Total in figures					Total	253923.00
	Rate quoted by contractor +/-					
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Thalout Division ,
H.P.W.D, Thalout

SCHEDULE OF QUANTITY

Estimated Cost:-3,49,330.00

Estimated Cost:-3,49,330.
Earnest Money :-7,000.00

Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drg. and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other detritious material and disposal up to a lead of 50 metre dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.	40.60	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	16167
2	Providing and laying concrete for plain/reinforced concrete in 1:6:12 (one cement: six sand: Twelve crushed / stone aggregate) 40 mm (forty millimetre) nominal size open foundation complete as per drawing and technical specification Clause 802.803.1202 and 1203 with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	4.37	4400.60	Rs. four Thousand four hundred and paise Sixty only	Per Cubic Metre	19231.00
3	Providing and laying concrete for plain/reinforced concrete in 1:4:8 (one cement: four sand: eight crushed/ stone aggregate) 40 mm (fourty millimeter) nominal size in open foundation complete as per drawing and technical specification Clause 802.803.1202 and 1203 with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	60.84	4891.60	Rs. Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	297605
4	Providing weepholes in brick masonry/stone masonry /plain reinforced cement abutment wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1:20 with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	20	391.20	Rs. Three hundred ninety one and paise Twenty only	Each	7824
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	6.73	1263.40	Rs. One Thousand two hundred sixty three and paise Forty only	Per Cubic Metre	8503
	Total in figures					349330.00
	Quoted rate in figure		Percent			
	Quoted rate in words					

Executive Engineer,
Thalout Division,
HP, PWD, Thaloud

Executive Engineer,
Thalout Division,
HP, PWD, Thalout

14

SCHEDULE OF QUANTITY

Name of work:- R.R.D on Satuir to mThatta road Km 0/00 to 5/00 (SH:- C/o R/wall at RD. 1/451 to 1/458.50).

Estimated Cost:-333411.00
Earnest Money :-7000.00
Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per dig. and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of slumps and other deleterious material and disposal up to a lead of 50 metre dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	41.81	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	16649
2	Providing and laying dowel bar in foundation in hard rock including making holes for dowel bar and fixing 25mm dia for steel in cement slurry with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	20.00	850.00	Rs. Eight hundred fifty and paise zero only	Each	17000
3	Providing and laying concrete for plain/reinforced concrete in 1:4:8 (one cement: four sand: eight crushed/ stone sggregate) 40 mm (fourty millimeter) nominal size in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	28.80	4891.60	Rs. Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	140878
4	Providing weepholes in brick masonry/stone masonry /plain reinforced cement abutment wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1:20 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	15.00	391.20	Rs. Three hundred ninety one and paise Twenty only	Each	5868
5	Providing and laying of Boulder upon laid in wire crates with 4 mm dia G.I wire conforming to IS : 280 and IS:4826 in 100 mm x 100 mm mesh (woven) diagonally including 10 percent extra for laps and joints laid with stones boulders weighing not less than 25 kg each as per drawing and technical specifications clause 1301 within all leads , lifts,carriage of materials and other incidental complete.	41.46	3254.70	Rs. Three thousand two hundred fifty four and paise seventy only	Per Cubic Metre	134940.00
6	Construction of dry rubble masonry for retaining walls, breast walls revetment walls and parapets etc. for sub structur and super structre complete as per drawing and technical specification Clause 704.6 and 1302.5 as per entire satisfaction and direction of Engineer-in-Charge.	3.00	3751.20	Rs. Three thousand Seven hundred fifty one and paise twenty only	Per Cubic Metre	11254.00
7	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	5.40	1263.40	Rs. One Thousand two hundred sixty three and paise Forty only	Per Cubic Metre	6822
Total in figures						333411.00
			Percent			
Quoted rate in figure						
Quoted rate in words						

Executive Engineer,
Thalout Division,
HP,PWD,Thalout

SCHEDULE OF QUANTITY

Estimated Cost: 3,48,516.00

Earnest Money :-7,000.00

Time :- One Month

Executive Engineer,
Thalout Division
HP, PWD, Thalout

(6)

SCHEDULE OF QUANTITY

Name of work:- R.R.D on Jala Khini road Km 0/00 to 2/465 (SH:- C/O crated B/wall at RD 0/885 to 0/897.50)

Estimated Cost: 3,12,747.00

Earnest Money :-6,500.00

Time :- One Month

S. No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Excavation in soil in hilly area by mechanical means i/c cutting and trimming of side slopes and disposing of excavated earth with a lift up to 1.5 metre and a lead upto 20 metre as per technical specification clause 1603.1, 1603.2 and as per the entire satisfaction and direction of Engineer-in-Charge.	48.44	140.20	Rs. one hundred forty and paise twenty only	Per Cubic Metre	6791.000
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil and with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	8.63	398.20	Rs. Three hundred Ninety eight and paise twenty only	Per Cubic Metre	3436.00
3	Providing and laying of Boulder upron laid in wire crates with 4 mm (four millimeter) dia G.I.wire conforming to IS : 280 and IS:4826 in 150 mm x 150 mm (onehundred into one hundred millimeter) mesh (woven) diagonally including 10 % (Ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 kg (Twenty five kilogramme)each as per drawing and technical specifications clause 1301 with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	97.65	3098.00	Rs. Three thousand ninety eight and paise zero only	Per Cubic Metre	302520.00
					Total	312747.00

Executive Engineer,
Thalout Division
P.W.D. Thalout

(17)

SCHEDULE OF QUANTITY

Name of work:- RRD on Aut Takoli Parashar road Km 0/00 to 27/00 (SH: - C/O Balance work of R/wall & B/wall at RD 22/415 to 22/425 & Crated R/wall at RD 22/855 to 22/870) at Rd 21/578 to 21/583)

Estimated Cost:-3,81,594.00
Earnest Money :-8,000.00
Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Excavation in soil in hilly area by mechanical means i/c cutting and trimming of side slopes and disposing of excavated earth with a lift up to 1.5 metre (One point five meter) and a lead upto 20 metre (Twenty meter) as per technical specification clause 1603.1 + 1603.2 and with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	50.93	140.20	Rs. one hundred forty and paise twenty only	Per Cubic Metre	7140.00
2	Earth work in excavation for structure as per dry. and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 metre (fifty meter) dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil and with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge	7.50	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	2987.00
3	Providing and laying of Boulder upon laid in wire crates with 4 mm (four millimeter) dia G.I. wire conforming to IS : 280 and IS:4826 in 150 mm x 150 mm (one hundred into one hundred millimeter) mesh (woven) diagonally) including 10 % (Ten percent) extra for laps and joints laid with stones boulders weighing not less than 25 kg (Twenty five kilogram) each as per drawing and technical specifications clause 1301 with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	78.14	3098.00	Rs. Three thousand ninety eight and paise zero only	Per Cubic Metre	242078.00
4	Providing and laying concrete for plain/reinforced concrete in 1:4:8 (one cement: four sand: eight crushed/ stone ssgregate) 40 mm (fourty millimeter) nominal size in open foundation complete as per drawing and technical specification Clause 802.803,1202 and 1203 with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	23.50	4891.60	Rs. Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	114953.00
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204. 3.8 including all lead and lift and with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	8.33	1263.40	Rs. One Thousand two hundred sixty three and paise Forty only	Per Cubic Metre	10524.00
6	Providing weepholes in brick masonry/stone masonry /plain reinforced cement abutment wing wall. return wall with 100 mm (hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One vertical : twenty horizontal) with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	10	391.20	Rs. Three hundred ninety one and paise twenty only	Each	3912.00
Total						381594.00

Executive Engineer,
Thalout Division
H. P. M. Thalout

(187)

SCHEDULE OF QUANTITY

Name of work:- R.R. P.O.A.
 Location of: Sansoi to Kashna road Km 0/0 to 6/250 (Balance work) (SH:- C/o
 Rwall at RD 3/683 to 3/705).

Estimated Cost: 413547.00
 Earnest Money :- 8500.00
 Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Excavation in soil in hilly area by mechanical means i/c cutting and trimming of side slopes and disposing of excavated earth with a lift up to 1.5 metre (One point five meter) and a lead upto 20 metre (Twenty meter) as per technical specification clause 1603.1 + 1603.2 and with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	19.01	140.20	Rs. one hundred forty and paise twenty only	Per Cubic Metre	2665.00
2	Providing and laying of Boulder upron laid in wire crates with 4 mm dia G.I.wire conforming to IS : 280 and IS:4826 in 150 mm x 150 mm mesh (woven) diagonally including 10 percent extra for laps and joints laid with stones boulders weighting not less then 25 kg each as per drawing and technical specifications clause 1301 within all leads , lifts, carriage of materials and other incidental complete.	128.13	3098.00	Rs. Three thousand ninety eight and paise zero only	Per Cubic Metre	396947.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 including all lead and lift and as per the entire satisfaction and direction of Engineer-in-Charge.	11.03	1263.40	Rs. One thousand two hundred sixty three and paise forty only	Per Cubic Metre	13935.00
Total in figures					Total	413547.00
Rate quoted by contractor +/-						
Quoted rate in figure						
Quoted rate in words						

Executive Engineer,
 Thaloat Division,
 H.P, PWD, Thaloat

(19)

Name of work:- P.R.D.O.
Restoration of Sansoi to Kashna road Km 0/0 to 6/250 (Balance work) (SH:- C/o
R/wall at RD 3/645 to 3/664).

SCHEDULE OF QUANTITY

Estimated Cost: 493180.00
 Earnest Money :- 10000.00

Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Excavation in soil in hilly area by mechanical means i/c cutting and trimming of side slopes and disposing of excavated earth with a lift up to 1.5 metre (One point five meter) and a lead upto 20 metre (Twenty meter) as per technical specification clause 1603.1 + 1603.2 and with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	78.38	140.20	Rs. one hundred forty and paise twenty only	Per Cubic Metre	10989.00
2	Providing and laying of Boulder upron laid in wire crates with 4 mm dia G.I. wire conforming to IS : 280 and IS-4826 in 150 mm x 150 mm mesh (woven) diagonally) including 10 percent extra for laps and joints laid with stones boulders weighing not less than 25 kg each as per drawing and technical specifications clause 1301 within all leads , lifts, carriage of materials and other incidental complete.	148.44	3098.00	Rs. Three thousand ninety eight and paise zero only	Per Cubic Metre	459867.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 including all lead and lift and as per the entire satisfaction and direction of Engineer-in-Charge.	17.67	1263.40	Rs. One thousand two hundred sixty three and paise forty only	Per Cubic Metre	22324.00
Total in figures					Total	493180.00
Rate quoted by contractor +/-						
Quoted rate in figure						
Quoted rate in words						

Executive Engineer,
 Talabot Division,
 P.W.D., Talabot

20

SCHEDULE OF QUANTITY

Name of work:- RRD on road from Mahudhar to Nalwagi Km. 0/0 to 4/265 (SH:- C/O B/wall at RD 3/980 to 4/005)

Estimated Cost:- Rs. 177422.00
Earnest Money :- Rs. 3700.00
Time :- One Month

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means over areas (exceeding 30 cm in depth, 1.50 metre in width as well as 10 sqm. on plan) including getting out and disposal of excavated earth lead up to 50 metre and lift up to 1.50 metre including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	34.00	140.20	Rupees One hundred forty and paise twenty only.	Per Cubic Metre	4767.00
2	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto in all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	5.00	398.20	Rupees Three hundred ninety eight and paise twenty only.	Per Cubic Metre	1991.00
3	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803, 1202 and 1203 plain cement concrete 1:4:8 (one cement four Sand: eight graded stone aggregate forty millimetre nominal size) including form work and curing complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	32.81	4891.60	Rupees Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	160493.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V/20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614.709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge	26	391.20	Rupees Three hundred ninety one and paise twenty only	Each	10171.00
Quoted rate in figures					Total	177422.00
Quoted rate in words						

Executive Engineer,
Thalout Division,
HPPWD Thalout.

(21)

SCHEDULE OF QUANTITY

Name of work:- R/R D. onvarious road under Nagwain Section (SH:- Hiring of JCB for removal of slips/muck debris in various RDs)

Estimated Cost:- 199200.00
 Earnest Money:- 4000.00
 Time:- One Month

	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of JCB machinerries to deployed for cutting excavation/filling/removal of slips on cost of fuel oil lubricants and wedges of operating staff, any repair during operation will be carried out by the owner at his risk and cost of the shifting machinery from one place to other at required location actual working hours will be accounted for the payment. Excavation in all kind of soil and loading in truck during the process of removal of slips/debris if required at site complete in all respect as per the direction of the Engineer-in Charge.	166.00	1200.00	Rs. One thousand two hundred and paise zero only	Per Hours	199200.00
					Total	199200.00

Executive Engineer,
 Thalout Division,
 HP PWD Thalout.

(22)

SCHEDULE OF QUANTITY

Name of work:- R.R.D on Sansol to Kashna road Km 0/00 to 6/250 (SH:- C/O crated B/wall at RD 3/165 to 3/185)

Estimated Cost: 240666.00

Earnest Money :-5000.00

Time :- One Month

S. No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in any leads and lifts as per technical specification 302.3.5 and 1611 including carriage of material and other incidentals in all leads and lifts and as per the direction of the Engineer-in-Charge.	302.500	125.10	Rs. One hundred Twenty five and paise ten only	Per cubic metre	37843.00
2	Excavation in soil in hilly area by mechanical means i/c cutting and trimming of side slopes and disposing of excavated earth with a lift up to 1.5 metre and a lead upto 20 metre as per technical specification clause 1603.1, 1603.2 and as per the entire satisfaction and direction of Engineer-in-Charge.	23.00	140.20	Rs. one hundred forty and paise twenty only	Per Cubic Metre	3225.000
3	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil and with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	15.00	398.20	Rs. Three hundred Ninety eight and paise twenty only	Per Cubic Metre	5973.00
4	Providing and laying of Boulder upon laid in wire crates with 4 mm (four millimeter) dia G.I.wire conforming to IS : 280 and IS:4826 in 150 mm x 150 mm (onehundred into one hundred millimeter) mesh (woven) diagonally) including 10 % (Ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 kg (Twenty five kilograme)each as per drawing and technical specifications clause 1301 with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	62.50	3098.00	Rs. Three thousand ninety eight and paise zero only	Per Cubic Metre	193625.00
Total						240666.00

Executive Engineer,
Thalout Division ,
HP, PWD, Thalout

(23)

(389)

SCHEDULE OF QUANTITY

Name of work:- R.R.D on Rahla Shayan road Km 0/00 to 2/500 (SH:- C/O crated B/wall at RD 0/465 to 0/485)

Estimated Cost: 4,97,070.00

Earnest Money :-10,000.00

Time :- One Month

S. No	Description of item	Quantity	In figure		Rate		Unit	Amount
					In word			
1	Excavation in soil in hilly area by mechanical means i/c cutting and trimming of side slopes and disposing of excavated earth with a lift up to 1.5 metre and a lead upto 20 metre as per technical specification clause 1603.1, 1603.2 and as per the entire satisfaction and direction of Engineer-in-Charge.	141.00	140.20		Rs. one hundred forty and paise twenty only		Per Cubic Metre	19768.000
2	Providing and laying of Boulder upron laid in wire crates with 4 mm (four millimeter) dia G.I. wire conforming to IS : 280 and IS:4826 in 150 mm x 150 mm (onehundred into one hundred millimeter) mesh (woven) diagonally) including 10 % (Ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 kg (Twenty five kilograme)each as per drawing and technical specifications clause 1301 with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	148.44	3098.00		Rs. Three thousand ninety eight and paise zero only		Per Cubic Metre	459867.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 including all lead and lift and with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	13.80	1263.40		Rs. One Thousand two hundred sixty three and paise Forty only		Per Cubic Metre	17435.00
							Total	497070.00

Executive Engineer,
Thalout Division,
HP, PWD, Thalout

(24)

SCHEDULE OF QUANTITY

Name of work:- RRD on Nagwain to Balu road Km 0/0 to 12/500 (SH:- C/O Bl/wall in wire crate at RD 1/700 to 1/720).

Estimated Cost: 217317.00
Earnest Money :- 4500.00
Time :- One Month

S. No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Excavation in soil in hilly area by mechanical means i/c cutting and trimming of side slopes and disposing of excavated earth with a lift up to 1.5 metre (One point five meter) and a lead upto 20 metre (Twenty meter) as per technical specification clause 1603.1 + 1603.2 and with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	25.30	140.20	Rs. one hundred forty and paise twenty only	Per Cubic Metre	3547.00
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.	30.40	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	12105.00
3	Providing and laying of Boulder upron laid in wire crates with 4 mm dia G.I. wire conforming to IS : 280 and IS-4826 in 150 mm x 150 mm mesh (woven) diagonally) including 10 percent extra for laps and joints laid with stones boulders weighting not less then 25 kg each as per drawing and technical specifications clause 1301 within all leads, lifts, carriage of materials and other incidental complete.	76.10	2650.00	Rs. Two thousand six hundred fifty and paise zero only	Per Cubic Metre	201665.00
Total in figures					Total	217317.00
Quoted rate in figure		Rate quoted by contractor +/-				
Quoted rate in words						

Executive Engineer,
Thalout Division,
H.P. PWD, Thalout

(25)

SCHEDULE OF QUANTITY

Name of work:- C/O Panarsa Sojha Rahdi road to link road Nichla Surth km 0/0 to 0/370 (SH:- P/L 80mm thick precast cement concrete inter locking paver in M-50 Grade between RD 0/00 to 0/065).

Estimated Cost:-364962.00
Earnest Money :-7500.00
Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Stone soling properly hand packed filling interstices with kharanja stones and consolidating with power road roller to the requested gradient and cambor including spreading watering and rolling of binding materials moorum or earth etc. with in all leads , lifts as per entire satisfaction and direction of Engineer-in-Charge.	28.28	1654.00	Rs. One thousand six hundred fifty four and paise zero only	Per Cubic Metre	46775
2	Providing and laying concrete for plain/reinforced concrete in 1:3:6 (one cement: three sand: six crushed/ stone ssgregate) 40 mm (fourty millimeter) nominal size in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	14.14	5771.80	Rs. Five thousand seven hundred seventy one and paise eighty only	Per Cubic Metre	81613
3	Providing and laying concrete for plain/reinforced concrete in 1:2:4 (one cement: two sand: four crushed/ stone ssgregate) 40 mm (fourty millimeter) nominal size in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	1.56	6334.80	Rs. Six thousand three hundred thirty four and paise eighty only	Per Cubic Metre	9882.00
4	Providing and laying heavy duty precast cement concrete inter locking paver blocks vibro compacted upto M 50 grade i/c border or kurb block grey or coloured over sub-base of concrete with 25mm thick average thickness of cement mortar 1:4 (1 cement : 4 sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks i/c curing rubbing & polishing complete (Sub base concrete floor to be paid for 80mm thick inter locking blocks with in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge.	188.58	1202.10	Rs. One thousand two hundred two and paise ten only	Per Square Metre	226692
Total in figures						364962.00
	Quoted rate in figure			Percent		
	Quoted rate in words					

Executive Engineer,
Thalout Division
H.P. PWD, Thalout

SCHEDULE OF QUANTITY

Name of work:- C/O Panarsa Sojha Rahdi road to link road Nichia Surth km 0/0 to 0/370 (SH:- P/L 80mm thick precast cement concrete inter locking paver in M-50 Grade between RD 0/065 to 0/130).

Estimated Cost:-364962.00
Earnest Money :-7500.00

Time :- One Month

S.No	Description of item	Quantity	In figure	Rate In word	Unit	Amount
1	Stone soling properly hand packed filling interstices with kharanja stones and consolidating with power road roller to the requested gradient and camber including spreading watering and rolling of binding materials moonum or earth etc. with in all leads , lifts as per entire satisfaction and direction of Engineer-in-Charge.	28.28	1654.00	Rs. One thousand six hundred fifty four and paise zero only	Per Cubic Metre	46775
2	Providing and laying concrete for plain/reinforced concrete in 1:3:6 (one cement: three sand: six crushed/ stone sggregate) 40 mm (fourty millimeter) nominal size in open foundation complete as per drawing and technical specification Clause 802,803, 1202 and 1203 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	14.14	5771.80	Rs. Five thousand seven hundred seventy one and paise eighty only	Per Cubic Metre	81613
3	Providing and laying concrete for plain/reinforced concrete in 1:2:4 (one cement: two sand: four crushed/ stone sggregate) 40 mm (fourty millimeter) nominal size in open foundation complete as per drawing and technical specification Clause 802,803, 1202 and 1203 with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	1.56	6334.80	Rs. Six thousand three hundred thirty four and paise eighty only	Per Cubic Metre	9882.00
4	Providing and laying heavy duty precast cement conrete inter locking paver blocks vibro compacted upto M 50 grade i/c border or curb block grey or coloured over sub-base of concrete with 25mm thick average thickness of cement mortar 1:4 (1 cement : 4 sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks i/c curing rubbing & polishing complete (Sub base concrete floor to be paid for 80mm thick inter locking blocks with in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge.	188.58	1202.10	Rs. One thousand two hundred two and paise ten only	Per Square Metre	226692
Total in figures						364962.00
	Rate quoted by contractor +/-		Percent			
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
HP.PWD, Thalout

Executive Engineer,
Thalout Division,
HP, PWD, Thalout.

(27)

SCHEDULE OF QUANTITY

Name of work:- Preparation of DPR for balance work Up-Gradation of Thalout Panjain Thachi Naraingaloo Shetadhar Chet Chiuni Lambathach road km.0/0 to 75/0 (Portion Thalout to Thachi in km. 0/0 to 22/500) (S/-:- (Preparation of detailed project report and drawings plan, L-section & X-section in km. 0/0 to 22/500)						Estimated Cost:- 450000.00
						Earnest Money:- 9000.00
						Time:- One Month
S.No.	Sub Head and item of work	Qty.	Unit	Rate in		Amount
				Figure	Word	
1	Preparing of detailed Project Report of manuscript copy of detailed estimate and drawing complete including plan, cross sections, L- sections , cross Drainage works , R/walls, B/walls and other necessary provision taken in the estimate in the shape of manuscript copy to be fair out after approval from the Circle office, Chief Office, preparation of approved copies of detailed estimates along with relevant working drawings (5 Sets of DPRS complete) & Soft copies in the form of compact disc (CD) if any correction/amendment is desired by the head office the same may be corrected as desired and directed by the engineer in charge complete in all respect.	22.50	Per km.	20000.00	Rs. Twenty thousand only.	450000.00
Total in figures						4,50,000.00
Rate quoted by contractor +/-			Percent			
Quoted rate in figure						
Quoted rate in words						


 Executive Engineer,
 Thalout Division(B&R),
 PWD, Thalout

28

SCHEDULE OF QUANTITY

Name of work:- RRD on Pandoh Takoli Kullu By pass NH-21 km 222/700 to 228/500 km (SH: - C/O R/wall in (wire crate) at RD223/049 to 223/051.50).

Estimated Cost: 1,43,527.00
Earnest Money :- 3000.00
Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated ssuitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.	16.50	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	6570.00
2	Providing and laying of Boulder upron laid in wire crates with 4 mm dia G.I.wire conforming to IS : 280 and IS:4826 in 100 mm x 100 mm mesh (woven) diagonally) including 10 percent extra for laps and joints laid with stones boulders weighing not less then 25 kg each as per drawing and technical specifications clause 1301 within all leads , lifts,carriage of materials and other incidental complete.	39.06	3254.70	Rs. Three thousand two hundred fifty four and paise seventy only	Per Cubic Metre	127129.00
3	Construction of dry rubble masonry for retaining walls, breast walls revetment walls and parapets etc. for sub structur and super structure complete as per drawing and technical specification Clause 704.6 and 1302.5 as per entire satisfaction and direction of Engineer-in-Charge.	2.62	3751.20	Rs. Three thousand Seven hundred fifty one and paise twenty only	Per Cubic Metre	9828.00
		Total in figures			Total	143527.00
		Rate quoted by contractor +/-				
Quoted rate in figure						
Quoted rate in words						

Executive Engineer,
Thalout Division,
HP, PWD, Thalout

29

SCHEDULE OF QUANTITY

Name of work:- BSP/2023/1040 Construction of Panarsa Solha Rahdi road Km 0/0 to 11/640 (SH:- C/o PCC R/wall at RD 8/322 to 8/334) Deposit

Estimated Cost:-3,49,330.00
Earnest Money :-7,000.00

Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drg. and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 metre dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.	40.60	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	16167
2	Providing and laying concrete for plain/reinforced concrete in 1:6:12 (one cement six sand: Twelve crushed / stone aggregate) 40 mm (forty millimetre) nominal size open foundation complete as per drawing and technical specification Clause 802.803, 1202 and 1203 with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	4.37	4400.60	Rs. four Thousand four hundred and paise Sixty only	Per Cubic Metre	19231.00
3	Providing and laying concrete for plain/reinforced concrete in 1:4:8 (one cement four sand: eight crushed/ stone aggregate) 40 mm (fourty millimeter) nominal size in open foundation complete as per drawing and technical specification Clause 802.803, 1202 and 1203 with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	60.84	4891.60	Rs. Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	297605
4	Providing weepholes in brick masonry/stone masonry /plain reinforced cement abutment wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1:20 with in all lead and lift as per entire satisfaction and direction of Engineer-in-Charge.	20	391.20	Rs. Three hundred ninety one and paise Twenty only	Each	7824
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	6.73	1263.40	Rs. One Thousand two hundred sixty three and paise Forty only	Per Cubic Metre	8503
Total in figures						349330.00
Quoted rate in figure			Percent			
Quoted rate in words						

Executive Engineer,
Thalout Division,
HP, PWD, Thalout

Estimated Cost:-495497.00
Earnest Money :-10000.00

Time :- One Month

Executive Engineer,
Thalab Division
PP PWD, Thalab

312

SCHEDULE OF QUANTITY

Name of work:- RRD on Sudhrani to Thatta road Km. 0/0 to 5/500 (SH:- C/O R/wall at RD 1/240 to 1/250)

Estimated Cost:- Rs. 220212.00

Earnest Money :- Rs. 4500.00

Time :- One Month

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out, construction of shorting and bracing, removal of stumps and other deleterious material and disposal upto in all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	17.95	398.20	Rupees Three hundred ninety eight and paise twenty only.	Per Cubic Metre	7148.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 plain cement concrete 1:6:12 (one cement: six sand: twelve graded stone aggregate forty millimetre nominal size) including form work and curing complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	4.30	4400.60	Rupees Four thousand four hundred and paise sixty only	Per Cubic Metre	18923.00
3	Stone masonry in cement mortar for sub structure complete as per drawing and technical specification clauses 702,704,1202 & 1204 random rubble masonry in cement mortar 1:6 (one cement: six sand) complete within all leads, lifts carriage of material and other incidentals as per entire satisfaction and direction of Engineer-in-Charge.	16.90	5197.20	Rupees Five thousand one hundred ninety seven and paise twenty only.	Per cubic metre	87833.00
4	Construction of Random Rubble dry stone masonry as per MORD specification Clause 704.6 and 1302.5 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	21.00	3751.20	Rupees Three thousand seven hundred fifty one and paise twenty only	Per Cubic Metre	78775.00
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and as per the entire satisfaction and direction of Engineer-in-Charge.	15.60	1263.40	Rupees One thousand two hundred sixty three and paise forty only	Per Cubic Metre	19709.00
6	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical is to twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge	20	391.20	Rupees Three hundred ninety one and paise twenty only	Each	7824.00
					Total	220212.00
	Rate Quoted by contractor (+/-)					
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
PPWD, Thalout

322

SCHEDULE OF QUANTITY

Name of work:- RRD on Bali Thachi road Km. 0/0 to 25/0 (Sh:- C/O R/wall at RD 5/540 to 5/550)

Estimated Cost:- Rs.	461507.00
Earnest Money :- Rs.	9200.00
Time :- One Month	

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto in all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	29.80	398.20	Rupees Three hundred ninety eight and paise twenty only.	Per Cubic Metre	11866.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802, 803, 1202 and 1203 plain cement concrete 1:6:12 (one cement: six sand: twelve graded stone aggregate forty millimetre nominal size) including form work and curing complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	4.80	4400.60	Rs. Four thousand four hundred and paise sixty only	Per Cubic Metre	21123.00
3	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802, 803, 1202 and 1203 plain cement concrete 1:4:8 (one cement: four Sand: eight graded stone aggregate forty millimetre nominal size) including form work and curing complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	79.60	4891.60	Rupees Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	389371.00
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and as per the entire satisfaction and direction of Engineer-in-Charge.	18.60	1263.40	Rupees One thousand two hundred sixty three and paise forty only	Per Cubic Metre	23499.00
5	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge	40	391.20	Rupees Three hundred ninety one and paise twenty only	Each	15648.00
					Total:-	461507.00
	Rate Quoted by contractor (+/-)					
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
HPPWD, Thalout

33

SCHEDULE OF QUANTITY

Name of work:- R.R.D on Pandoh to Shiva road Km 0/00 to 13/00 (SH:- C/o R/wall at RD. 5/533 to 5/541.80).

Estimated Cost:-360696.00

Earnest Money :-7500.00

Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per dty. and technical specification clause 305.1 l/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 metre dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	22.79	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	9075
2	Providing and laying concrete for plain/reinforced concrete in 1:4:8 (one cement: four sand: eight crushed/ stone ssgregate) 40 mm (fourty millimeter) nominal size in open foundation complete as per drawing and technical specification Clause 802.803,1202 and 1203 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	68.00	4891.60	Rs. Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	332629
3	Providing weepholes in brick masonry/stone masonry /plain reinforced cement abutment wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1:20 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	20.00	391.20	Rs. Three hundred ninety one and paise Twenty only	Each	7824
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	8.84	1263.40	Rs. One Thousand two hundred sixty three and paise Forty only	Per Cubic Metre	11168
Total in figures						360696.00
	Quoted rate in figure		Percent			
	Quoted rate in words					

Executive Engineer,
Thalout Division,
P.W.D. Thalout

(34)

SCHEDULE OF QUANTITY

Name of work:- R.R.D on Pandoh to Shiva road Km 0/00 to 13/00 (SH:- C/o R/wall at RD. 5/525 to 5/533).

Estimated Cost:-255160.00
Earnest Money :-5500.00

Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drg. and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 metre dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	20.72	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	8251
2	Providing and laying concrete for plain/reinforced concrete in 1:4:8 (one cement: four sand: eight crushed/ stone ssgregate) 40 mm (fourty millimeter) nominal size in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	46.80	4891.60	Rs. Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	228927
3	Providing weepholes in brick masonry/stone masonry (plain reinforced cement abutment wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1:20 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	20.00	391.20	Rs. Three hundred ninety one and paise Twenty only	Each	7824
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	8.04	1263.40	Rs. One Thousand two hundred sixty three and paise Forty only	Per Cubic Metre	10158
Total in figures						255160.00
Rate quoted by contractor +/-			Percent			
Quoted rate in figure						
Quoted rate in words						

Executive Engineer,
Thalout Division,
P.W.D. Thalout.

(25)

BILL OF QUANTITY

Name of work:- Restoration of damages on various roads under Pandoh Sub Division (SH:- Hiring of JCB for removal of slips / muck debris in various roads under Pandoh section B) Job No. 1					Estimated Cost:- 499200.00	
					Earnest Money:- 10000.00	
					Time:- Two Months	
S.No.	Description of item		Figure	Rate in Words	Unit	Amount
1	Hiring of JCB Machine to be deployed for snow/cutting excavation/filling removal on cost of fuel oil Lubricants and wages of operating staff any repair during operation will be carried out by the owner on his risk and cost of the shifting of machinery from one place to other at required location actual working hours will be accounted for the payment. Excavation in all kind of soil and loading in truck during the process of removal of debris if required at site complete in all respect as per direction of Engineer-in Charge.	416	1200.00	Rs. One thousand two hundred only	Per Hour	499200.00
	Total in figures				Total	499200.00
	Rate quoted by contractor +/-		Percent			
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Thalout Division (B&R),
HP PWD Thalout.

(20)

SCHEDULE OF QUANTITY

Name of work:- R.R.D on Pandoh to Shiva road Km 0/00 to 13/00 (SH:- C/o R/wall at RD. 4/818 to 4/826.20).

Estimated Cost:-293841.00

Earnest Money :-6000.00

Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drg. and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 metre dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	26.06	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	10377
2	Providing and laying concrete for plain/reinforced concrete in 1:4:8 (one cement: four sand: eight crushed/ stone ssgregate) 40 mm (fourty millimeter) nominal size in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	19.68	4891.60	Rs. Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	96267
3	Stone masonry work in cement mortar 1:6 (One cement: six sand) in foundation complete as per drawing and technical specifications Clause 702,704,1202 and 1203 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	16.73	5197.20	Rs. Five thousand one hundred ninety seven and paise twenty only	Per Cubic Metre	86949
4	Construction of dry rubble masonry for retaining walls, breast walls revetment walls and parapets etc. for sub structur and super structre complete as per drawing and technical specification Clause 704.6 and 1302.5 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	22.97	3751.20	Rs. Three thousand Seven hundred fifty one and paise twenty only	Per Cubic Metre	86165
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	8.36	1263.40	Rs. One Thousand two hundred sixty three and paise Forty only	Per Cubic Metre	10562
6	Providing weepholes in brick masonry/stone masonry /plain reinforced cement abutment wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1:20 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	9.00	391.20	Rs. Three hundred ninety one and paise Twenty only	Each	3521
Total in figures						293841.00
Rate quoted by contractor +/-			Percent			
Quoted rate in figure						
Quoted rate in words						

Executive Engineer,
Thalout Division,
HP PWD, Thalout.

(372)

SCHEDULE OF QUANTITY

Name of work:- R.R.D on Shiva to Gharan road Km 0/00 to 10/100 (SH:- C/o R/wall at RD. 2/120 to 2/135).

Estimated Cost:-412165.00

Earnest Money :-8500.00

Time :- One Month

S.No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per dfg. and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 metre dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	60.08	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	23924
2	Providing and laying concrete for plain/reinforced concrete in 1:4:8 (one cement: four sand: eight crushed/ stone sggregate) 40 mm (fourty millimeter) nominal size in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	32.40	4891.60	Rs. Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	158488
3	Providing weepholes in brick masonry/stone masonry (plain reinforced cement abutment wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1:20 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	6.00	391.20	Rs. Three hundred ninety one and paise Twenty only	Each	2347
4	Providing and laying of Boulder upon laid in wire crates with 4 mm dia G.I.wire conforming to IS : 280 and IS:4826 in 100 mm x 100 mm mesh (woven) diagonally) including 10 percent extra for laps and joints laid with stones boulders weighting not less then 25 kg each as per drawing and technical specifications clause 1301 within all leads , lifts,carriage of materials and other incidental complete.	62.22	3254.70	Rs. Three thousand two hundred fifty four and paise seventy only	Per Cubic Metre	202507.00
5	Construction of dry rubble masonry for retaining walls, breast walls revetment walls and parapets etc. for sub structr and super structre complete as per drawing and technical specification Clause 704.6 and 1302.5 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	3.00	3751.20	Rs. Three thousand Seven hundred fifty one and paise twenty only	Per Cubic Metre	11254
6	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	10.80	1263.40	Rs. One Thousand two hundred sixty three and paise Forty only	Per Cubic Metre	13645
Total in figures						412165.00
Rate quoted by contractor +/-			Percent			
Quoted rate in figure						
Quoted rate in words						

Executive Engineer,
Thalout Division,
HP,PWD,Thalout.

SCHEDULE OF QUANTITY

Name of work:- Restoration of damages on various roads under Pandoh Sub Division (SH:- Hiring of JCB for removal of slips / much debris in various roads under Pandoh section -I) Job No.1

Estimated Cost:-	499200.00
Earnest Money:-	10000.00
Time:-	Two Months

S.No.	Description of item		Rate in		Unit	Amount
			Figure	Words		
1	Hiring of JCB Machine to be deployed for snow/cutting excavation/filling removal on cost of fuel oil Lubricants and wages of operating staff any repair during operation will be carried out by the owner on his risk and cost of the shifting of machinery from one place to other at required location actual working hours will be accounted for the payment. Excavation in all kind of soil and loading in truck during the process of removal of debris if required at site complete in all respect as per direction of Engineer-in Charge.	416	1200.00	Rs. One thousand two hundred only	Per Hour	499200.00
	Total in figures				Total	499200.00
	Rate quoted by contractor +/-		Percent			
	Quoted rate in figure					
	Quoted rate in words					

Executive Engineer,
Thalout Division (B&R),
HP PWD Thalout.

Executive Engineer,
Thalout Division (B&R),
HP PWD Thalout.

(29)

SCHEDULE OF QUANTITY

Name of work:- RRD on Pandoh to Shiva road Km 0/00 to 13/00 (SH:- C/O R/wall in wire crate at RD 4/620 to 4/634.50).

Estimated Cost: 312404.00

Earnest Money :- 6500.00

Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.	59.16	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	23558.00
2	Providing and laying of Boulder upon laid in wire crates with 4 mm dia G.I. wire conforming to IS : 280 and IS:4826 in 150 mm x 150 mm mesh (woven) diagonally) including 10 percent extra for laps and joints laid with stones boulders weighting not less than 25 kg each as per drawing and technical specifications clause 1301 within all leads , lifts, carriage of materials and other incidental complete.	74.21	3098.00	Rs. Three thousand ninety eight and paise zero only	Per Cubic Metre	229903.00
3	Construction of dry rubble masonry for retaining walls, breast walls revetment walls and parapets etc. for sub structur and super structure complete as per drawing and technical specification Clause 704.6 and 1302.5 as per entire satisfaction and direction of Engineer-in-Charge.	9.56	3751.20	Rs. Three thousand Seven hundred fifty one and paise twenty only	Per Cubic Metre	35861.00
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 including all lead and lift and as per the entire satisfaction and direction of Engineer-in-Charge.	18.27	1263.40	Rs. One thousand two hundred sixty three and paise forty only	Per Cubic Metre	23082.00
Total in figures					Total	312404.00
	Quoted rate in figure					
	Quoted rate in words					

Rate quoted by contractor +/-


Executive Engineer,
Thalout Division,
HP, PWD, Thalout

Name of work:- B R D on Shiva to Gharan road Km 0/00 to 10/100 (SH:- C/o R/wall at RD. 10/090 to 10/100).

Earnest Money :-8000.00

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drg. and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 metre dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	33.00	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	13141
2	Providing and laying concrete for plain/reinforced concrete in 1:3:6 (one cement: three sand: six crushed/ stone ssgregate) 40 mm (fourty millimeter) nominal size in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	60.00	5771.80	Rs. Five thousand seven hundred seventy one and paise eighty only	Per Cubic Metre	346308
3	Providing weepholes in brick masonry/stone masonry /plain reinforced cement abutment wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1:20 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	20.00	391.20	Rs. Three hundred ninety one and paise Twenty only	Each	7824
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 with in all lead , lift as per entire satisfaction and direction of Engineer-in-Charge.	9.60	1263.40	Rs. One Thousand two hundred sixty three and paise Forty only	Per Cubic Metre	12129
	Total in figures					379402.00
	Rate quoted by contractor +/-		Percent			
	Quoted rate in figure					
	Quoted rate in words					


 Executive Engineer,
 Thalout Division,
 HP, PWD, Thalout.

412

SCHEDULE OF QUANTITY

Name of work:- RRD on Bakhali to Kholanal road Km. 0/0 to 8/600 (SH:- C/O R/ wall at RD 1/105 to 1/114.60

Estimated Cost:- Rs. 374582.00

Earnest Money :- Rs. 7500.00

Time :- One Month

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto in all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	22.18	398.20	Rupees Three hundred ninety eight and paise twenty only.	Per Cubic Metre	8832.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803, 1202 and 1203 plain cement concrete 1:4:8 (one cement four Sand: eight graded stone aggregate forty millimetre nominal size) including form work and curing complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	32.26	4891.60	Rupees Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	157803.00
3	Providing and laying of Boulder upon laid in wire crates with 4 mm (Four millimetre) dia G.I. wire conforming to IS - 280 and IS 4826 in 150 mm x 150 mm (one hundred fifty millimetre x one hundred fifty millimetre) mesh (woven) diagonally) including 10 (Ten) percent extra for laps and joints laid with stones boulders weighing not less than 25 kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	48.38	3098.00	Rs. Three thousand ninety eight and paise zero only	Per Cubic Metre	145681.00
4	Construction of Randum Rubble dry stone masonry as per MORD specification Clause 704.6 and 1302.5 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	5.94	3751.20	Rupees Three thousand seven hundred fifty one and paise twenty only	Per Cubic Metre	22282.00
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and as per the entire satisfaction and direction of Engineer-in-Charge.	22.75	1263.40	Rupees One thousand two hundred sixty three and paise forty only	Per Cubic Metre	28742.00
6	Providing weep hole in brick masonry / stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical iso twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614.709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge	18	391.20	Rupees Three hundred ninety one and paise twenty only	Each	7042.00
Total						374582.00
Rate Quoted by contractor (+/-)						
Quoted rate in figures						
Quoted rate in words						

Executive Engineer,
Thalout Division,
PPPWD, Thalout.

SCHEDULE OF QUANTITY

Name of work:- RRD on Jala to Khini road Km 0/00 to 2/465 (SH: - C/O R/wall In wire crate at RD 0/615 to 0/625)

Estimated Cost: 115637.00
Earnest Money :- 2500.00
Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other delerarious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated ssuitable material ordinary soil and as per the entire satisfaction and direction of Engineer-in-Charge.	23.40	398.20	Rs. Three hundred ninety eight and paise twenty only	Per Cubic Metre	9318.00
2	Providing and laying of Boulder upon laid in wire crates with 4 mm dia G.I.wire conforming to IS : 280 and IS:4826 in 150 mm x 150 mm mesh (woven) diagonally) including 10 percent extra for laps and joints laid with stones boulders weighting not less then 25 kg each as per drawing and technical specifications clause 1301 within all leads , lifts,carriage of materials and other incidental complete.	31.26	3098.00	Rs. Three thousand ninety eighth and paise zero only	Per Cubic Metre	96843.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 including all lead and lift and as per the entire satisfaction and direction of Engineer-in-Charge.	7.50	1263.40	Rs. One thousand two hundred sixty three and paise forty only	Per Cubic Metre	9476.00
					Total	115637.00

Executive Engineer,
Thalout Division
TP, PWD, Thalout

43

SCHEDULE OF QUANTITY

Name of work:- RRD on Bali to Thachi road Km. 0/0 to 25/0 (SH:- C/O PCC protection wall at RD 14/710 to 14/727)

Estimated Cost:- Rs. 489454.00

Earnest Money :- Rs. 9800.00

Time :- One Month

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto in all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	26.78	398.20	Rupees Three hundred ninety eight and paise twenty only.	Per Cubic Metre	10664.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803.1202 and 1203 plain cement concrete 1:6:12 (one cement: six sand: twelve graded stone aggregate forty millimetre nominal size) including form work and curing complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	9.18	4400.60	Rupees Four thousand four hundred and paise sixty only	Per Cubic Metre	40398.00
3	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803.1202 and 1203 plain cement concrete 1:4:8 (one cement: four Sand: eight graded stone aggregate forty millimetre nominal size) including form work and curing complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	82.54	4891.60	Rupees Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	403753.00
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and as per the entire satisfaction and direction of Engineer-in-Charge.	16.58	1263.40	Rupees One thousand two hundred sixty three and paise forty only	Per Cubic Metre	20947.00
5	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614.709.1204.3.7 including Carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge	35	391.20	Rupees Three hundred ninety one and paise twenty only	Each	13692.00
	Rate Quoted by contractor (+/-)				Total	489454.00
	Quoted rate in figures					
	Quoted rate in words					

Executive Engineer,
Thalout Division,
P.P.W.D., Thalout.

(44)

SCHEDULE OF QUANTITY

Name of work:- RRD on Bhurrah to Panjain road Km. 0/0 to 11/0 (Sh:- C/O B/wall at RD 0/474 to 0/488)

Estimated Cost:- Rs. 458264.00

Earnest Money :- Rs. 9200.00

Time :- One Month

Sr No.	Description of item	Qty.	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means over areas (exceeding 30 cm indepth, 1.50 metre in width as well as 10 sqm. on plan) including getting out and disposal of excavated earth lead up to 50 metre and lift up to 1.50 metre including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	47.95	140.20	Rupees One hundred forty and paise twenty only.	Per Cubic Metre	6723.00
1	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out, construction of shorting and bracing, removal of stumps and other deleterious material and disposal upto in all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material in all kind of soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	18.55	398.20	Rupees Three hundred ninety eight and paise twenty only.	Per Cubic Metre	7387.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 plain cement concrete 1:4:8 (one cement: four Sand: eight graded stone aggregate forty millimetre nominal size) including form work and curing complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	88.56	4891.60	Rupees Four thousand eight hundred ninety one and paise sixty only	Per Cubic Metre	433200.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204,3.7 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge	28	391.20	Rupees Three hundred ninety one and paise twenty only	Each	10954.00
Rate Quoted by contractor (+/-)					Total	458264.00
Quoted rate in figures						
Quoted rate in words						

Executive Engineer,
Thalout Division
HPPWD, Thalout