



E-Mail id – ce-bil2-hp@nic.in
Phone No. 01978-222551

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

"NOTICE INVITING TENDERS"

Sealed items rates tender for the following works are hereby invited by the Executive Engineer Bilaspur Division No. II HPPWD Bilaspur (H.P.) from the eligible contractors of the appropriate class registered in HPPWD, as per revised enlistment rules so as to reach in the office undersigned on 12/02/2024 up to 10:30 AM and will be opened on the same day at 11:00 AM in the presence of intending contractors. The tender application will be received in this office against cash payment on 09/02/2024 up to 10:00 AM to 02:00 PM and tender form can be had from this office on same day from 03:00 PM to 05:00 PM. The earnest money as shown against each in the shape of FDR of any bank in Himachal Pradesh duly pledged in the name of undersigned must accompany with each tender. The tender form will be issued on contractor giving proof of enlistment, GST, PAN No. etc. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 90 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors on the office of the undersigned on any working day during the office hours.

Sr. No.	Name of work	Estimated cost	Earnest Money	Cost of form	Time limit
1	Restoration of Rain damages on Sh. Naina Devi Ji Bhakra road Km. 19/0 to 37/300 (SH:- C/o B/wall as Protection wall at RD 26/135 to 26/160) Deposit work	Rs. 1,31,232	Rs. 2,700	Rs. 350/-	Three Month
2	Improvement of Blind curve on SNB road Km. 13/0 to 37/300 (SH:- Cutting of blind curve in Km. 22/280 to 22/360)	Rs. 4,99,487/-	Rs. 10,000/-	Rs. 350/-	Three Month
3	Construction of link road to Soldha Bagfuglata Chandpur Sikroha road Km. 0/0 to 6/0 (SH:- Construction of 900mm dia hume pipe culverts at RD 4/300)	Rs. 2,50,822/-	Rs. 5,100/-	Rs. 350/-	Three Month
4	Construction of link road from Makri to village Bariwala Km. 0/0 to 4/500 (SH:- C/o R/wall at RDs 2/195 to 2/212)	Rs. 3,78,722/-	Rs. 7,600/-	Rs. 350/-	Three Month
5	Restoration of Rain damages on Sh. Naina Devi Ji Bhakra road Km. 0/0 to 37/300 (SH:- C/o R/wall at RD 28/458 to 28/472)	Rs. 3,91,603/-	Rs. 7,900/-	Rs. 350/-	Three Month
6	Restoration of Rain damages on Ghiyal Dabar road Km. 0/0 to 11/0 (SH:- C/o R/wall at RD 0/375 to 0/385)	Rs. 2,07,776/-	Rs. 4,200/-	Rs. 350/-	Three Month
7	Restoration of Rain damages on Soldha Bagfuglata Chandpur Sikroha road Km. 0/0 to 6/0 (SH:- Construction of B/wall at RD 5/700 to 5/715)	Rs. 1,68,772/-	Rs. 3,400/-	Rs. 350/-	Three Month
8	Restoration of Rain damages on Deoth Lagghat Jamli road Km. 0/0 to 13/180 (SH:- C/o R/wall at RD 5/810 to 5/818)	Rs. 4,20,023/-	Rs. 8,100	Rs. 350/-	Three Month
9	Restoration of Rain damages on various road under Namhol Sub-Division (SH:- Hiring of one No. Excavator cum loader/JCB removal of slips, dressing of berms, clearance of drain at various RDs) for the year 2023-24 (Job No. 30)	Rs. 1,78,050/-	Rs. 3,600/-	Rs. 350/-	One Month
10	Restoration of Rain damages on Sh. Naina Devi Ji Bhakra road Km. 0/0 to 37/300 (SH:- Removal of land slide/Slips in portion 16/060 to 16/075 and 16/120 to 16/210)	Rs. 99,386/-	Rs. 2,000/-	Rs. 350/-	Three Month
11	Construction of Boundary wall surrounding wall Govt. Sr. Sec. School Jamli in Distt. Bilaspur (HP) (SH:- C/o PCC work and P/F steel fencing work) Deposit work	Rs. 2,04,603/-	Rs. 4,100/-	Rs. 350/-	Three Month
12	Improvement of Blind curve on SNB road Km. 13/0 to 37/300 (SH:- Cutting of Blind curve in Km. 36/765 to 36/945)	Rs. 2,04,720/-	Rs. 4,100/-	Rs. 350/-	Three Month

Certified that tender of above works are being called of emergent nature in exigency of Public interest.

Terms and Conditions:-

- The contractor should produce a copy of enlistment/renewal letter at time of application.

2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/firm shall have his registration and GST No., the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Bilaspur Division No. II HPPWD Bilaspur and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall be similarly rejected.
5. The contractor/firms are requested to insert the rate of each item in words as in figures failing which XEN reserves the rights to accept/reject any tender without assigning any reason at any stage.
6. The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
Bilaspur Divn.No.II,
HP.PWD., Bilaspur.

No.PW/NBT/CB/Tender-State/EA-1/2023-

13509-18

Dated:- 03/02/2024

Copy forwarded to the following for information and necessary action:-

1. The Engineer-In-Chief HPPWD Nirman Bhawan Nigam Vihar Shimla-2.
2. The Chief Engineer (HZ) HPPWD Hamirpur
3. The Superintending Engineers, 10th Circle, HPPWD Bilaspur.
4. The Executive Engineer (IT) O/o Engineer-in-Chief HPPWD Shimla through email- eeict-pwd-shi@hp.gov.in & cc-pwd-hp@nic.in for uploading the same on HPPWD web portal.
5. All the Assistant Engineers working under this Division.
6. Drawing Branch in this office/Notice Board.

Executive Engineer,
Bilaspur Divn.No.II,
HP.PWD., Bilaspur.

SCHEDULE OF QUANTITY.

SCHEDULE OF QUANTITY.		Estimated Cost:- Rs.=1,31,232 /-Only.				
		Earnest Money:- Rs.= 2,700/-				
		Time:- Three Months.				
Name of work :- Restoration of Rain damages on SNB road km 19/00 to 37/300 (SH:- C/o B/wall as protection wall at RD 26/135 to 26/160)(Deposit Work).						
Sr No.	Description of items.	Quantity	Rate In In Figure	In words.	Unit	Amount
		4	5			6
1	3 Excavation in hilly area in all heights and depths in all kinds of soil by manual /mechanical means including saturated soil comprising of ordinary soil , soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grade width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification Clause 300,1603.1,1603.2, & sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un -useful material for filling in road way, camber ,embankments for grade improvements and disposal of all surplus un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, alongwith its levelling fine dressing , and carriage of machineries, materials tools equipments and safety measures and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work hard rock 1/6th(One sixth) of blasting work/soft rock and 1/10th of jumper work in all cases failing which recovery shall be effected on the prevailing market rates.Any loss to the public/private property during the course of execution shall be the absolute responsibility of all the Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, heavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	25.25	Cubic Metre		Per Cubic Metre	
2	Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock , hard rocks, chiseling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification 2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials up to any leads and upto any lift including dressing of sides and bottom and backfilling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leadss and lifts.Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him.The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, heavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	17.25	Cubic Metre		Per Cubic Metre	

3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and Technical Specification Clauses, 802, 803, 1202 and 1203 (1:5:10) without plumb, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	58.77	Cubic metre.			Per Cubic metre	
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	21.00	Nos.			Each	
Total							

Executive Engineer,
Bilaspur Division No. 2,
H.B. No. 2, Bilaspur (H.P.).

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.4,99,487/-Only.

Earnest Money :- Rs.10,000/-

Time:- Three Months.

NAME OF WORK:- Improvement of Blind Curve on SNB road km 13/00 to 37/300 (SH:- Cutting of blind curve in km 22/280 to 22/360)

Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual /mechanical means including saturated soil comprising of ordinary soil , soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grade width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification Clause 300.1603.1,1603.2, & sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un -useful material for filling in road way, camber ,embankments for grade improvements and disposal of all surplus un-useful materials to required width of the road or on approved dumping sites* through all modes of transportation including head load or animals transport or mechanical means, alongwith its levelling fine dressing and carriage of machineries, materials tools equipments and safety measures and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work hard rock 1/6th(One sixth) of jumper work in all cases failing which recovery shall be effected on the prevailing market rates.Any loss to the public/private property during the course of execution shall be the absolute responsibility of all the Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage,of material within all leads and lifts. The rate includes octroi, royalty, Malkana,toll tax sale tax or other taxes imposed by the Government. A recovery of useful stones for 358.28 (Three Hundred Fifty Eight Six point Twenty Eight) cubic metre @ Rs.300/- (three hundred) Per cubic metre shall be done on pro-rata basis in each running bill for this item **	3	1324.90	Cubic metres.	6	7
Total						

Executive Engineer
Bilaspur Division No. 11
P.W.D., Bilaspur (M.P.)

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.2,50,822/-Only.
Earnest Money :- Rs 5,100/-
Time:- Three Months.

NAME OF WORK:- Construction of link road Soldha Bagfuglata Chandpur Sikroha road km 0/00 to 6/00 (SH):- Construction of 900 mm dia Hume pipe culverts at RD 4/300)

Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2 Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. All kind of soil including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3 52.71	4 cubic metre	5 Per cubic metre	6 Per cubic metre	7 7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, Malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	24.96	Cubic metre	Per Cubic metre	Per Cubic metre	
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (one Cement : Four coarse sand) : Eight graded stone aggregate 40 mm (forty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.12	Cubic Metre	Per Cubic Metre	Per Cubic Metre	
4	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:3:6 (one Cement : Three coarse sand : six graded stone aggregate 20 mm (Twenty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	13.07	Cubic metre.	Per Cubic Metre	Per Cubic Metre	
5	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (One cement : Two fine sand) including testing of joints etc. complete 900 mm (Nine Hundred Millimeter) dia. R.C.C. pipe including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.50	Running Meter	Per Running Meter	Per Running Meter	

6	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.40	Cubic metre.			Per Cubic Metre
7	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.00	Nos.			Each
Total:-						

Executive Engineer
Bhagpur Division No. 2,
H.R. PWD, Bhagpur (H.P.).

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.3,78,722/-Only.

Earnest Money :- Rs.7,600/-

Time:- Three Months.

NAME OF WORK:- Construction of link road from Makri to village Bariwala km 0/00 to 4/500 (SH:- C/o R/wall at RDs 2/195 to 2/212)

Sr No.	Description of items.	Quantity		Rates in		Unit	Amount
		Figure.	Words.	Figure.	Words.		
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	45.56	cubic metre	4	5	Per cubic metre	7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	70.76	Cubic metre			Per Cubic metre	
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	22.95	Cubic metre			Per Cubic Metre	
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v) : 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	28.00	Nos.			Each	
Total:-							


 Executive Engineer,
 Bilaspur Division No. 2,
 B.P.W.D., Bilaspur (H.P.).

SCHEDULE OF QUANTITY.						
Estimated cost:- Rs.3,91,603/-Only.						
Earnest Money :- Rs.7,900/-						
Time:- Three Months.						
NAME OF WORK:- Restoration of Rain Damages on Sh. Naina Devi ji Bakhra road km 0/00 to 37/300 (SH:- C/O R/wall at RD 28/458 to 28/472)						
Sr No.	Description of items.	Quantity		Rates in		Amount
		Figure.	Words.	Figure.	Words.	
		3		4	5	6
1	2	29.82	cubic metre			Per cubic metre
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	74.00	Cubic metre			Per Cubic metre
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	23.10	Cubic metre.			Per Cubic Metre
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	36.00	Nos.			Each
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (V): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess ,royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.					
Total:-						

Executive Engineer,
Bilaspur Division No. 2,
H.P.D., Bilaspur (H.P.)

SCHEDULE OF QUANTITY.					
Estimated cost:- Rs.2,07,776/-Only.					
Earnest Money :- Rs.4,200/-					
Time:- Three Months.					
NAME OF WORK:- Restoration of Rain Damages on Ghiyal Dabber road km 0/000 to 11/000 (SH:- C/O R/wall at RD 0/375 to 0/385)					
Sr No.	Description of items.	Quantity	Rates in		Unit
			Figure.	Words.	
1	2	3	4	5	6
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty ,Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.20	cubic metre		Per cubic metre
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	41.60	Cubic metre		Per Cubic metre
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor, and Government shall not entertain any claim whatsoever in this respect of the same.	12.00	Cubic metre.		Per Cubic Metre
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty ,Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	24.00	Nos.		Each
Total:-					

Executive Engineer,
Bilaspur Division No. 2,
H.P. P.W.D., Bilaspur (H.P.)

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.1,68,772/-Only.						
Earnest Money :- Rs 3,400/-						
Time:- Three Months.						
NAME OF WORK:- Restoration of Rain Damages on Soldha Bagfuglata Chandpur Sikroha road km 0/00 to 6/00 (SH:- Construction of B/wall at R.D 5/700 to 5/715)						
Description of items.	Quantity	Rates in		Unit	Amount	
		Figure.	Words.			
2	3	4	5	6	7	
Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. All kind of soil including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	26.70	cubic metre		Per cubic metre		
Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	35.25	Cubic metre		Per Cubic metre		
Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	26.00	Nos.		Each		
	**					
Total:-						

Executive Engineer,
Bharatpur Division No. 2,
Bharatpur, Bharatpur (H.P.)

SCHEDULE OF QUANTITY.						
Estimated cost:- Rs.4,20,023/-Only.						
Earnest Money :- Rs.8,100/-						
Time:- Three Months.						
NAME OF WORK:- Restoration of Rain Damages on Deoth Lagghat Jamli road 0/00 to 13/180 (SH:- C/o R/wall at RD 5/810 to 5/818)						
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2	3	4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. ordinary rock including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	53.04	cubic metre		Per cubic metre	7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	89.44	Cubic metre		Per Cubic metre	
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	14.88	Cubic metre.		Per Cubic Metre	
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	21.00	Nos.		Each	
Total:-						


 Executive Engineer,
 Pilesapur Division No. 4
 PWD, Bhopal

SCHEDULE OF QUANTITY.						Estimated Cost:- Rs.=1,78,050 /-Only.	
						Earnest Money:- Rs.= 3,600/-Only.	
						Time:- one Months.	
Name of work :- Restoration of Rain damages on various road under Namhol Sub-Division (SH:-Hiring of one No.Excavator cum loader/JCB removal of slips ,dressing of berms, clearance of drain at various Rds) For the Year 2023-24 (Job No.-30)							
Sr No.	Description of items.	Quantity		Rate In In Figure	In words.	Unit	Amount
1	3 1 Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4 150.00	Hours	5		Per Hours	6.
	Terms and Condition:-						
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge						
2	The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period						
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work						
	Total						

Executive Engineer,
Bilaspur Division No. 2,
H.P.W.D., Bilaspur (H.P.)

SCHEDULE OF QUANTITY.						
Estimated cost:- Rs.99,386/-Only.						
Earnest Money :- Rs. 2,000/- only						
Time:- Three Months.						
NAME OF WORK:- Restoration of Rain Damages on Sh. Naina Devi Bhakhra road km 0/00 to 37/300 (SH):- Removal of land Slide/ Slips in portion 16/060 to 16/075 and 16/120 to 16/210).						
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2	3	4	5	6	7
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611.including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	699.90	Cubic Metre		Per Cubic Metre	
Total:-						


 Executive Engineer,
 Nilgajar Division No. 2,
 PWD, Bangalore (H.P.).


SCHEDULE OF QUANTITY.

Estimated cost:- Rs.2,04,603/-Only.

Earnest Money :- Rs.4,100/-

Time:- Three Months.

NAME OF WORK:- Construction of Boundary wall Surrounding Govt. Sr. Sec. School Jamli in Distt. Bilaspur (HP) (SH:-C/O PCC work and P/F steel fencing work) (Deposit Work)

Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
		3	4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. All kind of soil including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.38	cubic metre		Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:3:6 (one Cement : Three coarse sand : six graded stone aggregate 20 mm (Twenty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.20	Cubic metre.		Per Cubic Metre	
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:2:4 (one Cement : Two coarse sand : Four graded stone aggregate) 20 mm (Twenty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.175	Cubic metre.		Per Cubic Metre	
4	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	975.20	Kilogram		Per Kilogram	

5	Supplying and fixing expended metal to wood or steel member in partition etc. (Steel Bracket) weight exceeding 3 kg not exceeding 5 Kg. Per Square metre including carriage of materials, within all leads and lift and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	60.00	square meter			per square meter
6	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.80 ltr/10 sqm of approved brand and manufacture including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi, royalty, Malkana toll tax goods and service tax, building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	120.00	square meter			per square meter
Total:-						

Executive Engineer.
 Bilaspur Division No. 14
 H.P. PWD., Bilaspur

SCHEDULE OF QUANTITY.				Estimated cost:- Rs.2,04,720/-Only.		
				Earnest Money :- Rs.4,100/-		
				Time:- Three Months.		
NAME OF WORK:- Improvement of Blind Curve on SNB road km 13/00 to 37/300 (SH:- Cutting of blind curve in km 36/765 to 36/945)						
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	s	3	4	5	6	7
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual /mechanical means including saturated soil comprising of ordinary soil , soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grade width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification Clause 300,1603.1,1603.2, & sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un -useful material for filling in road way, camber ,embankments for grade improvements and disposal of all surplus un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, alongwith its levelling fine dressing and carriage of machineries, materials tools equipments and safety measures and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work hard rock 1/6th(One sixth) of jumper work in all cases failing which recovery shall be effected on the prevailing market rates.Any loss to the public/private property during the course of execution shall be the absolute responsibility of all the Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate includes octroi, royalty, Malkana,toll tax sale tax or other taxes imposed by the Government. A recovery of useful stones for 18.25 (Eighteen point Twenty Five) cubic metre @ Rs.300/- (three hundred) Per cubic metre shall be done on pro-rata basis in each running bill for this item	912.30	Cubic metres.		Per Cubic metre	
Total						

Executive Engineer,
Bilaspur Division No. 11
HB PWD, Bilaspur