




Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:- ee-baij-hp@nic.in

CERTIFICATE

**CERTIFIED THAT THE TENDERS OF WORKS, AS
CALLED VIDE THIS OFFICE LETTER NO.PWD/BD/TA/NIT/2023-24/-
18745-18794 DATED 22-02-2024 ARE URGENT NATURE
AND PUBLIC INTEREST.**


Executive Engineer,
Baijnath Division,
HP.PWD, Baijnath.



Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:- ee-baij-hp@nic.in

"NOTICE INVITING TENDER"

Sealed item rate of tender form No. 6 & 8 are hereby invited by the Executive Engineer, Baijnath Division H.P.PWD, Baijnath on behalf of the Governor of HP for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rule and also registered under the HP General Sales Tax act 1968 so as to reach in this office on or before 07.03.2024 up to 11.30 A.M and will be opened on the same day at 12.00 Noon in the presence of intending contractors or their authorized representatives. The tender forms can be had from his office against cash payment (Non refundable) on 06.03.2024 between 2.00 PM up to 4.30 P.M and the application for issue of tender forms shall be received on 05.03.2024 up to 12.00 Noon.

The earnest money in the shape of National Saving Certificate/Time Deposit accounts/Saving Accounts in any Post Office/Bank in H.P. duly pledged in favour of the XEN H.P.PWD., Baijnath must be accompanied with the each tender. Conditional/incomplete tenders and the tenders received without earnest money as mentioned above will be similarly rejected. the offer of the tender shall be kept open for 75 days. The XEN reserves the right to accept or reject any or all tenders or to drop the proposal of the tender without assigning any reasons.

| Sr. No. | Name of work. | Amount put to tender/Estimated cost. | Earnest Money | Cost of tender form | Time limit |
|---------|--|--------------------------------------|---------------|---------------------|------------|
| 1 | Restoration of rain damages on Chobin Sansai Road Km 0/00 to 13/860) (SH: Removal of slips at various reaches) | Rs.3,55,348/- | Rs.7,100/- | Rs.350/- | Two Months |
| 2 | C/O Link Road from Balh to Raina Bari Km 0/0 to 1/600 (SH: Formation Cutting in Earth work Km 0/850 to 1/150) | Rs.4,97,567/- | Rs.10,000/- | Rs.350/- | Two Months |
| 3 | C/O HPPWD Sub Division/Division & A.E. Residence Building at Baijnath (SH: C/O Aluminum work) | Rs.2,55,896/- | Rs.5,200/- | Rs.350/- | Two Months |
| 4 | C/O Road from Sabji Mandi to village Sangrehar Near Sarman Km 0/0 to 4/0 (Portion link road to village Sarman (SH: F/C in Km 2/225 to 2/450) | Rs.4,99,288/- | Rs.10,000/- | Rs.350/- | Two Months |
| 5 | Holta Chadhar Road to Saklani Basti G.P. Drug Km 0/00 to 0/700 (SH: Providing and Laying Cement concrete Pavement RD 0/535 to 0/667) | Rs.4,95,502/- | Rs.10,000/- | Rs.350/- | Two Months |

Terms and conditions:-

1. The contractor should be registered as dealer under H.P. GST Tax Act. 2018 and also produce the Tin number, H.P. sales Tax clearance certificate from the Excise and Taxation Department.
2. The Pan Number, latest Income Tax clearance certificate and EPF No (Where applicable) duly attached with the application.
3. The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained.
4. In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
5. Only two tenders form will be issued to the contractor/firm which may be noted.
6. The contractor will also have to attach the labour employer license from the labour office with the application.
7. Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
8. The contractor shall be responsible for rectifying defects noticed within One year from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
9. The contractor shall have all required machinery such as Truck/ Tipper, Mixture, water tanker Vibrator etc or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
10. The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an under taking viz he will get complete the works in hand before award of work with in schedule time.
11. All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
12. The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/ permit.

Executive Engineer,
Baijnath Division.,
H.P.PWD., Baijnath.

For & On behalf of the governor of H.P.

NO:-PWD/BD/TA/NIT/2023-24/-

18745-18794

Dated:- 22.02.2024

- 1 Copy to the F.C. cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
- 2 The Engineer-in-chief, HPPWD, Shimla
- 3 The Chief Engineer (MZ), HPPWD, Mandi.
- 4 The Superintending Engineer, JNR, Circle HPPWD, Joginder Nagar.
- 5 All the Assistant Engineer working under this Division.
- 6 Drawing Branch in this office.
- 7 Notice Board.
- 8 The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
Baijnath Division.,
H.P.PWD., Baijnath.

①

| D.N.I.T/ SCHEDULE OF QUANTITY | | | | | | |
|--|--|---------------|---------|----------------------------|---------|-----------------|
| Name of Work:-Restoration of rain damages on Chobin Sansai Road (km 0/00 to 13/860) | | | | Estimated Cost:- 355348.00 | | |
| (SH:- Removal of slips at various reaches 4/730 to 4/790 .) | | | | Earnest Money:- 7100.00 | | |
| | | | | Time:- Two Months | | |
| SR. No. | Description of work | No.or Qty. | Unit | Rate | | AMOUNT Rs. P |
| | | | | In Figure | Figures | |
| 1 | Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.50 mtr. And less than 100 mtr. As per technical specification 302.3.5 and 1611. Including carriage of materials within leads and lifts and other incidental.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government. | 2854.20 | Per cum | | | |
| Total:- | | | | | | |

Executive Engineer
Bajnat Division
H.P.P.V. S., Bajnat

SCHEDULE OF QUANTITY

Name of Work: C/O Link Road from Balh to Raina Bar/ Km 0/0 to 1/600
(SH: Formation Cutting in Earth work Km 0/850 to 1/150).

Estimated Cost: Rs. 497567/-
Earnest Money: Rs. 10000/-
Time Limit : Two Months

SCHEDULE OF WORKS

| S No. | Description of work | No. or Qty. | Unit | Estimated Rate | | AMOUNT Rs. P |
|----------|---|----------------|-----------------|----------------|-------|-----------------|
| | | | | Figure | Words | |
| 1 | Excavation in earthwork in hilly areas in all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and levels as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification clause 1603.1 and 1603.2 to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, up to all leads & lift and finishing of the road to specified dimensions or as directed by the Engineer-in charge for smooth riding. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases. The recovery @ Rs. 300.00 per cubic metre for 52.37 cubic metre useful stones already deducted in the preparing of estimate. The rate including of octroi, royalty, Malkana, tolltax, GST or other taxes imposed by the government | 1745.85 | Per Cubic Meter | | | |

Execd. by
Baljnan D. J.
H.P.F.W.D. Baljnan

SCHEDULE OF QUANTITY

Name of Work: C/O HPPWD Sub Division / Division & A.E. Residence Building at Baijnath
SH: (C/O Aluminium Work)

Estimated Cost: Rs. 255896/-
Earnest Money: Rs. 5200/-
Time Limit : Two Months


SCHEDULE OF WORKS

| S No | Description of work | No. or Qty. | Unit | Estimated Rate | | AMOUNT Rs. P |
|---------|---|----------------|------|----------------|-------|-----------------|
| | | | | Figure | Words | |
| 1 | Providing and fixing anodised aluminium extrusion section of Jindal/ Hindalco aluminium or its equivalent work for door, window, ventilator and partition with extruded built up standard tubular and other sections of approved make conforming to IS:733 and IS:1285 anodised transparent or dyed to require shade accordingly to IS.1868 (minimum anodic coating of grade AC15) fixed with raw plugs and screws or with fixing clips, necessary filling up of gaps and junctions at top, bottom and sides with required with PVC / neoprene fillers etc. aluminium section shall be smooth rust free, straight, milled and jointed mechanically wherever required including cleats angle, aluminium, snap beading for glazing/ panelling C.P brass / stainless steel screws all complete as per Architectural Drawings and the direction of the Engineer-in Charge for doors, windows and ventilators and glazed partitions frames complete in all respect as per direction of Engineer-Charge. The rates are inclusive all taxes levy by the Govt. time to time including GST | 130.34 | Kg | | | |
| 2 | Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer in-charge. (Cost of aluminium snap beading shall be paid in basic item With glass panes of Modi Gaurd 5 5 mm (Five point five) millimeter thickness (weight not less than 12.50 kg/ sqm) (twelve point fifty) complete in all respect as per direction of Engineer-Charge. The rates are inclusive all taxes levy by the Govt. time to time including GST. | 19.82 | Sqm | | | |
| 3 | Providing and fixing Fly proof stainless steel grade 304 wire gauge with 0.5 (zero point five) mm dia. wire and 1.4mm (one point four) millimeter wide aperture with matching wood beading complete in all respect. complete in all respect as per direction of Engineer-Charge. The rates are inclusive all taxes levy by the Govt. time to time including GST | 2.64 | Sqm | | | |
| 4 | Providing and fixing 12 mm (twelve) millimeter thick pre-laminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer-in-charge. Pre-laminated particle board with decorative lamination on one side and balancing lamination on other side complete in all respect as per direction of Engineer-Charge. The rates are inclusive all taxes levy by the Govt. time to time including GST. | 13.10 | Sqm | | | |

| | | | | | | |
|----|--|--------|------|--|--|--|
| 5 | Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS - 1868) transparent or dyed to required colour or shade, with necessary screws etc. Complete 100 mm complete in all respect as per direction of Engineer-Charge. The rates are inclusive all taxes levy by the Govt. time to time including GST. | 9.00 | Each | | | |
| 6 | Providing and fixing PTMT Handle with necessary screws 125x34x24 (one hundred twenty five into thirty four into twenty four) complete in all respect as per direction of Engineer-Charge. The rates are inclusive all taxes levy by the Govt. time to time including GST. | 13.00 | Each | | | |
| 7 | Providing and laying Polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm (eighteen) thick stone slab over 20 (twenty) mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge complete in all respect as per direction of Engineer-Charge. The rates are inclusive all taxes levy by the Govt. time to time including GST. | 0.65 | Sqm | | | |
| 8 | Providing and fixing magnetic catcher for cup boards all complete as specified and as directed by the Engineer-in-Charge. complete in all respect as per direction of Engineer-Charge. The rates are inclusive all taxes levy by the Govt. time to time including GST. | 4.00 | Each | | | |
| 9 | Providing and fixing chromium plated brass curtain rod having wall thickness of 125mm with two chromium plated brass brackets fixed with C.P. Brass screws and PVC sleeves etc. wherever necessary complete 20 (twenty) mm Dia complete in all respect as per direction of Engineer-Charge. The rates are inclusive all taxes levy by the Govt. time to time including GST. | 1.50 | Rmt | | | |
| 10 | Providing and fixing 15cm (fifteen centimetre) wide 45cm (forty five millimetre) over all semicircular plain G.I. sheet gutter with iron brackets 40x3mm size bolts and nuts and washers etc. including making necessary connections with rain water pipe complete as per design 0.63mm thick sheet with zinc coated not less than 275 gram/m ² , complete in all respect as per direction of Engineer-Charge. The rates are inclusive all taxes levy by the Govt. time to time including GST. | 60.00 | Rmt | | | |
| 11 | Fixing 0.60mm thick prepainted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 microns over 5 microns primer coating to back coat of polyester of 5 microns over 5 microns primer coating i/c fixing with screws prepainted iron J or L hooks, bolts and nuts 6mm dia metre with prepainted impet and rubber washers complete with all accessories as required as per the direction of Engineer-in-charge. including carriage of material with in all leads and lifts and other incidental. complete in all respect as per direction of Engineer-Charge. The rates are inclusive all taxes levy by the Govt. time to time including GST. | 200.00 | Sqm | | | |

(3)(2)

| | | | | | | |
|----|--|------|------|--|--|--|
| 12 | Providing and fixing 600x120x5 (six hundred into one hundred twenty into five) mm glass shelf with edges round off, supported on anodised aluminium angle frame with C.P. brass brackets and guard rail complete fixed with 40 (forty) mm long screws, rawl plugs etc., complete in all respect as per direction of Engineer-Charge. The rates are inclusive all taxes levy by the Govt. time to time including GST. | 4.00 | Each | | | |
| 13 | Providing and fixing 600x450 (six hundred into four hundred fifty) mm beveled edge mirror superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete in all respect as per direction of Engineer-Charge. The rates are inclusive all taxes levy by the Govt. time to time including GST. | 2.00 | Each | | | |


 Executive Engineer
 Bajjnath Division
 H.P.P.W.D. Bajjnath



SCHEDULE OF QUANTITY

Name of Work: C/O Road from Sabji Mandi to village Sangrebar Near Sarman Km 0/0 to 4/0 (Portion link road to village Sarman)
(SH: F/C in Km 1/215 to 2/450).

Estimated Cost: Rs. 499288/-
Earliest Money: Rs. 10000/-
Time Limit: Two Months

SCHEDULE OF WORKS

| S No. | Description of work | No. or Qty | Unit | Estimated Rate | | AMOUNT Rs. P |
|----------|--|---------------|-----------------|----------------|-------|-----------------|
| | | | | Figure | Words | |
| 1 | Excavation in earthwork in hilly areas in all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and levels as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification clause 1603.1 and 1603.2 to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, up to all leads & lift and finishing of the road to specified dimensions or as directed by the Engineer-in charge for smooth riding. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases. The recovery @ Rs. 300.00 per cubic metre for 134 cubic metre useful stones already deducted in the preparing of estimate. The rate including of octroi, royalty, Malkana, tolltax, GST or other taxes imposed by the government. | 2233.35 | Per Cubic Meter | | | |



By, 
Bainath Division,
H. J. B.V.D. Ba, 

D.N.I.T/ SCHEDULE OF QUANTITY

Name of Work:- Hotla Chadhar Road to Saklani Basti G.P Drug Km 0/00 to 0/700,
(SH:- Providing and Laying Cement Concrete Pavement & ~~Kharajpur~~ RD 0/535 to 0/667).

Estimated Cost 495502.00
Earnest Money ~~250000~~ / 5,00,000
Time limit Two Months

| Sr No. | Description of work | No. or Qty. | Unit | Estimated Rate | | AMOUNT Rs. P |
|-----------|--|----------------|-----------------|----------------|-------|-----------------|
| | | | | Figure | Words | |
| 1 | Providing and laying mechanically mixed vibrated reinforced cement concrete in substructure using concrete grade M-20 (Twenty) design Mix with cement contents not less than 330 kg (three hundred and thirty kilogram) per cubic meter as per drawing and M.O.R.D. Technical specification section 800, 900, 1200. Including the cost of form work in bed block and dirt wall etc. excluding the cost of reinforcement for reinforced concrete work but including curing complete as per direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government. | 68.74 | Per Cubic Meter | | | |
| | | | | | | |

Execd. 
Bar. 
H. 