


HPPWD NOTICE INVITING TENDER BHARWAIN DIVISION HPPWD BHARWAIN TEHSIL AMB DISTRICT UNA (H.P).
Phone No. 01976-255822 , Web :- www. hppwd.gov.in & email address ee-bharw-hp@nic.in.

Sealed tenders on item rates basis are hereby invited on behalf of Governor of Himachal Pradesh by the Executive Engineer Bharwain Division, HPPWD, Bharwain Tehsil Amb District Una (HP) from the experienced contractors/ firms enlisted in appropriate class with Himachal Pradesh PWD for the following works. The tender shall be received in his office on or before 17.02.2024 up to 10.30 A.M and shall be opened on the same day at 11.00 A. M in the presence of contractors / firms or their authorized representatives , who wish to be present at the time of opening of tenders. The tender applications shall be entertained and tender form shall be sold up to two days before the date of opening of tender i.e 15.02.2024 up to 12.00 Noon. Draft Notice Inviting Tenders/ Drawing/ Specifications can be seen in the office of the Executive Engineer on any working day between 11.00 A. M to 4.00P. M. Ambiguous / Telegraphic / Conditional tenders or tender by Fax shall not be entertained/ considered in any case. The earnest money in the shape of National Saving Certificate / Time Deposit Account / FDR in any of the Post Office in H.P./ Nationalized Bank duly pledged in favour of Executive Engineer must be accompanied with the application. Conditional tenders and the tenders received without earnest money will out rightly be rejected. The contractor shall accompany his enlistment/ renewal orders with his application for obtaining the tender documents. The Executive Engineer reserves the right to reject the tender without assigning any reasons. The work will be completed by the contractor within the stipulated period. The contractor will have to submit his registration under the H. P General Sale Tax Act 1968 and also labour license under contract Act 1970 from the competent authority. The contractors/ firms are requested to insert the rate of each item in words as well as figures, failing which XEN reserves the right to accept/ reject any or overall tenders. The tender shall only be issued to those contractors/ firms, who are found eligible/ suitable and competent as per the above conditions. The offer shall remain valid up to 45 days after the opening of tender. If any of the date mentioned above happens to be Local / Gazetted Holidays the same shall be process on next date. The contractor should be registered as dealer under GST Act. Valid copy of Registration as required, copy of PAN Card, EPF failing which no tender form will be issued to him.

Sr. No	Name of work.	Estimate d cost.	Earnest Money	Time Limit	Form No.	Cost of
1	Restoration on Bharwain Chintpurni Talwara road Km. 0/0 to 15/300 (SH:- C/O Balance work of Retaining wall at RD 14/308 to 14/320)	496762/-	10000/-	One month	PWD-8	350/-
2	C/O Link road Bhaira to Satothar Km. 0/0 to 1/800 (SH:- Balance work for C/O Approach wall at RD 1/439 to 1/467 LHS of road) Under MMGSY	499366/-	10000/-	One Month	PWD-8	350/-
3	C/O Ambulance road Panjpeeri to Barkhedi Km. 0/0 to 1/0 ward No. 4 in G.P Bhagrah (SH:- C/O Abutment toward Panjpeeri side 3 mtr Span RCC slab culvert at RD 0/650) MPLAD (RS)	289702/-	6000/-	One Month	PWD-8	350/-
4	Balance work for construction of link road to village Satothar to Chhamma Km. 0/0 to 1/0 (SH:- C/O Retaining wall at RD 0/430 to 0/455 LHS of road under MMGSY)	497891/-	10000/-	One month	PWD-8	350/-
5	Restoration of rain damages on link road Kinnu to Guret Km. 0/0 to 8/435 (SH:- C/O Retaining wall at RD 4/990 to 5/010 & 5/070 to 5/090)	498359/-	10000/-	One month	PWD-8	350/-
6	Restoration of rain damages on Sohari to Behlna road Km. 0/0 to 4/0 and link road to Sada Shiv Temple Km. 0/0 to 2/00 (SH:- Removal of slips , C/O Earthen Shoulder and cosntruction of unlined drain at various RDs)	310997/-	6300	One month	PWD-8	350/-
7	C/O Ambulance road Panjpeeri to Barkhedi Km. 0/0 to 1/0 ward No. 4 in G.P Bhagrah (SH:- C/O Abutment toward Barkhedi side & superstructure for C/O 3.00 mtr Span RCC slab culvert at RD 0/650) Under VKVNY	499700/-	10000/-	One month	PWD-8	350/-
8	Restoration on Saloi to Koharchan via Phanger road Km. 0/0 to 3/0 (SH:- C/O Retaining wall at RD 1/245 to 1/260)	458226/-	9200	One month	PWD-8	350/-

9	Restoration of rain damages on Link road Govt. High School Suhin to Mandholi Km. 0/0 to 1/0 (SH:- C/O U-shape drain at RD 0/281 to 0/300 , 0/306 to 0/351 C/O Breast wall at RD 0/405 to 0/420 & C/O Retaining wall at RD 0/775 to 0/785)	471068/-	9500	One month	PWD-8	350/-
10	Restoration of road due to pipe laying on Channi Devi to Guret Km 0/0 to 5/420(SH:- purchase of 3 No. Computer 4 No 600 KVA offline UPS system along 4 No printer for the office of the Assistant Engineer Amb , Jole and C/branch Bharwain Division)	455711/-	9200/-	One month	PWD-8	350/-

1. The Xen reserve the right to accept or reject the tender with assigning any reason.
2. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
3. The list of similar type of work executed & work done performance certificate issued by the concerned Executive Engineer/GST/EPF No should accompanied with application.
4. Certificate: - Certificate that the tender have been invited in exigencies/emergency of work.


Executive Engineer,
Bharwain Division,
HPPWD, Bharwain.

No. PWB/CB/TA /Tender /2024- 14988 - 0/8 Dated 09/02/2024

Copy forwarded to the following for information and necessary action, please.

1. The Engineer in Chief, HppWD, Shimla for information.
2. The Chief Engineer, (HZ) HppWD, Hamirpur.
3. The Superintending Engineer, 15th Circle, HPPWD, Una.
4. All the contractor working under this Division.
5. Drawing Branch in this office.
6. All the Assistant Engineer, working under this Division.
7. Notice Board.


Executive Engineer,
Bharwain Division,
HPPWD, Bharwain.

Certificate

Certified that the works are of urgent in nature and for large public Interest, so there are exigencies /emergency in calling these without press vide this office letter No PWB/CB/TA-1/ Tender/2024:- 14988-018 dated 09/02/2024


Executive Engineer,
Bharvain Division,
MPPWD, Bharvain.

Schedule Of Quantity

Estimated Cost:- 496762

Earnest Money:- 10000/-

Time :- One Month

Name of Work:- Restoration of rain damages on Bharwain Chintpurni Talwara road Km. 0/0 to 15/300 (SH:- C/O Balance work of Retaining wall at RD 14/308 to 14/320)

Sr.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Excavation in earth work in foundation and trenches etcetera in all kind and classification of soil such as pick work, jumper work, pick jumper work, blasting work and hard blasting work and saturated soil any other mixed verity of soil in dry or saturated condition upto any depth and lift upto any height including chiseling/wedging out rocks where blasting prohibited dewatering pumping or bailing out water where required and/ removal of slush separately as directed which may arise during the execution including stacking the serviceable and unserviceable material and then returning stacked soil in any thickness of layers when required into plinth side of foundation etcetera consolidating each deposited layers by ramming and watering then disposing of all surplus unserviceable excavated earth as specified dumping place as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi , royalty , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	47.36	180.00	Rs one hundred eighty and paise zero only	Per cubic metre	8525
2	providing and laying in position cement concrete 1:4:8(one cement: four sand: eight graded/crushed stone aggregate 40mm (forty millimeter) nominal size mechanically mixed and vibrated curing complete including cost of centering and shuttering in Retaining wall / Breast wall as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of material/ machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi , royalty , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	136.57	3450.00	Rs three thousand four hundred fifty and paise zero only	Per cubic metre	471167
3	Providing weepholes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeters) dia PVC pipe OF MAKE D-PLAST/POLY having pressure of 4.5 kg per square meter extending through the full width of the structures with slope of 1(V):20(H) (one vertical: twenty horizontal) towards drawing face complete as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi , royalty , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	21.00	230.00	Rs two hundred thirty and paise zero only	Each	4830
4	Back filling with granular material behind abutment, wing wall and return wall complete as per drawing and direction of Engineer in charge including carriage of materials/machinery required to execute the work as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkhana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	20.40	600.00	Rs. Six hundred and paise zero only	Per cubic metre	12240
	Total					496762
	Percentage rate (Above or Below)					

Executive Engineer,
Bharwain Talwara
PPWD Bharwain

Schedule Of Quantity

Estimated Cost:- 49366

Earned Money:- 10000/-

Time :- One Month

Name of Work:- C/O Link road Bhaira to Satothar Km. 0/0 to 1/800 (SH:- Balance work for C/O Approach wall at RD 1/439 to 1/467 LHS of road) Under MMGSY

Sr.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Excavation in earth work in foundation and trenches etcetera in all kind and classification of soil such as pick work, jumper work, pick jumper work, blasting work and hard blasting work and saturated soil any other mixed variety of soil in dry or saturated condition upto any depth and lift upto any height including chiseling/wedging out rocks where blasting prohibited dewatering pumping or bailing out water where required and/ removal of slush separately as directed which may arise during the execution including stacking the serviceable and unserviceable material and then returning stacked soil in any thickness of layers when required into plinth side of foundation etcetera consolidating each deposited layers by ramming and watering then disposing of all surplus unserviceable excavated earth as specified dumping place as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkhana, toll tax, goods service tax, labour cess or other taxes imposed by the Govt.	56.63	180.00	Rs one hundred eighty and paise zero only	Per cubic metre	10193
2	providing and laying in position cement concrete 1:4:8(one cement: four sand: eight graded/crushed stone aggregate 40mm (forty millimeter) nominal size mechanically mixed and vibrated curing complete including cost of centering and shuttering in Retaining wall / Breast wall as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of material/ machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkhana, toll tax, goods service tax, labour cess or other taxes imposed by the Govt.	134.02	3400.00	Rs three thousand four hundred and paise zero only	Per cubic metre	455668
3	Providing and laying non-pressure NIP2 class (light duty) 600mm (six hundred millimetre) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkhana, toll tax, goods service tax, labour cess or other taxes imposed by the Govt.	7.50	2750.00	Rs two thousand seven hundred fifty and paise zero only	Per cubic metre	20625
3	Providing weepholes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeters) dia PVC pipe OF MAKE D-PLAST/POLY having pressure of 4.5 kg per square meter extending through the full width of the structures with slope of 1(V):20(H) (one vertical: twenty horizontal) towards drawing face complete as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkhana, toll tax, goods service tax, labour cess or other taxes imposed by the Govt.	56.00	230.00	Rs two hundred thirty and paise zero only	Each	12880
	Total					49366
	Percentage rate (Above or Below)					


 Engineer
 Bhairav Division
 MMGSY Bhairav

Schedule Of Quantity

Estimated Cost:- 289702/-
Earnest Money:- 6000/-

Time :- One Month

Name of Work:- C/O Ambulance road Panipeeri to Barkheddi Km. 0/0 to 1/0 ward No. 4 in G.P Bhagrah (SH:- C/O Abutment toward Panipeeri side for C/O 3 mtr Span RCC slab culvert at RD 0/650) MPLAD (RS)

Sr.	Sub-Head and Items of work	Quantity	Figures	Words	Unit	Amount
1	Excavation in earth work in foundation and trenches etcetera in all kind and classification of soil such as pick work, jumper work, pick jumper work, blasting work and hard blasting work and saturated soil any other mixed verity of soil in dry or saturated condition upto any depth and lift upto any height including chiseling/wedging out rocks where blasting prohibited dewatering pumping or bailing out water where required and/ removal of slush separately as directed which may arise during the execution including stacking the serviceable and unserviceable material and then returning stacked soil in any thickness of layers when required into plinth side of foundation etcetera consolidating each deposited layers by ramming and watering then disposing of all surplus unserviceable excavated earth as specified dumping place as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi , royalty , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	68.33	170.00	Rs one hundred seventy and paise zero only	Per cubic metre	11616
2	Providing and laying in position cement concrete 1:3:6 (one cement three sand: six graded/crushed stone aggregate 40mm (forty millimeter) nominal size mechanically mixed and curing complete including cost of centring and shuttering in foundation and plinth level as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi , royalty , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	9.22	4000.00	Rs four thousand and paise zero only	Per cubic metre	36880
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced cement concrete in foundation of bridge complete of plain/ reinforced concrete grade M-15 (M fifteen) in under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including form work in abutments, and return walls, and pier footing etcetera as per drawings and MORTH technical 1500, 1700, 2100 specification and as per direction of Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes octroi , royalty , Malkhana , toll tax, goods service tax , labour cess or other taxes	57.43	4200.00	Rs four thousand two hundred and paise zero only	Per cubic metre	241206
	Total					289702
	Percentage rate (Above or Below)					


Executive Engineer
Bharwad Division
MPT&WD Bharwad

Schedule Of Quantity

Estimated Cost:- 497891/-

Earnest Money:- 10000/-

Time :- One Month

Name of Work:-Balance work for construction of link road to village Satothar to Chhamma Km. 0/0 to 1/0 (SH:- C/O Retaining wall at RD 0/430 to 0/455 LHS of road under MMGSY)

Sr.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Excavation in earth work in foundation and trenches etcetera in all kind and classification of soil such as pick work, jumper work, pick jumper work, blasting work and hard blasting work and saturated soil any other mixed verity of soil in dry or saturated condition upto any depth and lift upto any height including chiseling/wedging out rocks where blasting prohibited dewatering pumping or bailing out water where required and/ removal of slush seprately as directed which may arise during the execution including stacking the serviceable and unserviceable material and then returning stacked soil in any thickness of layers when required into plinth side of foundation etcetera consolidating each deposited layers by ramming and watering then disposing of all surplus unserviceable excavated earth as specified dumping placè as per CPWD specifications 2019 complete and direction of Engineer-in- charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi , royalty , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	54.63	180.00	Rs one hundred eighty and paise zero only	Per cubic metre	9833
2	Excavation in all kind of soil work by mechanical means (Hydraulic Excavator)/manual means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil setting out true to the required line, grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	106.95	135.00	Rs. One hundred thirty five and paise zero only	Per Cubic Meter	14438
3	providing and laying in position cement concrete 1:4:8(one cement: four sand: eight graded/crushed stone aggregate 40mm (forty millimeter) nominal size mechanically mixed and vibrated curing complete including cost of centering and shuttering in Retaining wall / Breast wall as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of material/ machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi , royalty , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	127.15	3400.00	Rs three thousand four hundred and paise zero only	Per cubic metre	432310

Schedule Of Quantity

Estimated Cost:- 498359/-

Earnest Money:- 10000/-

Time :- One Month

Name of Work:-Restoration of rain damages on link road Kinnu to Guref Km. 0/0 to 8/435 (SH:- C/O Retaining wall at RD 4/990 to 5/010 & 5/070 to 5/090)

Sr.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Excavation in earth work in foundation and trenches etcetera in all kind and classification of soil such as pick work, jumper work, pick jumper work, blasting work and hard blasting work and saturated soil any other mixed verity of soil in dry or saturated condition upto any depth and lift upto any height including chiseling/wedging out rocks where blasting prohibited dewatering pumping or bailing out water where required and/ removal of slush seprately as directed which may arise during the execution including stacking the serviceable and unserviceable material and then returning stacked soil in any thickness of layers when required into plinth side of foundation etcetera consolidating each deposited layers by ramming and watering then disposing of all surplus unserviceable excavated earth as specified dumping place as per CPWD specifications 2019 complete and direction of Engineer-in- charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentials.The rate includes octroi , royalty , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	54.84	180.00	Rs one hundred eighty and paise zero only	Per cubic metre	9871
2	Providing and laying in position cement concrete 1:3:6 (one cement three sand: six graded/crushed stone aggregate 40mm (forty millimeter) nominal size mechanically mixed and curing complete including cost of centring and shuttering in foundation and plinth level as per CPWD specifications 2019 complete and direction of Engineer-in- charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentials.The rate includes octroi , royalty , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	8.28	4000.00	Rs four thousand and paise zero only	Per Cubic Meter	33120
3	providing and laying in position cement concrete 1:4:8(one cement: four sand: eight graded/crushed stone aggregate 40mm (forty millimeter) nominal size mechanically mixed and vibrated curing complete including cost of centring and shuttering in Retaining wall / Breast wall as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of material/ machinery required to execute the work in all leads and lifts and other incidentials. The rate includes octroi , royalty , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	120.15	3450.00	Rs three thousand four hundred fifty and paise zero only	Per cubic metre	414518

Schedule Of Quantity

Estimated Cost:- 310997/-

Earnest Money:- 6300/-

Time :- One Month

Name of Work:- Restoration of rain damages on Sobari to Behna road Km. 0/0 to 4/0 and link road to Sada Shiv Temple Km. 0/0 to 2/00 (SH:- Removal of slips, C/O Earthen Shoulder and construction of unlined drain at various RDs)

Sr.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material upto any lift and lead as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	1578.00	100.00	Rs one hundred and paise zero only	Per cubic metre	157800
2	Construction of embankment with approved material obtained from borrow pits or other sources in layers of suitable thickness not exceeding 200mm(two hundred millimetre) spreading to required slope and compacted with three wheel 80 -100 KN static/vibratory road roller meet the requirements of table 300.1 and 300.2 of MORD specifications to lines grade, level and cross sanction as per drawing and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkhana, toll tax, goods service tax, labour cess or other taxes imposed by the Govt.	564.99	260.00	Rs. two hundred sixty and paise zero only	Per cubic metre	146897
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions excavated material to be used in embankment at site with in any lead and lift as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	180.00	35.00	Rs thirty five and paise zero only	Per running metre	6300
	Total					310997
	Percentage rate (Above or Below)					


Executive Engineer
Bharvati Division
BPPWD Bhawan

Schedule Of Quantity

Estimated Cost:- 499700/-

Earnest Money:- 10000/-

Time :- One Month

Name of Work:- C/O Ambulance road Panjpeeri to Barkhedhi Km. 0/0 to 1/0 ward No. 4 in G.P Bhagrah (SH:- C/O Abutment toward Barkhedhi side & superstructure for C/O 3.00 mtr Span RCC slab culvert at RD 0/650) Under VKVNY

Sr.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Providing and laying in position specified grade of reinforced cement concrete, including the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level 1:2.5:5 (1 cement : 2.5 coarse sand) : 5 graded stone aggregate 20 mm nominal sizes per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi , royalty , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	77.77	4200.00	Rs four thousand two hundred and paise zero only	Per cubic metre	326634
2	Providing and laying in position cement concrete M-20 design mix to obtain the minimum compressive strength of 20N/mm ² with graded crushed stone aggregate 20mm (twenty millimeter) nominal size to give smooth and even surface and cement contents not less than at the rate of 340 kg (three hundred forty kilogram) per cubic meter mechanically mixed including curing complete including cost of form work in foundation and plinth level as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkhana, toll tax, goods service tax, labour cess or other taxes imposed by the Government	3.02	5000.00	Rs. Five thousand and paise zero only	Per cubic metre	15100
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced cement concrete in foundation of bridge complete of plain/ reinforced concrete grade M-15 (M fifteen) in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including form work in abutments, and return walls, and pier footing etcetera as per drawings and MORTH technical 1500, 1700, 2100 specification and as per direction of Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes octroi , royalty , Malkhana , toll tax, goods service tax , labour cess or	3.99	6000.00	Rs six thousand and paise zero only	Per cubic metre	23940
4	Providing steel reinforcement and Thermo-Mechanically Treated bars of grade Fe-500D or more approved make i.e. SAIL, RINL, Shyam Steel/TISCO, Jindal Panther (JSPL) for reinforced cement concrete work including bending cutting straightening and placing in position binding all complete upto any floor level/height as per CPWD specifications 2019 complete and direction of Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkhana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	0.91	80000.00	Rs. Eighty thousand and paise zero only	Per Tonne	72800
5	Back filling with granular material behind abutment, wing wall and return wall complete as per drawing and direction of Engineer in charge including carriage of materials/machinery required to execute the work as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkhana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	21.60	600.00	Rs. Six hundred and paise zero only	Per cubic metre	12960

Schedule Of Quantity

Estimated Cost:- 458226/-

Earnest Money:- 9200/-

Time :- One Month

Name of Work:- Restoration of rain damages on Saloi to Koharchan via Phanger road Km. 0/0 to 3/0 (SH:- C/O Retaining wall at RD 1/245 to 1/260)

Sr.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Excavation in earth work in foundation and trenches etcetera in all kind and classification of soil such as pick work, jumper work, pick jumper work, blasting work and hard blasting work and saturated soil any other mixed verity of soil in dry or saturated condition upto any depth and lift upto any height including chiseling/wedging out rocks where blasting prohibited dewatering pumping or bailing out water where required and/ removal of slush separately as directed which may arise during the execution including stacking the serviceable and unserviceable material and then returning stacked soil in any thickness of layers when required into plinth side of foundation etcetera consolidating each deposited layers by ramming and watering then disposing of all surplus unserviceable excavated earth as specified dumping place as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi , royalty , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	64.80	180.00	Rs one hundred eighty and paise zero only	Per cubic metre	11664
2	providing and laying in position cement concrete 1:4:8(one cement: four sand: eight graded/crushed stone aggregate 40mm (forty millimeter) nominal size mechanically mixed and vibrated curing complete including cost of centering and shuttering in Retaining wall / Breast wall as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of material/ machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi , royalty , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	119.10	3500.00	Rs three thousand five hundred and paise zero only	Per cubic metre	416850
3	Providing weepholes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeters) dia PVC pipe OF MAKE D-PLAST/POLY having pressure of 4.5 kg per square meter extending through the full width of the structures with slope of 1(V):20(H) (one vertical: twenty horizontal) towards drawing face complete as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi , royalty , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	48.00	220.00	Rs two hundred twenty and paise zero only	Each	10560
4	Back filling with granular material behind abutment, wing wall and return wall complete as per drawing and direction of Engineer in charge including carriage of materials/machinery required to execute the work as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkhana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	34.20	560.00	Rs. five hundred sixty and paise zero only	Per cubic metre	19152
	Percentage rate (Above or Below)					
	Total					458226

Plav
Executive Engineer
Bharwan Division
HPPWD Bharwan

Schedule Of Quantity

Estimated Cost:- 471068/-
Earnest Money:- 9500/-

Time :- One Month

Name of Work:- Restoration of rain damages on Link road Govt. High School Suhin to Mandholi Km. 0/0 to 1/0 (SH:- C/O U-shape drain at RD 0/281 to 0/300 , 0/306 to 0/351 C/O Breast wall at RD 0/405 to 0/420 & C/O Retaining wall at RD 0/775 to 0/785)

Sr.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Excavation in earth work in foundation and trenches etcetera in all kind and classification of soil such as pick work, jumper work, pick jumper work, blasting work and hard blasting work and saturated soil any other mixed verity of soil in dry or saturated condition upto any depth and lift upto any height including chiseling/wedging out rocks where blasting prohibited dewatering pumping or bailing out water where required and/ removal of slush seprately as directed which may arise during the execution including stacking the serviceable and unserviceable material and then returning stacked soil in any thickness of layers when required into plinth side of foundation etcetera consolidating each deposited layers by ramming and watering then disposing of all surplus unserviceable excavated earth as specified dumping place as per CPWD specifications 2019 complete and direction of Engineer-in- charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentials. The rate includes octroi , royalty , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	79.92	170.00	Rs one hundred seventy and paise zero only	Per cubic metre	13586
2	Providing and laying in position cement concrete 1:3:6 (one cement three sand: six graded/crushed stone aggregate 40mm (forty millimeter) nominal size mechanically mixed and curing complete including cost of centring and shuttering in foundation and plinth level as per CPWD specifications 2019 complete and direction of Engineer-in- charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentials. The rate includes octroi , royalty , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	24.96	3800.00	Rs three thousand eight hundred and paise zero only	Per cubic metre	94848
3	providing and laying in position cement concrete 1:4:8(one cement: four sand: eight graded/crushed stone aggregate 40mm (forty millimeter) nominal size mechanically mixed and vibrated curing complete including cost of centering and shuttering in Retaining wall / Breast wall as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of material/ machinery required to execute the work in all leads and lifts and other incidentials. The rate includes octroi , royalty , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	99.96	3400.00	Rs three thousand four hundred and paise zero only	Per cubic metre	339864

Schedule of Quantity

Estimated Cost:- 455711/-
Earnest Money :-9200/-
Time :- One Month

Name or Work :- Restoration of road due to pipe laying on Channi Devi to Guref Km 0/0 to 5/420 (SH:- purchase of 3 No. Computer 4 No. 600 KVA offline UPS system along with 4 No. printer for the office of the Assistant Engineer Amb , Jole, and C/Branch Bharwain Division)

Sr. No.	Sub-Head and Items of work	Quantity		Rates in		Unit	Amount
				Figures	Words		
1	Dell Desktop:- 5420 AIO DESCRIPTION Processor 13th Generation intel i5 1335U / 10 core up to 4.60 GHz Windows 11 Office Home & Student 2021 Lifetime / Ram 8GB 3200 MHz / Hard Disk-512 GB SSD /24 inch FHD SCREEN Intel UHD Graphics, WEB CAM, SOUND BAR / 15 month Antivirus, Wifi & Bluetooth / Hardware Warranty 3 Year onsite	3.00	Nos.	71000.00	Rs. Seventy one thousand and paise zero only	Each	213000
2	600KVA Off line UPS System make 12 Vx7AH x 2 Nos SMF batteries to provide back up (with three years warranty on UPS 12 month on battery from delivery date).	4.00	Nos.	3500.00	Rs. Three thousand five hundred and paise zero only	Each	14000
3	HP Laserjet M1136MFP orequivalent (A4size) Printer with Print, Scan & Copy, Print upto 18ppm, Auto on/off technology One year warranty except Toner & plastic parts.	4.00	Nos.	26500.00	Rs. Twenty six thousand five hundred and paise zero only	Each	106000
	Total						333000
	Add Gst @ 18% & 1% Labour Cess	19%					63270
	Total						396270
	Add C.P + OHC. @ 15%	15%					59441
	Grand Total						455711
	Rate (Above or Below)						

Executive Engineer
Bharwain Division
HPPWD Bharwain

Job No - 10